BYTE

the small systems journal

JULY 1981 Vol. 6, No. 7
$2.50 in USA/$2.95 in Canada
A McGraw-Hill Publication

ENERGY CONSERVATION



What Cromemco computer card capability can do for you

The above diagram shows in a functional way one of the most complete lines of computer cards in the industry.

Look it over carefully. It could be well worth your while.

These are all cards that plug into our S-100 bus microcomputers.

You can also assemble them into a custom system in convenient Cromemco card cages.

MULTI-PROCESSING AND INTELLIGENT I/O

The range of capabilities and versatility you can draw upon is enormous.

In processors, for example, you have a choice of CPU's including our extremely useful new I/O Processor. This can be used as a satellite processor to do off-line processing, multi-processing, and to form intelligent I/O. It opens the door to a whole new group of applications and tasks. Ask us about it.

HIGH RESOLUTION COLOR GRAPHICS

Again, you can have beautiful high-resolution color graphics with our color graphics interface. You can select from over 4000 colors and have a picture with a resolution at least equal to quality broadcast-TV pictures.



You have an unprecedented selection of memory including our unusual 48K and 16K **two-port** RAMs which allow high-speed color graphics.

LOTS OF STORAGE

These days you often want lots of disk storage. So you can select from our disk controller card which will operate our 5" and 8" floppy disk drives (up to 1.2 megabytes). Or select our WDI interface to operate our 11-megabyte hard disk drives.

POWERFUL SOFTWARE AND PERIPHERAL SUPPORT

There's much more yet you can do with our cards. And, of course, there's an easy way to put them to work in our 8-, 12-, and 21-slot card cages. Our PS8 power supply makes it simple to get the system into operation.

Finally, Cromemco offers you the strongest software support in the industry with languages like FORTRAN, C, COBOL, ASSEMBLER, LISP, BASIC and others. There is also a wide choice from independent vendors.

To top it all off, you can draw from a substantial array of peripherals: terminals, printers, color monitors and disk drives.

CONTACT YOUR CROMEMCO REP

There is even more capability than we're able to describe here.

Contact your Cromemco rep now and get this capability working for you.

CROMEMCO COMPUTER CARDS

- **PROCESSORS** — 4 MHz Z-80 A CPU, single card computer, I/O processor • **MEMORY** — up to 64K including special 48K and 16K two-port RAMS and our very well known BYTESAVERS® with PROM programming capability • **HIGH RESOLUTION COLOR GRAPHICS** — our SDI offers up to 754 x 482 pixel resolution. • **GENERAL PURPOSE INTERFACES** — QUADART four-channel serial communications, TU-ART two-channel parallel and two-channel serial, 8PIO 8-port parallel, 4PIO 4-port isolated parallel, D+7A 7-channel D/A and A/D converter, printer interface, floppy disk controller with RS-232 interface and system diagnostics, wire-wrap and extender cards for your development work.

Cromemco™
incorporated
280 BERNARDO AVE., MOUNTAIN VIEW, CA 94040 • (415) 964-7400
Tomorrow's computers today

Circle 107 on inquiry card.



Management Information Display



Ultrasonic heart sector scan



High-resolution display with alphanumerics

Get the professional color display that has BASIC/FORTRAN simplicity

LOW-PRICED, TOO

Here's a color display that has everything: professional-level resolution, enormous color range, easy software, NTSC conformance, and low price.

Basically, this new Cromemco Model SDI* is a two-board interface that plugs into any Cromemco computer.

The SDI then maps computer display memory content onto a convenient color monitor to give high-quality, high-resolution displays (756 H x 482 V pixels).

When we say the SDI results in a high-quality professional display, we mean **you can't get higher resolution than this system offers in an** NTSC-conforming display.

The resolution surpasses that of a color TV picture.

BASIC/FORTRAN programming

Besides its high resolution and low price, the new SDI lets you control with optional Cromemco software packages that use simple BASIC- and FORTRAN-like commands.

Pick any of 16 colors (from a 4096-color palette) with instructions like DEFCLR (c, R, G, B). Or obtain a circle of specified size, location, and color with XCIRC (x, y, r, c).

*U.S. Pat. No. 4121283



Model SDI High-Resolution Color Graphics Interface

HIGH RESOLUTION

The SDI's high resolution gives a professional-quality display that strictly meets NTSC requirements. You get 756 pixels on every visible line of the NTSC standard display of 482 image lines. Vertical line spacing is 1 pixel.

To achieve the high-quality display, a separate output signal is produced for each of the three component colors (red, green, blue). This yields a sharper image than is possible using an NTSC-composite video signal and color TV set. Full image quality is readily realized with our high-quality RGB Monitor or any conventional red/green/blue monitor common in TV work.

Model SDI plugs into Z-2H 11-megabyte hard disk computer or any Cromemco computer

DISPLAY MEMORY

Along with the SDI we also offer an optional fast and novel **two-port** memory that gives independent high-speed access to the computer memory. The two-port memory stores one full display, permitting fast computer operation even during display.

CONTACT YOUR REP NOW

The Model SDI has been used in scientific work, engineering, business, TV, color graphics, and other areas. It's a good example of how Cromemco keeps computers in the field up to date, since it turns any Cromemco computer into an up-to-date color display computer.

The SDI has still more features that you should be informed about. So contact your Cromemco representative now and see all that the SDI will do for you.

Cromemco
incorporated
280 BERNARDO AVE., MOUNTAIN VIEW, CA 94043 • (415) 964-7400
Tomorrow's computers today

Circle 107 on inquiry card.

In The Queue

Volume 6, Number 7 July 1981

Features

Reviews

Nucleus

BYTE

Page 26



Page 38



Page 48



Page 60

Editor in Chief
Christopher Morgan

Managing Editor
Mark Haas

Technical Editors
Gregg Williams, Senior Editor;
Richard S Shuford; Curtis P Feigel;
George Stewart; Stan Miastkowski;
Kevin Cohan; Charles Freiberg,
New Products Editor;
Steve Ciarcia, Mark Dahmke,
Consulting Editors;
Jon Swanson, Draftsman

Copy Editors
Richard Friedman, Chief; Faith Hanson;
Warren Williamson; Anthony J Lockwood;
Ann Graves; Beverly Cronin

Assistants
Faith Ferry; Debe Wheeler;
Karen A Cilley

Production
Nancy Estle, Director; Christine Dixon,
Asst Director; Wai Chiu Li;
Deborah Porter; Jonathan M Graves;
Patrice Scribner; Sherry McCarthy,
Chief Typographer; Debi Fredericks;
Donna Sweeney; Valerie Horn

Advertising
Thomas Harvey, Director; Marion Gagnon;
Barbara J Greene; Rob Hannings;
Marilyn Williams; Jacqueline Earnshaw,
Reader Service Coordinator

Circulation
Gregory Spitzfaden, Manager;
Andrew Jackson, Asst Manager;
Agnes E Perry; Barbara Varnum;
Louise Menegus; Bill Watson;
James Bingham, Dealer Sales

Marketing
Laura Hanson

Controller's Office
Daniel Rodrigues, Controller; Mary E Fluhr,
Acct D/P Mgr; Karen Burgess; Jeanne Cilley;
Mary Beth Ireland

Traffic
N Scott Gagnon; Robert A Fiske;
William Fluhr

Receptionist
Joanne Colburn

Publishers
Virginia Londoner; Gordon R Williamson;
John E Hayes, Associate Publisher;
Cheryl A Hurd, Publisher's Assistant;
Kathe LaRiviere, Administrative Assistant

Officers of McGraw-Hill Publications Company: Paul F McPherson, President; Executive Vice Presidents: James E Boddorf, Gene W Simpson; Group Vice President: Daniel A McMillan; Senior Vice President-Editorial: Ralph R Schulz; Vice Presidents: Kemp Anderson, Business Systems Development; Robert B Doll, Circulation; James E Hackett, Controller; Eric B Herr, Planning and Development; H John Sweger, Marketing.

Officers of the Corporation: Harold W McGraw Jr, President, Chief Executive Officer and Chairman of the Board; Robert F Landes, Senior Vice President and Secretary; Ralph J Webb, Treasurer.



In This Issue

This month's cover painting by Robert Tinney shows our own solution to the energy crunch: a computerized "solar system." To illustrate this month's theme of energy conservation, we present a variety of articles, including "Harvesting the Sun's Energy," "Computer Simulation of a Solar Energy System," "Energy Conservation With a Microcomputer," and "Energy Measurement With the Apple."

Also in this issue are a discussion of IBM's new personal computer; the first part of Steve Ciarcia's exciting new Z8 single-board computer project (about which there was much interest at the recent National Computer Conference); another solution to the traveling-salesman problem; Micromodem support in Apple Pascal; Kalman filters; hurricane tracking by computer; the Atari Assembler/Editor; a report on the Santa Cruz Computer Othello tournament; and much more, including all the regular BYTE features.

BYTE is published monthly by BYTE Publications Inc, 70 Main St, Peterborough NH 03458, phone (603) 924-9281, a wholly-owned subsidiary of McGraw-Hill, Inc. Address subscriptions, change of address, USPS Form 3579, and fulfillment questions to BYTE Subscriptions, POB 590, Martinsville NJ 08836. Controlled circulation postage paid at Waseca, Minnesota 56093 - USPS Publication No. 528890 (ISSN 0360-5280). Canadian second class registration number 9321. Subscriptions are $19 for one year, $34 for two years, and $49 for three years in the USA and its possessions. In Canada and Mexico, $21 for one year, $38 for two years, $55 for three years. $43 for one year air delivery to Europe. $35 surface delivery elsewhere. Air delivery to selected areas at additional rates upon request. Single copy price is $2.50 in the USA and its possessions, $2.95 in Canada and Mexico, $4.00 in Europe, and $4.50 elsewhere. Foreign subscriptions and sales should be remitted in United States funds drawn on a US bank. Printed in United States of America.

Address all editorial correspondence to the editor at BYTE, POB 372, Hancock NH 03449. Unacceptable manuscripts will be returned if accompanied by sufficient first class postage. Not responsible for lost manuscripts or photos. Opinions expressed by the authors are not necessarily those of BYTE.

BYTE® is available in microform from University Microfilms International, 300 N Zeeb Rd, Dept PR, Ann Arbor MI 48106 USA or 18 Bedford Row, Dept PR, London WC1R 4EJ England.

Subscription WATS Line: (800) 258-5485
Office hours: Mon-Thur 8:30 AM - 4:30 PM, Friday 8:30 AM - Noon, Eastern Time





"...stands well above other S-100 graphics displays in its price and performance range."
BYTE, Product Review



"...better monochromatic ...display...."
ELECTRONIC DESIGN, 1981 Technology Forecast

MICROANGELO

HIGH RESOLUTION GRAPHICS SINGLE BOARD COMPUTER

512 x 480 resolution black and white **and** vivid color displays

- RS-170 composite or direct drive output
- Local or external sync generation
- 4 Mhz Z80 microprocessor
- 60 hertz real-time clock
- 8 level interrupt tie-in
- IEEE S100 bus compatible



- Light pen interface
- Time multiplexed refresh
- 4K resident Screenware™ Pak I operating system
- 32K RAM isolated from host address space
- High speed communications over parallel bus ports

Screenware™ Pak I

A 4K byte operating system resident in PROM on MicroAngelo™. Pak I emulates an 85 character by 40 line graphics terminal and provides over 40 graphics commands. Provisions exist for user defined character sets and directly callable user extensions to Screenware™ Pak I.

Screenware™ Pak II

An optional software superset of Pak I which adds circle generation, polygon flood, programmable split screen for separate graphics and terminal I/O, relative coordinates, faster vector and character plotting, a macro facility, full UCSD Pascal compatibility, and more.

And now...COLOR!!

The new MicroAngelo™ Palette board treats from 2 to 8 MicroAngelos as "bit planes" at a full 512 x 480 resolution. Up to 256 colors may be chosen from 16.8 million through the programmable color lookup table. Overlays, bit plane precedence, fade-in, fade-out, gray levels, blinking bit plane, and a highly visual color editor are standard.

SCION

8455-D Tyco Road • Vienna, Virginia 22180 • TWX: 710-831-9087 • (703) 827-0888

Circle 346 on inquiry card.

Editorial

IBM's Personal Computer

by Chris Morgan, Editor in Chief

The year 1981 will be important in the history of personal computing for two reasons: the "invasion" of Japanese personal computers, and the entry of major computer companies such as IBM into the market. Rumors abound about personal computers to come from giants such as Digital Equipment Corporation and the General Electric Company.

But there is no contest.

IBM's new personal computer (most likely to be officially announced this month) is far and away the media star, not because of its features, but because it exists at all. When the number eight company on the Fortune 500 list enters our field, that is news. And when you take a close look at the computer's design, that is news, too. Although the complete description of the computer is still subject to conjecture, sources close to IBM have given me an intriguing glimpse of the machine.

System Details

Seemingly contradictory rumors about IBM have raced along the personal computer grapevine for several months now. Part of the confusion stems from the fact that IBM has had not one but *two* projects going on simultaneously to develop a personal computer—one in Japan, the other in the United States. The Japanese project (code-named "Go") was jointly sponsored by IBM and Matsushita. The culmination of the project was to have been a *series* of personal computers produced in Japan bearing the IBM logo. That project now appears to have been either scrapped or indefinitely delayed.

That leaves us with the American design. The computer (code-named "Chess") looks like IBM's low-cost ASCII terminal, but with a few inches of extra height to accommodate two double-density, double-sided 5-inch floppy disk drives immediately beneath the black-and-white video display (with 640 by 400 resolution). The keyboard, designed as a separate module, has received high marks from people who have tested it. Internally, the computer uses an Intel 8088 microprocessor (a 16-bit processor with an 8-bit data bus) and an "IBM" bus. There are five slots on the motherboard—à la Apple II—to accommodate additional interface, memory, and peripheral boards.

The machine will probably be available in a low-cost version with entry-level BASIC in ROM and with program storage and retrieval via cassette recorder (the latter will be a separate module rather than built in). The more expensive version will have disk BASIC and a CP/M-like DOS (disk operating system) to be called, simply, "IBM Personal Computer DOS." Color will also be available in at least two modes: four out of a possible eight colors with 640 by 200 resolution, and eight colors with 320 by 200 resolution. A 6-megabyte

Percom Mini-Disk Drive Systems for TRS-80* Computers...

Now! Add-On *and* Add-In Mini-Disk Storage for your Model III.

The industry leader in microcomputer peripherals, Percom not only gives you better design, better quality and first-rate service, but you pay less to *boot*.

New for the TRS-80* Model III

Patterned after our fast-selling TFD Model I drives. And subjected to the same reliability controls. These new TFD mini-disk systems for the Model III provide more features than Tandy drives, yet cost far less.

- **Flippy Capability:** Both internal (add-in) and external (add-on) drives permit recording on either side of a diskette.
- **Greater Storage Capacity:** Available with either 40- or 80-track drive mechanisms, Percom TFD mini-disk systems store more. A 40-track drive stores up to 180 Kbytes — formatted — on one side of a 5-inch diskette. An 80-track drive stores a whopping 364 Kbytes.
- **1.5 Mbyte On-line:** The Percom drive controller (included with the initial drive) handles up to four drives. With four 80-track mini-disk drives you can access over 1.5 million bytes of on-line file data.
  Moreover, the initial drive may be **either** an internal add-in drive or an external add-on drive. And whichever configuration you get, the initial drive kit comes complete with our advanced 4-drive controller, interconnecting cables, power supplies, installation hardware, a DOS and of course the drive mechanism itself.
- **First Drive Includes DOS:** OS-80™, Percom's fast extendable BASIC-language disk operating system, is included on diskette when you purchase an initial drive kit. Originally called MicroDOS, OS-80 was favorably reviewed in the June 1980 issue of Creative Computing magazine.
- **Works with Model III TRSDOS:** Besides being fully hardware compatible, Percom's Model III 40-track drive systems may be operated with Tandy's Model III TRSDOS — without any modifications whatsoever. And, TRSDOS may be easily upgraded with simple software patches for operating 80-track drives.

Percom TFD add-on drives start at only $399. Model III Drive kits start at only $749.95.

Quality Percom products are available at authorized dealers. Call *toll free 1-800-527-1592* for the address of your nearest dealer or to order direct from Percom.

Still #1 for Model I

As if greater storage capacities, exceptional quality control measures and lower prices aren't reasons enough to make Percom your first choice for Model I add-on drives, **all** Percom Model I drives are also rated for double-density operation.

Add our innovative DOUBLER™ adapter to your Model I Expansion Interface, and with Percom drive systems you can enjoy the same double-density storage capability as Model III owners.

The DOUBLER includes a TRSDOS*-like double-density disk operating system called DBLDOS™

We also offer a double-density Model I version of OS-80 as well as DOUBLEZAP programs for modifying NEWDOS/80 and VTOS 4.0† for DOUBLER compatibility.

Of course you don't have to upgrade your computer for double-density operation to use Percom mini-disk drive systems. In single-density operation, our TRS-80* Model I compatible 40-track drives store 102 Kbytes of formatted data on one side of a diskette, and our 80-track drives store 205 Kbytes. By comparison, Tandy's standard drive for the Model I stores just 86 Kbytes.

And like our Model III drives, Model I add-on drives are optionally available with "flippy" storage capability.

System Requirements:

Model III: 16-Kbyte system (min) and Model III BASIC. The second internal drive may be installed after the first internal drive kit is installed, and external drives #2, #3 and #4 may be added if either an internal or external first-drive kit has been installed. External drives #3 and #4 require an optional interconnecting cable.

Model I: 16-Kbyte system (min), Level II BASIC, Expansion Interface, disk operating system and an interconnecting cable. For double-density storage, a Percom DOUBLER must be installed in the Expansion Interface and DBLDOS (comes with the DOUBLER) or other double-density DOS must be used. For single-density operation, a Percom SEPARATOR™ adapter, installed in the Expansion Interface, will virtually eliminate "CRC ERROR — TRACK LOCKED OUT" read errors. Prices and specifications subject to change without notice.

PERCOM

PERCOM DATA COMPANY, INC.
211 N. KIRBY GARLAND, TEXAS 75042
(214) 272-3421

*Trademark of Tandy Radio Shack Corporation which has no relationship to Percom Data Company.
™DOUBLER, DBLDOS, OS-80 and SEPARATOR are trademarks of Percom Data Company, Inc.
†Trademark of Virtual Technology Corporation.

A simple algorithm

We work with the serious systems integrator ... on terms that make sense to you. That means giving you a set of products which expand your limits, not reduce them.

We manufacture the most complete family of high quality IEEE/696 S-100 mainframes on the market. Choices include three mainframes in rack-mount or table-top packages with complete board sets, to serve as the building blocks for your 8 or 16 bit system. We also provide other options ranging from complete floppy disk systems right up to our proven Pascal development system.

The ∫ factor: one source.

No matter which option you choose, you get the benefit of working with completely integrated products ... fully assembled and tested ... under one warranty and one price structure ... leaving you free to concentrate on value-added application development and sales.

Choose from mainframe options ...

Select from three packaging options: Rack-mount, table-top or front panel models. All three feature our 20 slot S-100 motherboard with 25 amp power supply and are delivered fully assembled and tested with our Series II™ board sets. Any board configuration you choose works with any DPS-1 version, allowing you to vary your package offering, or develop on one version and market another.

- Front Panel model — a powerful development and diagnostic tool for Z-80† systems, which can be used for prototyping, servicing, debugging, and software or hardware development. Use its features to set breakpoints, trigger scopes, single step, slow step and more.
- Front Panelless desk top model—a lower cost option for OEM or other turnkey operations which do not require the extra capability of our Front Panel.
- Rack Mount version — features a heavy gauge frame designed to fit into standard 19" racks. CVT power supply for brown out immunity is standard.

*In Calculus, a fundamental statement in the definition of limit; interpreted here to imply: "For your integration problem, Intersystems has a solution."

† Registered trademark of Zilog, Inc.



Board level options...

Intersystems mainframe packages, equipped with Series II boards, are operational in both 8 and 16 bit settings and support extended addressing in both I/O and memory space, recognizing 16 bit I/O addresses and 24 bit memory addresses. Just look at these individual features:



- MPU-80—uses a Z-80, 8 vectored interrupt lines and two 4K windows to address up to 1 Megabyte of RAM without bank select.
- 64KDR—sophisticated refresh circuitry allows unlimited DMA and absolutely reliable operation without wait states.
- 6 SI/O — six individually software-controllable serial I/O ports with optional interrupts. Each can run RS 232 at up to 19,200 BAUD, as can our VI/O board.
- VI/O—has two serial ports; two 8-bit parallel output and two 8-bit parallel input ports plus 8 individually controllable command lines and 16 levels of vectored interrupts.
- FDC II—can DMA up to a full track into 16 Megabytes of memory. Optionally generates interrupts and handles up to four 8" floppies.
- MPU-8000 — available with the non-segmented Z-8002†, which directly addresses 64K, or the segmented Z-8001†, which can directly address 8 Megabytes.

Extended systems options...



Interfacing disk drives is not a trivial matter, so when your objectives and resources dictate you spend your energy elsewhere, use our resources to perform the service for you. We can add our disk drive package to any Z-80 or Z-8000 configuration we provide ... again, fully assembled and tested and covered under one warranty.

Or our complete Pascal Development System.

We use it for our own hardware and software development. It includes either table-top mainframe, two 8" floppy disks, 128K RAM, CP/M#, and Intersystems Pascal/Z™ compiler and Cache BIOS™.

THIS SYSTEM IS FAST! Why? Because our ultra-fast Cache BIOS automatically buffers whole tracks, eliminating most disk accesses. This delivers up to three times the throughput of any other floppy-based system we know and is equal to many small hard disk systems.

The system is versatile, too. SET program allows you to change many BIOS parameters and specify control characters to enable special features such as diagnostic output to trace program execution. It can also provide remote I/O to link your system to almost any other computer, large or small.

And it's reliable. The Cache BIOS System runs continuous memory tests when idle, and verifies with a Read after Write and Read after Read.

And the system also includes our Pascal/Z, a true native compiler producing ROMable and Re-entrant code. It features a minimum of extensions chosen for the development of your scientific and business applications. And it's compatible with our native code Pascal for Z-8000, providing a graceful upward path to 16 bit applications. So what you write now is right later.

One choice you won't have to make...

We don't believe you should ever have to sacrifice good technical support to find a good product. We'll back you to the hilt with services like free technical consultation, board-swapping, diagnostic packages, and documentation that gives you all you need to integrate, operate and maintain your system ... right down to schematics of the boards.

Your solution should be clear.

Whether you're integrating for scientific, governmental or commercial applications, Intersystems can provide a Delta for your Epsilon.

Talk to us today.



Ithaca Intersystems Inc.,
Dept. B
1650 Hanshaw Road,
P.O. Box 91
Ithaca, NY 14850

Phone
(607) 257-0190

InterSystems™
Ithaca Intersystems Inc.

Micros for bigger ideas.

Circle 193 on inquiry card.

#Registered trademark of Digital Research

™Trademark of Ithaca Intersystems, Inc.

Editorial

Winchester drive (manufactured by Tandon Magnetics) will eventually be available for the machine. IBM has signed agreements with Sears Roebuck and Co and Computerland to market the new machine; J C Penney is reportedly interested, too.

The price? That's a difficult question, but the more expensive version will probably retail in the $3000 to $4000 range. Pricing for the stripped-down version is harder to estimate.

To my mind, the new IBM computer is aimed squarely at the low-end word processing market. It will certainly give machines like the Apple III a run for their money.

The influence of a personal computer made by a company whose name has literally come to mean "computer" to most of the world is hard to contemplate. Its design is a mixture of the conventionally safe (some would say reactionary) coupled with a bit of daring-do (the 8088 holds up the possibility of further 16-bit development).

On the whole I am heartened by the news of IBM's computer. Some factions in our industry have looked upon IBM as the "enemy," the company that gave rise to the mainframe mentality and the coterie of high priests—the computer operators who ran the old behemoths and who formed the only link between the lowly user and the all-powerful computer. Elements of this syndrome are unfortunately still in evidence today. Yet where would we be in the personal computer world if IBM had not sunk millions of dollars into the development of such now commonplace inventions as the floppy disk? Besides, it may not be that easy for IBM to gain wide acceptance for its new computer. Competition is growing from all sides. Last year, for example, Fujitsu outsold IBM in the mainframe market in Japan. It is inconceivable that other American computer companies such as Xerox, Data General, Honeywell, and the like will remain on the sidelines for long. This competition can only further the state of the art. And today's successful microcomputer companies will most certainly not fold up and die in the presence of the giants. Good large companies don't always supplant good small companies. As an example from another field, many small specialty book publishing companies are flourishing today in the midst of a general publishing recession. Why? Low overhead, flexibility, unconventional solutions to problems, attention to customer service—the list goes on.

It would be burying my head in silicon, however, to deny the enormous marketing potential of IBM. But that's all right. I want to see personal computing take a giant step. I liked the recent jocular warning from Intel's Stan Masor to "never trust a computer you can't lift." Perhaps the warning's unnecessary: the way things are going, small computers may soon be the only game in town. ■

Make the Apple II* a powerful IEEE-488 Controller in a snap.

Just plug the SSM A488 board into any Apple II* expansion slot for a low-cost, full-featured instrumentation interface. SSM gives the Apple II the power and versatility of a $9,000 IEEE-488 controller. At a fraction of the price. Our board converts the Apple II into a truly sophisticated controller that programs and controls up to 15 different instruments connected together on the 488 bus.

We make programming easy. The 68488 chip, designed by Motorola, forms the heart of our A488. We back this chip with powerful on-board firmware to give you system control via simple string commands. The only software you need is easy-to-program Applesoft* Basic. To develop special purpose firmware, simply replace our PROM with a RAM. With the A488, bus communications operate at top speed—without depending on software loops for timing. And like the more expensive IEEE-488 controllers, this system interfaces with more than 1200 instruments and peripherals.

Suitable for OEMs as well as end users. Whether you make test/measurement systems for resale, or simply for yourself, the SSM/Apple combo gives you top performance. As it cuts your costs. Call your local dealer or SSM today for complete details.



SSM's A488 board expands the Apple II to a high-performance IEEE-488 controller.

SSM Microcomputer Products, Inc.
2190 Paragon Drive
San Jose, CA 95131
(408) 946-7400 Telex: 171171
TWX: 910-338-2077

*Registered trademarks of Apple Computer Inc.

Reddy Chirra improves his vision with an Apple.

Reddy is an optical engineer who's used to working for big companies and using big mainframes.

But when he started his own consulting business, he soon learned how costly mainframe time can be. So he bought himself a 48K Apple II Personal Computer.

And, like thousands of other engineers

and scientists, quickly learned the pleasures of cutting down on shared time and having his own tamper-proof data base.



His Apple can handle formulas with up to 80 variables and test parameters on 250 different optical glasses.

He can even use BASIC, FORTRAN, Pascal and Assembly languages.

And Apple's HI-RES graphics come in handy for design.

Reddy looked at other microcomputers, but chose Apple for its in-depth documentation, reliability and expandability.

You can get up to 64K RAM in an Apple II. Up to 128K RAM in our new Apple III. And there's a whole family of compatible peripherals, including an IEEE-488 bus for laboratory instrument control.

Visit your authorized Apple dealer to find out how far an Apple can go with scientific/technical applications.

It'll change the way you see things.

The personal computer. apple®

For the dealer nearest you, call (800) 538-9696. In California, call (800) 662-9238. Or write: Apple Computer Inc., 10260 Bandley Dr., Cupertino, CA 95014.

Circle no. 28 for more information or Circle no. 205 for special OEM information

Letters

"Bug" Takes Flak

In the January 1981 BYTE, W D Maurer reported on a "bug" that he had found in a number of BASIC interpreters on stack-oriented machines. (See "A Bug in BASIC," page 188.)

I ran Mr Maurer's test on the BASIC interpreter that I use. My BASIC is provided with the OASIS operating system by Phase One Systems. The bug doesn't appear to be present in this BASIC.

Donald M Dealy
EDP Director
Fuller Memorial Hospital
231 Washington St
South Attleboro MA 02703

W D Maurer has identified a vexing problem in some BASICs: the abnormal exit from a FOR . . . NEXT loop. Another problem with abnormal exits occurs when the interpreter is designed to stack, or nest, FOR . . . NEXT loops. A simple search algorithm such as

```
10 INPUT "MATCH?="; X
20 FOR I = 1 TO N
30   IF A(I) = X THEN 60
40 NEXT I
50 GO TO 10
60 PRINT "FOUND "; X
70 GO TO 10
```

can end abnormally if the number of matches in line 30 (ie: abnormal exits) exceeds the nesting level of the interpreter.

Ens G K Baird, SC, USN
USS Peleliu (LHA-5) Bx4
FPO San Francisco CA 96624

I enjoyed W D Maurer's article, but I beg to differ with his conclusion that the Atari 400 and 800 suffer from this problem.

In the *Atari BASIC Reference Manual*, the POP instruction is discussed. POP is a BASIC command that performs a PLA (Pull Accumulator) instruction on the 6502 processor. If line 135 is added to Maurer's program:

```
135 POP
```

the top location of the stack (which controls the number of loops to be executed) is cleared, and all test runs in listing 2, page 190 of the article, run without error.

Atari provides this instruction for use when an abnormal exit occurs from a FOR . . . NEXT loop or a GOSUB/RETURN sequence.

William Hanson
Kentron International
2508 W 22nd St
Yuma AZ 85364

The *PET Users Manual* warns not to use abnormal exits from loops. So is this really a bug or a design trade-off?

James E Borden
641 Adams Rd
Carlisle PA 17013

Surely the "elegant" solution to the BASIC bug problem is not to stack more information for each loop or to search stacks differently, but to clean up the programming by setting a flag if needed, resetting the counter variable to the end value, and executing the NEXT on the way out. The FOR . . . NEXT structure thus becomes a variant of a REPEAT . . . UNTIL structure, which, by coincidence, is more or less what David Carew was up to in his "Programming Quickie." (See "Change Your GOTOs to FOR . . . NEXT Loops," January 1981 BYTE, page 334.)

John C Miller
110 Riverside Dr #14C
New York NY 10024

Maurer's article "A Bug in Basic" was a bitter reminder of the many hours I've spent chasing down this particular problem in Applesoft BASIC. His solution—to replace a FOR . . . NEXT loop with an open-coded equivalent—is a practical one. However, there's an alternative solution that keeps the structure of the FOR . . . NEXT loop, but it requires a little more coding.

Recognizing that the problem arises from an abnormal exit from the loop, you can circumvent the difficulty by ensuring that all FOR . . . NEXT loops exit normally. This can be done by setting the index of the loop to its final value inside the loop at the point at which the abnormal exit would be made, then proceeding through one more cycle of the loop. The occurrence of abnormal termination can be stored in a flag. In terms of Maurer's example, this code could be used:

OUR MEDIA IS OUR MESSAGE.

Over the past seven years we've earned a name for ourselves by making the best magnetic media in the business. Precision magnetic media — Diskettes, Mini Diskettes, Diagnostic Diskettes, Rigid Discs, Disc Packs, and Disc Cartridges — all certified to be 100% error free both on-track **and** between the tracks.

Now we're making it easier for you to buy the best.

Just dial Dysan direct TOLL FREE at 800/538-8150 or 408/988-3472 (in California) or contact your local Dysan office.

Precision magnetic media from Dysan.

Our media says it all.

Dysan® CORPORATION

5440 Patrick Henry Drive
Santa Clara, CA 95050
408/988-3472
TLX: 171551 DYSAN SNTA

Circle 133 on inquiry card.

```
 75  FLAG = 0
 80  FOR C = 1 TO N
 90  IF T(C)< >0 THEN 100
 92  C = N
 94  FLAG = 1
100  NEXT C
110  IF FLAG = 1 THEN 130
120  PRINT "ZERO IS NOT PRESENT"
125  GOTO 140
130  PRINT "ZERO IS PRESENT"
140  ...............................
```

The key step here is line 92, in which the loop index is set to its final value when abnormal termination is required.

John Figueras
65 Steele Rd
Victor NY 14564

Mr Maurer's article was quite enlightening. As a Radio Shack TRS-80 Model I Level II owner (a machine that "bombed" on the tests), I too ran into the mysterious NEXT without FOR error. Maurer suggests changing the interpreter or the loop variable, but each of these solutions has problems: the first is either impossible (as with a BASIC in read-only memory) or impractical; the second can be cumbersome to patch into an existing program. There is an easier solution, one that presents few, if any, problems and is easy to implement into an incorrect program.

The problem, as Mr Maurer states, is the "illegal" exit from the loop. The correction I suggest is to "fool" the interpreter into thinking the loop is completed by changing the loop variable to a value greater than the end value of the loop.

Joe Sewell
6776 Sheridan Rd
Melbourne Village
Melbourne FL 32901

W D Maurer Replies:

I have received numerous communications from people who have tried out my "buggy" program on eight or ten versions of BASIC not covered in my article. The results are very much like those I reported: most do not have the bug, but a sizable minority do.

Mr Hanson exhibits a common confusion about bugs in programming-language systems. Just because there is a way to rewrite a program exhibiting a system bug in such a way that the new program does not manifest it, does not mean there is no bug. Mr Hanson's solution also has the drawback of reducing portability in a particularly essential way.

Mr Borden's comments on the PET can only be answered by noting that abnormal exits from loops are an essential part of programming. Also, when most people are faced with a system that discourages abnormal exits from FOR . . . NEXT loops, they will simply rewrite their programs to avoid the FOR and NEXT statements (usually with comments showing where the FOR and NEXT statements would have gone and what they would have been).

Messrs Miller, Figueras, and Sewell have a higher-level confusion about structured programming that I have met with many times before. The fact is that changing the loop index value inside the loop is expressly forbidden in almost every algebraic language except BASIC (eg: FORTRAN, Pascal, PL/I). It should, therefore, not be considered as a technique dictated by structured programming, which is essentially a study of language-independent *methods of improving the readability and provability of programs.*

I also want to respond specifically to Mr Sewell's contention that changing the interpreter is either impossible or impractical. The way to change interpreters, Mr Sewell, is for everyone who knows about the bugs in them to mention these bugs to computer-store salespeople when shopping for new equipment. It was partly for this reason that I intended my investigations of this particular bug to be published in a magazine with as large a circulation as BYTE's.

Structured Programming Clarifications

I agree 100% with the sentiments expressed by Gregg Williams in "Structured Programming and Structured Flowcharts." (See the March 1981 BYTE, page 20.) For too long, programmers have worried almost exclusively about program size, coding techniques, and execution speed. Logical simplicity, program reliability, and ease of modification (inevitable in every environment) have taken a back seat.

However, I want to point out the following:

- A design *notation* is not the same thing as a design *method*. A notation tells you *how to write down* something you have already structured mentally. A design method tells you *how to arrive* at the

You'll be a little richer after building one of these.

Richer in knowledge
Once you build your own computer, you'll know it inside out. You'll know how to make it work for you, how to make it grow as your skills grow.

Richer in savings
Build-it-yourself kits cost less – about 30% less than comparable assembled computers. And you'll probably never need to pay someone for service because no one will know your computer better than you.

Is it hard?
Not at all. Heath makes it simple with easy-to-assemble designs and with step-by-step manuals that guide you from unpacking to final plug-in. And a Heathkit helping hand is always just a phone call away.

Innovative software
Heath offers you innovative programs for running your home or business, and exciting games for your family. You can have Microsoft™ BASIC™, one of the most powerful and widely used languages.

Heath User's Group (HUG) will share with you a library of over 500 programs to make your computer serve you in ways you never imagined.

Complete hardware
Choose from three computer systems:

The H89 All-In-One Computer gives you everything in one compact, convenient unit.

The flexible H8 gives you the freedom to combine memory and interfacing for exactly the system you require.

And the powerful H11A gives you 16-bit power for your most complex programs.

The Heathkit line includes video terminals, matrix and letter-quality printers and a complete selection of accessories. You'll even find award-winning self-instruction packages to teach yourself programming in BASIC or Assembly.

FREE CATALOG

It's all in the new 104-page Heathkit Catalog, along with nearly 400 electronic kits for your home, work or pleasure. Send for your free catalog today, or pick one up at your Heathkit Electronic Center.*

Heathkit®

*Visit your Heathkit Electronic Center in the U.S. or Canada where Heathkit Products are displayed, sold and serviced. See your white pages for the location nearest you. Heathkit Electronic Centers are units of Veritechnology Electronics Corporation in the U.S.

Write to Heath Company, Dept. 334-784, Benton Harbor, MI 49022
(In Canada write Heath Company, 1480 Dundas St. E., Mississauga, Ont. L4X 2R7)

CP-186

Circle 169 on inquiry card.

structure and how to write it down. This is a very important distinction. I suggest that figuring out what the structure ought to be is the hardest part of programming.

I find that data-structured design produces programs that are simple, modifiable, and that accurately reflect the problem they are supposed to be solving. This method is explained in *Principles of Program Design*, by Michael Jackson (New York: Academic Press, 1975).

• Mr Williams's table-search program used as an example of structured flowcharting has some difficulties. The index of the largest element (MAXINDEX) is described in table 1 (page 22) as:

$$1 < \text{MAXINDEX} < \text{N}$$

This means that neither the first nor the last entry can be the largest, and that there must be at least three elements in the table.

$$1 \leq \text{MAXINDEX} \leq \text{N}$$

would have been better, and was probably intended.

Also, the initial setting of MAXVAL to -9×10^{20} is much too machine dependent. This number would have to be changed for each compiler/computer combination. Why should a programmer even have to know what the smallest possible number is? It would be much better to set MAXVAL to the contents of the first entry in the table, and MAXINDEX to 1. INDEX can then start at 2, since the first entry in the table does not have to be compared with MAXVAL—it *is* MAXVAL.

There is another weakness in the program. What if the table has no entries at all? I know this is outside the specification, but it really shouldn't be. As written, the program will print:

MAXINDEX = 0, MAXV = -9×10^{20}

Clearly, this is not true. The program

Listing 1

```
program FINDMAX
  if array is empty (N = 0)
    print "V ARRAY IS EMPTY"
  else array is not empty (N > 0)
    set first entry as largest (MAXINDEX = 1, MAXV = V(1))
    comparisons start at second entry (INDEX = 2)
    while INDEX ≤ N
      find value of current array element (CURRV = V(INDEX))
      if current array element > largest element so far (CURRV > MAXV)
        new maximum element = current element (MAXV = V(INDEX))
        new maximum index = current index (MAXINDEX = INDEX)
      endif
      increment index by 1 (INDEX = INDEX + 1)
    endwhile
    print MAXV, MAXINDEX
  endif
endprogram
```

should test explicitly for an empty table. The final pseudocode is shown in listing 1.

Listing 1 exhibits none of the problems I've mentioned, and it was patterned using data-structured design.

Mayer Wantman
3D Systems
17 Grange Rd
Elstree, Hertfordshire,
WD6 3LY, England

Gregg Williams Replies:

Mr Wantman's distinction between notation *and* method *is a particularly incisive one. Because it is one of those ideas that illuminates the mind and helps clarify its intended subject, I'm sure I will find it useful in the future.*

Also, his corrections concerning MAXINDEX, the initialization of MAXVAL, and the possibility of an empty V array are correct. The first was a typographical error, but the last two were, alas, design errors on my part. My thanks to Mr Wantman for pointing them out.

Praise from All Over

It would be nice if more software companies took a leaf from Versawriter's sales program and offered a sample of their products—perhaps a demonstration disk for a dollar plus your disk. Boy, that would certainly help in evaluating the stuff they're offering.

Evans M Harrel
342 Sequoia Dr
Marietta GA 30060

Southwestern Data Systems has recently introduced The Courier, a demonstration disk for dealers. It contains program samples from several manufacturers. While not as convenient as trying out programs in your home, you now have the opportunity to evaluate programs from several sources at your local computer store. . . . MH

In a day when companies charge you at the drop of a hat for an update to their software, here comes Tom Gibson providing an update to tiny-c, *without charge*. (See the letter from Tom, below.)

I've seen or heard of no other company doing this. Practices such as this will



MAKING MINIS OUT OF MICROS.

Here's the system builder's solution for successful computers and applications. Push in the CCS component. **Push in** the operating software. And **push on** with your application. CCS systems and components are designed to go together quickly, and to keep running reliably, with a proven return rate of less than 1%.

And you get performance. The systems deliver hardware vectored interrupts and the capability to interleave DMA data transfers with rates as high as two megabytes per second, plus bank select memory of up to 512K bytes. This 8-bit system provides single user, multiuser, and multitasking capability with ample speed to prevent operator waiting or loss of incoming real-time data.

The systems are available with CP/M or MP/M operating systems. For real-time or multiuser applications, the CCS OASIS real-time multitasking operating system supports re-entrant programs and relocatable code modules, with facilities for task-to-task communication, file protection, time-of-day bookkeeping, spooling, task overlay, dynamic memory management, ISAM file structures and device-independent I/O. CCS OASIS includes debug, text editing, linkage, and file sort utilities; the system supports a host of existing languages, applications, and utilities from a range of vendors.

Powerful computer systems you can configure to your demanding requirements quickly, and with confidence. Choose from a variety of systems. Expand with CCS board-level modules for memory, disk control, high-speed arithmetic, and I/O, plus subsystems for floppy and hard disk storage.

If you sell, install, or use computer systems, you should know more about the CCS product line. **We've got a lot more to tell. Tear out and return the coupon for more information. Or call.**

○ Please have a sales representative call me.

○ Please send more information on CCS Systems and Expansion Modules.

Name __________

Company __________

Address __________

City/State/Zip __________

Phone: (   ) __________

California Computer Systems
250 Caribbean Drive
Sunnyvale, CA 94086
(408) 734-5811

CP/M and MP/M are trademarks of Digital Research. OASIS is a trademark of Phase One Systems.

Circle 52 on inquiry card.

guarantee tiny-c associates a good reputation and a long life.

Jack M Williams
902 Anderson Dr
Fredericksburg VA 22401

To: tiny-c Two customers

Enclosed is a revision of tiny-c Two. Usually we charge a small fee for updates. But because tiny-c Two is a brand-new product and this is a significant revision, we are sending it without charge to all our tiny-c Two customers.

You may keep your old disk. We would appreciate it if you would remove and destroy its "tiny-c" label, and erase all its files. Then you may use it as a scratch disk.

Tom Gibson
Tiny-c Associates
POB 269
Holmdel NJ 07733

When post-warranty service from a microcomputer manufacturer can be described only with superlatives such as "exemplary" and "outstanding," the time has come to bring it to BYTE readers' attention. In a field noted for its past lack of customer support, my experience with Dynabyte's civilized and decent way of treating consumers convinces me it is in a league with such legendary firms as Rolls-Royce (automobiles) and McIntosh (stereo equipment).

I called Dynabyte in Menlo Park, California, from London, Canada, about an intermittent disk problem with my Dynabyte 5200. Although the warranty period had expired, Roy Wheaton, Dynabyte's new national service manager, telephoned me. He not only spent some time on the phone "walking me through" the problem (I know nothing about the inside of a computer), but also arranged to rush me hundreds of dollars' worth of new parts without payment in advance. He called back several times to check whether they had arrived. The problem, an auxiliary disk controller, was sent back with the unneeded parts he sent, on an exchange basis for $65.

Dynabyte's policy of total customer satisfaction should be contrasted with an increasing number of firms in our society that become incommunicado after the sale. I have never experienced anything like the customer support given by Dynabyte.

Benjamin D Singer
Faculty of Social Science
Department of Sociology
University of Western Ontario
London, Ontario, N6A 5C2, Canada

Null Way To Run

William Sommerfeld's self-replicating program is an elegant one, but not quite the shortest. (See "Letters," March 1981 BYTE, page 16.) That honor goes to the "null" program:

which, if run, also prints exactly itself.

Here is, I think, the smallest self-replicating *and* self-modifying program. Notice that the program it *becomes* is also self-replicating (in fact, the one mentioned above):

```
1 LIST
2 NEW
```

Finally, if mere self-replication isn't enough, an *infinitely* self-replicating program:

```
1 LIST
2 RUN
```

Robert F Barnes
905 Delaware Ave
Bethlehem PA 18015

Expert Advice

On page 52 of the January 1981 BYTE, there is a photo showing a power-line filter in a video terminal. (See photo 2 in Steve Ciarcia's "Electromagnetic Interference.")

The label on the capacitor is 0.1 μF at 1000 V DC. BYTE readers should be warned that the selection of a DC-rated capacitor for use across the power line is a task for an expert. Nonexperts should use capacitors rated for the AC line voltage and recognized for this use by Underwriters Laboratories.

R E Stutz
Engineering Manager
Special Components Operations
Sprague Electric Company
26899 S Mooney Blvd
POB 5000
Visalia CA 93278■

MANAGER'S DILEMMA NO. 2

How to put a system together by tomorrow.

MOSTEK®





You can reduce the time lag between an idea and its execution with Mostek MD Series STD-Z80 BUS modules. In this system component approach, your engineer selects the functions he needs — CPU, memory, I/O, etc. Then, he inserts the compact STD-Z80 BUS modules into a card cage. Redesigns are as easy as adding, exchanging, or deleting modules.

Our broad software line further speeds the design cycle. A real-time multi-tasking executive is available. And a CP/M* compatible operating system. And a new Process BASIC that is a development system and a stand-alone executive.

And now, more than ever, STD-Z80 BUS boards are the cost-effective edge. Because we've just reduced prices an average of 30%! Delivery is from stock through your Mostek distributor.

We also offer OEM discounts, a one-year warranty, and more. Get *all* the facts today. Because you never know when you'll have to put a system together by tomorrow. Contact Mostek, 1215 West Crosby Road, Carrollton, Texas 75006; (214) 323-1829. In Europe, phone Mostek Brussels: 762.18.80.

Prototype with STD-Z80 BUS microsystems. The cost effective edge.

Terminal Width Problems with the OSI Challenger

Shel Sacks, 2 Eldorado Blvd, Plainview NY 11803

If you use an OSI (Ohio Scientific) Challenger 1P computer with a video display having a line length or TW (terminal width) of less than 24 characters, you know that you cannot properly save programs on cassette. This is due to OSI's BASIC-in-ROM requiring a 72-character terminal width. In fact, 72 is the default value for the TW parameter, which is requested after the system is booted. But this problem of properly saving programs is easily solved.

The TW parameter is found in memory location 15 (decimal). The value of this parameter can be easily changed by a POKE, either given in immediate mode or from within a program. You might want to try a few different values and watch the changes in the display when listing a program.

Due to overscan on the television that I use for a video display, I program with TW set at 22 so that I can see all characters as they are entered. When I'm ready to save the program on tape, I begin with a POKE 15,72, which returns the TW parameter to 72 and ensures that the program is saved properly. I then SAVE the program as usual. ■

Turn your Apple into the world's most versatile personal computer.

The SoftCard™ Solution. SoftCard turns your Apple into two computers. A Z-80 and a 6502. By adding a Z-80 microprocessor and CP/M to your Apple, SoftCard turns your Apple into a CP/M based machine. That means you can access the single largest body of microcomputer software in existence. Two computers in one. And, the advantages of both.

Plug and go. The SoftCard system starts with a Z-80 based circuit card. Just plug it into any slot (except 0) of your Apple. No modifications required. SoftCard supports most of your Apple peripherals, and, in 6502-mode, your Apple is still your Apple.

CP/M for your Apple. You get CP/M on disk with the SoftCard package. It's a powerful and simple-to-use operating system. It supports more software than any other microcomputer operating system. And that's the key to the versatility of the SoftCard/Apple.

BASIC included. A powerful tool, BASIC-80 is included in the SoftCard package. Running under CP/M, ANSI Standard BASIC-80 is the most powerful microcomputer BASIC available. It includes extensive disk I/O statements, error trapping, integer variables, 16-digit precision, extensive EDIT commands and string functions, high and low-res Apple graphics, PRINT USING, CHAIN and COMMON, plus many additional commands. And, it's a BASIC you can compile with Microsoft's BASIC Compiler.

More languages. With SoftCard and CP/M, you can add Microsoft's ANSI Standard COBOL, and FORTRAN, or Basic Compiler and Assembly Language Development System. All, more powerful tools for your Apple.

Seeing is believing. See the SoftCard in operation at your Microsoft or Apple dealer. We think you'll agree that the SoftCard turns your Apple into the world's most versatile personal computer.

Complete information? It's at your dealer's now. Or, we'll send it to you and include a dealer list. Write us. Call us. Or, circle the reader service card number below.

SoftCard is a trademark of Microsoft. Apple II and Apple II Plus are registered trademarks of Apple Computer. Z-80 is a registered trademark of Zilog, Inc. CP/M is a registered trademark of Digital Research, Inc.

MICROSOFT
CONSUMER PRODUCTS

Microsoft Consumer Products, 400 108th Ave. N.E., Bellevue, WA 98004. (206) 454-1315

Circle 250 on inquiry card.

The Santa Cruz Open

Othello Tournament for Computers

Peter W Frey
Visiting Professor
University of California
421 Kerr Hall
Santa Cruz CA 95064

In mid January, when the Midwest and Northeast were weathering heavy snows and subzero temperatures, programmers from the US and abroad, laden with microcomputers or terminals and modems, traveled to the University of California in sunny Santa Cruz, for the Santa Cruz Open Othello Tournament. Each programming team had been preparing for months for decisive head-to-head competition in which only one program would triumph as champion. For individuals accustomed to solitary, cerebral pursuits, this tournament provided a public arena in which to demonstrate their skills.

The focus of this concentrated preparation was a complex strategy game, originally called Annexation, then renamed Reversi. It is now known as Othello, a trade name of CBS Inc. The rules of play and strategic ideas for this game have been discussed in earlier issues of BYTE (see references at the end of this article).

The University of California, Santa Cruz (UCSC), was an unconventional site for this electronic confrontation. The campus buildings are nestled among redwood trees on a hill overlooking Monterey Bay, an area of mostly undisturbed natural beauty. When the visitors arrived on campus for the weekend tournament, many must have thought they had been misdirected to a meeting of the Sierra Club.

The weekend was filled with many little surprises. Despite our careful plans, campus security forgot to open the fortress-like Applied Science building at the appointed hour. After traveling great distances at considerable expense, the competitors found themselves at a closed gate surrounded by dense forest. Members of the security force finally responded to our panicky telephone calls and opened the main gate, but then they promptly departed, leaving all of the rest rooms locked. The problems were eventually taken care of, however, and the Othello tournament gained a momentum of its own and proceeded in reasonable order.

Twenty teams were represented—more entries than in any computer-chess competition.

Tournament information was sent to potential participants last September. Later in the fall, most of the personal computing magazines carried announcements of the event. Even though Othello is a recent introduction to this country from Japan, it has gained a loyal following, and the organizers were surprised by the large number of individuals who responded enthusiastically. When tournament day arrived, 20 teams were represented—*more entries than in any computer-chess competition.*

The Santa Cruz Open was noteworthy also in respect to its budget. There wasn't any. Nevertheless, the event managed to take on the appearance of a big-time competition because of the enormous enthusiasm of the participants and the generous support from various segments of the computing community.

At the request of Dan and Kathe Spracklen, Fidelity Electronics and the Hayden Book Company provided air transportation from New York for the tournament director, Jonathan Cerf. Jonathan had recently returned from London where he had wrested the World Othello Championship from the Japanese. It was the first time that anyone outside Japan had held the title. For US Othello players, Jonathan's victory was akin to our hockey team's victory over the Russians at the 1980 Winter Olympics. We were extremely pleased to have Jonathan with us, and he turned in an absolutely superb job as tournament director. His efforts were aided by a computer program I had written to keep track of match outcomes,

Text continued on page 32

megastor and apple*

the perfect couple

MEGASTOR consists of two very reliable 8-inch drives, complete with integral power supply and controller card for APPLE II.

Any software currently running under APPLE II DOS will run on MEGASTOR.

Special software is available to convert APPLE II DOS files to IBM 3741 Ebcdic-formatted files, and to read IBM-formatted files.

MEGASTOR offers the user:

1.1 or 2.2 megabytes of storage per dual-drive unit.

Full APPLE II compatibility.

Distributorship and overseas enquiries welcomed.

*Apple is a trade mark of Apple Computer Inc.

Vlasak Computer Systems

Vlasak House,
8 Stuart Road,
High Wycombe, Bucks,
HP13 6AG, England.
Tel. H.W. (0494) 448633

ANNOUNCING

A Major Breakthrough

The SYSTEM 2800

The System 2800 is the next logical step in the continuing line of innovative products from the Systems Group.

Unbeatable S-100 Memory Boards

First was the development of the DMB6400 series of S-100 Memory boards featuring the innovative Bank Select switching technique. This enables users to software select up to four totally independent memory banks per board.



The 2nd Generation

Then came the 2nd Generation of IEEE S-100 COMPATIBLE Z80 PROCESSORS, FLOPPY DISK CONTROLLERS and SERIAL I/O BOARDS. Each has been designed for single user, multi-user or network operating systems such as CP/M®, MP/M™, CP/Net™ and OASIS™.



The Next Logical Step ...

We challenged our design team to create an innovative yet competitive system utilizing our existing line of field proven, dependable S-100 boards. The result: a highly reliable, quality built, state of the art microcomputer that gives you the cost/performance edge you need to be a leader in your field.

The System 2800 comes with a choice of operating systems: CP/M with an enhanced CBIOS for single user systems and either MP/M or OASIS for multi-user, multi-tasking systems. MP/M is available with either a standard or

CP/M MP/M and CP/Net are trademarks of Digital Research
OASIS is a trademark of Phase One Systems



enhanced XIOS. The CP/M based System 2800 provides improved diagnostic reporting capability and increased sector sizes of 1024 bytes yielding disk performance throughput increases up to 400% over standard unblocked systems.

The enhanced multi-user, multi-tasking MP/M based System 2800 provides the same advanced features as CP/M. In addition, this interrupt driven implementation can offer performance throughput increases up to 2000% thru extensive disk buffering for applications requiring a large number of disk accesses.

Also available is the OASIS operating system with ISAM files, automatic record locking and multiple-user print spooling.

All operating systems are available in either floppy or hard disk configurations. The disk drive selection includes single or double sided, double density 8-inch floppies with up to 2.52 megabytes of formatted storage per system, expandable to 5.04 megabytes, and an 8-inch 10 megabyte winchester hard disk.

Cost Effective Reliability

Dealers, OEM's and System Integrators share many common needs. Not the least of these is dependable products. That's why we back our System 2800 with our established reputation for high quality products, superior support, prompt and courteous service, and a one-year warranty.

Take the next logical step. See your nearest computer dealer, or contact us for the complete story on our S-100 family of board products and enhanced systems.

Systems Group

A Division of MEASUREMENT systems & controls incorporated

1601 Orangewood Ave.
Orange, Calif. USA 92668
(714) 633-4460 TWX/TELEX: 678 401 TAB IRIN

For International Sales Inquiries contact: SIGMA INTERNATIONAL, INC., P.O. Box 1118, Scottsdale, AZ 85252 USA (602) 994-3435 / Telex 165 745 Sigma

Introducing 4 new programs from the

These new programs are going to do for you just what our VisiCalc™ program has done: make your computer work harder, so you can work smarter!

They'll enable a personal computer to take over more of those tasks eating up so much of your time. That'll give you more time to concentrate on the tasks where your skills, experience and intuition can do the most good. Things like thinking, planning and managing.

A personal computer can help you do all these things better. And Personal Software™ programs will help you do them best!

VisiDex. The VisiDex™ program makes it a snap for you to remember anything, and everything, you don't want to forget.

It's a free-form personal filing program with nearly unlimited cross referencing.

VisiDex "thinks" and "remembers" just the way you ask it to—so you can access it anyway you want, and find exactly what you want—instantly!

VisiPlot. The VisiPlot™ program makes it easy to see what your numbers really say.

It adds real meaning to financial analysis, forecasting, budgeting and business planning. Because VisiPlot takes hard-to-grasp numbers and automatically turns them into easy-to-comprehend charts and graphs, right before your eyes!

All kinds of charts and graphs, with all kinds of flexibility in titling, shading, and color—all at the touch of a few buttons!

Ask your favorite retail computer dealer for a demonstration of the Personal Software programs.

HOW TO WORK SMARTER NOT HARDER

people who brought you VisiCalc!

VisiTrend/VisiPlot. If you want sophisticated trend forecasting and statistical analysis—and you know how hard it is to create them by hand—you'll want to get your hands on the VisiTrend/VisiPlot™ program!

This program will enable you to rapidly perform regressions and time series analysis, plus providing you with comprehensive charting and graphing capabilities.

VisiTerm. The VisiTerm™ program enables you to reach out to the world.

With VisiTerm, you'll be able to use your personal computer to communicate with larger computers, to tap into data networks, to communicate with other personal computers.

VisiTerm gives you all the benefits of a personal computer, plus all the advantages of an intelligent terminal, all in one package.

All of these programs are currently available for the Apple II and II Plus. Besides their many individual benefits, these new programs deliver an even greater total benefit. That's because many of them interact with each other and with our new, enhanced version of VisiCalc.

Together, they give you an unprecedented family of personal computing capabilities; making the computer work harder, so you can work smarter!

PERSONAL SOFTWARE INC.

Or call us at (408) 745-7841 for the name of the Personal Software dealer nearest you. Or write us at 1330 Bordeaux Drive, Sunnyvale, CA 94086.

Circle 314 on inquiry card.

Text continued from page 26:
calculate standings, and make pairings for each new round. The program ran on a Radio Shack Model III TRS-80 lent to us by the local Radio Shack retailer.

We also received generous assistance from many others. BYTE Publications offered a prize of an autographed, bound set of its early volumes. The Computer Room, a retail establishment in nearby Scotts Valley, provided two Commodore PET computers for the weekend. One of these machines was used to run the program of our most distant entrant, Anders Kierulf, who was competing by proxy from the University of Zurich in Switzerland. Members of the local Apple and TRS-80 users' groups also volunteered their assistance. Several ran programs for entrants who could not be at the tournament site.

Photo 1: *Peter Frey, the author, waits patiently for his TRS-80 to calculate its next move.*

Photo 2: *Dan and Kathe Spracklen record the move of Larry Atkin's machine as he reaches for the chess clock.*

To accommodate individuals operating from large machines at distant locations, six of my colleagues at UCSC donated the use of their offices and telephones for the weekend. This arrangement avoided the considerable expense of installing telephones in the main tournament room and also provided some unexpected entertainment. Prior to the tournament, we had completed a university requisition to obtain keys for each office. On the first day of the tournament, I assigned office keys to each of the mainframe participants so that their terminals and modems would be secure. Imagine my chagrin when I learned that most of these keys did not work. The weekend was only a few hours old, and already some of the participants were starting to wonder if the tournament organizer had all of his marbles in the right place. A hastily discovered master key saved us.

Having six participants located in faculty offices away from the main tournament room also led to some logistical complications. When a microcomputer was paired with a mainframe, it was a simple matter to move the microcomputer into the proper office. When two mainframes were paired, the solution was not so easy since each was anchored to a telephone outlet. The problem was eventually solved by borrowing a few tricks from the ancient Greeks. Spectators who had dropped by to see this curious event were treated to a modern version of the marathon. Moves were relayed from one office to another, sometimes located on different floors, by messengers running as fast as possible. The spectators, I am sure, were impressed by our brilliant use of modern technology.

The tournament involved a David versus Goliath theme as well. Not only were lowly TRS-80s matched against large systems like the Control Data Cyber 170/730 and the Univac 11/40, but many first-time competitors found themselves sitting across the table from computer

Easy on your eyes and your budget.







This high quality professional computer monitor provides sharp, clear display of up to 80 characters by 25 lines of text, making it ideal for word processing as well as standard business applications.

Lightweight industrial grade construction gives maximum portability with reliable operation.

Color monitor also available for Apple,® Atari® and other popular computers. See your authorized NEC America Dealer.

Apple is a registered trademark of Apple Computer, Inc.
Atari is a registered trademark of Atari Inc.

80 character display makes it ideal for word processing and scientific applications.

NEC

NEC America, Inc.
1401 Estes Avenue
Elk Grove Village, IL 60007

Rank	Author(s)	Affiliation	Representative at Tournament Site	Hardware	Programming Language	Wins-Losses
1	Paul Rosenbloom	Carnegie-Mellon Univ Pittsburgh PA	Kate Rosenbloom	DEC KA10	SAIL	8-0
2	Charles Heath	Instant Software Peterborough NH	author	Model I TRS-80	Assembler	7-1
3	Dan and Kathe Spracklen	Fidelity Electronics Miami FL	authors	4 MHz 6502	Assembler	7-3
4a	Peter Frey	Northwestern Univ Evanston IL	author	Model I TRS-80	Assembler	7-4
4b	Larry Atkin Peter Frey	Applied Concepts Garland TX	Larry Atkin	2 MHz 6502	Assembler	5-4
6	Stephen Cheng	DataSoft Inc San Jose CA	author	Model I TRS-80	Assembler	4-4
7	Anders Kierulf	Univ of Zurich Zurich, Switzerland	Stuart Hastings	Commodore PET	Assembler	5-4
8	Rob Phillips	Univ of Maryland College Park MD	James Morgan	Univac 11/40	Pascal	5-4
9a	Douglas Larson Paul Gootherts	Hewlett-Packard San Jose CA	authors	HP-1000	FORTRAN	4-4
9b	Bill Tomlinson Mark Faron Chris Gates	California State Univ, Northridge	authors	CDC CYBER 170/730	BASIC	4-4
11	Richard Adams	Data General Dayton OH	author	C/330 Eclipse	Pascal	4-3
12	David Levy Kevin O'Connell	Philidor Software London, England	authors	2 MHz 6502	Assembler	4-4
13	Nick Jacobs	Univ of California Berkeley CA	author	MODCOMP	BCPL	3-5
14	Michael Riley	AB Computers Montgomeryville PA	Ernest Maharenke	Commodore PET	Assembler	3-4
15a	Gerhard Ringel Dan Jones	Qantel Corporation Hayward CA	authors	Qantel System 220	Assembler	3-5
15b	Ron Burke	Summit NJ	Philip Manoff	Model I TRS-80	Assembler	3-5
17	Bill Kemper	Hewlett-Packard Corvallis OR	John Sechrest	HP-85	BASIC	2-6
18	Brian Redman Lynn Aston	Bell Telephone Labs, Whippany NJ	Brian Redman	VAX 11/780	C	2-6
19	Peter Frey	Northwestern Univ Evanston IL	Kurt Inman	Model I TRS-80	BASIC	1-5
20	Jack Decker	The Alternate Source Lansing MI	Greg Vaughan	Model I TRS-80	BASIC	1-7

Table 1: *Final standings for the Othello Tournament held at UCSC on January 17 and 18, 1981.*

luminaries such as Dan and Kathe Spracklen, David Levy, or Larry Atkin. These tournament regulars had ten times as much experience as everyone else combined. Despite this, several of the newcomers turned in impressive performances.

Tournament Rules

The tournament rules closely followed those adopted for human competition by the United States Othello Association (USOA). Each contestant was allowed a maximum of 30 minutes for each game and moves were communicated using standard USOA notation. Pairings in the first round were determined by a random process. This was necessary because many programs had not been used in tournaments or they had been modified extensively since their last public performance.

A modified Swiss procedure was used to make the pairings for all subsequent rounds. At the end of each round, all of the contestants were ranked on the basis of their won-lost records and by cumulative piece differential when records were equivalent. Matches were then slated between the programs in first and second place, third and fourth place, fifth and sixth place, and so on. When this led to a pairing between contestants who had already met, a modified set of pairings was prepared which approximated the initial plan as closely as possible. The Model III TRS-80 performed these contestant-juggling acts quickly and accurately. This system of pairings insured that each contestant met an opponent of relatively similar strength. Although this decreased the number of lopsided outcomes, the won-lost records did not accurately reflect the relative playing strength of each program.

After the planned eight rounds had been completed, five programs were tied with records of five wins and three losses. Tournament director Cerf arranged several playoff matches between contestants who could stay a few extra hours. The addition of these extra matches, plus the cancellation of several others because of telephone problems, led to an unequal number of matches for the different programs. To arrive at final rankings, we used a Guttman scaling technique, instead of more conventional procedures. This is an iterative

TRS-80* COMPUTING EDITION

 The Percom Peripheral 35 cents

Percom's DOUBLER II™ tolerates wide variations in media, drives

GARLAND, TEXAS — May 22, 1981 — Harold Mauch, president of Percom Data Company, announced here today that an improved version of the Company's innovative DOUBLER™ adapter, a double-density plug-in module for TRS-80* Model I computers, is now available.

Reflecting design refinements based on both theoretical analyses and field testing, the DOUBLER II™, so named, permits even greater tolerance in variations among media and drives than the previous design.

Like the original DOUBLER, the DOUBLER II plugs into the drive controller IC socket of a TRS-80 Model I Expansion Interface and permits a user to run either single- or double-density diskettes on a Model I.

With a DOUBLER II installed, over four times more formatted data — as much as 364 Kbytes — can be stored on one side of a five-inch diskette than can be stored using a standard Tandy Model I drive system.

Moreover, a DOUBLER II equips a Model I with the hardware required to run Model III diskettes.

(*Ed. Note:* See "OS-80™: Bridging the TRS-80* software compatibility gap" elsewhere on this page.)

The critical clock-data separation circuitry of the DOUBLER II is a proprietary design called a ROM-programmed digital phase-lock loop data separator.

According to Mauch, this design is more tolerant of differences from diskette to diskette and drive to drive, and also provides immunity to performance degradation caused by circuit component aging.



Percom DOUBLER II

Mauch said "A DOUBLER II will operate just as reliably two years after it is installed as it will two days after installation."

The digital phase-lock loop also eliminates the need for trimmer adjustments typical of analog phase-lock loop circuits.

"You plug in a Percom DOUBLER II and then forget it," he said.

The DOUBLER II also features a refined Write Precompensation circuit that more effectively minimizes the phenomena of bit- and peak-shifting, a reliability-impairing characteristic of magnetic data recording.

The DOUBLER II, which is fully software compatible with the previous DOUBLER, is supplied with DBLDOS™, a TRSDOS*-compatible disk operating system.

The DOUBLER II sells for ~~$219.95~~, including the DBLDOS diskette. NOW $169.95!

Owners of original DOUBLERs may purchase a DOUBLER II upgrade kit, without the disk controller IC, for $30.00. Proof of purchase of an original DOUBLER is required, and each DOUBLER owner may purchase only one DOUBLER II at the $30.00 price.

The Percom DOUBLER II is available from authorized Percom retailers, or may be ordered direct from the factory. The factory toll-free order number is 1-800-527-1592.

Ed. note: Opening the TRS-80 Expansion Interface may void the Tandy limited 90-day warranty. **Circle 309 on inquiry card.**

Circuit misapplication causes diskette read, format problems.

High resolution key to reliable data separation

GARLAND, TEXAS — The Percom SEPARATOR™ does very well for the Radio Shack TRS-80* Model I computer what the Tandy disk controller does poorly at best: *reliably* separates clock and data signals during disk-read operations.

Unreliable data-clock separation causes format verification failures and repeated read retries.

CRC ERROR–TRACK LOCKED OUT

The problem is most severe on high-number (high-density) inner file tracks.

As reported earlier, the clock-data separation problem was traced by Percom to misapplication of the internal separator of the 1771 drive controller IC used in the Model I.

The Percom Separator substitutes a *high-resolution* digital data separator circuit, one which operates at 16 megahertz, for the low-resolution one-megahertz circuit of the Tandy design.

Separator circuits that operate at lower frequencies — for example, two- or four-megahertz — were found by Percom to provide only marginally improved performance over the original Tandy circuit.

The Percom solution is a simple adapter that plugs into the drive controller of the Expansion Interface (EI).

Not a kit — some vendors supply an untested separator kit of resistors, ICs and other paraphernalia that may be installed by modifying the computer — the Percom SEPARATOR is a fully assembled, fully tested plug-in module.

Installation involves merely plugging the SEPARATOR into the Model I EI disk controller chip socket, and plugging the controller chip into a socket on the SEPARATOR.

The SEPARATOR, which sells for only $29.95, may be purchased from authorized Percom retailers or ordered directly from the factory. The factory toll-free order number is 1-800-527-1592.

Ed. note: Opening the TRS-80 Expansion Interface may void the Tandy limited 90-day warranty. **Circle 310 on inquiry card.**

All that glitters is not gold

OS-80™ Bridging the TRS-80* software compatibility gap

Compatibility between TRS-80* Model I diskettes and the new Model III is about as genuine as a gold-plated lead Krugerrand.

True, Model I TRSDOS* diskettes can be *read* on a Model III. But first they must be converted and re-recorded for Model III operation.

And you *cannot write* to a Model I TRSDOS*diskette. Not with a Model III. You cannot add a file. Delete a file. Or in any way modify a Model I TRSDOS diskette with a Model III computer.

Furthermore, your converted TRSDOS diskettes cannot be converted *back* for Model I operation.

TRSDOS is a one-way street. And there's no retreating. A point to consider before switching the company's payroll to your new Model III.

Real software compatibility should allow the *direct, immediate* interchangeability of Model I and Model III diskettes. No read-only limitations, no conversion/re-recording steps and no chance to be left high and dry with Model III diskettes that can't be run on a Model I.

What's the answer? The answer is Percom's OS-80™ family of TRS-80 disk operating systems.

OS-80 programs allow *direct, immediate* interchangeability of Model I and Model III diskettes.

You can run Model I single-density diskettes on a Model III; install Percom's plug-in DOUBLER™ adapter in your Model I, and you can run double-density Model III diskettes on a Model I.

There's no conversion, no re-recording.

Slip an OS-80 diskette out of your Model I and insert it directly in a Model III.

And vice-versa.

Just have the correct OS-80 disk operating system — OS-80, OS-80D or OS-80/III — in each computer.

Moreover, with OS-80 systems, you can add, delete, and update files. You can read *and write* diskettes regardless of the system of origin.

OS-80 is the original Percom TRS-80 DOS for BASIC programmers.

Even OS-80 utilities are written in BASIC.

OS-80 is the Percom system about which a user wrote, in Creative Computing magazine, ". . . the best $30.00 you will ever spend."†

Requiring only seven Kbytes of memory, OS-80 disk operating systems reside completely in RAM. There's no need to dedicate a drive exclusively for a system diskette.

And, unlike TRSDOS, you *can* work at the track sector level, defining and controlling data formats — in BASIC — to create simple or complex data structures that execute more quickly than TRSDOS files.

The Percom OS-80 DOS supports single-density operation of the Model I computer — price is $29.95; the OS-80D supports double-density operation of Model I computers equipped with a DOUBLER or DOUBLER II; and, OS-80/III — for the Model III of course — supports both single- and double-density operation. OS-80D and OS-80/III each sell for $49.95.

PRICES AND SPECIFICATIONS SUBJECT TO CHANGE WITHOUT NOTICE. PRICES DO NOT INCLUDE HANDLING AND SHIPPING.

PERCOM DATA COMPANY, INC. 211 N. Kirby Street Garland, Texas 75042 (214) 272-3421

™Trademark of Percom Data Company, Inc. *TRS-80 and TRSDOS are trademarks of Tandy Corporation which has no relationship to Percom Data Company. †Creative Computing Magazine, June, 1980, page 26.

process that attempts to order the contestants in a way that produces the greatest degree of transitivity. That is, each program should be able to defeat those below it in the standings and should lose to those above it. Our final standings, shown in table 1, closely approximate this goal in respect to the matches that were played in the tournament.

The Winners

The champion program was Iago, written by Paul Rosenbloom, a fifth-year graduate student in computer science at Carnegie-Mellon University in Pittsburgh. His DEC KA10 program performed remarkably well, defeating all opponents. In a tournament held six months earlier at Northwestern University, Paul's program placed third in the machine competition, finishing behind the Spracklens' program and my program. Since then, everyone had made major improvements. Paul had apparently learned more than the rest of us. Progress has been so substantial that any one of the top eight programs at Santa Cruz is probably strong enough to defeat the program that placed first at Northwestern. Paul could not be in Santa Cruz, so he vigilantly monitored the contests from Pittsburgh while his sister Kate, a professional programmer working in Mountain View, California, operated a terminal at UCSC.

Second place, and top microcomputer honors, was won by first-time competitor Charles Heath of Waltham, Massachusetts. After several playoff matches, the Spracklens placed third. Fourth place was shared by Larry Atkin and myself. Stephen Cheng from San Jose, another newcomer to the tournament circuit, came in sixth. Anders Kierulf, the Swiss entrant, finished seventh and Rob Phillips, who recently received his PhD from the University of Maryland, took eighth place.

One of the surprises of the tournament was the impressive showing of the microcomputers and hand-held electronic units. Devices based on the Zilog Z80 or the MOS Technology 6502 microprocessors finished in positions two through seven. The Cyber 170 entry tied for ninth place and the VAX 11/780 system came in 18th. All of the programs running on large machines were operated in time-sharing environments and this hindered their performance. In addition, these programs were compiled from high-level languages, while the microprocessor-based entries that placed well in the tournament were all written in assembly language. Some of the advantages of the larger machines, such as bigger word size or faster floating-point arithmetic, are not particularly important for Othello where most operations involve simple symbol manipulation.

Microprocessor-based units have also benefited from recent hardware improvements. For example, the 6502-based units entered by David Levy and Larry Atkin are designed to run at twice the speed of the Apple computer. The tournament version of the Spracklens' program used specially prepared hardware to run four

times as fast as the Apple. At this speed, the 6502 generates so much heat that a special cooling unit is required. The two strongest TRS-80 programs were also run at clock rates faster than Tandy intended. The unit as it comes from the factory runs its Z80 processor at 1.8 MHz, less than half the speed for which it was designed. There are several speed-up kits available commercially for the TRS-80, and these may be useful options for the serious chess or Othello player. I have been especially pleased with the reasonable price and reliable operation of the kit from Archbold Electronics.

Learning and Playing

Machine Othello programs are becoming good enough to make useful contributions to human play. In the endgame, computers can play perfectly, selecting a final sequence of moves that guarantees them the maximum final disk count. In this respect, they are as good or better than any human. Cerf has played several of these programs and reports that his endgame play has improved noticeably. This may be the first case in which a machine has become sufficiently proficient at a complex strategy game to serve as a useful sparring partner for the world champion.

Tournaments like the Santa Cruz Open provide a rigorous test for new software and the occasion for information exchange. Few programmers are eager to reveal their most important secrets, but one must divulge some information in order to get ideas from others. Santa Cruz was a great learning experience. It was comforting to discover that other apparently sane persons had been working day and night for months on their creations. The enjoyable camaraderie reinforces each one's belief that the shared enterprise is reasonable and worthwhile.

Othello seems to be rapidly overtaking chess as the most popular strategy game for computer programming. Eighteen months ago few serious Othello programs existed. Today there are more than two dozen, and the number is increasing at a rapid pace.

The keen interest in machine Othello reflects the inherent fascination of the game and its logical structure that facilitates programming. The game is conceptually complex and yet the move-generation and evaluation routines can be compact and architecturally aesthetic. The challenge of chess is there with fewer programming headaches. I expect that the current love affair between Othello and microcomputers will produce a long and happy marriage. Long before the final match was played at Santa Cruz, one question was asked by many: "When is the next tournament?"■

References

1. Frey, Peter W. "Simulating Human Decision-Making on a Personal Computer." July 1980 BYTE, page 56.
2. Maggs, Peter B. "Programming Strategies in the Game of Reversi." November 1979 BYTE, page 66.

Build a Z8-Based Control Computer with BASIC, Part 1

Steve Ciarcia
POB 582
Glastonbury CT 06033

I hope you believe me when I say that I have been waiting years to present this project. For what has seemed an eternity, I have wanted a microcomputer with a specific combination of capabilities. Ideally, it should be inexpensive enough to dedicate to a specific application, intelligent enough to be programmed directly in a high-level language, and efficient enough to be battery operated.

My reason for wanting this is purely selfish. The interfaces I present each month are the result of an overzealous desire to control the world. In lieu of that goal, and more in line with BYTE policy, I satisfy this urge by stringing wires all over my house and computerizing things like my wood stove.

There are many more places I'd like to apply computer monitoring and control. I want to modify my home-security system to use low-cost *distributed* control rather than central control. I want to try my hand at a little energy management, and, of course, I am still trying to find some reason to install a microcomputer in a car. (How about a talking dashboard?)

Generally, the projects I present each month are designed to be attached to many different commercially available microcomputers through existing I/O (input/output) ports. Most of my projects are applicable for use on the small (by IBM standards) computers owned by many readers, but, unfortunately, a typical home-computer system cannot be stuffed under a car seat.

The Z8-BASIC Microcomputer is a milestone in low-cost microcomputer capability.

The time has come to present a versatile "Circuit Cellar Controller" board for some of these more ambitious control projects. I decided not to adapt an existing single-board computer, which would be larger, more expensive, and generally limited to machine-language programming. Instead, I started from scratch and built exactly what I wanted.

The microcomputer/controller I developed is called the Z8-BASIC Microcomputer. Its design and application will be presented in a two-part article beginning this month. In my opinion, it is a milestone in low-cost microcomputer capability. It can be utilized as an inexpensive tiny-BASIC computer for a variety of changing applications, or it can be dedicated to specialized tasks, such as security control, energy management, solar-heating-system monitoring, or intelligent-peripheral control. [**Editor's Note:** *We are using the term "tiny BASIC" generically to denote a small, limited BASIC interpreter. The term has been used to refer to some specific commercially available products based on the Tiny BASIC concept promulgated by the People's Computer Company in 1975....* **RSS**]

The entire computer is slightly larger than a 3 by 5 file card, yet it includes a tiny-BASIC interpreter, 4 K bytes of program memory, one RS-232C serial port and two parallel I/O ports, plus a variety of other features. (A condensed functional specification is shown in the "At a Glance" text box.) Using a Zilog Z8 microcomputer integrated circuit and Z6132 4 K by 8-bit read/write memory device, the Z8-BASIC Microcomputer circuit board is completely self-contained and optimized for use as a dedicated controller.

To program it for a dedicated application, you merely attach a user terminal to the DB-25 RS-232C connector, turn the system on, and type in a BASIC program using keywords such as GOTO, IF, GOSUB, and LET. Execution of the program is started by typing RUN. If you need higher speed than BASIC provides, or if you just want to experiment with the Z8 instruction set, you can use the

GO@ and USR keywords to call machine-language subroutines.

Once the application program has been written and tested with the aid of the terminal, the finished program can be transferred to an EPROM (erasable programmable read-only memory) via a memory-dump program and the terminal disconnected. Next, the 28-pin Z6132 memory component is removed from its socket and either a type-2716 (2 K by 8-bit) or type-2732 (4 K by 8-bit) EPROM is plugged into the lower 24 pins. (The choice of EPROM depends upon the length of the program.) When the Z8 board is powered up, the stored program is immediately executed. *The EPROM devices and the Z6132 read/write memory device are pin-compatible.* Permanent program storage is simply a matter of plugging an EPROM into the Z6132's socket.

There is much more power on this board than is alluded to in this simple description. That is why I decided to use a two-part article to explain it. This month, I'll discuss the design of the system and the attributes of the Z8 and Z6132. Next month, I'll describe external interfacing techniques, a few applications, and the steps involved in transferring a program into an EPROM.



Photo 1: *A prototype of the versatile "Circuit Cellar Controller," formally called the Z8-BASIC Microcomputer. The printed-circuit board measures 4 by 4½ inches and has a 44-pin (two-sided 22-pin) edge connector with contacts on 0.156-inch centers. A 2716 or 2732 EPROM can be substituted for the Z6132 Quasi-Static memory, plugging into the same socket.*

Single-Chip Microcomputers

The central component in the Z8-BASIC Microcomputer is a member of the Zilog Z8 family of devices. The specific component used, the Z8671, is just one of them. Unlike a micro*processor*, such as the well-known Zilog Z80, the Z8 is a single-chip micro*computer*. It contains programmable (read/write) memory, read-only memory, and I/O-control circuits, as well as circuits to perform standard processor functions. Microprocessors such as the Z80 or the Intel 8080 require support circuitry to make a functional computer system. A single-chip microcomputer, on the other hand, can function solely on its own.

The concept is not new. Single-chip microcomputers have been around for quite a while, and millions of them are used in electronic games. The designers of the Z8, however, raised the capabilities of single-chip microcomputers to new heights and provided many powerful features usually found only in general-application microprocessors.

Typically, single-chip microcomputers have been designed for microcontroller applications and optimized for I/O processing. On a 40-pin dual-inline package, as many as 32 of the pins can be I/O related. A ROM-programmed single-chip microcomputer used in an electronic chess game might offer a thousand variations in game tactics, but it could not be reprogrammed as a word processor. The ability to reorient processing functions and reallocate memory has generally been the province of microprocessors, with their memory-intensive architecture.

The Z8 architecture (shown in figure 1a on page 40) allows it to serve in either memory- or I/O-intensive applications. Under program control, the Z8 can be configured as a stand-alone microcomputer using 2 K to 4 K bytes of internal ROM, as a traditional microprocessor with as much as 120 K to 124 K bytes of external memory, or as a parallel-processing unit working with other computers. The Z8 could be used as a controller in a microwave oven or as the processor in a stand-alone data-entry terminal complete with floppy-disk drives.

Getting Specific: The Z8671

The member of the Z8 family used in this project is the Z8671. This component differs from the garden-variety Z8601 chiefly in the contents of the ROM set at the factory. The pinout specification of the Z8671 is shown in figure 1b, and the package is shown in photo 2 on page 41. The Z8671 package contains the processor circuitry, 2 K bytes of ROM (preprogrammed with a tiny-BASIC interpreter and a debugging monitor), 32 I/O lines, and 144 bytes of programmable (read/write) memory.

The operational arrangement of memory-address space is shown in figure 1c. The internal read/write memory is actually a register file (illustrated in figure 2) composed of 124 general-purpose registers (R4 thru R127), 16 status-control registers (R240 thru R255), and 4 I/O-port registers (R0 thru R3). Any general-purpose register can be used as an accumulator, address pointer, index register, or as part of the internal stack area. The significance of these registers will be explained when I describe the tiny-BASIC/Debug interpreter/monitor.

The 32 I/O lines are grouped into four separate ports and treated internally as 4 registers. They can be configured by software for either input or output and are compatible with



Figure 1a: *Block diagram of the Zilog Z8-family single-chip microcomputers. Their architecture allows these devices to serve in either memory- or I/O-intensive applications. This figure and figures 1b, 1c, 2, 3, and 4 were provided through the courtesy of Zilog Inc.*



Figure 1b: *Pinout specification of the Zilog Z8671 microcomputer. The Z8671 is a variant of the basic Z8601 component of the Z8 family. The Z8671 is used in this project because it contains the BASIC/Debug interpreter/monitor in read-only memory. Other members of the Z8 family are supplied in different packages, chiefly to support system-development work.*

LSTTL (low-power Schottky transistor-transistor logic). In addition, port 1 and port 0 can serve as a multiplexed address/data bus for connection of external memory and peripheral devices.

In traditional nomenclature, port 1 transceives the data-bus lines D0 thru D7 and transmits the low-order address-bus signals A0 thru A7. Port 0 supplies the remaining high-order address lines A8 thru A15, for a total of 16 address bits. This allows 62 K bytes of *program* memory (plus 2 K bytes of ROM) to be directly addressed. If more memory is required, one bit in port 3 can be set to select another memory bank of 62 K bytes, which is referred to as *data* memory. In the Z8-BASIC Microcomputer presented here, a separate data-memory bank is not implemented, and program and data memory are considered to be the same.

The Z8 has forty-seven instructions, nine addressing modes, and six interrupts. Using a 7.3728 MHz crystal (producing a system clock rate of 3.6864 MHz) most instructions take about 1.5 to 2.5 μs to execute. Ordinarily, you would not be concerned about single-chip-microcomputer instruction sets and interrupt handling because the programs are mask-programmed into the ROM at the factory. In the Z8671, however, only the BASIC/Debug interpreter is preprogrammed. Using this interpreter, you can write machine-language programs that can be executed through subroutine calls written in BASIC. This feature greatly enhances the capabilities of this tiny computer and potentially allows the software to control high-speed peripheral devices. (A complete discussion of the Z8 instruction set and interrupt structure is beyond the scope of this article. The documentation accompanying the Z8-BASIC Microcomputer Board describes the instruction set in detail.)

The final area of concern is communication. The Z8 contains a full-duplex UART (universal asynchronous receiver/transmitter) and two counter/timers with prescalers. One of the counters divides the 7.3728 MHz crystal frequency to one of eight standard data rates. With the Z8671, these rates range between 110 and 9600 bps (bits per second) and are switch- or software-selectable.

A block diagram of the serial-I/O section is shown in figure 3. Serial data is received through bit 0 of port 3 and transmitted from bit 7 of port 3. While the Z8 can be set to transmit odd parity, the Z8671 is preset for 1 start bit, 8 data bits, no parity, and 2 stop bits. Received data must have 1 start bit, 8 data bits, at least 1 stop bit, and no parity (in this configuration).

Quasi-Static Memory

A limiting factor in small controller



Figure 1c: *The operational arrangement of memory-address space in the Z8 family. The regions labeled "program memory" and "data memory" may map to the same physical memory, or two separate banks may be used, selected through one bit of I/O port 3. The internal programmable (read/write) memory is a register file containing 124 general-purpose registers, 16 status-control registers, and 4 I/O-port registers.*



Figure 2: *An expanded view of the register-memory section of figure 1c, showing the organization of the register file. Any general-purpose register can be used as an accumulator, address pointer, index register, or as part of the internal stack area.*

designs has always been the trade-off between memory size and power consumption. To keep the number of components down and simplify construction, a designer generally selects a limited quantity of static memory. Frequently, the choice is to use two type-2114 1 K by 4 NMOS (negative-channel metal-oxide semiconductor) static-memory devices. In practice, however, the 1 K-byte memory size thereby provided is rather limited. It would be much better to expand this to at least 4 K bytes. Unfortunately, eight 2114 chips require considerably more circuit-board space and consume about 0.7 amps at +5 V. Not only would this make the design ill suited for battery power, it could never fit on my 4- by 4½-inch circuit board.

Another approach is to use dynamic memory, as in larger computers. Dynamic memory costs less, bit for bit, than static memory and consumes little power. Unfortunately, most dynamic-memory components require three separate operating voltages and special refresh circuitry. Adding 4 K bytes of dynamic memory would probably take about twelve chips. The advantages gained in reduced power consumption hardly justify the expense and effort.

The solution to this problem, surprisingly enough, also comes from Zilog, in the form of the Z6132 Quasi-Static Memory. The Z6132, shown in photo 4 on page 43, is a 32 K-bit dynamic-memory device, organized into 4 K 8-bit (byte-size) words. It uses single-transistor dynamic bit-storage cells, but the device performs and controls its own data-refresh operations in a manner that is completely invisible to the user and the rest of the system. This eliminates the need for external refresh circuitry. Also, the Z6132 requires only a +5 V power supply. The result is a combination of the design convenience of static memory and the low power consumption of dynamic memory. All 4 K bytes of memory fit in a single 28-pin dual-inline package, which typically draws about 30 milliamps.

An additional benefit in using the Z6132 is that it is pin-compatible with standard type-2716 (2 K by 8-bit) and type-2732 (4 K by 8-bit) EPROMs. This feature is extremely beneficial when you are configuring this Z8 board for use as a dedicated controller. As previously mentioned, the Z6132 can be removed and an EPROM inserted in the low-order 24 pins of the same socket. Thus, any program written and operating in the Z6132 memory can be placed in a

Text continued on page 44



Photo 2: *The Zilog Z8671 single-chip microcomputer, a member of the Z8 family of devices. This dual-inline package contains the processor circuitry, 2 K bytes of ROM, 32 I/O lines, and 144 bytes of programmable memory.*



Photo 3: *A photomicrograph of the silicon chip containing the working parts of a Z8 microcomputer.*

The following items are available from:
The MicroMint Inc
917 Midway
Woodmere NY 11598
Telephone:
(800) 645-3479 (for orders)
(516) 374-6793 (for technical information)

Z8-BASIC Microcomputer
Documentation includes:
Z8 Technical Manual, Z8 Product Specification
Z6132 Product Specification
BASIC/Debug Manual
Z8-BASIC Microcomputer Construction/Operator's Manual
Assembled and tested....$170
Kit....$140

Z8-BASIC Microcomputer power supply
(Size: 2⅞ by 4½ inches)
Provides: +5 V, 300 mA
+12 V, 50 mA
−12 V, 50 mA
Assembled and tested....$35
Kit....$27

All printed-circuit boards are solder-masked and silk-screened.
The documentation supplied with the Z8 board includes approximately 200 pages of materials. It is available separately for $25. This charge will be credited toward any subsequent purchase of the Z8 board.
Please include $4 for shipping and handling. New York residents please include 7% sales tax.



Photo 4: *The Zilog Z6132 Quasi-Static Memory device, shown with the hood up. This component stores 32 K bits in the form of 4 K bytes in invisibly refreshed dynamic-memory cells.*



Photo 5: *The Z8-BASIC Microcomputer Board attached to a power supply. Power can be supplied either through the separate power connector, as shown, or through the edge connector.*

At a Glance

Name
Z8-BASIC Microcomputer

Processor
Zilog Z8-family Z8671 8-bit microcomputer with programmable (read/write) memory, read-only memory, and I/O in a single package. The Z8671 includes a 2 K-byte tiny-BASIC/Debug resident interpreter in ROM, 144 bytes of scratchpad memory, and 32 I/O lines. System uses 7.3728 MHz crystal to establish clock rate. Two internal and four external interrupts.

Memory
Uses Z6132 4 K-byte Quasi-Static Memory (pin-compatible with 2716 and 2732 EPROMs); 2 K-byte ROM in Z8671. Memory externally expandable to 62 K bytes of program memory and 62 K bytes of data memory.

Input/Output
Serial port: RS-232C-compatible and switch-selectable to 110, 150, 300, 1200, 2400, 4800, and 9600 bps.
Parallel I/O: two parallel ports; one dedicated to input, the other bit-programmable as input or output; programmable interrupt and handshaking lines; LSTTL-compatible.
External I/O: 16-bit address and 8-bit bidirectional data bus brought out to expansion connector.

BASIC Keywords
GOTO, GO@, USR, GOSUB, IF...THEN, INPUT, LET, LIST, NEW, REM, RETURN, RUN, STOP, IN, PRINT, PRINT HEX. Integer arithmetic/logic/operators: +, −, /, *, and AND; BASIC can call machine-language subroutines for increased execution speed; allows complete memory and register interrogation and modification.

Power-Supply Requirements
+5 V ±5% at 250 mA
+12 V ±10% at 30 mA
−12 V ±10% at 30 mA
(The 12 V supplies are required only for RS-232C operation.)

Dimensions and Connections
4- by 4½-inch board; dual 22-pin (0.156-inch) edge connector. 25-pin RS-232C female D-subminiature (DB-25S) connector; 4-pole DIP-switch data-rate selector.

Operating Conditions
Temperature: 0 to 50°C (32 to 122°F)
Humidity: 10 to 90% relative humidity (noncondensing)



Figure 3: *Block diagram of the serial-I/O section of the Z8-family microcomputers. The Z8 contains a full-duplex UART (universal asynchronous receiver/transmitter). The data rates are derived from the clock-rate crystal frequency. Serial data is received through bit 0 of port 3 and is transmitted from bit 7 of port 3. An interrupt is generated within the Z8 whenever transmission or reception of a character has been completed.*



Photo 6: *The Z8-BASIC Microcomputer in operation, communicating with a video terminal (here, a Digital Equipment Corporation VT8E). A memory-dump routine, written using the BASIC/Debug interpreter, is shown on the display screen. The starting address of the dump is the beginning of the user-memory area; the hexadecimal values displayed are the ASCII (American Standard Code for Information Interchange) values of the characters that make up the first line of the memory-dump program.*

Text continued from page 41:
nonvolatile EPROM. (There are some limitations placed on the number of subroutine calls and variables allowed by this substitution because variable data and return addresses must be stored in the Z8's register area instead of in external read/write memory.)

Z8-BASIC Microcomputer

Figure 5 on pages 46 and 47 is the schematic diagram of the seven-integrated-circuit Z8-BASIC Microcomputer Board, shown in prototype form, with a power supply, in photo 5. IC1 is the Z8671 microcomputer, the member of the Z8 family that contains Zilog's 2 K-byte BASIC/Debug software in read-only memory. IC2 is the Z6132 Quasi-Static Memory, and IC3 is an 8-bit address latch. Under ordinary circumstances, the Z6132 is capable of latching its address internally, but IC3 is included to allow EPROM operation. IC4 and IC5 form a hard-wired memory-mapped input port used to read the data-rate-selection switches. IC6 and IC7 provide proper voltage-level conversion for RS-232C serial communication.

The seven-integrated-circuit computer typically takes about 200 milliamps at +5 V. The +12 V and −12 V supplies are required only for operating the RS-232C interface. Power required is typically about 25 milliamps on each.

The easiest way to check out the Z8-BASIC Microcomputer after assembly is to attach a user terminal to the RS-232C connector (J2) and set the data-rate-selector switches to a convenient rate. I generally select 1200 bps, with SW2 closed and SW1, SW3, and SW4 open. After applying power, simply press the RESET push button.

Pressing RESET starts the Z8's initialization procedure. The program reads location hexadecimal FFFD in memory-address space, to which the data-rate-selector switches are wired to respond. When it has acquired this information, it sets the appropriate data rate and transmits a colon to the terminal. At this point, the Z8 board is completely operational and programs can be entered in tiny BASIC.



Figure 4: *Block diagram of the Zilog Z6132 Quasi-Static Memory component. This innovative part stores 32 K bits in the form of 4 K bytes, using single-transistor dynamic random-access bit-storage cells, but all refresh operations are controlled internally. The memory-refresh operation is completely invisible to the user and the other components in the system. The Z6132 draws about 30 milliamps from a single +5 V power supply.*

(With the simple address selection employed in this circuit, the data-rate switches will be read by an access to any location in the range hexadecimal C000 thru FFFF. This should not unduly restrict the versatility of the system in the type of application for which it was designed.)

BASIC/Debug Monitor

I'll go into the features of the tiny-BASIC interpreter in greater detail next month, but I'm sure you are curious about the capabilities present in a 2 K-byte BASIC system.

Essentially an integer-math dialect of BASIC, Zilog's BASIC/Debug software is specifically designed for process control. It allows examination and modification of any memory location, I/O port, or register. The interpreter processes data in both decimal and hexadecimal radices and accesses machine-language code as either a subroutine or a user-defined function.

BASIC/Debug recognizes sixteen keywords: GOTO, GO@, USR, GOSUB, IF...THEN, INPUT, IN, LET, LIST, NEW, REM, RUN, RETURN, STOP, PRINT, and PRINT HEX. Standard syntax and mathematical operators are used.

The Z8 board is not my idea of what should be available; it is available now.

Twenty-six numeric variables, designated by the letters A thru Z, are supported. Variables can be used to designate program line numbers. For example, GOSUB B*100 and GOTO A*B*C are valid expressions.

In my opinion, the 2 K-byte interpreter is extremely powerful. Because it operates easily on register and memory locations, arrays and blocks of data can be easily manipulated.

(Full appreciation of the Z8-BASIC Microcomputer comes after a complete review of the operating manuals and a little experience. Documentation approximately 200 pages long is supplied with the unit; the documentation is also available separately.)

In Conclusion

It's easy to get spoiled using a large computer as a simple control device. I have heard of many inexpensive interfaces that, when attached to any computer, supposedly perform control and monitoring miracles. Frequently overlooked, however, is the fact that implementation of these interfaces often requires the software-development tools and hardware-interfacing facilities of relatively large systems. The Z8-BASIC Microcomputer, with its interpretive language, virtually eliminates the need for costly development systems with memory-consuming text editors, assemblers, and debugging programs.


SERIAL OUT (TTL)
SERIAL IN (TTL)
PORT 3
PORT 2
PORT 0
CONTROL
PORT 1
POWER
C4 0.1μF
+5V
10pF
CRYSTAL 7.3728MHz
10pF
IC1
Z8671
Z8 MICROCOMPUTER WITH BASIC/DEBUG
RESET
SERIAL OUT (P37)
SERIAL IN (P30)
VCC
XTAL2
XTAL1
A15
A14
A13
A12
A11
A10
A9
A8
R/W
DS
AS
A0/D0
A1/D1
A2/D2
A3/D3
A4/D4
A5/D5
A6/D6
A7/D7
+5V
IC2
Z6132
4K BY 8
PROGRAMMABLE (R/W) MEMORY
A11
AC
VSS
BUSY
VBB
CS
+12V SUPPLY
C7 10μF 25V
TYPICAL FOR 3
C8
-12V SUPPLY
+5V SUPPLY
C9
J1 CONNECTOR
JUMPERS
RAM
32K
16K
RAM
EPROM
C6 0.1μF
+5V



Number	Type	+5 V	GND	− 12 V	+ 12 V
IC1	Z8671	1	11		
IC2	Z6132	28	14		
IC3	74LS373	20	10		
IC4	74LS244	20	10		
IC5	74LS10	14	7		
IC6	MC1488		7	14	1
IC7	MC1489	14	7		

If you need a proportional motor-speed control for your solar-heating system, you don't have to dedicate your Apple II or shut off your heating system when you balance your checkbook. From now on, there is a small, cost-effective microcomputer specifically designed for such applications. The Z8 board described in this article is not my idea of what *should be* available; it *is* available now.

Next Month:

I will elaborate on interfacing and applications for the Z8-BASIC Microcomputer. ■

Acknowledgment

Special thanks to Steve Walters and Peter Brown of Zilog Inc for help in production of this article.

Editor's Note: *Steve often refers to previous Circuit Cellar articles as reference material for the articles he presents each month. These articles are available in reprint books from BYTE Books, 70 Main St, Peterborough NH 03458.* Ciarcia's Circuit Cellar *covers articles appearing in BYTE from September 1977 thru November 1978.* Ciarcia's Circuit Cellar, Volume II *presents articles from December 1978 thru June 1980.*

Figure 5: *Schematic diagram of the Circuit Cellar Z8-BASIC Microcomputer. Five jumper connections are provided so different memory devices can be used. For general-purpose use and program development, the 4 K-byte Z6132 read/write memory device will be used; for dedicated applications, two kinds of EPROMs can be substituted in the same integrated-circuit socket. Standard 450 ns type-2716 or type-2732 EPROM chips can be used. The connection labeled "32 K" should be closed if a type-2732 EPROM is installed; the connection labeled "16 K" should be closed for use of a type-2716 EPROM.*

The pull-up resistors adjacent to IC4 (the 74LS244 buffer) are contained in a SIP (single-inline package).

Harvesting the Sun's Energy

George E Mobus
3984 60th St #30
San Diego CA 92115

As the cost of fuel continues to skyrocket, more people are looking toward the sun to meet their energy needs. The potential use of solar energy for both heating and electric power generation is tremendous. By some estimates, energy from the sun could account for more than one-third of the nation's total energy needs by the year 2000. There are even more optimistic estimates that are based on technological "breakthroughs" such as the much-publicized solar space station. If solar energy can be "harvested" in outer space by a station in geosynchronous orbit, it can be beamed down to the earth's surface as low-power microwaves. In such a scenario, as much as 80% of our energy may come from the sun.

No doubt such highly developed systems for exploiting this vast, non-depletable energy source will come into play as the economics of energy production make solar-conversion technology more competitive with conventional, nonrenewable forms of fuel such as oil, gas, and coal.

The Collector

For most of us, however, the immediate use of solar energy will be to heat our homes and hot water. Already the technology exists for the conversion of sunlight into thermal energy at convenient temperatures and affordable costs compared to the fossil fuel alternative. The solar-energy collector most commonly used involves a thin plate of metal (usually copper, stainless steel, or, sometimes, aluminum) sealed behind a glass panel. A working medium (water, air, or antifreeze) passes behind it to carry away the heat. The plate is coated with a black, light-absorbing substance such as flat black engine paint. The *flatplate* collectors are connected in parallel by some appropriate ducting or tubing, mounted facing, generally, in a southerly direction. The fluid is circulated through the collectors and then to a storage device, usually a bed of pebbles for air systems or a tank of water for water-based systems. The heat contained in the storage devices is removed and circulated to the point of use by a thermostatically controlled recovery system.

As the engineering details of systems designs are becoming better understood, the technology is gaining wider acceptance. In areas with very high fuel costs, such as the Northeast and Midwest, the price of the hardware may, indeed, be a worthwhile investment. Solar collector panels are showing up now on rooftops all over the country. The best and most efficient collectors, however, are still far from inexpensive.

Orientation

It is very important that the collector be properly oriented in order to maximize the heat gain during the peak of the heating season. Unfortunately, every location has varying constraints such as the position of the house, sun availability, and heating-load periods. All of these must be taken into consideration when designing the system. Detailed information on the timing and amount of solar energy available for a specific location is required when designing a collector. Since the design process involves trade-offs, it would be helpful to be able to predict the gains and losses of alternative strategies, particularly when it comes to the placement of the solar collector array. The governing factor in orienting collectors is that the actual light that can be absorbed falls off as the cosine of the angle of incidence increases between the light beam and the collector surface. When the beam of light is exactly normal (perpendicular) to this surface, as it would be when the collectors face the sun directly, the cosine of the angle (zero degrees) is 1.0 and all of the light is available for conversion into heat. At angles more than zero degrees, the available light falls off, slowly at first, then more rapidly as the angle of incidence increases. It can be seen from this that the proper orientation of the collectors (ie: the tilt angle with respect to the horizontal and the azimuth angle with respect to due south) is extremely important. Of course, there are many important design criteria in addition to collector placement and orientation that will affect the overall performance of the system. However, how and where the collectors are placed are the most important factors contributing to the success of the system.

The program described in listing 1 was developed to assess various placement strategies. It is one of a series of programs that can help a designer make the best use of the sun's energy. In fact, this program uses a simulation model of the theoretical maximum amount of collimated (ie: direct) sunlight striking a tilted flat surface facing southward. The units of output are in Btus (British thermal units) per square foot per solar hour. A solar hour is actually an arc of 15° thru which the sun moves across the sky (360°/24 hours = 15°/hour). This will not always correspond precisely to the local time. The variance, however, will not cause significant errors in the calculations.

A table of values is printed for each

Text continued on page 52

datasouth announces...
THE TOTAL PRINTER PACKAGE!



With so many matrix printers on the market today, it may seem tough to find exactly the right one for your application. Some models may offer the speed you need, others the communications flexibility and still others the forms handling capability. But no printer offers **all** the features you need... until now.

The DS180 matrix printer provides the total package of performance features and reliability required for applications such as CRT slave copy, remote terminal networks and small to mid-range systems. Not a "hobby-grade" printer, the DS180 is a real workhorse designed to handle your most demanding printer requirements. And pricing on the DS180 is hundreds of dollars below competitive units.

High Speed Printing—Bidirectional, logic-seeking printing at 180 cps offers throughput of over 200 lpm on average text. A 9-wire printhead life-tested at 650 million characters generates a 9x7 matrix with true lower case descenders and underlining.

Non-volatile Format Retention—a unique programming keypad featuring a non-volatile memory allows the user to configure the DS180 for virtually any application. Top of form, horizontal and vertical tabs, perforation skipover, communications parameters and many other features may be programmed and stored from the keypad.When your system is powered down, the format is retained in memory. The DS180 even remembers the line where you stopped printing. There is no need to reset the top of form, margins, baud rate, etc.... it's all stored in the memory. If you need to reconfigure for another application, simply load a new format into the memory.

Communications Versatility—The DS180 offers three interfaces including RS232, current loop and 8-bit parallel. Baud rates from 110-9600 may be selected. A 1K buffer and X-on, X-off handshaking ensure optimum throughput.

Forms Handling Flexibility—Adjustable tractors accommodate forms from 3"-15". The adjustable head can print 6-part forms crisply and clearly making the DS180 ideal for printing multipart invoices and shipping documents. Forms can be fed from the front or the bottom.

If you would like more information on how the DS180's low-cost total printer package can fill your application, give us a call at Datasouth. The DS180 is available for 30-day delivery from our sales/service distributors throughout the U.S.

datasouth
computer corporation

4740 Dwight Evans Road • Charlotte, North Carolina 28210 • 704/523-8500

Listing 1: *Computer model that will calculate the daily solar flux on a flatplate solar-energy collector given the collector's latitude north or south, the tilt angle with respect to the ground, and azimuth angle with respect to true south. Written in BASIC-11 for use on a DEC PDP-11/V03 microcomputer, this program can be easily adapted to other versions of BASIC.*

```
SOLRA2                 MU BASIC/RT-11 V01-01C

1 REM  ************ PROGRAM TO COMPUTE AND PRINT ***********
2 REM  ************   THE DAILY SOLAR FLUX ON A   ***********
3 REM  ************      FLAT PLATE COLLECTOR     ***********
5 Z=SYS(6,81)
10 RESTORE
20 PRINT CHR$(26);
30 DIM I(11) \ F=PI/180
40 PRINT ,'TABLE OF BEAM RADIATION'
50 PRINT ,'    SOLAR ENERGY'
60 PRINT  \ PRINT
70 PRINT 'ENTER DATA IN DECIMAL VALUES AS REQUESTED.'
80 PRINT  \ PRINT 'LATITUDE'; \ INPUT L \ L=L*F
90 PRINT  \ PRINT 'TILT ANGLE'; \ INPUT T \ T=T*F
100 PRINT  \ PRINT 'AZIMUTH ANGLE'; \ INPUT A \ A=A*F
110 PRINT CHR$(26);TAB(28);'TABLE OF SOLAR RADIATION'
120 PRINT TAB(24)'BTU'S/SQ.FT.*HR. ON A FLAT SURFACE'
130 PRINT  \ PRINT 'DAY';TAB(33);'SOLAR HOUR'
140 PRINT 'OF';TAB(20);'AM';TAB(36);'NOON';TAB(56);'PM';TAB(74);'DAILY'
150 PRINT 'YEAR';TAB(7);'7';TAB(13);'8';TAB(19);'9';TAB(25);'10';TAB(31)
;'11';
160 PRINT TAB(37);'12';TAB(43);'1';TAB(49);'2';TAB(55);'3';TAB(61);'4';T
AB(67);'5';TAB(74);'TOTAL'
165 FOR I=1 TO 79 \ PRINT '='; \ NEXT I \ PRINT '='
170 FOR Q=1 TO 12
180 READ N \ D$=STR$(Q)+'/21' \ H=75 \ P=0
190 FOR B=1 TO 11
200 H1=H*F \ GOSUB 500 \ I(B)=I \ H=H-15 \ P=P+I(B)
210 NEXT B
220 B=6
230 PRINT D$; \ FOR Z=1 TO 11 \ PRINT TAB(Z*B);I(Z); \ NEXT Z \ PRINT TA
B(74);P
260 NEXT Q
270 PRINT 'END OF RUN' \ GO TO 1000
500 REM ****** SUBROUTINE TO COMPUTE **********
510 REM **** SOLAR INCIDENCE PER HOUR *********
520 I=429*(1+(.034*COS(360*N/365*F)))
530 D=23.45*SIN(360*(284+N)/365*F) \ D=D*F
540 S=SIN(L)*SIN(D)+(COS(L)*COS(D)*COS(H1))
550 M=SQR(1229+(614*S)^2)-(614*S)
560 IF M>94.976 THEN E1=0 \ GO TO 580
570 E1=EXP(-.65*M)
580 E2=EXP(-.095*M)
590 I=I*.56*(E1+E2)
600 C=SIN(D)*(SIN(L)*COS(T)-(COS(L)*SIN(T)*COS(A)))
610 C=C+COS(D)*COS(H1)*(COS(L)*COS(T)+(SIN(L)*SIN(T)*COS(A)))
620 C=C+COS(D)*SIN(T)*SIN(A)*SIN(H1)
630 I=I*C \ R=INT(I) \ O=I-R
640 IF O>.5 THEN I=R+1 \ GO TO 660
650 I=R
660 IF I<0 THEN I=0
670 RETURN
800 DATA 21,52,80,111,141,172,202,233,264,294,325,355
1000 END
```

IT WAS INEVITABLE

Sooner or later, someone had to take all this proven microcomputer hardware and software technology and wrap it up in a portable package at a price that shocks the industry. Adam Osborne decided to do it sooner.

The OSBORNE 1®, from Osborne Computer Corporation. You get full CP/M® disk computer capabilities—Z80A® CPU, 64K bytes of RAM memory, a full business keyboard, a built-in monitor, and two floppy drives with 100K bytes each of storage. You get two interfaces, the IEEE 488 and the RS-232C. Just connect a printer, via either interface.

Software? You get CP/M®, CBASIC-2®, Microsoft BASIC®, the WORDSTAR® word processing system with the MAILMERGE® mailing list feature, and the SUPERCALC® electronic spreadsheet package. All standard. All for $1795.



And it's *portable.* When the keyboard is clipped over the display panel, only the weatherproof plastic case is exposed. (There are even optional modem electronics, couplers, battery packs, and external monitor connections, providing practically unlimited system portability.)

It's all business. The OSBORNE 1 delivers *significant* productivity at an irresistable price. At $1795, it's immediate and lasting success as a personal business computer is, quite simply, inevitable.

$1795

OSBORNE

COMPUTER CORPORATION

26500 Corporate Avenue Hayward, California 94545 (415) 887-8080

Orders for the Osborne 1 Computer can be placed over the telephone at (415) 887-8080. Your order will be forwarded by the factory for delivery by your nearest authorized Osborne 1 dealer.

Circle 293 on inquiry card.

Text continued from page 48:
daytime solar hour (7 am to 5 pm) when the light intensity is high enough to be collectible. Representative days for each month are used to print out an hour-by-hour averaged value. The daily amount is totaled and printed in the rightmost column. This allows the comparison of the expected variance between months.

Modeling a System

The program was written in BASIC-11, the DEC (Digital Equipment Corporation) implementation of BASIC. This particular version is running under the RT-11 operating system on a PDP-11/V03 microcomputer. DEC's BASIC is general enough so that you should have little difficulty adapting the program to your own computer's particular dialect. The SYS(n,n) command in line 5 is used to set the print buffer to 81 characters (normal default is 72). CHR$(26), which appears in lines 20 and 110, is the ASCII (American Standard Code for Information Interchange) code for *clear screen* to the ADM-3A terminal that I used. You will want to replace this code with the equivalent control code for your terminal.

All of the numbers in the DATA statement are the sequentially numbered days of the year for the 21st day of each month (January 1 = day 1). The program RUN samples were done on a DECWRITER terminal. If your system has an addressable printer, you may want to include provisions for an LPRINT type option. And for those hardy souls who might want to convert the program to another language, I've included the mathematical equations in table 1. The model was derived from work presented by Kreith and Kreider in *Principles of Solar Engineering* (McGraw-Hill, New York, 1978).

Three major features in the placement of collectors (in addition to making sure they aren't shaded) affect the amount of solar energy available for conversion. Two of these—the tilt angle (T) and the azimuth angle (A)—are controllable in the design (see figure 1). The third, latitude (L), simply depends on where you live.

An easy way to find your latitude is to call the nearest airport. They can tell you precisely where *they* are, which is close enough for this calculation. Tilt angle is measured relative to the horizontal. An upright wall has a tilt angle of 90°. The azimuth angle is measured with respect to true (not compass) south, with degrees east given positive signs and degrees west of south given negative signs by convention.

In addition to the above controllable factors, there are several more that contribute to the determination of the intensity of sunlight on a collector surface. Hourly varia-

1. Solar incidence outside the earth's atmosphere (the solar constant) — I_o
   $I_o = 429(1 + .034\cos(360N/365))$ where N = day number
2. Solar declination — D
   $D = 23.45\sin(360(284+N)/365)$ N as above
3. Mass of air along the path of light — M
   $M = (1229 + (614 \sin\alpha)^2)^{1/2} - 614\sin\alpha$ where $\sin\alpha$(solar altitude) $= \sin L \sin D + \cos L \cos D \cos H$ where L = latitude, D as above, and H = solar hour angle
4. Solar incidence attenuated by the air mass — I_s
   $I_s = I_o \times 0.56(e^{-.65M} + e^{-.095M})$ where e = base of natural logarithm
5. Solar power on a tilted surface — I_p
   $I_p = I_s \cos i$ where i = angle of incidence
   where $\cos i = \sin D \sin L \cos T - \cos L \sin T \cos A$
   $+ \cos D \cos H \cos L \cos T$
   $+ \sin L \sin T \cos A$
   $+ \cos D \sin T \sin A \sin H$
   where T = tilt angle and A = azimuth (true south = 0)

Table 1: *These equations form the basis of the calculations performed in the author's computer model.*

tions are due, in part, to the distance of the light path through the atmosphere. The path is longer in the early morning and late afternoon, which is why we can watch sunsets and sunrises without burning our eyeballs. Even more important, however, is the fact that the amount of light reflected back from the flat surface increases as the angle of incidence increases. This results in the cosine factor mentioned previously. This fact has prompted some designers to develop special mounting systems for tracking the sun across the sky, thus keeping the collector surface always pointing directly toward the sun. While this will increase the solar power considerably, it also increases cost and mechanical complexity. These increased expenses must be considered carefully for home heating applications.

Monthly variation in daily totals is due to several factors. First, though of lesser importance, is the fact that the earth's orbit around the sun is elliptical; hence, the sun is farther away when the planet is at its apogee. But the major factor is the tilt of the planet with respect to the plane of its orbit. Viewed from the planet's surface, this is perceived as the difference in the sun's altitude between June 21 and December 21, the summer and winter solstices. The sun is lower in the winter sky and, since this is the heating season, the typical design strategy calls for tilting the collector array so that the beam radiation at solar noon on the coldest days of the year (usually January) is almost perpendicular to the surface of the collectors—if the array is used for space heating. If the system is to provide domestic hot water, the collectors must be tilted to split the difference between the two seasons.

The Weather

Finally, there is the age-old variable that can't be predicted, but that has a major impact on the light availability — the weather. The table of hourly radiation produced by this program cannot provide a prediction of how the local cloud cover will attenuate the sunshine. However, if the monthly cloud-cover factors for your area have been tracked for the past twenty years or so, then they can be used to modify the data in the table. The table provides the theoretical "clear day" values. The daily totals for the month can be multiplied by the percent of cloud cover averaged over the past years for that month and by the number of days in the month to get a fair picture of the probable light availability. (As it turns out, the values predicted by this model for clear-day radiation have been verified by empirical methods to within a very small deviation.)

Application

The model has several uses in designing a solar collector. Primarily, you will want to know how much sunlight your area could produce. Suppose your house is oriented such that the section of roof on which you want to mount the collectors faces

Text continued on page 58



Figure 1: *Diagram of the various solar angles used in calculating the total beam energy striking a roof-mounted solar collector.*

STRUCTURED SYSTEMS FINANCIAL SOFTWARE.

ANYTHING LESS IS CHEATING YOUR OWN BUSINESS.



Penny wise and software foolish. One of the best ways to cheat your business is to waste a whole lot of time on solutions that don't work, or that can't grow with your business. And frankly, we get phone calls every day from computer users who've tried to get by on "bargain" software, and found that "bargain" software is the most expensive kind a business can own.

Here's a fact: if you have a real need for a computer in any of these areas:

General Ledger
Accounts Receivable
Accounts Payable
Order Entry
Inventory Control
Payroll,

any business software less than Structured Systems Financial Software is cheating your business. You'll cheat yourself out of lots of time. Time spent with systems which aren't designed for high volume use. You'll cheat yourself out of reliable audit controls and reliable error prevention features. Out of the training you invest in a system you outgrow when you need to add more disk storage, more customers, more data. You'll be cheating yourself out of a software bargain in the truest sense of the word—the greatest value for your dollar.

CP/M® microcomputer systems can do the job of minicomputers. Structured Systems software makes that potential a reality. Right now, hundreds of businesses are profiting from the financial controls and operating efficiency of SSG financial software. So can yours.



Take it easy on yourself. But sentence your computer to hard labor.

Please send more information on your

☐ General Ledger ☐ Accounts Receivable ☐ Order Entry
☐ Accounts Payable ☐ Payroll ☐ Inventory Control

Name __________
Company __________
Address __________
City State Zip __________
Telephone ( ) __________

CP/M is a registered trademark of Digital Research.

Structured Systems Group INCORPORATED

5204 Claremont, Oakland, California 94618 (415) 547 1567

Circle 369 on inquiry card.

Listing 2: *Sample data obtained by running the program in listing 1. It shows the solar energy that would strike a collector mounted directly on the author's roof. In this case, the roof and the collector have an azimuth of 10°, a tilt with respect to the ground of 18°, and a latitude of 32.5° north. The energy, given in Btus per square foot per hour, is calculated for each daylight hour on the the 21st of each month.*

```
RUN

SOLRA2   13-OCT-80   MU BASIC/RT-11  V01-01C

                 TABLE OF BEAM RADIATION
                     SOLAR ENERGY


ENTER DATA IN DECIMAL VALUES AS REQUESTED.

LATITUDE? 32.5

TILT ANGLE? 18

AZIMUTH ANGLE? 10
                              TABLE OF SOLAR RADIATION
                          BTU'S/SQ.FT.*HR. ON A FLAT SURFACE
```

DAY OF YEAR	7	8	AM 9	10	11	SOLAR HOUR NOON 12	1	2	PM 3	4	5	DAILY TOTAL
1/21	5	70	140	197	233	243	226	184	123	55	2	1478
2/21	27	99	174	235	273	283	264	220	155	80	16	1826
3/21	51	129	206	268	306	316	297	251	184	106	33	2147
4/21	72	152	227	286	323	332	314	270	205	127	51	2359
5/21	85	161	232	288	322	331	313	272	211	137	62	2414
6/21	88	163	232	286	318	327	310	270	211	139	66	2410
7/21	84	160	231	286	320	329	311	270	209	136	62	2398
8/21	72	150	225	284	319	329	311	267	203	126	51	2337
9/21	50	128	204	265	303	312	294	249	183	105	33	2126
10/21	25	97	171	231	268	278	260	216	151	78	15	1790
11/21	4	69	137	195	231	240	223	181	121	54	2	1457
12/21	1	58	125	181	216	226	209	168	109	45	0	1338

```
END OF RUN

READY
```

Listing 3: *In this sample, the collector on the author's roof has been optimally mounted so that it faces directly south (zero azimuth) and is tilted at a more optimum angle (47.5°). Note that the solar energy striking the collector has increased about 27%.*

```
RUN

SOLRA2   13-OCT-80   MU BASIC/RT-11 V01-01C

                  TABLE OF BEAM RADIATION
                      SOLAR ENERGY


ENTER DATA IN DECIMAL VALUES AS REQUESTED.

LATITUDE? 32.5

TILT ANGLE? 47.5

AZIMUTH ANGLE? 0
                              TABLE OF SOLAR RADIATION
                          BTU'S/SQ.FT.*HR. ON A FLAT SURFACE
```

DAY OF YEAR	AM 7	AM 8	AM 9	AM 10	11	SOLAR HOUR NOON 12	1	2	PM 3	PM 4	PM 5	DAILY TOTAL
1/21	8	93	173	239	281	296	281	239	173	93	8	1884
2/21	32	111	191	257	300	314	300	257	191	111	32	2096
3/21	42	118	196	261	303	317	303	261	196	118	42	2157
4/21	40	112	185	245	284	298	284	245	185	112	40	2030
5/21	33	100	168	223	260	272	260	223	168	100	33	1840
6/21	29	94	159	213	247	259	247	213	159	94	29	1743
7/21	33	99	166	221	257	269	257	221	166	99	33	1821
8/21	40	111	183	242	281	294	281	242	183	111	40	2008
9/21	42	117	194	258	299	313	299	258	194	117	42	2133
10/21	31	109	188	254	296	311	296	254	188	109	31	2067
11/21	7	92	171	237	279	293	279	237	171	92	7	1865
12/21	1	83	163	228	270	284	270	228	163	83	1	1774

```
END OF RUN

READY
```

Text continued from page 54:

10° east of due south. Furthermore, you would like to mount the collectors flush on the roof, to keep a low profile. Let's say the roof has an 18° tilt. If you should happen to live in San Diego, as I do, your latitude is approximately 32.5° (use decimal values for all minutes of arc). By plugging these values into the keyboard when requested, you should get an output such as listing 2.

If you can determine how much heat you need to keep warm during January, by doing heat-load calculations on your home, then you can estimate how much collector surface area you'll need. Incidentally, don't forget a factor for thermal efficiency. In many states, each collector manufacturer is required to state a standardized rating for its product. This factor modifies considerably the performance of the collectors in absorbing the available sunlight.

Now, if you want to determine how much more light you might get with a more "ideal" orientation, try plugging in some alternatives. One rule of thumb for the optimal tilt angle is to add 15° to the latitude—so let's try a tilt angle of 47.5° (32.5 + 15 = 47.5). Due south is 0° azimuth. And, of course, you can't change the latitude unless you move your house, so that remains 32.5°. The resulting output is shown in listing 3. Notice the difference in the values for January between the two mounting strategies. You've gained a whopping 406 Btus per square foot for the day; that's approximately a 27% increase. Now, you have to decide if it's worth forgoing the low profile to gain that much more heat. For one thing, it means you will be able to reduce the amount of collector surface by 27%. Since the collectors are the single largest cost factor in a typical installation, it might be worth it!

Play around with the model to generate various schemes. If nothing else, you can give your friends their very own, personalized printout of the solar energy they could be enjoying.

A final word of caution about this model. As with any model, simplifying assumptions have been made. The numbers represent theoretical maximums only and can in no way predict the actual performance of a particular solar system installation, so they must be interpreted with care. Use the program for comparing strategies. Who knows, it may help you find a way to beat the escalating cost of energy, or at the very least, you can snub your nose at OPEC! ■

NEVER UNDER$OLD.

Thats right. If you can find a lower price in this magazine WE WILL BEAT IT! Period.*

S-100 HARDWARE

SD SYSTEMS
- Versa Floppy I kit $259
- Versa Floppy II kit $349
- ExpandoRam II kit $249

ITHICA INTERSYSTEMS .... $CALL
ALTOS .... $CALL
NORTHSTAR .... $CALL

SUPPLIES

Verbatim Datalife Diskettes
MD525-01,10,16 .... $26.50
FD34-9000 .... $30.00
FD34-8000 .... $44.00

Avery Tabulables
5,000 3½ X 15/16 ...... $18.75
3,000 3½ X 15/16 ...... $14.25
1,000 3½ X 15/16 .... $8.15

UARCO Paper (prices are FOB S.P.)
9½ X 11, 15 or 18 Lb. $25.95
14 7/8 X 11, 15 or 18 Lb. . $35.00

SOFTWARE

Microsoft Basic-80 .... $299
Microsoft Basic Compiler $319
Microsoft Fortran-80 .... $399
Magic Wand $275
Apple Visicalc $113
Pickles and Trout CP/M® $175

APPLE HARDWARE

Microsoft Z-80 Softcard . $259
Microsoft Ramcard $170
SSM AIO A&T $165
SYMTEC Apple Light Pen . $219
MOUNTAIN HARDWARE:
- Super Talker $270
- ROMWRITER $157
- INTROL/X-10 .... $180
- ROMPLUS + ... $162
- MUSICSYSTEM $499
- Apple Clock $252

Lobo Drive .... $CALL
Videx 80 x 24 .... $299
Andromeda $170
M & R Sup-R-Term $299
Enhancer $100
NEC Green Monitor $240
Sanyo Green Monitor $240
D.C. Hayes Micromodem . $299
CALIFORNIA COMPUTER SYSTEMS
See our full page ad in this magazine.

PRINTERS

EPSON MX-80 .... CALL
MX-80 Graphics ROM ... CALL
NEW EPSON MX-80 TF .. CALL
Okidata Microline 80 .... $415
Okidata Microline 82 .... $625
Okidata Microline 83 .... $899
IDS Paper Tiger 460G .. $1050
Anadex DP-9000,1 .... $1195
Anadex DP-9500,1 .... $1295
Centronics 737 .... $689
NEC Spinwriter .... $CALL
NEC w/ Sellum Option ... $CALL
C. Itoh Starwriter 25 cps $1440
C. Itoh Starwriter 45 cps $1770
Diablo 630 .... $2195
Malibu 165 .... $1995
Malibu 200 .... $CALL
MPI 88G $495

TRS-80 HARDWARE

TRS-80's .... $CALL
Micropolis 77 track $399
Percom Doubler $199
Percom Separator $27
Orchestra 80 .... $79

ALPHA BYTE STORES

5115 Douglas Fir Road • Suite B • Calabasas, CA 91302

*Include $2.00 shipping and handling on all orders. Visa and Master Card accepted. Never undersold offer applies only to items currently deliverable from other retail vendors at advertised price. All never undersold offers good as supply lasts. Please add $2.00 for all COD orders. Please call for items not listed. We gladly answer any questions on all of our hardware, software, and supply needs. Quanitity discounts available. School purchase orders accepted. Please remember to figu competitors shipping and handling charges when arriving at never undersold price.

(213) 883-8594

Mountain Computer's MusicSystem

Robin B Moore, Warner Hill Rd, RFD 5, Derry NH 03038

You've probably heard them at computer shows or in the local computer store—the music synthesizer peripherals that, along with your Apple II computer, can help you "compose," "turn your Apple into a family music center," or offer "flash and crash sound effects." Six or seven music synthesizers are already available for the Apple II, and in this article we'll examine the most significant new entry into the marketplace—the Mountain Computer MusicSystem—and see how it compares with the competition.

Mountain Computer (formerly Mountain Hardware) is a well-known manufacturer of high-quality Apple peripheral products that have been well received by the Apple-user community. Mountain Computer's products have never been cheap, and the MusicSystem is no exception. At $545 it is one of the more expensive music synthesizers available for the Apple II, and yet, when its capabilities are considered, it costs less than some of the lower-priced units. No other Apple synthesizer on the market offers sixteen programmable waveforms, and the most popular "square-wave" unit, the ALF AMS (by ALF Products, of Denver, Colorado) can cost as much as $795 when expanded to its maximum (nine voices).

Unlike many of the less-expensive music boards that are available for the Apple II, the MusicSystem is a true synthesizer in the sense that a Moog or an ARP is a synthesizer. The user can not only specify the frequency and the amplitude envelope for each note, but also the waveform, waveform variation (within certain limits), and frequency variations during each note. This allows for a simulation of real instrument sounds that is impossible to achieve with a fixed-waveform music board.



Photo 1: *The MusicSystem circuit boards with light pen and stereo outputs. The boards may occupy any two adjacent expansion slots, except slot 0, in the Apple II.*

The MusicSystem

The MusicSystem is a combined package of hardware and software that allows the user to enter and edit musical scores, to create and edit instrument definitions, and to combine both scores and instruments into PLAY files that produce the final musical output. Some of the pertinent MusicSystem features and specifications are:

- 16 programmable waveform generators (or oscillators)
- 31 KHz sample rate that gives a 13 KHz output frequency bandwidth
- Frequency resolution of 0.5 Hz
- Stereo audio outputs with up to eight waveforms (voices) per output
- Assignment of voices to either right, left, or both stereo speakers
- An integral light pen that is user-accessible for use with other programs
- Music entry and display on Apple high-resolution screen using the light pen, keyboard, or game paddles
- Use of *standard* music notation throughout the music editor portion of the system
- Multiple editing menus in high-resolution graphics to allow use of all the editing features without having to remember commands
- Part-by-part graphic printout of music scores on Apple's Silentype printer (other printers not yet supported)
- User definition of instrument waveforms, amplitude envelopes, and frequency histories
- Polyphony (chords) within a single part or through the use of multiple parts and multiple instruments
- Interrupt-driven software that allows foreground/background mode operation so that two programs can run concurrently
- The capability to merge COMP (composition) files with the Music Merger program so that extra-long scores can be created
- DMA (direct memory access) to waveform tables stored in the Apple's memory

Many of the features incorporated into the MusicSystem can be found in existing products, but for the price the combination of features and capabilities is unique.

The MusicSystem package consists of two printed-circuit boards, two double-sided disks of software and demonstration files, and a comprehensive manual. The two circuit boards (see photo 1) are interconnected and designed to occupy any two adjacent Apple II expansion slots (except slot 0). The MusicSystem searches for them automatically wherever they are installed. A light pen and the stereo output jacks are preconnected to the boards, and their cables emerge through the slots in the back of the Apple's case.

At a Glance

Name
Mountain Computer MusicSystem

Type
Music composition/synthesis system

Manufacturer
Mountain Computer
300 Harvey West Blvd
Santa Cruz CA 95060
(408) 429-8600

Price
$545

Hardware
Two interconnected PC boards designed to occupy two adjacent expansion I/O slots in the Apple II; includes a light pen and stereo audio outputs suitable for external amplification or headphones with RCA phono plugs

Software
Four disk sides consisting of four main programs, various overlays, and four types of files; demonstration music and some predefined instruments are included

Language
Software is written in a combination of 6502 assembly language and XPLO (a block-structured, Pascal-like language); object code only is included

Software Format
Disks are provided in Apple's DOS 3.2 format; they are not protected, however, and may be converted to DOS 3.3 with Apple's Muffin program

Computer
Apple II or Apple II+ with 48 K bytes of programmable memory and at least one disk drive with Apple's DOS 3.2 or DOS 3.3 operating system

Documentation
Comprehensive manual that describes operations and provides many walk-through examples; additional sections describe installation, background theory, user interface and software file structures

Audience
Any Apple II owner who would like a flexible, high-quality music synthesis system

The Light Pen

At first glance, the most unusual feature of the MusicSystem is the light pen. The light pen is used to make menu selections, either from the main system menus or from the various editor menus. Due to its limited resolution, the pen is not used to enter music; this must be done with either the keyboard or the game paddles. The pen is very effective when used with the Music Editor, for it provides a quick means of selecting items from the various graphic editor menus. Mountain Computer has thoughtfully provided information that describes how to access the pen so that you can experiment and use it with other software.

The light pen is accessed by the software as a single bit in one of the MusicSystem hardware registers. The state of the pen bit simply indicates whether or not the pen is picking up light. The software recognizes use of the light pen by detecting the 60 Hz flicker from the monitor screen. Once the flicker is detected, the program blinks each allowable portion of the screen until the blink is recognized by the pen. (This is the same technique used by some of the very inexpensive light pens that plug into the Apple's game-paddle connector.)

Hardware Flexibility

It takes a while to really appreciate the extreme flexibility inherent in the hardware design. The MusicSystem boards can produce sixteen simultaneous waveforms, each with independent control of amplitude, frequency, and waveshape. A master volume control affects all sixteen waveform generators.

Each waveform is generated from a 256-byte waveform table stored in the Apple's memory. These tables can be created either with the Instrument Definer program or, as shown in the manual, with a user-written program. The MusicSystem boards read values out of the waveform tables by using DMA. When the system is playing music, the tables are accessed by the MusicSystem boards about 500,000 times per second, and so the Apple's 6502 microprocessor is effectively slowed from 1 MHz to 500 KHz (MusicSystem takes half of the available memory cycles). Even though the processor has been slowed down, it can still run normal software, and the speed difference is rarely noticeable. This use of DMA is the key to the MusicSystem's high performance: the technique is not used by any other Apple music synthesizers, although the Casheab synthesizer for the S-100 bus has similar capabilities. (See reference 1.)

Each waveform generator on the MusicSystem boards has software loadable registers that specify amplitude, waveform-table address, and frequency. There are also registers that control overall volume, access the light pen and random-number generator, and enable or disable the DMA and interrupts. Again, Mountain Computer provides all the information necessary to operate the boards with your own programs.

Frequency Histories

One unusual feature of the MusicSystem is the ability to specify note frequency histories. Most synthesizers

allow you to specify amplitude envelopes, and some allow you to vary the waveform while the note is playing. The MusicSystem provides both of these features and also allows you to specify up to fifteen relative frequency changes *during* each note. This is done as part of the instrument definition process, and the feature may be used to create warble or vibrato, or to simulate tonguing effects. Unfortunately, frequency changes during each note are performed in steps, rather than following a smooth envelope. This makes it impossible to simulate an instrument like a steel guitar that uses long frequency glides. However, short glides can be simulated with a series of close frequency steps—the ear doesn't notice the difference. This limitation is a characteristic of the software, rather than the hardware, and could be improved in the future.

Sound Quality

The MusicSystem sound quality is excellent. Although there is a very slight background hiss—due to the limited signal-to-noise ratio of the 8-bit D/A (digital-to-analog) converters—it is not objectionable.

The system's 13-KHz frequency response is better than most home cassette tape decks, and it is almost as good as an FM receiver. If your record of *Switched-On Bach* has been played more than a few times on an average-quality turntable, it probably doesn't extend beyond 13 KHz either.

The separate individual and overall volume controls provide a wide dynamic range with no evidence of distortion at either high or low volumes.

Human Engineering

Mountain Computer has gone to a good deal of effort to make the MusicSystem as user-oriented as possible by providing detailed prompting, menu-driven operation, and operational feedback.

When an input is required, the choices are almost always spelled out on the screen. If an illegal command is entered, the system doesn't die a horrible death or misinterpret the command—it simply beeps, and usually informs you of your mistake. Any command that could cause loss of data requires a second, confirming command. Throughout the system, commands are kept as simple as possible, while still retaining their meaning. The user is not required to remember commands, for the system generally tells you what the choices are when the time comes to make them.

MusicSystem software is accessed through a series of nested menus (see photo 2) rather than direct commands. From the time the software is loaded, the system functions are controlled by selections from the menus. Each selection results in either a direct action, or it causes another menu to appear if further details are needed. The menus are clearly written and most selections consist of a single keystroke and a carriage return.

Visual feedback in the MusicSystem indicates proper operation and shows the results of your input. If the system is compiling a COMP file, it displays: WAIT

New from HIPLØT™
6-pen plotting for as little as $1480*.

FCC class B tested.
UL listed.

the Houston way

And you can retrofit your present single pen HIPLØT for only $395.

The new HIPLØT DMP Series 6-pen option makes high performance multi-pen plotting affordable. It's available on all six models in the HIPLØT family so you can enjoy the advantages of multi-colored plots on surfaces of 8½″ × 11″ (DIN A4) or 11″ × 17″ (DIN A3). Of course, you also get the standard HIPLØT range of capabilities such as intelligence, controls, interfaces and resolutions. There's a model for virtually every plotting application.



Big Performance in a Small Plotter

Since it's introduction, the HIPLØT DMP Series has been recognized as the innovative plotter line which made low-cost, high performance digital plotting a reality.



Now, with our new 6-pen option, there's an exciting new dimension in the DMP Series' versatility. Imagine two standard models with RS-232-C and parallel interfaces, four intelligent models with RS-232-C or Centronics® compatible interfaces, a choice of controls, resolutions, and pen speeds. Add to this the ability to plot with 6-pens on paper, vellum or mylar (ideal for overhead projectors) and you have the ultimate plotter price/performance combination — the perfect choice for the user or OEM.

Easily Retrofitted to Existing HIPLØT Models

If you already have a single pen DMP-2, 3 or 4, don't despair. For as little as $395* you can upgrade these models with our 6-pen conversion kit. It's simple to do . . . and the complete change can be made by the user in only six minutes.

So why wait? Let us send you complete information on this breakthrough in affordable, multi-pen plotting. *Contact Houston Instrument, One Houston Square, Austin, Texas 78753. (512) 837-2820. For rush literature requests, outside Texas, call* toll free 1-800-531-5205. *For technical information ask for operator #5. In Europe contact Houston Instrument, Rochesterlaan 6, 8240 Gistel, Belgium. Phone 059/27-74-45.*

houston instrument
GRAPHICS DIVISION OF
BAUSCH & LOMB

TM Trademark of Houston Instrument.
* U.S. Suggested retail prices.
Centronics® registered trademark of Centronics Data Computer Corp.

Circle 175 for literature
Circle 176 to have representative call



Photo 2: *The System 1 main menu. Selections can be made by touching the light pen to the block at the left of each item. The tiny square in the top block indicates the presence of the game-paddle cursor. If the button on paddle 0 is pressed, the Music Player is selected.*

--COMPILING. If you select a new instrument for a play file, the parameter display changes to show the results of your selection. Messages from the system are clearly spelled out, with no cryptic abbreviations.

The Software

The MusicSystem software is an integrated package of four main programs and four types of files (see figure 1), divided functionally and physically into two separate systems.

System 1 inputs and edits musical scores, and plays music. It includes the Music Editor, Music Merger, and Music Player programs, and comes with several demonstration COMP and PLAY files on the back side of the disk.

System 2 primarily creates waveforms and instruments (although it also includes a copy of the Music Player program). There are a number of predefined instruments and waveforms on the flip side of the System 2 disk.

System 1 and System 2 are tied together with the Music Player program. The Music Player compiles the COMP files produced by the Music Editor and binds in IDEF (instrument definition) files produced by the Instrument Definer, to produce the final PLAY files. Once a PLAY file is complete, it may be played at any time, and the original COMP and IDEF files may be discarded. The Music Player can also be used to alter instrument and speaker assignments in an existing PLAY file.

The System 1 and System 2 disks are received in Apple's DOS 3.2 format, and they are not copy protected. In fact, Mountain Computer recommends that you copy them as soon as possible to avoid inadvertent destruction of the master disks. If you have Apple's DOS 3.3, the MusicSystem software should be converted to sixteen-sector format rather than run in the thirteen-sector mode, because the system reloads from disk before returning to the main menus.

The system software is written in a combination of 6502 assembly language and XPLO (a block-structured Pascal-like language). The source program is not provided, but the manual contains detailed descriptions of all the file formats. All files and programs are in Apple DOS standard format, and may be copied with the DOS 3.3 FID utility or similar programs.

Interrupt Driven

Although the MusicSystem boards can run continuously under DMA once the appropriate registers have been initialized, playing real music requires changes in frequency and amplitude, while maintaining a specified tempo. MusicSystem accomplishes this with a constant-rate interrupt, which serves as a time-base reference for the *play* software. Every 8 ms (milliseconds), the MusicSystem interrupts the Apple's processor, and vectors to a

Text continued on page 70

NEC
Month
New Product (P) / Monthly R.O.I. ($000)
NEC
I/O Unit
PC-8012A
NEC
PC-8001A

The end of the compromise.

Shake hands with the PC-8000 Series from NEC America.

It combines the most-wanted features of today's most popular microcomputers, together with some added wonders of its own. Five user-programmable keys, for instance. A 248-symbol character set. Z-80A equivalent chip. Access to CP/M software. Powerful N-BASIC by Microsoft.™ Text processing in 8 colors. Keyboard editing convenience. 160 x 100 graphics matrix. Easy interfacing, too.

Just contact your authorized NEC America dealer.



NEC

NEC America, Inc.
1401 Estes Avenue
Elk Grove Village, IL 60007

Circle 276 on inquiry card.



Figure 1: *Data-flow diagram showing the relationships between various programs and files used by the MusicSystem. The Music Merger is used primarily to combine COMP files into larger COMP files, and it allows the creation of larger scores than the Music Editor can hold.*

Text continued from page 66:
series of routines that update the registers in the MusicSystem boards. These routines vary the waveform amplitudes to create note envelopes, and update the frequency registers to change notes. They can also vary the overall volume. Once the updates are complete, execution returns to the program that was interrupted. This technique is called *foreground/background* operation.

Because the play software is interrupt-driven, the entire task of playing a song file can be accomplished during the time another program is running. A good example of this is the Instrument Definer program, in which the MusicSystem continuously plays a short PLAY file to provide audible feedback while the user is creating waveforms and defining instrument characteristics. In this case, the Instrument Definer program runs in the *foreground* while the MusicSystem plays and runs its interrupt routines in the *background*.

There is one main drawback to the use of interrupts (and DMA). The user manual cautions that no other device on the Apple's bus can generate interrupts or use DMA while the MusicSystem is playing. If this happens, both the MusicSystem and the conflicting device fail to work properly. This restriction would probably be encountered only with devices that interrupt continuously (eg: a real-time clock/home-control system combination). In any case, the problem can be avoided by temporarily stopping the conflicting device and then restarting it when you are finished with the MusicSystem.

The Music Editor

The Music Editor program is similar in format to a number of its competitors, but it offers a variety of additional features. The Music Editor divides the screen into two separate functional areas: the upper two thirds of the screen becomes a graphic music display, while the lower portion holds the various editor menus and the status and command lines.

The music display acts as a window on the score in memory. The display can be scrolled right and left through a given part, or up and down from part to part. The display staff formats include the treble, bass, alto, and tenor clefs, as well as the System Clef (ie: the combination of treble and bass clefs used in keyboard sheet music). You can change the clef at any time, and the score will be redisplayed correctly on the new clef. Photo 3 (the Music Editor main menu) shows an example of the system clef.



Photo 3: *The Music Editor main menu. In this example, the music cursor is at measure twelve of the song "America," the music staff is the system clef, and the editor is in the CHORD mode. Chords may be entered within a part, or through the use of multiple parts.*



Photo 4: *The Music Editor Signature Commands menu displays part two on the bass clef in NOTES mode. This menu is used to select key, time signature, and clef.*



Photo 5: *The Note Modifier menu inserts dynamic or normal accents, and sets or removes ties between notes. The dynamic* sfffz *has just been inserted at the first note in measure nine. In this photo, part one is displayed on the treble clef.*

You can select items from any of the editor's four graphic menus, with either the light pen or with game paddle 1. Most of your time will be spent with the main menu: it is used to select note durations, rests, measure bars, and to handle all editing functions. The other three menus are selected from the main menu, and they all return to it. The commands are also available through the keyboard, and a few operations such as LOAD, SAVE, and PRINT can only be executed by typing the command. The various editor menus are shown in photos 3, 4, 5, and 6.

The Music Editor provides a large selection of accents and dynamics that add life and emphasis to your music. Overall loudness is controlled with the SOUND COMMANDS menu, and individual notes may be accented with the NOTE MODIFIER menu. Unfortunately, note dynamic accents, although provided for in the editor, are not fully functional in the Music Player program: they are played as normal accents. The MusicSystem manual states that this will be corrected in a later version of the software. Two other unimplemented commands are user SYNC (designed to synchronize external devices like a slide projector) and GRAD (specifies gradual volume changes to create crescendos and diminuendos). According to the manual, SYNC will be implemented in a later version. GRAD appears only in the SOUND COMMANDS menu; the manual doesn't mention it at all.

The editor's PRINT command allows you to print out part or all of a score in graphics on the Apple Computer Inc Silentype printer. The score is printed as it is shown on the screen, and may be printed in one of two sizes. Each part is printed separately on its own staff, and the printout can be cut and pasted to form a sort-of-orchestral score. I would have liked to have the ability to print out several parts simultaneously, on one set of staves, as this would have made the printout a more useful piece of sheet music. Other graphics printers, such as Integral Data Systems' Paper Tiger, are not supported in this version of the MusicSystem.

You can enter music in either NOTES or CHORDS mode. In CHORDS mode, the music cursor doesn't advance while you are entering notes of the same duration. Most synthesizers require that you use separate parts to enter chords, but the MusicSystem doesn't have this limitation. Multiple parts are only required to define the music played by *different* instruments.

Notes are placed on the screen with either game paddle 0 or with the keyboard. A small cursor is moved vertically through the staff when paddle 0 is turned, and the note appears when you press the button. You can enter music surprisingly fast through the keyboard. Once the duration and octave are selected, a string of notes may be entered as simply as typing C D E F G A B and pressing RETURN.

I was a little disappointed to find that the editor doesn't provide audio feedback during music entry. However, it

MORROW DESIGNS

Leading edge technology in hard disk systems.



Complete systems. Morrow Designs hard disk subsystems are delivered complete with hard disk, controller, cabinet, power supply, fan, cables and CP/M* 2.2 operating system.

Widest range. Morrow Designs offers the widest range of hard disk systems available from a single supplier. 5¼," 8," 14." Five to over 100 megabytes of formatted hard disk storage. $2,995 to $19,980. Cost effective systems that work. And keep working.

S-100 and more. Morrow Designs hard disk systems are designed for use with the CP/M operating system. Available software packages allow our systems to run on any IEEE696/S-100 Standard system with no hardware modification. Plus, Cromemco,† North Star,** Vector Graphics, Godbout, Dynabyte, Exidy,†† IMSAI, Micromation, Processor Technology and California Computer Systems.

Reliable systems. Morrow Designs is committed to hard disk system reliability. Not simply with a 90-day warranty, but with a money back guarantee. If our system fails to perform to specification, send it back. We'll send back your money.

Experience. As of April, 1981, there were over fifteen hundred Morrow Designs hard disk systems successfully installed. In fact, over 200 independent systems integrators now use our hard disks to solve their mass storage problems.

Performance answers. Morrow Designs hard disk systems have been benchmarked against all other systems. None is faster under CP/M. Morrow Designs hard disks operate at 10 times the speed of a floppy disk drive. Transfer rates range from 590,000 bytes to 900,000 bytes per second. That kind of performance can become addictive.

Cost effective answers. Compare Morrow prices and performance to anything presently available for S-100 systems. You'll find Morrow's price/megabyte/performance ratio to be unmatched. Leadership in disk systems technology earned us leadership in price/performance. And that may have earned us a call from you. Circle the Reader Service Number for our full line data sheets. Can't wait? Call us at (415) 524-2101. And yes, OEM quantity prices are available. **LOOK TO MORROW FOR ANSWERS.**

MORROW DESIGNS

5221 Central Avenue, Richmond, CA 94804
(415) 524-2101

*CP/M is a trademark of Digital Research.
**Northstar is a trademark of North Star Computers, Inc.
†Cromemco is a trademark of Cromemco, Inc.
††Exidy is a trademark of Exidy Corporation.

Circle 264 on inquiry card.

does sharp and flat notes to match the key signature, so this potential source of errors is removed.

The size of the score that can be handled by the editor is somewhat limited. If you actually entered sixteen separate parts, there would not be room for many measures of music. Fortunately, the Music Merger program can be used to combine COMP files to produce a much larger final result. (There has been talk at Mountain Computer of designing a true "virtual score" capability into the MusicSystem by spooling the score on and off disk as the editor scrolls through it. Whether or not this will be implemented in the next version remains to be seen.)



Photo 6: *The Sound Commands menu controls overall loadness, sets tempo, and assigns parts to speakers. Dynamic (loudness) may be specified as either absolute (with the menu) or relative (with the keyboard). The* mf *dynamic has just been inserted to the left of the music cursor.*

The editing functions provided by the editor are simple and effective. Unless otherwise specified, the editor is always in insert mode. Music events may be inserted at any time and at any place in the score. The editor provides commands to scroll right and left, delete right and left, and change note durations. You can jump to other locations in the score by using the keyboard GOTO command to access specific measures. I found the editor's responses to be a little slower than I liked, but it wasn't objectionable.

The editor has only two real weaknesses: it lacks both triplets and the capability to repeat musical phrases. The former makes it difficult to enter certain pieces of music, and the latter adds time and wastes space when repeated phrases are encountered. There is no reason why you should have to reenter the same section of music when the computer could do it for you. Also, the editor will not automatically place measure bars, but this drawback is not important because both measure bars and time signatures have no effect on the music played.

My overall reaction to the Music Editor is mixed. On the one hand it is an excellent piece of software with many features that are not found in most music editors. On the other hand there are the unimplemented features

MORROW DESIGNS

Cost effective answers to floppy disk problems.

DMA answers. Standard, accumulator transfer floppy disk controllers can stall your microcomputer system's CPU for as long as 160 milliseconds. Just to access and transfer a sector of data to main memory. If CPU processing speed and system performance are critical, you need something better. That's where Morrow Designs' new intelligent Disk Jockey DMA™ controller comes in. This new breed of perpheral handles both 5¼" and 8" drives and can read almost any format in existence. Speed? Your CPU runs at full tilt while the DMA controller seeks and gathers a sector of data. How? Information transfers to and from main memory occur as "cycle steals" from the system bus. And the missing memory cycles are transparent to the CPU totalling only two milliseconds instead of the usual 80.

Build a buffer. Give the Disk Jockey DMA a little extra memory and your system's performance gets even better. The extra storage is used as a track buffer. So, whenever a sector on a new track is read, the track buffer is automatically filled with the other sectors on the track. The result? Additional data on the track is immediately available. Without the 80 millisecond rotational latency normally encountered. And similar efficiencies occur with disk writes. Sectors in the track buffer are conditionally written on the disk only if a new track is accessed. And only one revolution of the disk is required.

Now, prices:* All systems listed are supplied with a floppy disk drive, Disk Jockey Direct Memory Access Controller, CP/M** 2.2 operating system, power supply, fan, cables, cabinet and Microsoft 5.2 BASIC.

Even lower prices. Morrow Designs' floppy disk systems with Disk Jockey™ 2D controllers offer the same high quality at even lower prices. Now without memory mapping!

Fast answers. See Morrow Designs' family of cost effective floppy disk systems at your computer dealer. For a somewhat more leisurely answer, circle the reader service number below. For immediate answers, phone us at (415) 524-2101.

LOOK TO MORROW FOR ANSWERS.

5¼ Inch Systems (formatted data)

400,000 Bytes (1) Dual Sided 48 TPI Drive	$1110
800,000 Bytes (2) Dual Sided 48 TPI Drive	$1899
800,000 Bytes (1) Dual Sided 96 TPI Drive	$1499
1,600,000 Bytes (2) Dual Sided 96 TPI Drive	$2599

OEM pricing available

8 Inch Systems (formatted data)

500,000 Bytes (2) Single Sided Drive	$1199
1,000,000 Bytes (2) Single Sided Drive	$1975
1,000,000 Bytes (2) Dual Sided Drive	$1595
2,200,000 Bytes (2) Dual Sided Drive	$2675

OEM pricing available

*Prices subject to change without notice.
Disk Jockey DMA and Disk Jockey 2D are trademarks of Morrow Designs
**CP/M is a trademark of Digital Research.

MORROW DESIGNS

5221 Central Avenue, Richmond, CA 94804
(415) 524-2101

Circle 265 on inquiry card.

ALTOS
BRAND
PROVEN VALUE
DELIVERY
COMPUTER · SYSTEMS
PRODUCED IN THE HEART OF SILICON VALLEY, CALIFORNIA U.S.A.
ALTOS



Photo 7: *The Instrument Definer main menu. The audio feedback level has been reduced and the pitch transposed down one octave by setting DYNAMIC to 30 and TRANSPOSE to −12.*



Photo 8: *An example of an Attack Profile plot from the Instrument Definer. The plot shown is for oscillator 2 from the instrument WOODDRUM. This example shows an alternate method of defining envelopes. In this case, the entire envelope is defined during the attack phase, so there is no sustain or release.*



Photo 9: *A sample frequency-history plot. Note that rather than changing smoothly, the frequency changes in steps. In this example the steps are not audible, so it sounds like a smooth change.*

and the omissions previously mentioned. The current version of the software (2.0) is much improved from the original version 1.2. I look forward to the next version, and hope that the few remaining problems will be fixed. In any case, the editor is still very usable, and I enjoyed the time that I spent with it.

The Instrument Definer

The process of creating and playing different instruments is one of the more interesting aspects of the MusicSystem. Here the MusicSystem's unique capabilities clearly separate it from the rest of the synthesizers available for the Apple. Other synthesizers can define instruments, but their capabilities are limited compared with the MusicSystem (see the "Music Making" text box on page 84).

In the MusicSystem, each instrument definition (see figure 2) is composed of one or more logical oscillators, each with a defined waveform, relative amplitude, attack envelope, sustain-decay rate, and frequency profile. (The term "logical oscillator" is used because the actual physical waveform generator will not be chosen until play-time.) In addition, there are several global parameters that affect all of the oscillators used in an instrument definition (see photo 7). You can specify attack and decay times, and whether the amplitude scale should be logarithmic (to match the human ear's response) or linear.

During the instrument definition process (see photos 8 and 9), there is continuous audio feedback, so that you can hear the effect of your changes as you make them. The feedback is normally a C-major scale, but a short PLAY file can be loaded and used instead. The audio level of the feedback may be changed or transposed so that you can hear how your instrument sounds at different pitches. As previously described, the audio feedback runs under interrupts in the *background* while you define instruments and create waveforms with the Instrument Definer in the *foreground*.

A special subprogram of the Instrument Definer, called the Wavemaker, is used to create waveforms through a process called Fourier (or additive) synthesis. Just as *Fourier analysis* breaks down a waveform into its harmonic components, *Fourier synthesis* creates a waveform from a set of harmonic amplitudes. The process is also called additive synthesis because it is done by adding sine waves of various harmonic frequencies and amplitudes to produce the final result (see reference 6).

The Wavemaker allows you to specify the amplitudes of up to twenty-four harmonics, and you can switch to the waveform display to view the wave at any time during the process. The audio feedback responds to the harmonic changes as you make them, so you can literally design your waveform "by ear." The view of the waveform is interesting, but not really important: it is easier to relate the timbre of the sound to the harmonic mix than to the waveshape. Photos 10 and 11 show ex-

Text continued on page 82

Now proven baZic can be run on any Z80® computer under CP/M® baZic is written entirely in Z80 code—runs faster than any other BASIC interpreter. The greater execution speed is significantly advantageous for heavy number crunching, multi-user and multi-tasking operations.

baZic has all the features of North Star® BASIC— and then some. baZic, with minor exceptions, is 100% compatible with existing North Star BASIC programs. Our new baZic runs under all Micro Mike's timesharing and hard disk operating software.

CHECK THESE FEATURES AT YOUR COMPUTER DEALER:

- Takes full advantage of the Z80 instruction set.
- Can be used on any Z80-based microcomputer operating under North Star® DOS or CP/M.
- Support North Star floating point board for even faster execution of compute-intensive programs.
- The most friendly BASIC available.
- Improves performance of multi-user hard disk systems.
- baZic adds functions to assist in screen formatting, as well as features to simplify programming, e.g. APPEND as a statement, ON GOSUB, cursor-addressable PRINT, enhanced editing features, etc.
- baZic as shipped includes 8, 10, 12, and 14 digit precisions, including both software and hardware floating point versions.
- baZic is also available for the Apple II® under CP/M with the SoftCard.™

OEMs and dealers contact Silverman Associates for details. 4010 Opal Street, Oakland, CA 94609. (415) 428-2954. All other inquiries should be to your dealer or Micro Mike's.

®North Star Computers
®Digital Research, Inc.
®Apple Computers, Inc.
®Zilog, Inc.
®Microsoft

MMike's
Micro Mike's, Inc.
3015 Plains Blvd., Amarillo, Texas 79102

Hard fact:

$150 makes your Z80-based computer run up to 40% faster!



Figure 2: *Structural diagram of the Instrument Definer program, showing access paths to various menus and displays. The Instrument Definer is a large program that operates by loading program segments from disk as different functions are required.*

This Single Board...

...is the Heart of the Microprocessor World's Best Multi-User System ...



THE DISCOVERY MULTIPROCESSOR

The dedicated power of this complete single board computer is provided to each user, making the DISCOVERY MULTIPROCESSOR unique among multi-user systems. With the power and expandability of distributed processing ● With the economy of shared peripherals ● With the flexibility of shared and public files ● And all of this with full CP/M* and S-100 compatibility.

Multiprocessing Software

Our Distributed Processing Operating System, **dpc/os**©, resides in the Service Processor, establishing a CP/M environment for each user and managing access to the shared system resources. Multiuser facilities are provided for print spooling, for interprocessor communication and for private, public and shared-update files. Several processors can be employed concurrently by a single user via the enhanced batch submit facilities. And with **DISCOVERY** all CP/M compatible programs will execute without modification, thus protecting your software investment.

Multiprocessing Hardware

The ACE 64K Distributed Processing Single Board Computer, the **dpc-180**™ gives the **DISCOVERY** MULTIPROCESSOR its own unique architecture. One DPC is dedicated to each user providing exclusive use of the onboard Z-80, 64K ram and serial I/O. Access to the shared resources is provided by an expanded DPC used as a Service Processor. Additional users can be added at any time by simply inserting additional DPC's into the standard S-100 bus — up to a total of sixteen user processors in a single chassis!

*CP/M is a registered TM of Digital Research, Inc.



The ACE **DISCOVERY MULTIPROCESSOR** dedicates a complete 64K Z-80 Distributed Processing single board Computer, the **dpc-180**™ to each user. An expanded DPC coordinates all of the system activities.

Multiuser mainframes with 192K ram start at under $6000. The 64K **dpc-180**™ is priced at $1395. Immediate delivery. A complete line of standard peripherals including a 26M byte hard disk subsystem can be supplied on request. Dealer and OEM inquiries are invited.

DISCOVERY has been proven in installations throughout the World. If you need the Power of Multiprocessing... it's time you discovered us!

Action Computer Enterprise, Inc.
The Multiprocessing Company

55 West Del Mar Boulevard, Pasadena, California 91105 USA ● Cable ACEPAS Pasadena ● (213) 793-2440



Figure 3: *Logical model of the MusicSystem hardware. The hardware is actually more complex than indicated here, but there is sufficient information provided in the manual to operate the board with your own software.*

Text continued from page 78:
amples of the waveform creation process.

Envelopes

In the Instrument Definer, the envelope is specified through a combination of oscillator and global parameters (see figure 3). Each oscillator in an instrument definition has five specified characteristics:

- Weight: its amplitude relative to any other oscillators used
- Attack profile: the pattern of volume changes during the attack portion of the envelope
- Frequency history: the pattern of frequency changes during the attack
- Sustain exponential: the sustain amplitude half-life in milliseconds
- Waveform

The attack and frequency profiles can each be specified with as many as fifteen segments to allow detailed instrument models. The global attack time defines the interval over which the oscillator attack and frequency profiles are spread.

Instruments whose timbre changes during each note

Text continued on page 88

Circle 189 on inquiry card. →

SOLVE THE STORAGE SHORTAGE

with ten multi-user megabytes

CompuStar's 8-inch Winchester


Intertec's exclusive 255 User Controller

CompuStar Cable Assembly

If you could think of just one way to improve our phenomenally popular SuperBrain, what would it be? More disk storage? Well, we already thought about it. And for only a few thousand dollars for a whopping 10 megabytes of lightning-fast storage, it's nothing short of another major breakthrough! From the company that wrote the book on price/performance . . . Intertec.

Our New CompuStar™ 10 Megabyte Disk Storage System (called a DSS) features an 8 inch Winchester drive packaged in an attractive, compact desktop enclosure. Complete with disk, controller and power supply. Just plug it into the Z80 adaptor of your SuperBrain and turn it on.* It's so quiet, you'll hardly know it's there. But, you'll quickly be astounded with its awesome power and amazing speed.

The secret behind our CompuStar DSS is its unique controller/multiplexor. It allows many terminals to "share" the resources of a single disk. So, not only can you use the DSS with your SuperBrain, you can configure multiple user stations using our new series of CompuStar™ terminals, called Video Processing Units or VPU's™.

Four CompuStar VPU's are available. At prices starting at less than $2,500. Some models are designed to operate as stand-alone microcomputers, with internal disk storage. Just like your SuperBrain. Each model features its own 64K of RAM and can be "daisy-chained" into a powerful multi-user network. Just connect one VPU into the next. Using easy-to-install cable assemblies. Connect up to 255 users in a single system. One at a time. As you need them.

Whether you need an extra 10 megabytes for your SuperBrain or an enormous multi-user network, the CompuStar™ DSS solves your storage shortage problems. Sensibly. And economically. Plus, your investment is protected by a nationwide service network with outlets in most major U.S. cities. Providing efficient on-site or depot maintenance.

Get a demonstration of this extraordinary new system today. Call or write now for the name and address of your nearest CompuStar dealer.

INTERTEC DATA SYSTEMS®
2300 Broad River Rd. Columbia, S.C. 29210
(803) 798-9100 TWX: 810-666-2115

*Some models require hardware/software modification.

Music Making

Two main music-synthesis techniques have been used on the Apple II computer. Each of these techniques has strong and weak points, and each presents features that the other does not. However, neither offers the power and flexibility of the MusicSystem which, in fact, uses a combination of the two techniques.

Square-Wave Music

The first widely available music synthesizer for the Apple II was produced by ALF Products Inc. The ALF synthesizer could generate three square-wave "voices" with note-envelope control and a wide frequency range. Up to three ALF circuit cards could be installed in an Apple II, which provided up to nine musical parts through three separate audio outputs. The ALF software was well written, and the same unit, the ALF Apple Music Synthesizer, is still quite popular today.

The technique used by ALF to generate tones is also used by a number of similar, but lower-quality and less-expensive, synthesizers currently on the market. This technique involves the use of several programmable hardware frequency dividers. Each divides a master frequency by a number that is provided by the controlling software. Different output frequencies are provided by varying the software-supplied divisor. The square-wave output of each frequency divider is then fed into a programmable attenuator, typically a D/A (digital-to-analog) converter, to vary the output level. Thus, the software simply supplies the frequency and output-level information to the card and the hardware does the rest.

One of the advantages of this technique is that the number of voices can be increased by simply adding more synthesizer cards. Even with nine-part music, the software has enough time left over to provide a real-time music display on the Apple's screen.

The main disadvantage of this technique is that it is not true music synthesis. It is impossible to reproduce a wide range of instrumental sounds with a waveform that is limited to a square wave. The control of each note's envelope allows a range of effects to be produced, but the high notes are invariably sharp and brilliant while the low notes have a buzzy sound.

Since the introduction of the ALF synthesizer, a number of similar units have appeared on the market. Most use the General Instrument AY-3-8910/8912 music synthesizer integrated circuit to produce tones. This is an inexpensive approach, but it offers limited frequency accuracy and only sixteen levels of output volume. The AY-3-8910 also includes a pseudo-white-noise generator that allows these units to offer (as one advertiser puts it) "flash and crash sound effects."

Software-Driven D/A Synthesis

Another popular approach to personal computer music synthesis utilizes a software-driven D/A converter. The D/A receives a constant stream of numbers from the computer and produces a correspondingly varying voltage at its output. With carefully written software, this technique is capable of producing surprisingly good-quality music.

The current state of the art was largely developed by Hal Chamberlin of Micro Technology Unlimited and his associates, Frank Covitz and Cliff Ashcraft. The software steps through precomputed waveform lookup tables, summing the values found and outputting the sum to the D/A at a constant rate. This allows complex waveforms to be computed and stored in advance, thus reducing the amount of computation required at play time. Note envelopes and timbre variations during each note are accomplished by storing a series of waveforms for each voice. Each stored waveform represents the waveshape and amplitude of the note at a given duration. The amplitude and timbre variations are generated by rapidly switching waveform tables.

Using the current software, the Apple's 1 MHz 6502 microprocessor can produce four-part music with realistic-sounding instruments and a 3.5 KHz frequency bandwidth. Faster processors can produce more parts and a greater frequency response. The technique is extremely flexible and can provide a wide range of instrument sounds. The hardware required is simple and inexpensive because the software does most of the work.

The main disadvantage of the system is that the software uses virtually all available processor time. The bandwidth or the number of musical parts cannot be increased without using a faster processor. Adding another D/A circuit board can provide stereo outputs but will not increase the music capacity of the system. Another disadvantage is that overall volume control and dynamic accents are difficult to implement due to time and memory-capacity limitations. It is not uncommon to fill 32 K bytes of memory with waveform tables without allowing for varying volumes for each instrument. This limitation could be removed by using a multiplying (variable gain) D/A to control the output level, which would also tend to effectively improve the limited signal-to-noise ratio of the 8-bit D/A.

Even with these limitations, the technique has a large number of avid users, and the quality of the music produced continues to improve as the software is refined. Examples of products using this method are devices built by Micro Music Inc (309 Beaufort St, Normal IL 61761, (309) 452-6991) for the Apple II, and products produced by Micro Technology Unlimited Inc (2606 Hillsborough St, POB 12106, Raleigh NC 27605, (919) 833-1458) for the Apple, PET, Aim, and other 6502-based computers.

Introducing quality print at matrix speed. For only $1295.*

Until now, word processing output was a slow, expensive proposition. You could pay thousands for a slow, letter-quality character printer. Or give up print quality for matrix speed and price.

But that was before Paper Tiger™ 460 offered you a better choice.

The new Paper Tiger 460 is the first matrix printer with high-density dot matrix characters plus high speed. At a low price.

The secret? A unique nine-wire, staggered matrix head provides overlapping dots in both horizontal and vertical planes. The result is dense, high-quality characters you'll be proud to show off.

What's more, Paper Tiger 460 gives you a combination of features simply not available on any other printer, at any price. Like bi-directional, logic-seeking printing at speeds in excess of 150 characters per second. Microprocessor electronics, with built-in diagnostics and self-test. Proportional spacing. Automatic text justification. DotPlot™ high resolution graphics option. RS232 and parallel interfaces. And more.

```
Integral Data Systems stands rea
performance printers ideally su
printer, the IDS 460, offers feat

Automatic proportional spacing,
processing systems, plus the cap
resolution of 84 by 84 dots per
```

Paper Tiger 460 Print Sample

But its most important feature is high reliability. Paper Tiger 460 is designed to be tough and dependable. It has rugged, stepper-motor head and paper drives. A new rugged ballistic-type print head.

And its simple, chassis-mounted cartridge ribbon lasts up to four times longer than cassette or spool ribbons.

Paper Tiger 460 is the one printer that gives your Apple,† TRS-80,‡ or other small business computer both data processing and word processing output. At a price you can afford.

Get your paws on Paper Tiger 460, and join the tens of thousands of satisfied Integral Data Systems users. For the name of the Paper Tiger dealer nearest you. Call us toll-free: 800-258-1386. (In New Hampshire, Alaska, and Hawaii, call (603) 673-9100.) Or, write for complete specifications. Integral Data Systems Inc., Milford, New Hampshire 03055.

Paper Tiger 460

Integral Data Systems, Inc.

*Suggested single-unit U.S. retail price.
† Apple is a trademark of Apple Computer Inc.
‡ TRS-80 is a trademark of Radio Shack, a division of Tandy Corp.

Circle 184 on Inquiry card.

Space Shuttle Columbia is a symbol of the commitment to explore the limits of science and technology.
The Denver Software Company has made a similar commitment: to simplify these breakthroughs for everyday use.
By developing applications software in UCSD Pascal*, the newest microcomputer language, and by using a unique approach to design, The Denver Software Company creates high quality programs for use in business, industry, and the home.
The speed and flexibility of UCSD Pascal enable DSC to manufacture versatile programs, usable on more microcomputers, while at the same time reducing costs to the consumer. In addition, DSC has combined the strength of this language with a new, low-cost portable computer, the Attache from Otrona, to provide the user with even more efficient computer capability.
Pascal-related products now available from The Denver Software Company include:
The PASCAL TUTOR™: Teaches persons at the entry level how to write simple programs. Using the computer as instructor, this self-paced program is the first in a series of Pascal teaching tools. Price $125
The PASCAL PROGRAMMER™: A programming aid for those familiar with UCSD Pascal. Provides pre-tested modules which reduce programming efforts by approximately 70%. Includes two diskettes with source code and library units, user's manual, complete module documentation, and ideas for modifications. Price: $125
The FINANCIAL PARTNER™: A one- or two-drive accounting system designed specifically for households or for small businesses with an annual gross of up to $1,000,000. All necessary "how-to" is contained in a comprehensive user's manual. Price: $175
PERT/Critical Path Management: Time analysis program which allows critical path supervision. For use in project management, this time-saving system considers manpower and skill levels, and provides for fulltime, fulltime plus overtime, and parttime employment of personnel. Price: $750
*UCSD Pascal is a trademark of the Regents of the University of California.
All programs available from your local dealer or contact:
THE DENVER SOFTWARE COMPANY
MANUFACTURERS OF MICROCOMPUTER SOFTWARE
DSC™
36 Steele Street, Suite 19 • Denver, Colorado 80206
Dealer inquiries welcome. 303 321-4551.

..."another giant step"...

"The success of the Columbia mission signifies another giant step in the on-going effort to adapt computer technology for individual use."

Wally Schirra

Applications software for business, industry, and home use.
The FINANCIAL PARTNER™: accounting for home or small business.
The PASCAL SERIES: computer language teaching aids.
PERT/Critical Path Management: for efficient project management.

All programs available from your local dealer or contact:

THE DENVER SOFTWARE COMPANY

MANUFACTURERS OF MICROCOMPUTER SOFTWARE

36 Steele Street, Suite 19 • Denver, Colorado 80206
Dealer inquiries welcomé. 303 321-4551.

Circle 114 on inquiry card.

Photo 10: *A plot of the harmonic partials required to create an approximate square wave. For each odd harmonic specified, the amplitude is equal to 100/n, where n is the harmonic number.*



Photo 11: *The waveform resulting from the harmonic specifications in photo 10. A good approximation of a square wave could be used to simulate some of the less expensive music boards that are available for the Apple.*

Text continued from page 82:
may be simulated by using multiple oscillators. If you wish to decay the higher harmonics faster than the low ones in order to simulate a plucked or struck string instrument, you can use two or three oscillators with different harmonic contents and design them to decay at different rates.

In contrast to the MusicSystem, many synthesizers use the ADSR (attack-decay-sustain-release) method to specify envelopes. In the ALF synthesizer, for example, you specify the *attack* slope, the initial *decay* slope, the *sustain* level, and the *release* slope which ends the note. The sustain is always at a constant volume, so it is difficult to simulate instruments, like a piano, which decay

TYPE-'N-TALK™ IS T.N.T.

The exciting text-to-speech synthesizer that has every computer talking.

- **Unlimited vocabulary**
- **Built-in text-to-speech algorithm**
- **70 to 100 bits-per-second speech synthesizer**

Type-'N-Talk,™ an important technological advance from Votrax, enables your computer to talk to you simply and clearly — with an unlimited vocabulary. You can enjoy the many features of Type-'N-Talk,™ the new text-to-speech synthesizer, for just $375.00.

You operate Type-'N-Talk™ by simply typing English text and a talk command. Your typewritten words are automatically translated into electronic speech by the system's microprocessor-based text-to-speech algorithm.

The endless uses of speech synthesis.

Type-'N-Talk™ adds a whole new world of speaking roles to your computer. You can program verbal reminders to prompt you through a complex routine and make your computer announce events. In teaching, the computer with Type-'N-Talk™ can actually tell students when they're right or wrong — even praise a correct answer. And of course, Type-'N-Talk™ is great fun for computer games. Your games come to life with spoken threats of danger, reminders, and praise. Now all computers can speak. Make yours one of the first.

Text-to-speech is easy.

English text is automatically translated into electronically synthesized speech with Type-'N-Talk.™ ASCII code from your computer's keyboard is fed to Type-'N-Talk™ through an RS 232C interface to generate synthesized speech. Just enter English text and hear the verbal response (electronic speech) through your audio loud speaker. For example: simply type the ASCII characters representing "h-e-l-l-o" to generate the spoken word "hello."

TYPE-'N-TALK™ has its own memory.

Type-'N-Talk™ has its own built-in microprocessor and a 750 character buffer to hold the words you've typed. Even the smallest computer can execute programs and speak simultaneously. Type-'N-Talk™ doesn't have to use your host computer's memory, or tie it up with time-consuming text translation.

Data switching capability allows for ONLINE usage.

Place Type-'N-Talk™ between a computer or modem and a terminal. Type-'N-Talk™ can speak all data sent to the terminal while online with a computer. Information randomly accessed from a data base can be verbalized. Using the Type-'N-Talk™ data switching capability, the unit can be "de-selected" while data is sent to the terminal and vice-versa — permitting speech and visual data to be independently sent on a single data channel.

Selectable features make interfacing versatile.

Type-'N-Talk™ can be interfaced in several ways using special control characters. Connect it directly to a computer's serial interface. Then a terminal, line printer, or additional Type-'N-Talk™ units can be connected to the first Type-'N-Talk,™ eliminating the need for additional RS-232C ports on your computer.

Using unit assignment codes, multiple Type-'N-Talk™ units can be daisy-chained. Unit addressing codes allow independent control of Type-'N-Talk™ units and your printer.

Look what you get for $375.00. TYPE-'N-TALK™ comes with:

- Text-to-speech algorithm
- A one-watt audio amplifier
- SC-01 speech synthesizer chip (data rate: 70 to 100 bits per second)
- 750 character buffer
- Data switching capability
- Selectable data modes for versatile interfacing
- Baud rate (75-9600)
- Data echo of ASCII characters
- Phoneme access modes
- RS 232C interface
- Complete programming and installation instructions

The Votrax Type-'N-Talk™ is one of the easiest-to-program speech synthesizers on the market. It uses the least amount of memory and it gives you the most flexible vocabulary available anywhere.

Order now. Toll free.

Call the toll-free number below to order or request additional information. MasterCard or Visa accepted. Charge to your credit card or send a check for $375.00 plus $4.00 delivery. Add 4% sales tax in Michigan.

1-800-521-1350.

Votrax® Circle 420 on inquiry card.

Distributed by Vodex
A Votrax Company — Dept. RT
500 Stephenson Highway, Troy, MI 48084
(313) 588-0341

Type-'N-Talk™ is covered by a limited warranty. Write Votrax for a free copy.

gradually while the note is sustained, but drop off abruptly when the key is released. The ADSR method is a simple way of specifying envelopes, but it does not have the flexibility required to simulate real instruments accurately. Figure 4 shows a comparison of the ADSR and MusicSystem envelopes.

Documentation

Mountain Computer provides a comprehensive manual with the MusicSystem. Within its two hundred pages are chapters on system operations, descriptions of all the system programs, and a good section on background and theory.

The MusicSystem manual makes extensive use of walk-through examples to introduce you to each of the MusicSystem programs. You are taken step by step through the Music Editor (through the process of entering the song "America" in two parts), and then through the Instrument Definer, where you learn while creating the instrument ORGAN. The manual also includes a complete list of error messages and their causes, by program, as well as reference material that describes the hardware, the system file formats, and how to control the hardware with your own software.

The manual, and in particular the chapters on the Instrument Definer and MusicSystem theory, should be carefully read by any MusicSystem purchaser. A number of fine points and operational details will not be understood if you "don't read the instructions until all else fails."

Comments

According to Avery Dee, Vice President of Marketing, Mountain Computer considers the MusicSystem an evolving product, and plans to support and expand the system through future software releases. The first release of the MusicSystem was version 1.2, which did not include the Instrument Definer or the PRINT command. Since then, the current version 2.0 has been released and made available *at no charge* to all purchasers of version 1.2. By the time you read this article, another version may have been released. Certainly the unimplemented commands should be fixed, and hopefully, n-tuplets and repeats will be added.

Mountain Computer is currently compiling and providing MusicSystem information to several vendors who are either designing software or interfacing the system to other products. For example, The Alpha-Syntauri keyboard (Syntauri Ltd, 3506 Waverly, Palo Alto CA 94306) is now available interfaced to the MusicSystem as well as ALF's music boards.

In a way, the development of the MusicSystem can be compared to that of the Apple II three years ago. It has some limitations at the moment, but it is still entirely usable, and shows great potential. With the planned software enhancements, it should satisfy most needs for

What has nine lives, three forms, multiple faces and a price tag that almost disappears?



The Magical Microline 80 Printer

It's magic! Well, almost. The Microline 80 will run all day at 80 cps with no duty cycle limitations. The head is warranted for 200,000,000 characters. That translates to over nine years on your TRS-80,™ APPLE® or other small computer.

Want to change forms? The magical Microline 80 is three printers disguised as one. There is a whisper-quiet rubber platen for cut sheets and roll paper, pins on nine inch centers for pin feed stock *and optional* snap-on tractors that adjust to suit all your other forms. The Microline 80 also saves paper by letting you tear off as close as one inch from the last print line.

Want to change your image? The magical Microline 80 really does tricks. It prints upper and lower case, condensed and double width characters *and* block graphics for charts, graphs and diagrams.

The Microline 80 is not a toy. With two motors, a rugged cast aluminum base and a head you never have to throw away, the Microline 80 is built to handle the most demanding business applications.

Which brings us to the biggest magic of all, the price tag, the one that almost disappears. If we're not the lowest, we are so close that it doesn't matter. There are stocking Microline distributors throughout the country. Call or write today for the name of the one near you and the price of the Magical Microline 80.

OKIDATA

Okidata Corporation, 111 Gaither Drive, Mount Laurel, New Jersey 08054 609-235-2600

Okidata is a subsidiary of Oki Electric Industry Company, Ltd.



Figure 4: *Comparison envelopes produced by the MusicSystem and by the ADSR method. The MusicSystem allows a more detailed envelope specification than the ADSR method, and is better able to emulate the characteristics of real instruments. The overall MusicSystem envelope is a composite of the various oscillator envelopes in the instrument definition.*

years to come. In any case, it is the most powerful synthesizer available for the Apple II, and it is price-competitive with its closest rival, the ALF unit.

Conclusions

- The Mountain Computer MusicSystem is a flexible, well-designed music synthesizer that provides a combination of features and capabilities currently unmatched by any other Apple II music synthesizer.
- The MusicSystem boards alone provide an interesting avenue for experimentation in computer music for those users who wish to write their own programs.
- The documentation provided by Mountain Computer is complete and comprehensive. In addition to operating instructions, it provides tutorial and theory sections and numerous appendices that cover such categories as the hardware interface, error message causes, and conversion to DOS 3.3.
- The Instrument Definer is a unique program that adds a new dimension to the synthesis process. As much creative effort may be spent defining instruments as was previously spent entering music.
- The two main weaknesses of the MusicSystem are the lack of repeats (musical subroutines) and triplets, or n-tuplets. Hopefully this omission will be rectified in a future software release.
- Other features I'd like to see added are a Play Multiple Songs program, the ability to adjust tempo at play time, and audio feedback in the Music Editor program. ■

References and Further Reading

1. Bondy, Jon. "The Casheab Music Synthesizer." January 1981 *Creative Computing*, pages 30 thru 35.
2. Chamberlin, Hal. "A Sampling of Techniques for Computer Performance of Music." September 1977 BYTE, pages 62 thru 83.
3. Chamberlin, Hal. "Advanced Real-Time Music Synthesis Techniques." April 1980 BYTE, pages 70 thru 94, and 180 thru 196.
4. Newcomb, Steven R and Gooch, Sherwin. "Rise Up, Rachmaninoff." June 1980 *Creative Computing*, pages 66 thru 71. (A good explanation of D/A conversion and sampling theory as applied to music.)
5. Tubb, Phil. "Apple Music Synthesizer." June 1980 *Creative Computing*, pages 74 thru 83. (ALF as described by its designer.)
6. Stanley, W D and Peterson, S J. "Fast Fourier Transforms on Your Home Computer." December 1978 BYTE, pages 14 thru 25.

Planning Your Future Growth?

OMNINET™ Can Help You Today.

OMNINET is the first low-cost high-performance carrier-sense-multiple access local network specifically designed for microcomputers. It provides everything that Ethernet promises for mainframes, but is available now with interfaces to a wide range of popular microcomputers, including the Apple II, DEC LSI-11, and Onyx C-8000.

OMNINET uses low-cost, easy-to-install twisted pair wire that makes both the initial and subsequent installation of computers as simple as hooking up stereo speakers. You can connect up to 64 different computers on a highly efficient 1 megabaud network that doesn't require costly extras like repeaters, isolation circuits, or dedicated network controllers. Microcomputer-based intelligent OMNINET transporters in each computer manage total network operations without stealing processing power or requiring significant software support from the host.

Corvus has helped you expand your personal computer into a powerful business tool with mass storage, low cost backup, and data sharing. Now, we give you an intelligent solution to your local communications needs. With OMNINET's microvirtual circuits, you can accomplish direct intercomputer communications with your microcomputers, a thing that was only dreamed of on mainframes yesterday. Contact your Corvus dealer now for full details.

CORVUS SYSTEMS
2029 O'Toole Avenue
San Jose, California 95131
408/946-7700 TWX: 910-338-0226

What Time Does the Sun Rise and Set?

Bruce Barkstrom
111 Pear Ave
Newport News VA 23607

Do you have to rise before the crack of dawn to go duck hunting? Do you need to know how many hours of sunlight to expect for your new solar collector? Do you want to know if you have enough time to jog ten miles before the sun sets? One way to answer these questions is to use your computer. All you need to know is your latitude, longitude, and the date. The program shown in listing 1 computes the time the sun rises or sets for any date and location on the earth. It uses a precise calculation of the sun's position in its apparent orbit around the earth and relates this to the time of sunrise and sunset by geometry.

The sun's orbital position is found with a general method that might be of use in your next space-war simulation. A general Julian-date calendar is also included, which might be useful in keeping track of days in an accounting program. The times of sunrise and sunset are computed with a method that also gives the amount of solar energy falling on the surface of the atmosphere for a given latitude and date. [*The amount of solar energy reaching the surface of the atmosphere is considerably different from the solar energy actually reaching the surface of the earth. Although the amount of energy actually radiating through the atmosphere can be calculated, it requires more complex mathematics than those used in this article. The solution involves solving a partial differential equation known as the* equation of radiative transfer....**SM**] For the twentieth century, the times computed are accurate to within two minutes.

The fact that the sun rises at different times during the year is not mysterious. It is caused by the tilt of the earth's axis with respect to its orbit around the sun. In the summer, the time between sunrise and sunset is longer than in the winter. The question is: "How much longer?"

Describing Celestial Objects

We first need to understand how astronomers describe where objects are in the sky. They start by assuming that all astronomical objects such as the sun, moon, and stars, can be painted on a large sphere around the earth. If you stand in an open field, your line of sight to the unobstructed horizon intersects this *celestial sphere* in a great circle. The point directly overhead is called the *zenith*, and the point near the North Star (Polaris) where the stars appear to rotate is known as the *north celestial pole*. A great circle running through the celestial poles and the local zenith is called the *local meridian*. These positions and circles are shown in figure 1. The position of the image on the sphere is described by a celestial "latitude" and "longitude," known as *declination* (δ) and *right ascension* (*RA*) (see figure 2).

The celestial sphere rotates once every 24 hours. By observing the angle between the meridian and a point on the celestial equator rotating with the celestial sphere,

Text continued on page 102

About the Author

Bruce R Barkstrom is a practicing scientist with a PhD in Astronomy from Northwestern University. Dr Barkstrom also has an active interest in word processing and computer-aided program design and development. He recently acquired a Cromemco System 3, on which this article and its associated software were written.

When it comes to Quality, Reliability, Price/Performance in CRT's, TeleVideo is "The Value Leader"

TeleVideo®

TeleVideo Systems, Inc.
1170 Morse Avenue
Sunnyvale, CA 94086
408/745-7760
800/538-8725 (outside CA)
TWX 910-338-7633

Santa Ana, CA 714/557-6095; Sunnyvale, CA 408/745-7760; Dallas, TX 214/980-9978; Atlanta, GA 404/255-9338; Bloomingdale, IL 312/351-9350; Boston, MA 617/668-6891; Morris Plains, NJ 201/267-8805; Overseas Office—England, West End, Surrey 44-9905-6464

Listing 1: *The Sunrise-Sunset program written in CBASIC Version 2.*

```
REM                        SUNRISE - SUNSET
REM       This program is intended to compute the time of sunrise and sunset,
REM       as well as the total solar energy incident on the top of the atmos-
REM       phere for a given latitude and longitude at a given time of year.
REM       Comments are welcome addressed to
REM               Bruce R. Barkstrom
REM               111 Pear Avenue
REM               Newport News, VA  23607.
REM       This program requires about 10k of text storage, and about 3.5k to run
REM       when compiled by the CBASIC Version 2 compiler.
          DIM First.Day.of.Month(12)
          FOR I=1 TO 12:READ First.Day.of.Month(I):NEXT I
          DATA 0,31,59,90,120,151,181,212,243,273,304,334
          Pi=3.1415926535898:TRUE%=-1:FALSE%=0:A=1:Debug%=TRUE%
REM ** Compute Julian Date  **********
          DEF FN.Julian.Date(Month,Day,Year)
          Yrs.since.0=Year+4712
          No.of.lp.yrs=INT((Yrs.since.0-1)/4)
          Julian.Date=365*Yrs.since.0 + No.of.lp.yrs
          IF Year>=1583 THEN \
                  Julian.Date=Julian.Date-10: \
                  No.of.cent.yrs.snc.1583=INT((Year-1501)/100):\
                  No.of.cent.lp.yrs.snc.1583=INT((Year-1201)/400):\
                  Julian.Date=Julian.Date-No.of.cent.yrs.snc.1583+\
                          No.of.cent.lp.yrs.snc.1583
               REM ** Deal with month and day **********
          Julian.Date = Julian.Date + First.Day.of.Month(Month) + Day
          IF 4*INT(Year/4)=Year AND Month>=3 THEN \
                  Julian.Date = Julian.Date + 1
          IF Year=1582 AND ((Month=10 AND Day>=15) OR Month>=11) THEN \
                  Julian.Date = Julian.Date - 10
          FN.Julian.Date = Julian.Date
          RETURN
          FEND
REM ** Compute Mean Anomaly **********
          DEF FN.M(T,D)
          M00 = -1.52417+(1.50E-4+3.E-6*T)*T*T+0.9856002670*D
          IF M00>360 THEN M00=M00-360*INT(M00/360)
          FN.M = M00*Pi/180
          RETURN
          FEND
REM ** Compute Obliquity of Ecliptic **********
          DEF FN.epsilon(T)=(23.452294-(1.30125E-2+ \
                  (1.64E-6 - 5.03E-7 * T)*T)*T)*Pi/180.
REM ** Compute Mean Longitude of Perigee **********
          DEF FN.omega(T,D)=(281.22083 + (4.53E-4 + 3.E-6 * T)*T*T \
                  + 4.70684E-5 * D)*Pi/180.
REM ** Compute Eccentricity **********
          DEF FN.eccentricity(T)=0.01675104 - (4.08E-5+1.26E-7*T)*T
REM ** Compute Longitude of Ascending Node of Lunar Oribt *****
          DEF FN.Lunar.Long(T,D)
          Lunar.Long = 259.183275 + (2.078E-3+2.E-6*T)*T*T
          Lunar.Long = Lunar.Long - .0529539222*D
          FN.Lunar.Long = Lunar.Long*Pi/180.
          RETURN
          FEND
REM ** Print time or angle in xx:xx:xx.xxx format
REM **    time.or.angle is assumed to be in radians
          DEF FN.Print.Angle(time.or.angle$,Y$,Angle)
          IF time.or.angle$="time" THEN factor=12: y0$="Hours" \
                   ELSE factor=180: y0$="Degrees"
          x1=factor*ABS(Angle)/Pi:x2=INT(x1):x3=60*(x1-x2):x4=INT(x3)
          x5=60*(x3-x4):x6=.001*INT(x5*1000)
          IF x2<>0 THEN x2=SGN(Angle)*x2
          IF x2=0 AND x4<>0 THEN x4=SGN(Angle)*x4
          IF x2=0 AND x4=0 THEN x6=SGN(Angle)*x6
```

Listing 1 continued on page 98

Listing 1 continued:

```
        PRINT Y$,x2;":";x4;":";x6;y0$
        RETURN
        FEND
REM ** Input Location Information
    Idne2=1
    WHILE Idne2
100     INPUT "Your latitude (Deg,Min,Sec), Pos for N, Neg for S";LatD,LatM,LatS
        Latitude=LatD+(LatM+(LatS/60))/60
        INPUT "E or W, Longitude (0 - 180 Deg,Min,Sec)";Dir$,LonD,LonM,LonS
        Longitude=LonD+(LonM+(LonS/60))/60
        INPUT "Your Standard Time Zone (1-24)";Std.Time.Zone
                Err=0
                IF Latitude<-90 OR Latitude>90 THEN \
                        PRINT "Latitude out of range":Err=Err+1
                IF Dir$<>"E" AND Dir$<>"W" THEN \
                        PRINT "You did not input E or W":Err=Err+1
                IF Longitude<0 OR Longitude>180 THEN \
                        PRINT "Longitude outside the range (0,180)":\
                        Err=Err+1
                IF Std.Time.Zone<1 OR Std.Time.Zone>24 THEN \
                        Print "Std Time Zone outside the range (1,24)":\
                        Err=Err+1
                IF Err<>0 THEN 100
REM ** Revise longitude and standard time zone to be consistent
        Latitude = Latitude*Pi/180.
        IF Latitude>=0 THEN x$="Arctic" ELSE x$="Antarctic"
        IF Dir$="E" THEN Longitude = 360 - Longitude
        Longitude = Longitude * Pi / 180
        Time.Diff=12*Longitude/Pi
        Tot.time.diff = Time.Diff - (Std.Time.Zone - 1)
REM ** Input Date and Check for Correctness **********
      Idne=1
      WHILE Idne
200     INPUT "Date (Month,Day,Year)";Month,Day,Year
                Err=0
                IF Month<0 OR Month>12 THEN \
                        PRINT "Month out of range, input again":\
                        Err=Err+1
                IF Day<0 OR Day>31 THEN \
                        PRINT "Day out of range, input again":\
                        Err=Err+1
                IF Err>0 THEN 200
        Day = Day - .5 + Time.Diff/24
REM ** Compute current Julian Date, and Time since 1900
        J.D.Current = FN.Julian.Date(Month,Day,Year)
        D = J.D.Current - FN.Julian.Date(1,0,1900):T = D/36525
REM ** Compute solar orbit
        ecc = FN.eccentricity(T):M0 = FN.M(T,D):E = M0
        FOR I=1 TO 3
                E = E + (M0 - (E-ecc*SIN(E)))/(1-ecc*COS(E))
                NEXT I
        V = 2*ATN(SQR((1+ecc)/(1-ecc))*TAN(0.5*E))
        IF V<0 THEN V=V+2*Pi
        r = A*(1-ecc*COS(E)):eps = FN.epsilon(T):omeg = FN.omega(T,D)
REM ** Nutation Terms are computed here ******************************
        L1 = FN.Lunar.Long(T,D)
        Nutation.of.Obliquity = (2.5583333E-3+2.5E-7*T)*COS(L1)*Pi/180.
        eps = eps + Nutation.of.Obliquity
        Nutation.of.Longitude = -(4.7872222E-3+4.72222222E-6*T)*SIN(L1)*\
                Pi/180.
REM ** Compute solar declination *****************************
        sine.del = SIN(eps)*SIN(V+omeg)
        cosine.del = SQR(1 - sine.del*sine.del)
        del = ATN(sine.del/cosine.del)
REM ** Compute Equation of Time ********************************
        mean.long=omeg+M0
        IF mean.long<0 THEN mean.long=mean.long+2*Pi
        IF mean.long>2*Pi THEN mean.long=mean.long-\
```

Listing 1 continued on page 100

NO MORE WAITING.

CIS COBOL™ software with FORMS-2™ for Apple II® computers is here. Now. From Micro Focus.

Apple II users . . . the wait is over. And your patience has paid off. Now you can create serious business programs with the world's most popular professional programming language—COBOL. And, run them on the industry standard operating system—CP/M™.

COBOL—the only standard language designed exclusively for business programming.

COBOL gives you programs that are easy to write, easy to read, easy to maintain and easy to learn.

A complete program in 20 minutes.

FORMS-2, a COBOL source-code generator, lets you begin with a blank screen . . . and end with a fully-operational program. FORMS-2 generates standard COBOL code. You can use it as is. Or build on it to create even more sophisticated programs.

Business computer compatibility.

CIS COBOL on Apple II is standard COBOL. (ANSI X3.23-1974) With it, you have the broadest applications flexibility available today. And the most reliable.

Powerful file handling.

You can grow with CIS COBOL. It provides you with all the power of ANSI COBOL file handling. Underlying B-tree technology takes care of large ISAM files . . . fast.

Quick, convenient program development.

With CIS COBOL and FORMS-2, you have your very own low-cost tools that allow you to get work done faster and less expensively than ever before. Features include interactive debug, fast compile-and-go, interactive screen creation and dynamic loading of modules.

GSA approved.

CIS COBOL is certified on Apple II by the General Services Administration. Which means it's been tested, re-tested and tested again . . . all under the most demanding conditions. No wonder it's been chosen for use by over 25 of the world's leading computer manufacturers.

See your Apple dealer for a demonstration.

Don't wait any longer. Get all the details about CIS COBOL and FORMS-2 today. For further information, visit your nearest Apple dealer. Or call us at (408) 248-3982 for a FREE fact-filled brochure.

MICRO FOCUS™
The COBOL Company

Micro Focus, Inc.
1601 Civic Center Dr., Santa Clara, CA 95050
Tel: (408) 248-3982
Telex: 171135 MISSION SNTA

Micro Focus LTD.
58 Acacia Rd., London N.W. 8, ENGLAND
Tel: (01) 722-8843/4/5/6/7
Telex: 28536 MICROF G

Listing 1 continued:

```
         2*Pi*INT(mean.long/(2*Pi))
      y=TAN(0.5*eps)
      y=y*y
      y=(1-y)/(1+y)
      alpha0=omeg+V+Nutation.of.Longitude
      IF alpha0<0 THEN alpha0=alpha0+2*Pi
      IF alpha0>2*Pi THEN alpha0=alpha0-2*Pi*INT(alpha0/(2*Pi))
      alpha = ATN(y*TAN(alpha0))
      Eqn.of.time = alpha-mean.long
      Eqn.of.time = Eqn.of.time - Pi*INT(Eqn.of.time/Pi)
      IF ABS(Eqn.of.time)>.9*Pi THEN \
         Eqn.of.time=Eqn.of.time-SGN(Eqn.of.time)*Pi
      a0=Eqn.of.time+mean.long
      IF a0>2*Pi THEN a0=a0-2*Pi*INT(a0/(2*Pi))
REM ** Print various orbital related quantities if desired *******
      IF Debug%=TRUE% THEN \
      x0=FN.Print.Angle("angle","mean anomaly  ",M0):\
      x0=FN.Print.Angle("angle","eccentric anom",E):\
      x0=FN.Print.Angle("angle","true anomaly  ",V):\
      x0=FN.Print.Angle("angle","obliquity     ",eps):\
      x0=FN.Print.Angle("angle","nutation of ob",Nutation.of.Obliquity):\
      x0=FN.Print.Angle("angle","longitude     ",alpha0):\
      x0=FN.Print.Angle("angle","nutation of ln",Nutation.of.Longitude):\
      x0=FN.Print.Angle("angle","solar declin  ",del):\
      x0=FN.Print.Angle("time","solar R. A.   ",a0):\
      x0=FN.Print.Angle("time","equation of tm",Eqn.of.time):\
      PRINT "eccentricity  ";ecc:\
      PRINT "r             ";r
REM ** Length of Day
      mum = COS(Latitude - del):mun = -COS(Latitude + del):mua = 0
REM ** Refraction Effect computed here
      x0=FN.Print.Angle("time","Tot time diff",Tot.time.diff*Pi/12)
      IF -mum*mun>0 THEN Refrac.corr = 0.0555555556/SQR(-mum*mun) \
              ELSE Refrac.corr = 0:\
              PRINT "The sun's upper limb does not cross the horizon."
      IF Debug%=TRUE% THEN \
              x0=FN.Print.Angle("time","Refraction corr is  ",\
                 Refrac.corr*Pi/12)
      IF mun>mua THEN mua=mun
      IF mum>mua THEN \
              x = SQR((mua-mun)/(mum-mua)):\
              frac.of.day.sun.up = 1 - (2/Pi)*ATN(x):\
              basic.sunset = 12.*frac.of.day.sun.up:\
              basic.sunrise = basic.sunset:\
              basic.sunset = basic.sunset + Refrac.corr + Eqn.of.time*12/Pi:\
              basic.sunrise = basic.sunrise + Refrac.corr - Eqn.of.time*12/Pi:\
              time.basic.sunset = 12 + basic.sunset:\
              time.basic.sunrise = 12 - basic.sunrise:\
              time.sunrise = time.basic.sunrise + Tot.time.diff:\
              time.sunset = time.basic.sunset + Tot.time.diff:\
              fraction.avail.sun = 0.5*((mum+mun)*frac.of.day.sun.up\
                     + (mum-mun)*SIN(Pi*frac.of.day.sun.up)/Pi):\
              PRINT:PRINT:\
              x0=FN.Print.Angle("time","Sunrise occurs at  ",time.sunrise*Pi/12):\
              x0=FN.Print.Angle("time","Sunset occurs at   ",time.sunset*Pi/12)\
          ELSE \
              PRINT "you are in the ";x$;" winter - the sun doesn't rise":\
              fraction.avail.sun = 0.
      PRINT "Sunlight available at the top of the atmosphere is"
      PRINT 1.188864E8*fraction.avail.sun;" Joules per square meter"
      INPUT "If this is the last date, input 0";Idne
      IF Idne<>0 THEN Idne=1
      WEND
      INPUT "If you have no other locations, input 0";Idne2
      IF Idne2<>0 THEN Idne2=1
      WEND
      END
```

Finally, a price-performance breakthrough for mass storage in a one-piece, handsomely styled desk-top computer.

SUPERFIVE™

A product of CMC International

- 5¼'' Micro-Winchester™ 5 Mbyte (formatted) hard disk
- 700K or 350K floppy disk back up
- Dual Z-80 processors with 64K RAM
- Dual RS232 ports
- Complete and ready to run with CP/M™ 2.2
- Also available 10 Mbyte hard disk, 5 MB removable
- 10 Mbyte hard disk SuperTen™

DEALER & OEM INQUIRIES INVITED
Telephone (206) 453-9777

CMC INTERNATIONAL

A Division of Computer Marketing Corporation
11058 Main, Suite 125, Bellevue, WA 98004

Circle 296 on inquiry card.

Listing 2: *A sample run of Sunrise-Sunset.*

```
Your latitude (Deg,Min,Sec), Pos for N, Neg for S 37,0,0
E or W, Longitude (0 - 180 Deg,Min,Sec) W,75,0,0
Your Standard Time Zone (1-24) 6
Date (Month,Day,Year) 9,1,1980
mean anomaly          237 : 54 : 53.025 Degrees
eccentric anom        237 : 6 : 37.387 Degrees
true anomaly          236 : 18 : 34.682 Degrees
obliquity             23 : 26 : 23.519 Degrees
nutation of ob        0 : 0 :-6.947 Degrees
longitude             158 : 54 : 51.928 Degrees
nutation of ln        0 : 0 :-11.323 Degrees
solar declin          8 : 13 : 35.673 Degrees
solar R. A.           10 : 42 : 4.382 Hours
equation of tm        0 : 0 :-1.057 Hours
eccentricity    0.0167180457765
r               1.00907827086
Tot time diff         0 : 0 : 0 Hours
Refraction corr is    0 : 4 : 14.545 Hours


Sunrise occurs at     5 : 30 : 43.307 Hours
Sunset occurs at      18 : 29 : 14.577 Hours
Sunlight available at the top of the atmosphere is
 35208038.2944  Joules per square meter
If this is the last date, input 0 1
Date (Month,Day,Year) 12,1,1980
mean anomaly          327 : 36 : 15.675 Degrees
eccentric anom        327 : 5 : 1.817 Degrees
true anomaly          326 : 33 : 34.599 Degrees
obliquity             23 : 26 : 23.934 Degrees
nutation of ob        0 : 0 :-6.415 Degrees
longitude             249 : 10 : 6.219 Degrees
nutation of ln        0 : 0 :-12.376 Degrees
solar declin         -21 : 49 : 34.492 Degrees
solar R. A.           16 : 29 : 54.062 Hours
equation of tm        0 :-10 : 57.915 Hours
eccentricity    0.0167179436184
r               0.98596584447 9
Tot time diff         0 : 0 : 0 Hours
Refraction corr is    0 : 4 : 42.959 Hours


Sunrise occurs at     6 : 54 : 34.914 Hours
Sunset occurs at      16 : 43 : 29.255 Hours
Sunlight available at the top of the atmosphere is
 16043293.0622  Joules per square meter
If this is the last date, input 0 0
If you have no other locations, input 0 0
A.
```

Text continued from page 94:

you can keep track of the time. For example, if the sun were on the celestial equator, at noon it would be on the meridian. You could measure 90° along the celestial equator between the local meridian and the sun's location at 6 PM; it would be 180° from its starting position at midnight. At dawn, it would be 270° around, and at noon 360°—back to its starting position. The angle between the local meridian and a certain celestial longitude is called the *hour angle, H.*

At any given time, θ_0, the angle between the sun and the zenith of an observer at latitude ϕ, is related to the hour angle and declination of the sun, δ, by the equation

$$\cos(\theta_0) = sin(\phi) \sin(\delta) + \cos(\phi) \cos(\delta) \cos(H) \quad (1)$$

When the sun sets, it is on the horizon 90° from the zenith, so $\cos(\theta_0)$ is 0. Thus, the sun sets when

$$\cos(H) = -\tan(\phi) \tan(\delta) \quad (2)$$

Computing the Amount of Solar Energy

The actual computation of the time of sunrise or sunset is more useful if, instead of solving equation (2), a method is used allowing you to estimate the amount of energy the sun radiates to the atmosphere during a day.

A BIG HAPPENING FOR YOUR APPLE ...



LOBO's New Hard Disk Memory Systems

Mass memory for your APPLE™ ... as big and fast as a charging Elephant ... that's LOBO's new family of disk memory systems.

Now you can connect up to four 5¼-inch hard disk drives (6 megabytes each*), and/or four 8-inch hard disk drives (up to 20 megabytes each*), and/or four 14-inch disk drives (up to 58 megabytes each*) to your APPLE, all at the same time. --You'll never have to run out of memory again.

Every LOBO Hard Disk Memory System comes complete with hard disk drives, size-compatible floppy disk drive (except 14-inch model), controller, DMA interface, chassis/power supply, cables, and DOS. And, they are compeletely compatible with most applications software on the market today.

Furthermore, LOBO's enhanced version of APPLEDOS™ permits you to build a data file as large as 16 megabytes.

No, you don't have to go on Safari to find mass memory. For the **BIG** story on Hard Disk Memory Systems, visit your nearest LOBO keeper, or contact our *" Maha Roger"*



**unformatted*

APPLE and APPLEDOS are trademarks of APPLE Computer Co.

LOBO drives INTERNATIONAL

LOBO DRIVES, INT'L
354 South Fairview Ave.
Goleta, CA 93117
(805) 683-1576

Circle 209 on inquiry card.

The power input to a small portion of the top of the atmosphere is proportional to $\cos(\theta_0)$. For the time between sunrise and noon (or noon and sunset), θ_0 is a monotonically decreasing (or increasing) function of time. Thus, in a time increment dt,

$$d(\cos(\theta_0)) = -\cos(\phi)\cos(\delta)\sin(Ct)\,C\,dt \qquad (3)$$

where $C=2\pi/24$ hr. In this same time increment, the amount of energy per unit area that reaches the top of the atmosphere is

$$dP = E_0\cos(\theta_0)\,dt \qquad (4)$$

E_0 is the *solar constant*, which is about 1370 watts per square meter. By converting to $\cos(\theta_0)$ as the variable of integration, you can compute both the time of sunrise (or sunset) and the amount of energy per unit area arriving during the hours of daylight.

The number of hours of sunlight is given by

$$LD = 24\left(1 - \frac{2}{\pi}\arctan\left(\sqrt{\frac{\mu_a - \mu_n}{\mu_m - \mu_a}}\right)\right) \qquad (5)$$

and the amount of energy is given by

$$AE = (1.184 \cdot 10^8)\left(\frac{a}{r}\right)^2\left\{\frac{1}{2}(\mu_m + \mu_n)LD + \frac{(\mu_m - \mu_n)\sin(\pi LD/24)}{2\pi}\right\} \qquad (6)$$

where LD is the length of day in hours, AE is the amount of energy per unit area in joules per square meter (J/m^2), a is the mean distance from the earth to the sun in kilometers, and r is the actual distance from the earth to the sun in kilometers. (To convert this figure to Btu per square feet, multiply by $8.80598 \cdot 10^{-5}$. About half of this energy reaches the surface on a clear day.)

In these expressions, μ_m has been used for cos(max of θ_0 during the day), μ_n for cos(min of θ_0 during the night), and μ_a for max(0,μ_n). In terms of latitude and solar declination

$$\mu_m = \cos(\phi - \delta) \qquad (7)$$

while

$$\mu_n = -\cos(\phi + \delta) \qquad (8)$$

Observe that μ_m can be less than zero during the arctic winter (δ less than zero and ϕ close to 90°) and μ_n can be greater than zero during the arctic summer (δ greater than zero and ϕ close to 90°). These conditions prevent us from computing a negative square root in equation (5).



Figure 1: *Positions on the celestial sphere for an observer at latitude ϕ. For observation from the earth, the points of reference are the* horizon *and* zenith. *The horizon has attached to it the compass points N, S, E, and W. The zenith is always directly overhead. The* meridian *is the great circle extending from N on the horizon through the zenith to S on the horizon. The* celestial sphere *rotates from E to W about the* north celestial pole. *When the sun is on the meridian, it is local solar noon, and the hour angle H is 0. As time passes, rotation of the celestial sphere carries the sun toward the western horizon, and the hour angle increases. At the same time, the solar-zenith angle also increases. When the sun is on the horizon (at sunrise and sunset), $\theta_0 = 90°$.*



Figure 2: *The position of an object is described by its* declination *and* right ascension. *For a person located at the North Pole, the north celestial pole is directly overhead. A person located on the equator has the celestial equator directly overhead. The vernal equinox (March 21) is where the sun intersects the equator in its apparent orbit around the earth.*



NO MATTER WHAT MIRACLES YOUR COMPUTER MAY PERFORM, THE 739 PUTS IT DOWN ON PAPER.



To get full advantage of your computer's versatility you must have an equally versatile printer. One designed for your office. Suited to your budget. And built to deliver all the management information, correspondence – and graphics – that good management demands.

Introducing the Centronics Model 739.

Backed by Centronics 12-year reputation for rugged dependability and superior service, the Model 739 brings big printer technology into your office environment. Still, its desk-top size, super-quiet operation and handsome styling effectively mask the 12-hour-a-day workhorse within.

You can feed the Model 739 three different ways, fan-fold forms, bond sheets, roll stock. But that's just the beginning.

It's the end result that impresses you most. The high density dot matrix characters produce printout of superior quality. Correspondence quality. True descenders, proportionally spaced and justified right and left.

In short, one printer that will meet all your needs for under a thousand dollars.

The Centronics Model 739. The strong, silent miracle-maker. You can see and try it at your nearest dealer. Or contact Centronics Data Computer Corp., Dept. B, One Wall Street, Hudson, N.H. 03051. (603) 883-0111.

CENTRONICS® PRINTERS

THE REALITY OF COMPUTER TECHNOLOGY

Circle 56 on Inquiry card.

Where's the Sun?

To use equations (5) and (6), you must know both your latitude, ϕ, and the solar declination, δ. Very roughly,

$$\delta = 22.5 \cdot \sin(360f - 90) \quad (9)$$

where f is the number of days since January 1 divided by 365.25, δ is in degrees, and the argument of the sine function is also in degrees.

This might be satisfactory if you just wanted to know where the sun is. But if it is used to estimate the time of sunrise and sunset, you find large errors (about twenty minutes) in the local solar time of sunrise and sunset. There are basically two kinds of difficulty. The first is that the sun's apparent orbit around the earth doesn't fall on the celestial equator. Once this is recognized, you realize that time is kept by a fictitious *mean sun* moving steadily along the equator. As a result of the nonzero orbital inclination, the right ascension of the actual sun rarely agrees with that of the mean sun.

The second difficulty is that when the earth is closer to the sun in January, it moves faster in its orbit than it does in June, when it is farther away. The correction for these two effects is known as the *equation of time.*

The proper way to find the sun's location on the celestial sphere is to find its position in apparent orbit around the earth, then find its right ascension and declination. This is not as difficult as it sounds. The basic orbit description requires only the actual distance from the earth to the sun, r, and the angle between the sun and its orbital position at its closest approach to earth. This angle, V, is known as the *true anomaly.*



Figure 3: True anomaly (V), eccentric anomaly (E), *and* mean anomaly (M). *The position of an object in orbit is given by radius r and angle V. By using the properties of an ellipse and a circle with radius a, it can be shown that $r=a(1-e \cdot \cos(E))$, where e is the orbital eccentricity. The mean anomaly (M) is the angle swept out in a circle of radius $a \cdot \sqrt[4]{1-e^2}$ by a radius vector so that the area swept out by that radius (crosshatched area marked as M) increases at the same rate as that of r for the elliptical orbit (crosshatched area marked as V). See the text for more details.*

You can compute V (giving the true position of the sun) through calculations geometrically equivalent to the diagram in figure 3. The apparent orbit of the sun is given by the ellipse in this figure, with earth not at the center of the concentric circles but at one of the foci of the ellipse. (For purposes of illustration, the "flatness" of the ellipse has been exaggerated; in truth, the ellipse is almost a true circle, and the focus where the earth lies is much closer to the center of the concentric circles.) Taking the intersection of the axes of the ellipse as a center, the dotted circle (with radius $a \cdot \sqrt[4]{1 - e^2}$) is the path of the imaginary mean sun, traveling at a constant speed along its orbit. The larger, solid circle has the same center but with radius a, which is the length of the semimajor axis of the ellipse.

V can be found by calculating two other angles: the mean anomaly, M, and the eccentric anomaly, E. Although the calculations are involved, the result is this: the area traced out by the mean sun from perigee to its current location (the crosshatched area traced out by angle M) is equal to the area traced out by the real sun from perigee to its current location (the crosshatched area traced out by angle V). The eccentric anomaly, E, is calculated as an intermediate step from M to V.

(Actually, the angle M must be adjusted. Its true value, in degrees, for f days into the year is

$$M = 360f + \epsilon' - \Omega \quad (10)$$

where ϵ' is the *mean longitude of the sun* and Ω is the *mean longitude at perigee.*)

An object with a position described by M can be geometrically related to another object moving at a con-



Figure 4: *Relation between the celestial equator and the apparent solar orbit. The sun's apparent orbit does not lie in the plane of the celestial equator. The angle between these two planes is the* obliquity of the ecliptic (ϵ). *The sun is closest to the earth at* perigee, *which occurs about January 20. Ω is the angle along the solar orbit from vernal equinox to perigee (about 280°).*

The tool you need to chop your software backlog can be yours now

TRAM™

TRAM Drastically Cuts Development Time and Can Increase Your Productivity by 2000%

TRAM is an advanced TRansaction Access Method developed in PL/I to run on a variety of CPU's and operating systems. With its screen manager, you are completely freed from the burdens of screen communication such as location, length, rendition and even text itself. In addition, TRAM takes care of full data validation, default value generation and housekeeping of past values.

Look at what TRAM can do for you:

TRAM will assist you in design:

TRAM forms, kept with your specifications, describe in detail the layout, along with the information and processing required to get and validate data. This documentation is of tremendous help when modification is required.

As an option, TRAM provides a multiple-level up-and-down generalized menu and chaining system allowing you to create tree-structured applications along with parameter passing.

TRAM will boost your productivity:

TRAM takes care of line-column positions and all video attributes. TRAM has a unique "no show" feature which extends the versatility and scope of your software. TRAM has a powerful exception processing handler. TRAM controls protected areas and echoing. TRAM formats and redisplays accepted data. TRAM retains past values for each item. TRAM builds default values based on past events. TRAM checks input for consistency, magnitude, match in a predefined list and even provides an interface for a search against your own external files, or, as an option, against a built-in fast direct access code file.

All those benefits lead to a deep reduction in the actual number of lines you have to code.

TRAM will give you environment freedom:

All TRAM features can be used on any display video terminal with cursor addressing. TRAM will also work on a variety of CPU's and operating systems from micros to minis and even mainframes. Any displayable text is program independent and can be in any foreign language. Even more, the date format can be any arrangement of day, month and year, with or without month spelling. And the decimal point is what you want it to be. The menu option gives you drive independence: programs, parameters and data files are freely scattered on different disk drive, with run-time choice.

CHECK IT BEFORE YOU BUY

Ask for the demo kit and you will see how a 2000 line program is reduced to 100. Send the coupon below, along with $50 and here is what you get:

- The screen generator and editor. You will immediately start creating and editing your own screens.
- The screen examiner. You will display and examine your new screens and see TRAM features at work.
- The utility programs you need to adapt TRAM to your environment.
- The demo program with source listing and documentation.
- The full TRAM screen manager manual set.
- A sample of TRAM screen forms.

The demo kit is for Z80, 8080 CP/M based systems with a minimum of 48K and comes on an 8" single side single density soft sectored diskette. TRAM's screen manager price is $295 and can be yours for $245 if bought less than 30 days after the demo.

Purchase price includes a 6 month maintenance and update period.

So act now to see how TRAM will solve your problem.

Concentrate on your application, TRAM concentrates on the technical burden.

TRAM is available now for Z80, 8080 CP/M and MP/M systems with 48K minimum and requires the PL/I-80 compiler (or the PL/I-80 run-time library if your application is not in PL/I).

Coming soon are versions for 8086/8088, Prime Computers, Data General, Digital Equipment (LSI 11, PDP 11 and VAX), IBM and others. Coming soon also are the multi-key multi-user file management system, the report writer, the file inquirer and the transaction processor.

REDDOX™

REDDOX CORPORATION
215 CHAPEL CREST TERRACE, PITTSBURGH, PA 15238
PHONE (412) 963-6532 TELEX 866 555

(CP/M, MP/M and PL/I-80 are registered trademarks of Digital Research)

It isn't just for small business anymore!

PLEASE SEND ME:

Qty.		Price ea.
☐	TRAM's screen manager (disk & doc)	$295
	+ code file option	75
	+ menu option (with doc)	100
☐	TRAM's menu system alone	150
☐	TRAM demo kit	50
☐	TRAM's screen manager - documentation only	30
☐	TRAM's menu system - documentation only	20
☐	PL/I compiler & run-time library (disk & doc)	500
☐	PL/I run-time library (disk & doc)	100
	PA residents add 6% tax	______
	shipping and handling	3
	TOTAL	______

I understand that if I decide to buy TRAM's screen manager in less than 30 days after the demo, $50 credit will be applied towards the total amount. I understand also that a signed software license agreement is required and that purchase price includes a 6 month maintenance and update period.

Send check or money order to Reddox Corporation, Dept. B3 - 215 Chapel Crest Terrace, Pittsburgh, PA 15238

NAME ________________________________

ADDRESS ________________________________

CITY ____________ STATE ________ ZIP ________

Circle 337 on inquiry card.

stant rate around an elliptical orbit with the same semimajor axis. The angle between perigee and the position of this second object is known as the eccentric anomaly, E. It is related to M by the transcendental equation

$$E = M - e \sin(E) \quad (11)$$

where e is the *orbital eccentricity* (a dimensionless constant). For the earth, e is small, and Newton's method is sufficient for solving equation (11). You start by assuming that

$$E = M \quad (12)$$

and then iterate a few times with the equation

$$E = E + (M - (E - e \sin(E)))/(1 - e \cos(E)) \quad (13)$$

Once E is available, V can be found using the relationship

$$V = 2 \arctan(\sqrt{(1 + e)/(1 - e)} \cdot \tan(E/2)) \quad (14)$$

If you are interested in solar energy, the correction for the distance to the sun is available directly, since

$$r = a(1 - e \cos(E)) \quad (15)$$

and a is the semimajor axis of the orbit. Equations (10) and (12) through (15) are general and can be used for orbits other than the sun's apparent orbit around the earth. For a derivation, see sections 67 and 68 of *Textbook on Spherical Astronomy* by W M Smart (see reference 4). You might want to try these equations for simulating the orbital elements of comets and for spacecraft in spacewar games.

With the true anomaly available, you can find the solar declination from additional orbital geometry which relates Ω and the *obliquity of the ecliptic*, ϵ (ie: the angle between the earth-sun orbital plane and the celestial equator). The relationship is

$$\sin(\delta) = \sin(\epsilon) \cdot \sin(V + \Omega) \quad (16)$$

The Solar Ephemeris and the Julian Date

Equations (12) and (5) are not entirely accurate. For precise computation, you should use

$$M = -1.52417 - (1.5 \cdot 10^{-4} + 3 \cdot 10^{-6}\, T)\, T^2 + 0.9856002670\, D \quad (17)$$

where T is the *Universal Time* since January 1, 1900 in Julian years of 365.25 days, D is the number of Julian days since that date, and the mean anomaly M is in degrees. The longitude of perihelion is

$$\Omega = 281.22083 + (4.53 \cdot 10^{-4} + 3 \cdot 10^{-6}\, T)\, T^2 + 4.70684 \cdot 10^{-5} \cdot D \quad (18)$$

CRYSTALWARE

12215 MURPHY AVENUE,
SAN MARTIN, CALIFORNIA 95046

THE FINEST IN FANTASY GAME SOFTWARE

APPLE	ATARI	PET	TRS-80
48K — w/disk	48K — w/disk	32K — w/disk	48 — w/disk

SPACE GAMES — Climb aboard the Starship Herman

GALACTIC QUEST Warp through the 64 solar systems in Hires graphics with Crystalsonics sound. Fire lasers and rifter pods as you battle the Vegans in real time simulation. In Galatic Quest we have attempted to combine the best elements of a Star Trek type game with one similar to Space Trader. What is Skishi and where is the Pleasure Planet? In some systems, lurking behind swarms of asteroids, are Space Pirates who will gut your ship and leave you a derelict in space. To win Galactic Quest you must be shrewd a business man as well as a top notch warrior. $29.95

LASAR WARS — Attacking aliens in 3D. Thousands of approach simulations and 10 levels of difficulty. Three kinds of invader craft scored by size and attack mode. An exciting Invaders type game with perspective and sound. For fantasy enthusiasts from 8 to 80. $29.95

SANDS OF MARS — You embark on the Maiden Voyage of the Starship Herman. This game takes up almost 200K and uses 2 disks. It includes more than 300 Hires screens animated scenarios, a 3 dimensional maze, and a Martian labyrinth drawn entirely with hexagons. The takeoff and landing sequences are paddle or joystick controlled for the Apple and Atari and the game has 5 full scenarios. Once you land on Mars, you wander through fields of Sasquati and Degwat. Beware of the Vishu and the Lizardmen of Meshim. Seek the wise Mudra and unlock secrets hidden for centuries. Glyphs written on the Martian Sand hold the key to the mystery for which we offer $100 to the first to solve it. To answer a question we have been asked many times — yes, Sands of Mars attempts to fully utilize the sound and graphics capabilities of the Apple and Atari to their max! $39.95

ADVENTURES — Cross the threshold to new worlds.

HOUSE OF USHER —Walk the dreaded corridors of the deadly House of Usher. Complete with 40 rooms and hundreds of aggressive monsters and unique treasures. This is not your typical text adventure game but goes far beyond that, with animated monsters and a visual display of each room. We believe this to be the first indoor-outdoor game ever written for a microcomputer game which includes graphics. You may choose to wander through Usher's scenic garden paths or brave the perils of the graveyard and descend into the crypt. Beneath the house there are labyrinths, shrinking rooms, and torture chambers with no doors or windows. Your character may pick up, drop, or use objects, fire arrows, or run frantically for the door when pursued by some loathsome creature. As the old grandfather clock ticks away, you will have until dawn to solve the Usher Mystery and win a real live $100 prize! $24.95

IMPERIAL WALKER (ATARI 16K) — For you Atari people out there, here's a fantastic game pack of 4 games with revolutionary new graphics routine and Crystalsonics. As Luke Skywalker you have taken control of an All Terrain Armored Transport and with your lasers are fending off the Imperial attack forces. Written especially for Atari by Mike Potter. The game pack also includes Laser Nim, Auto Race, and Gunfight. Will run on Atari 400 or 800 with disc and Joysticks. $29.95

FANTASY LAND 2041 (Coming June 1) — Step with us through the Crystal door into the world of tomorrow's fantasy. In the great Outback of Australia in the year of 2041, will be built the greatest Adventureland of all time. Through your computer, you can experience six separate worlds of fantasy. These programs will take up more than 500,000 bytes of memory and fill 6 disks. Many of the options may be played by up to six players and in many cases against the computer itself. $59.95

WAR GAMES

WORLD WAR III — This is a three scenario war game in Hires graphics with sound. It is not merely the conversion of a board game to computer, nor are your pieces represented by lifeless text charcters. It may be played by two persons and takes about 8 hours to complete. The rules are simple enough that you won't have to spend several days reading your manual before you can play. It contains 2 world maps and a fairly detailed map of the Iran-Iraq battle field. All scoring, animation, and positions are handled by the computer — no separate tablets to fool with. Moves are input by both players in series of 3 and when the space bar is pressed the battle becomes animated. A must see to believe $29.95

WATERLOO (Coming July 1) — A war game with graphics very similar to World War III. We have attempted to make this as detailed as possible, down to what each individual is wearing, his line of sight, and the number of bullets he has fired. It will occupy two disks and may be saved over a period of weeks. We will be publishing more information on this in BYTE MAGAZINE in July. $49.95

And for you PET Users let us introduce you to . . . **VIGIL** A brand new language for the PET computer: Video Interactive Game Interpretive Language. Make your own shape tables in 80 x 50 graphics. Write your own exciting games with sound, using this versatile tool by Roy C. Wainwright. With this package are 9 full length graphic games. Space War, Maze, and many more. VIGIL is now in the PET world and because of its possible application even by the beginner, it's a fun language. Available only on disk/32K PET $99.95

Order line open 24 hrs / day (408) 683-0696

VISA — We accept VISA & Mastercharge — master charge

where Ω is in degrees.

You can also write the obliquity of the ecliptic, which is the angle between the celestial equator and the earth's orbital plane, as

$$\epsilon = 23.452294 - (1.30125 \cdot 10^{-2} \cdot T + (1.64 \cdot 10^{-6} - 5.03 \cdot 10^{-7} \cdot T) \cdot T^2) \quad (19)$$

while the orbital eccentricity is

$$e = 0.01675104 - (4.18 \cdot 10^{-5} + 1.26 \cdot 10^{-7} \cdot T)\,T \quad (20)$$

It takes the sun 365.2596413 days to increase M by 360°, a period known as the *anomalistic year*. This is the time required for the sun to return to the same point in its orbit—perigee. However, as equation (18) shows, the zero-point for measuring the position of perigee moved 61.892 seconds of arc during the year. As a result, the time required for the sun to return to the same longitude is nearly 365.2422 days. You could repeat the position of the sun without correcting for this nonrational period only if the number were exactly 365 days.

The first-order correction is to add 0.25 days per year, one day every four years. This correction was instituted by Julius Caesar, resulting in the *Julian* calendar. However, 365.25 days is 0.0078 days per year too long. To improve the fit, Pope Gregory XIII decreed that October 5, 1582 was to be called the 15th and that, thereafter, three century leap years would be ignored every 400 years (ie: all leap years ending in 00 not divisible by 400). England did not adopt the change until 1752, when riots broke out because the rioters believed their lives were being shortened by twelve days.

Astronomers wish to be spared such complications, and they have agreed to keep track of the days continuously, beginning with January 1, 4713 BC. January 1, 4712 BC is day 366, January 1, 4711 BC is day 731, and so on. To compute the Julian date is not difficult. You start by taking 365 days times the number of years since 4713 BC. To this, add the number of leap years. In the years since 1581, the proper number of excess leap years must also be subtracted.

Anomalistic year: *The period of time (365.2596413 days) for the sun to increase the mean anomaly (M) by 360°.*
Celestial sphere: *An imaginary sphere around an observer positioned on the earth on which can be placed astronomical objects such as the sun, the moon, the planets, and the stars.*
Declination (δ): *The angular distance (north or south) from the celestial equator of an object located on the celestial sphere.*
Ecliptic: *The apparent annual path of the sun across the celestial sphere.*
Hour angle (H): *The angle between the local meridian and the right ascension (RA) of a celestial object.*
Local meridian: *A great circle running through the celestial poles and the local zenith.*
Mean anomaly (M): *The angle between perigee and a fictitious sun moving in a perfectly circular orbit at a constant speed.*
Mean sun: *A fictitious object used for calculating time because the real sun's apparent orbit around the earth does not fall on the celestial equator and the sun does not move at a constant speed in its apparent orbit.*
North celestial pole: *The point near the North Star (Polaris) around which all the other stars appear to rotate.*
Obliquity of the ecliptic: *The angle between the earth-sun orbital plane and the celestial equator.*
Orbital eccentricity: *An orbit of a celestial body deviating markedly from a circle.*
Perigee: *The point in the orbit of an object when it is closest to the earth.*
Perihelion: *The point at which the earth is closest to the sun.*
Precession of the equinoxes: *An effect caused by tidal friction which acts as a torque on the earth's rotation and causes the axis to precess like a top or gyroscope.*
Right ascension: *The east-west position of an object on the celestial sphere relative to a given reference point called the vernal equinox.*
True anomaly (V): *The angle between the sun and its orbital position at its closest approach to earth.*
Zenith: *The point directly overhead on the celestial sphere.*

Some Physical Complications

In computing the time of sunrise or sunset, there are two major corrections to the procedure described so far: the *equation of time* and *refraction*. With the advent of accurate clocks, timekeepers have invented a fictitious *mean sun*, located on the celestial equator, which advances at the same rate as the mean solar longitude. The solar position in its apparent orbit must be put into right ascension to find how far ahead or behind the true sun is with respect to the fictitious mean sun. The difference in right ascension is known as the equation of time. To compute it, simply compute the solar right ascension, using the relation

$$\tan(SRA) = \frac{1 - \tan^2(\epsilon/2)}{1 + \tan^2(\epsilon/2)} \tan(SL) \quad (21)$$

where SRA is the solar right ascension and SL is the solar longitude, both expressed in degrees. The equation of time is the difference between the solar right ascension and the right ascension of the fictitious mean sun.

The other significant factor is refraction. Although it has been assumed that the sun could be treated as a point mass for the orbital calculation, it subtends about one-


Take Your Cue From Vista . . .
When it comes to Apples, take your cue from Vista's A800 Eight-Inch Floppy Disk Controller. The A800 offers a cost-efficient approach to software compatible disk memory expansion for your Apple II® computer. The A800 Controller enables Apple II users to access up to five megabytes of online storage through conventional disk operating (DOS) commands.
The Control and DMA Logic provides high speed (1 microsecond per byte) transfer of data from the disk drive directly to the Apple II memory without processor intervention. Plus, the Phase-Locked Loop Data Separator provides the ultimate in data reliability.
AND THERE'S MORE.
The controller is compatible with the most popular disk operating systems for the Apple II computer. It also interfaces to all Shugart/ANSI Standard Eight-Inch Floppy Disk Drives. The A800 provides complete IBM format compatibility in both single and double-density modes.
It's a Sure Shot.
THE HOT SHOT AT A COOL PRICE.
The A800 is reasonably priced at $595. A price you can't beat when you compare its quality and performance.
CALL YOUR SHOTS.
Vista offers you a complete line of peripheral equipment to maximize the capabilities of your Apple system including: High capacity Mini-floppy Disk Drives, the Vista Music Machine 9 and the Vista Model 150 Type Ahead Buffer. In addition, Vista offers a line of advanced components fully compatible with the TRS-80* and S-100 based computers.
Vista Computer Company
1317 E. Edinger Avenue
Santa Ana, CA 92705
(714) 953-0523
Call Toll Free 800-854-8017
® Apple II is a registered trademark of Apple Computers, Inc.
* TRS-80 is a trademark of Radio Shack, A Tandy Co.

half degree in the sky. As the sun rises and sets, the rays from different portions of the disk are bent different amounts by refraction in the earth's atmosphere.

As a result, the center of the solar disk must be 51 seconds of arc below the horizon before the upper limb of the sun disappears. The first-order correction to the hour angle in equation (2) is provided by expanding the equation for a correction in H that depends upon having $\theta_0 = 90° + 51$ arc seconds. The number of minutes by which the sun's upper limb rises earlier or sets later is roughly given by

$$\triangle H = (51/15)\sec(\phi)\sec(\delta)\operatorname{cosec}(H) \qquad (22)$$

Changes in Orbital Elements

As we go forward or backward in time, the other planets and the moon act on the earth and its orbit to change the orbital elements. One sign of these changes is the *precession of the equinoxes*, which is the major cause of the 61 arc-second advance per year of the longitude of perihelion that has been noted.

Most of this effect is caused by the tidal friction, which acts as a torque on the earth's rotation and causes the earth's axis to precess like a top or gyroscope. In addition, because neither the moon nor the other planets lie exactly in the orbital plane and because their force is not uniform, the orbital elements reflect a change in the inclination of the earth's orbit. These changes appear in the equation for the ephemeris as terms in T and are known as *secular terms*.

Besides the secular terms, the earth wobbles in its motion in response to forces exerted by the moon on the mass distribution of the earth. The motion is not too large, but it is much faster than the motion accounted for by the secular terms. The largest element of the nutation (wobbling) is included in the program listing. The remaining terms are found in the *American Ephemeris and Nautical Almanac* (see reference 2) or in Smart's *Spherical Astronomy* (see reference 4).

Time Zone Correction

There is one more substantial correction to make. Most of us use standard time. The same time is kept for all points in a standard time zone. Standard time divides the world into twenty-four zones of longitude, each about 15° wide. The boundaries are not exactly longitude lines. They are arranged to miss centers of population.

In order to refer to the correct Julian date, you must have the time difference between the longitude of interest and both the Greenwich meridian and the standard time zone. The time difference between the standard meridian and the longitude of interest (LG) is

$$TD = \begin{cases} (24 \cdot LG)/360 & \text{if } LG \text{ is west of the Greenwich meridian} \\ \text{or} & \\ 24 - (24 \cdot LG)/360 & \text{if } LG \text{ is east of the Greenwich meridian} \end{cases} \qquad (23)$$

HOOK 3 WINNERS

DOLPHIN

$139.00
WINNER #1

$159.00
WINNER #2

$179.00
WINNER #3

data ed

WATCH THIS SPACE FOR COLOR WINNER

By TECO

DEMAND THESE UNITS FROM YOUR DEALER!

Data-Ed
18 Bridge Street
Salem, NH 03079
603-893-2047 (collect)

VISA
master charge

____ TM-12GX Monitors at $179.00 plus 2.75 shipping
____ TM-12G Monitors at $159.00 plus 2.75 shipping
____ TM-12 Monitors at $139.00 plus 2.75 shipping

Name ____________________
Address ____________________
City, State, Zip ____________________

☐ Please send OEM information about your low cost custom fit smart printers.
☐ Check or Money Order enclosed
☐ C.O.D. Orders Accepted
☐ Bill my-☐ VISA-☐ Mastercharge

Card No. __________
Exp. Date _____ Bank No. _____
Signature __________

Circle 409 on inquiry card.

where *TD* is the time difference measured in hours. Then, you can refer back to the standard time zone, using the longitude of the standard time zone:

$$TTD = TD - LSZ \cdot \frac{24}{360} \qquad (24)$$

where *TTD* is the total time difference (in hours), *LSZ* is the longitude of the center of the standard time zone, and the ratio 24/360 relates 24 hours per day to the 360° in a circle.

To calculate daylight savings time in any zone, subtract 1 from the zone number. For example, Eastern Standard Time for the United States is centered at 75° 0′ 0″ W longitude and is time zone 6. For daylight savings time, use zone 5 in the program input.

The Sunrise-Sunset Algorithm

The program shown in listing 1 was written in CBASIC Version 2. The features of this language that will strike users of standard BASICs are the long variable names and lack of line numbers. Variable names, which may be up to 31 characters, may be concatenated from shorter phrases by interspersing periods; this allows you to write programs that are considerably more readable than versions of BASIC allowing only 2-character variable names.

The line numbers at the left of listing 1 were added during compilation. The only line numbers in the source code were those connected with error handling on the input. Line numbers are optional when using the IF...THEN...ELSE and similar control structures that enter so prominently into structured coding.

The second set of features that makes programming in CBASIC2 relatively easy is the structured-control features, such as the IF...THEN...ELSE and WHILE...WEND statements. (The WHILE statement executes the loop as long as the stated condition is not zero.) The implementation of these structures is such that no line numbers are required. Within a set of operations, several replacement statements can be strung together by the use of a colon (:) to denote continuation of the activity. Backslashes (\ ) allow comments at the end of statement lines, making it easy to write self-documenting code.

Beyond these features, CBASIC2 contains the ability to define functions that take arguments. Functions must be defined before they are used, as in Pascal, although there is no requirement for all function definitions to occur before the body of the program. CBASIC2 is a well-designed product that fits well with CP/M.

Final Comments

A sample calculation with some intermediate results is shown in listing 2. This program was checked against the *Nautical Almanac and Ephemeris for 1977*. Solar positions appear to be correct within about 10 seconds of arc, the error to be expected by neglecting the short-period terms in the nutation. The sunrise and sunset times agreed with those for 50° N latitude within two minutes at all times of year. The major inaccuracy is in the approximation used for the refraction effect.

There are some simple extensions to this work. With a bit more work, the times of moonrise and moonset could be derived. Beyond this, it should be relatively easy to extend the orbital calculation to other planets, so that a complete computation of the material in the *Ephemeris* would be available. Finally, the amount of sunlight getting through the atmosphere could be calculated. This last task, however, would require considerable extra work.■

References

1. Abell, George. *Exploration of the Universe*. New York: Holt, Rinehart, and Winston, 1975.
2. *American Ephemeris and Nautical Almanac for the Year 1977, The*. Washington: US Government Printing Office, 1976.
3. *Explanatory Supplement to the Astronomical Ephemeris and to the American Ephemeris and Nautical Almanac, The*. Washington: US Government Printing Office, 1975.
4. Smart, W M. *Textbook on Spherical Astronomy*. New York: Cambridge University Press, 1965.
5. Wyatt, Stanley P. *Principles of Astronomy, Third Edition*. Boston: Allyn & Bacon, 1977.

8/16 RAM

FOR YOUR 8-BIT SYSTEM TODAY
FOR YOUR 16-BIT SYSTEM TOMORROW

16K Byte — Fully Static



Quantity 1-9 **$280**

- Can act as either an 8-bit or 16-bit wide memory. Dynamic data bus switching per IEEE Standard.
- Fully static design eliminates system timing problems. Promotes reliable operation with a wider range of CPU cards and DMA devices.
- Easy to Integrate into your system. Addressable on 4K boundaries. PHANTOM, extended addressing, 16-bit operation may be switched off if desired.
- Able to use the full 24-bit address bus of the IEEE S-100 Standard for a 16-megabyte address range. A single switch allows 16-bit addressing for your 8-bit CPU.
- Fast 200 nanosecond memory chips help you keep up with the ever-rising clock speeds of newer CPUs.
- The 8/16 RAM is designed to run at full speed with our 16-bit 8Mhz. 8086 CPU card. And, it has plenty of speed to spare.

OTHER HIGH-QUALITY 8-BIT RAMS

16K PLUS RAM — this fully static RAM has become the standard of the industry. It features 200 nsec. chips and Cromemco style bank select using port 40H. Addressable to any continuous 16K on 4K boundaries. Any 4K block may be disabled. High reliability, low noise design. Prices: 1-9, $280; 10-19, $260.

16K STANDARD RAM — this fully static RAM is frequently used by OEMs in systems which do not require bank select. High reliability, low noise design. Uses 200 nsec. chips. Addressable to any continuous 16K on 4K boundaries. Any 4K block may be disabled. Prices: 1-9, $265; 10-19, $245.

TO ORDER: May be ordered through your local computer store or factory direct. Personal checks, CODs, VISA and MC accepted from within USA. 10-day return privilege on factory orders. Shipping paid by SCP on prepaid USA and Canadian orders. Add $15 per board extra for shipping overseas. All boards fully assembled, guaranteed one year.

Seattle Computer Products, Inc.
1114 Industry Drive, Seattle, WA. 98188
(206) 575-1830

Circle 349 on inquiry card.

Epson Printers



PRINTERS, MONITORS, DISKS

Amdek Color Monitor	369
Amdek Green Screen	159
Amdek/Leedex B/W 12" Monitor	129
Centronics 737	737
Daisey Wheel Printer	1750
Epson MX70	CALL
Epson MX80 FT	CALL
Epson MX80	CALL
NEC Spinwriter #5510	2590
Paper Tiger 445G	725
Paper Tiger 460G	1175
Paper Tiger 560	1495
Silentype w/interface	529
Sanyo 9" B/W Monitor	169
Sanyo 12" B/W Monitor	255
Sanyo Green Screen	309
NEC Green Screen	239
Televideo 912C	669
Televideo 920C	749
Dysan Disks (pkg. 10)	50
Memorex Disks (pkg. 10)	40
Opus Disks (pkg. 10)	30
Verbatim "Gold" (pkg. 10)	35

ATARI 800
PERSONAL COMPUTER SYSTEM

$789

IF **ATARI**® MAKES IT, WE SELL IT

Assembler/Editor	45
Atari 800	789
Atari 400 8K	419
Atari 820 Printer	429
Atari 810 Disk Drive	499
Atari 410 Program Recorder	69
Atari 825 Printer	695
Atari 850 Interface	169
Atari Joystick	18
Atari Paddles	18
Le Stick	35
16k RAM Microtek	99
Microtek 32K RAM	189
Visicalc	180
Basketball	30
Video Easel	30
Super Breakout	30
Music Composer	45
Computer Chess	30
Star Raiders	45
3-D Tic-Tac-Toe	30
Invitation to Programing	17

LEEDEX VIDEO 100
12" Black & White $139

*** MONTHLY SPECIALS ***

CENTRONICS 737
cable extra
$737

25 CPS
$1750
DAISY-WHEEL PRINTER
Starwriter

AVAILABLE FOR IMMEDIATE SHIPMENT



- Print speed — 25 CPS
- Paper width — 381mm (15") max.
- Backed by C. Itoh's 1 yr. limited warranty
- Interface — standard parallel or RS232-C compatible
- Ready-to-use, requiring no changes in hardware or software
- Compatible with sheet feeders & uses industry standard ribbon cartridges
- Excellent letter-quality printing on 3 sharp copies

master charge
THE INTERBANK CARD

TO ORDER. Phone orders invited using Visa. Mastercard or bank wire transfers. Visa and MC service charge of 2%. Mail orders may send charge card number (include expiration date), cashiers check, money order, or personal check (allow 10 business days for personal or company checks to clear). Calif. residents add 6% sales tax. Please include phone number. No COD or PO accepted. APO and FPO include 5% for postage.

FOREIGN ORDERS include 1% handling — shipped air FREIGHT COLLECT only. Credit cards not accepted on foreign orders. All equipment is in factory cartons with manufacturers warranty. Opened products not returnable. Restocking fee for returned merchandise. Equipment subject to price change and availability. Retail store prices differ from mail order prices. WE SHIP THE SAME DAY ON MOST ORDERS!
Please add 3% shipping, handling, and insurance.

VISA®

(714) 579-0330 • MAIL TO: 1251 BROADWAY, EL CAJON, CA. 92021

AUTHORIZED APPLE SALES & SERVICE

COMPUTER SPECIALTIES

DIV. OF COMPUTER METRICS INC.

EXCITING DISCOUNTS

apple® II
16K computer

DISK with CONTROLLER
NEW DOS 3.3 $529
without . . . $445
Nearly Everything
for Apple

$1045

APPLE II 48K
$1095

WE WILL MEET OR BEAT ANY ADVERTISED PRICES ON MOST ITEMS IF MERCHANDISE IN STOCK

APPLE SOFTWARE

Adventure by Microsoft	27
ABM by Muse	22
Alien Rain by Broderbund	22
Applebug Debugger	29
Apple PIE	129
Apple Pilot	129
Apple Plot System	59
Applepost Mailing List System	44
Applesoft Cassette Demos	29
Apple Game Paddles	26
Applesoft Utility Programs	29
Applewriter Word Processor	65
Ascii Express	65
Asteroid Field by Cabalier	19
Autostart ROM Pkg.	59
Controller Bus. Pkg.	514
Cosmos Mission/Space Invaders	24
CCA Data Mgmt.	84
3-D Animation Pack	55
Data Factory by Microlab	129
Desktop Plan II	169
DB Master by Stoneware	209
DOS Tool Kit	65
DOS 3.3 Upgrade	49
Dow Jones Portfolio Evaluator	45
Forth II by Softape	45
Fortran for Language Sys.	159
Galaxian by Broderbund	23
Hi Res Football	33
Head-on	25
Integer Basic Cassette Demos	29
Pascal Language System	459
Peachtree Bus. Pkgs.	CALL
Personal Filing System	84
Phantoms Five	39
Raster Blaster by Budge Co	24
Sargon II Chess Game disk	32
Single Disk Copy Routines	35
Space Game Album by B Budges	39
Space Eggs	25
Star Cruiser	24
Stellar Trek	23
Sub-Logic FS-1 Flt. Sim. disk	34
Supertext II by Muse	129
3-D Graphics/Tool by B Budges	39
Tranquility Base	24
Trilogy by Bill Budge	24
Visicalc II	169
Visilist	CALL
Wizard and the Princess	32
Zork	34

LARGE SELECTION OF SOFTWARE IN STOCK — CALL FOR FREE BROCHURE —

APPLE COMPUTER INTERFACE CARDS

ALS Smartterm	324
Apple Clock/Calendar Card by Mtn. Comp.	225
Applesoft II Firmware Cd.	149
CCS Asynchronous 7710A	145
CCS Parallel Print Cd. 7720A	155
Centronics Interface Cd.	179
Comm. Cd. & DB25 Cable	179
CPS Multifunction by Mtn. Comp.	259
Expansion Chassis by Mtn. Comp.	649
HiSpeed Serial Int. Cd.	155
Integer Basic Firmware Cd.	149
ROMPLUS (keyboard filter extra)	135
Serial Interface Card	139
SSM AIO Serial/Parallel I/O Assembled & Tested	189

ACCESSORIES

A/D D/A Board by Mtn. Comp.	319
Andromeda 16k Ramcard	179
Arith. Processor 7811 A or B	339
COPYROM by Mtn. Comp.	51
Dan Paymar L.C. Kit 1 or 2	55
Extender Board	27
GPIB by CCS model 7490A	259
Graphics Input Tablet	649
Hayes Micromodem*	319
Introl X-10 Remote Control Sys.	239
K & D Joystick for the Apple	47
Keyboard Filter ROM chip	49
M & R Sup-R-Term 80 column board	319
Music System by Mtn. Comp.	479
Programmable Timer CCS 7440A	159
Prototyping Hobby Card	22
ROMWRITER by Mtn. Comp.	149
SuperTalker Speech Synthesizer	239
Symtec Light Pen	214
Versa-Writer Digitizer Drawing System	209
Videx Keyboard Enhancer	115
Videx Videoterm	319
Z-80 Soft Card Microsoft	295

CALL 1-800-854-2833
PHONE ORDERS
MON. - SAT. 8 to 6 P.S.T.

Circle 82 on inquiry card.

MEMBER CHAMBER OF COMMERCE

AUTHORIZED APPLE SALES & SERVICE

computer CS specialties

DIV OF COMPUTER METRICS INC

BYTE's Bugs

A Character Fault

In a table comparison of five low-cost microcomputers (see "The Commodore VIC 20 Microcomputer: A Low-Cost, High-Performance Consumer Computer," by Gregg Williams, May 1981 BYTE, page 46), it is stated that the TRS-80 Color Computer has no graphics characters available, but that the unit's color block is one-quarter normal-character size. To clarify this a bit, the Color Computer (without Extended BASIC) *does* have low-resolution graphics on a 64 by 32 grid. Each of these blocks can be turned on or off individually by using the SET and RESET commands.

Corrupted Interpolation

There are several typographical errors in the second subroutine of "A General Interpolating Graphics Package for the TRS-80," by D K Cohen and D Crowe. (See the November 1980 BYTE, page 296.)

Refer to page 308 of that issue for comparison with these improved program statements:

```
20150 IF A1=Z2-X2/A
  THEN P1=64 ELSE
  P1=-64
20220 PRINT @
  Z5+P1+DU, AX$;
20265 J6=J6+64
20275 W5=J6+A1/2-
  (INT(W3/2)-1)*64
20290 L8=L8+1
20295 PRINT @
  M8+P2,F$(18);
```

In line 20150 the original has F1, which is an undefined variable. In line 20220, the entry ends with a comma, which would cause the screen to scroll up one line when this statement is at the bottom of the screen. Lines 20265 and 20275 have the undefined variable J8 in the original listing. Line 20290 had the undefined L6 as a variable, and 20295 had M6, also undefined.

Thanks to Philip F Jackisch of Royal Oak, Michigan, for pointing out these bugs.

Knight Errant

While attempting to run the FORTH program given in the article "KNIGHT: A Knight's Tour Problem in MMSFORTH," by Ulrich Frei (February 1981 BYTE, page 325), Marcel Kurtagic of Caracas, Venezuela, got the error message

DCONSTANT ? 28 3

running under Version 1.9 of MMSFORTH.

He corrected the problem by inserting the statement "25 LOAD" into block 80, just after ": TASK;" and before "28 LOAD". With this modification, the program ran perfectly. ■

Hurricane Tracking

John E Bailey
24 Hibiscus St
Sulphur LA 70663

Tropical summer weather in Southwest Louisiana occasionally turns into vicious hurricanes. People in this part of the country, keenly aware of the destructive power of these storms, become very cautious when tropical depressions begin developing in the Caribbean or Gulf of Mexico. Local weather forecasters closely follow these weather patterns from their inception. Hurricane tracking charts appear everywhere. They are even printed on the back of the paper bags used at the local grocery stores.

In summer 1979, I began tracking hurricane David while it was far out in the Atlantic. I listened diligently to the daily weathercasts and recorded the storm's location on my grocery bag tracking chart. After several days of manually keeping track of David, I decided that this would be a perfect application for my computer. I wanted to give my program the ability to track different storms by name as they developed throughout the season, tell me the exact direction the storm was traveling, and the distance it had moved since its last recorded position.

At first, I decided to make the mathematics of the program simple by using plane trigonometry to compute storm direction and distance after I input latitude, longitude, date, and time. In fact, I tracked several storms during the 1979 season using this technique with reasonable accuracy. However, not being completely satisfied I checked out a library book that explained the development and use of spherical trigonometry. After several days of studying equations and trial-and-error testing on my computer, I was able to make my hurricane tracking program function more accurately.

Writing and rewriting this program was a great learning experience for me. I had never really worked with spherical trigonometry before. The equations are really quite simple. However, understanding how they work and making them work for you is not quite so simple.

There are two programs written in NorthStar BASIC: CSTORM and HURRICANE. Before running the

Tiny BASIC MICROCOMPUTER
K-8073

The Engineer's Product Development Board Level Computer

LOW COST
POWERFUL/VERSATILE
ENGLISH-LIKE PROGRAMMING

NEW! FIRST TINY BASIC MPU



$388
SINGLE UNIT

K-8073

THIS IS AN ENGINEER'S COMPUTER. Simply attach a CRT, connect 5 volts, and you have yourself one each powerful, versatile microcomputer that YOU can program.

If you're fed-up with board level computers that require expensive development systems plus the skills of an Assembly language programmer, then you need the K-8073. With an on-chip microinterpreter and the extra control devices we designed into the board, you can do your own programming in the most simple English-like language available—Tiny BASIC. Sophisticated application designs can be implemented in hours instead of days or weeks because you have eliminated expensive and time consuming hardware and software costs.

IN ADDITION TO ALL THIS, the K-8073 offers advantages unheard of in other board level computers. Among these are an onboard EPROM Programmer, A Real Time Clock, Autostart, 1K Byte local RAM for variables, 8K Byte EPROM, ART/RC and PPI W/24 line I/0.



8K Byte RAM $232.00

Development Station $195.00

THE K-8073 IS FOR OEM'S AS WELL AS END USERS. Whether you manufacture Industrial Process Control, Environmental or Test/Measurement systems, or simply for your own use, you can count on top quality performance. The K-8073 comes complete with all socketed devices including the powerful F-2 Utilities Firmware and a Hardware/Software manual.

In Industry, Education, or New Product Development, the K-8073 provides you with State-of-the-Art technology for microprocessor efficiency and ease. With a full line of support products, the TransWave line takes care of your every need at the most reasonable prices.

To order your K-8073 or for further information, write or call TRANSWAVE CORPORATION, Cedar Valley Building, Vanderbilt, PA 15486, **(412) 628-6370.**

TRANSWAVE
COMPUTER DIVISION OF UTSC

Listing 1: *Sample output of the hurricane tracking program as it monitored hurricanes David and Fred over a period of several days.*

```
   DAVID'S INITIAL POSITION WAS LAT - 16.9 , LONG - 67.4

DATE    TIME    LAT   LON   DISTANCE AND DIRECTION OF TRAVEL
08/31   12:00   17.7  70.0  181.3 MILES AT  18.2 DEG NORTH OF WEST
08/31   18:00   18.2  70.5   48.0 MILES AT  46.5 DEG NORTH OF WEST
08/31   22:00   18.8  70.7   43.8 MILES AT  72.5 DEG NORTH OF WEST
09/01   05:00   20.0  72.7  155.4 MILES AT  32.8 DEG NORTH OF WEST
09/01   11:00   20.0  74.5  117.6 MILES AT    .0 DEG DUE WEST
09/02   18:00   24.1  77.5  344.3 MILES AT  56.4 DEG NORTH OF WEST
09/02   22:00   24.7  78.4   70.6 MILES AT  36.4 DEG NORTH OF WEST
09/03   00:00   24.9  78.6   18.8 MILES AT  47.8 DEG NORTH OF WEST
09/03   18:00   27.9  80.8  249.4 MILES AT  57.2 DEG NORTH OF WEST
09/04   18:00   38.2  81.1  716.1 MILES AT  88.7 DEG NORTH OF WEST

ACTUAL MOVEMENT HAS BEEN   63.3 DEG NORTH OF WEST
DAVID IS  839.6 MILES AT   43.0 DEG NORTH OF EAST FROM LAKE CHARLES.

   FRED'S INITIAL POSITION WAS LAT - 14.1 , LONG - 54

DATE    TIME    LAT   LON   DISTANCE AND DIRECTION OF TRAVEL
09/01   22:00   17.0  60.6  485.6 MILES AT  25.4 DEG NORTH OF WEST
09/03   15:00   19.0  63.1  215.9 MILES AT  40.5 DEG NORTH OF WEST
09/03   22:00   18.3  64.0   76.7 MILES AT  39.2 DEG SOUTH OF WEST
09/04   18:00   18.1  68.0  264.5 MILES AT   2.4 DEG SOUTH OF WEST
09/09   18:00   22.3  83.7 1064.1 MILES AT  18.5 DEG NORTH OF WEST
09/10   18:00   23.5  83.7   83.4 MILES AT  90.0 DEG DUE NORTH
09/10   22:00   23.6  84.0   20.4 MILES AT  20.4 DEG NORTH OF WEST
09/11   05:00   24.1  84.4   43.1 MILES AT  53.9 DEG NORTH OF WEST
09/11   11:00   24.6  85.1   56.3 MILES AT  38.2 DEG NORTH OF WEST
09/11   14:00   25.0  85.5   37.5 MILES AT  47.9 DEG NORTH OF WEST
09/11   18:00   25.2  85.7   18.8 MILES AT  47.9 DEG NORTH OF WEST
09/11   20:00   25.6  85.8   28.5 MILES AT  77.3 DEG NORTH OF WEST
09/12   05:00   27.3  87.0  139.8 MILES AT  58.0 DEG NORTH OF WEST
09/12   07:00   27.6  87.3   27.8 MILES AT  48.4 DEG NORTH OF WEST
09/11   09:00   27.8  87.3   13.8 MILES AT  90.0 DEG DUE NORTH
09/12   13:00   28.2  87.3   27.8 MILES AT  90.0 DEG DUE NORTH
09/12   18:00   29.1  87.8   69.6 MILES AT  64.1 DEG NORTH OF WEST

ACTUAL MOVEMENT HAS BEEN   31.2 DEG NORTH OF WEST
FRED IS  320.5 MILES AT   10.0 DEG SOUTH OF EAST FROM LAKE CHARLES.
```

Listings 2 and 3 are on pages 126-132.

HURRICANE program, you must first initialize the storm file using the CSTORM program. CSTORM has to be run once for each new hurricane to be tracked. Then run the HURRICANE tracking program. It will ask if there are any new coordinates to add to the data file. If there are, the program will ask you to enter the date in the form (MM/DD), the time in the form (HH:MM), the latitude, and the longitude. You may enter all or as many new coordinates as you want to bring the file up to date. When all new coordinates are entered, type in END, to end the update phase. The program will then generate the latest tracking figures according to the data in the storm file. Listing 1 shows an example of its output. Listing 2 is the CSTORM program and listing 3 is the HURRICANE tracking program. Change lines 560 and 570 to reflect the longitude and latitude of your location and change line 600 to reflect the name of your city or location.

I can't say that I am anxiously awaiting the next hurricane season, but it will be fun and interesting to once again use this program to track the developing storms.■

PRINTERS

EPSON MX-80
Now in stock!
The MX-80 dot matrix printer. Unequalled Epson reliability. Has all the features of the MX-70 plus more power and extra functions. **CALL US**

C-ITOH STARWRITER: LETTER QUALITY PRINTING FOR UNDER $2000!/This daisywheel printer gives high quality at a low price. 25 cps. Parallel and serial interfaces available. **CALL**

NEC SPINWRITER FROM THE FIRST NAME IN LETTER QUALITY PRINTERS/Compumart offers beautiful print quality with NEC Spinwriter Terminals. We carry all models from RO THRU KSR WITH NUMERIC KEYPAD—5510-5530. All versions give unsurpassed hard copy output! **CALL FOR PRICES**

NEW INTEGRAL DATA'S 560 PRINTER/All the exciting features of the 400 series plus 14 1/2" paper capacity. 132 col. graphics printer.
IDS 445. Priced lower than the 440 and equipped with a better print head. With & w/o graphics.
IDS 460. Features include correspondence quality printing, high resolution graphics.
CALL FOR PRICES

CENTRONICS PRINTERS
MODEL 737/The closest thing to letter quality print for under $1000. List $899. **SPECIAL $795.**
737 -1 Parallel Interface
SALE PRICE $695.

PLUS EXCITING REBATE OFFER ON CENTRONICS PRINTERS.

OMNI 810 PRINTER FROM TEXAS INSTRUMENTS **CALL US**
The 820 RO PACKAGE includes machine mounted paper tray and cable. A compressed print option and device forms control are standard features.
THE 820 KSR PACKAGE includes fully ASCII Keyboard plus all of the features of the RO.
CALL FOR PRICES

MONITORS TERMINALS

CLEARANCE ZENITH COLOR VIDEO MONITOR **$349.**

SUPER SELLING TERMINALS FROM LEAR SIGLER/We have the following Lear Siegler terminals in stock at prices too low to print! Call for quotes.
ADM-3A/Industry's favorite dumb terminal for some very smart reasons/
ADM-3A + NEW from Lear Siegler. CALL!
IT IS HERE! It is the new Intermediate Terminal from Lear Siegler.
CALL FOR DETAILS

SANYO MONITORS AT LOW COMPUMART PRICES /Sanyo's new line of CRT data display monitors are designed for the display of alphanumeric or graphic data.

9" SANYO B/W	**$169.**
12" SANYO B/W	**CALL**
12" SANYO W/ GREEN SCREEN	**CALL**
13" SANYO COLOR	**CALL**

NEC MONITOR/RECEIVER/
Composite video using BNC connectors, 8-Pin connector for VCR/VTR video loop In/Out and television reception. **CALL US!**

Visit our giant
ANN ARBOR STORE
1250 North Main Street
Ann Arbor, Michigan

FREE MICRO/DEC LS1-11 CATALOGS
Send for them!

CALCULATORS MISC

HP-41C CALCULATORS
MEMORY MODULES for storing programs of up to 2000 lines of program memory.
"EXTRA SMART" CARD READER. Records programs and data back onto blank magcards.
THE PRINTER. Upper and lower case. High resolution plotting. Portable thermal operation.
APPLICATION MODULES
CALL FOR PRICES ON ALL

NEW SUPER 41-CV SYSTEMS with Quad RAMS built-in. Maximum memory on-board leaves slots open for Application Pacs and peripherals.
+ CARD READER
+ CARD READER + PRINTER
QUAD RAMS equivalent to four Memory Modules all packed into one. **CALL ON ALL**

MATROX PRODUCTS/Compumart stocks the complete line.
CALL ON SPECS

DEC LSI-11/Compumart now offers the entire product line.
CALL FOR PRICES AND DELIVERY

NOVATION CAT ACOUSTIC MODEM Answer Originate. **CALL**
NEW! D-CAT Direct Connect Modem from Novation. **CALL**



NEW! GILTRONIX RS 232 SWITCH/
The ultimate in flexibility. You can connect three peripherals to one computer or three computers to one peripheral. Switches the eight most important RS 232 signals.
CALL ON PRICE

DYSAN DISKETTES/Single side, single density. Hard or Soft Sector **$5. ea.**
MEMOREX 3401's/5 1/4" disks **$3.25.**
/with hub ring for Apple **$3.50.**
MEMORY INTEGRATED CIRCUITS/
Call for quantity discounts when ordering over 50 units. **CALL**
MOTOROLA 4116 (200 Nanosecond Plastic) **$4.50**

SYSTEMS SOFTWARE

RM EXPANSION ACCESSORIES FOR AIM—
CALL SPECS AND PRICES

APPLE III IS IN STOCK/Apple III Information Analyst Package—128K Apple III, Black and White Monitor 12", and information analyst software. **CALL**

TOP SOFTWARE PACKAGES FROM COMPUMART

VISICALC/FOR APPLE/FOR HP/FOR COMMODORE/FOR ATARI
SOFTWARE FROM APPLE/Apple Plot (the perfect graphic complement for Visicalc/Dow Jones News & Quotes/Apple Fortrom/Apple Writer/Pascal Language System/Controller Business System **CALL**
PERSONAL SOFTWARE/Visidex/VisiTrend/VisiPlot/VisiTerm **CALL**
MUSE/Super Text **CALL**

MOUNTAIN COMPUTER/
Expansion accessories for Apple/Super Talker/The Music System/ROM plus board with Keyboard filter/ROM Writer/Clock Calendar/AtoD and D to A Converter/Clock for Apple/CPS Multifunction Board **CALL**
VIDEX/Video Term (80 col. x 24 line, 7x9 Matrix plug in compatible board for Apple II) w/wo graphics EPROM/SSM Serial & Parallel, Apple Interface/ABT's Numeric Key Plan/California Microcomputer Keyboard **CALL**

IMPORTANT ORDERING INFORMATION
CALL 800 343-5504. in Massachusetts: (617) 491-2700, phones open from 8:30 a.m. to 7:00 p.m. Mon-Fri. 11:00 a.m. to 4:00 p.m. Sat.
PO's: Accepted from Dun & Bradstreet rated companies—shipment contingent upon receipts of signed purchase order.
SALE PRICES: Valid for month of magazine date only—all prices subject to change without notice. Our Ann Arbor retail store is open 11:00 a.m. to 7:00 p.m. Tues-Fri. 10:00 a.m. to 5:00 p.m. on Saturdays.

Listing 2: *NorthStar BASIC program CSTORM initializes data in the disk file and must be run for each new hurricane tracked.*

```
10 !"       THIS PROGRAM CREATES AND INITIALIZES THE FILE"
20 !"       CONTAINING THE STORM DATA."
30 !
40 INPUT "        WHAT IS THE NAME OF THE STORM ? ",A$
50 CREATE A$,5
60 OPEN #1,A$
70 !\INPUT "        ENTER INITIAL DATE (99/99) ? ",D$
80 IF LEN(D$)<>5 THEN 70
90 INPUT "        ENTER INITIAL TIME (99:99) ? ",T$
100 IF LEN(T$)<>5 THEN 90
120 INPUT "        ENTER INITIAL LATITUDE ? ",Y
130 INPUT "        ENTER INITIAL LONGITUDE ? ",X
140 WRITE #1,D$,T$,X,Y
150 CLOSE #1
160 END
```

Listing 3: *HURRICANE performs the actual tracking functions using spherical trigonometry and produces the output shown in listing 1.*

```
10 DIM C$(15)
20 FOR I=1 TO 11\!\NEXT
30 !"       THIS PROGRAM GENERATES A HURRICANE TRACKING TABLE."
40 !\INPUT "        WHAT IS THE NAME OF THE STORM ? ",A$
50 INPUT "        ANY NEW COORDINATES TO ADD (Y OR N) ? ",Z$
60 IF Z$="" THEN 240
70 IF Z$="N" THEN 240
80 !\!\!
90 OPEN #1,A$
100 IF TYP(1)=0 THEN 130
110 READ #1,D$,T$,X,Y
120 GOTO 100
130 !\!"        ENTER NEW DATA"
140 INPUT "              ENTER DATE (99/99) ? ",D$
150 IF D$="END" THEN 230
160 IF LEN(D$)<>5 THEN 140
170 INPUT "              ENTER TIME (99:99) ? ",T$
180 IF LEN(T$)<>5 THEN 170
190 INPUT "              ENTER LATITUDE ? ",Y
200 INPUT "              ENTER LONGITUDE ? ",X
210 WRITE #1,D$,T$,X,Y
220 GOTO 130
230 CLOSE #1
240 !\!\INPUT "       DO YOU WANT A HARD COPY (Y OR N) ? ",Z$
250 IF Z$="Y" THEN H=1
260 IF H=1 THEN 280
270 !\!\!
280 OPEN #1,A$
290 P1=12
300 READ #1,D$,T$,X,Y
310 !#H"        ",A$,"'S INITIAL POSITION WAS LAT -",Y," , LONG -",X,
320 IF H=0 THEN INPUT " ",Z$
330 !#H\!#H
```

Listing 3 continued on page 128

This book can save your company a lot of money.

You can rent just about any electronic instrument—including data terminals and printers—off-the-shelf for as short a time as 30 days.

Rental Electronics, Inc.
(800) 227-8409

In California (213) 993-7368 or (415) 968-8845 or (714) 879-0561

☐ Send me a copy of this book. Soon, please. In these inflationary times, my company would like to save money. Your Rental Catalog might help.

☐ I'd like a copy of your Equipment Sales Catalog, too.

☐ I'm interested in desktop computers. Send me a copy of your Hewlett-Packard Desktop Computer rental brochure.

☐ I'd like to see a brochure on Intel's Intellec● Microcomputer Development Systems now for rent.

☐ I understand you have scads of data terminals and printers for rent off-the-shelf. Send me a brochure.

☐ I need immediate assistance. Have someone phone me quickly here:
(A.C.) (number) (ext.)

☐ I have specific interest in the following electronic equipment:

NAME ______ TITLE ______

ORGANIZATION ______

ADDRESS ______ MAIL STOP ______

CITY/STATE/ZIP ______

PHONE ______

Please complete this coupon and mail to: Rental Electronics, Inc./19525 Business Center Dr./Northridge, CA 91324

Circle 338 on inquiry card.

Listing 3 continued:

```
340 X0=X
350 Y0=Y
360 IF TYP(1)=0 THEN 510
370 READ #1,D1$,T1$,X1,Y1
380 GOSUB 830
390 IF P1<11 THEN 430
400 !#H"   DATE    TIME     LAT    LON    ",
410 !#H"DISTANCE AND DIRECTION OF TRAVEL"
420 P1=1
430 !#H"   ",D1$,"   ",T1$,"  ",%5F1,Y1,"  ",X1,"   ",
440 !#H%6F1,Q," MILES AT ",%5F1,D," DEG ",C$
450 IF H=0 THEN P1=P1+1 ELSE 480
460 IF P1<>11 THEN 480
470 INPUT "    PRESS RETURN TO CONTINUE",Z$
480 X=X1
490 Y=Y1
500 GOTO 360
510 X=X0
520 Y=Y0
530 GOSUB 830
540 T1=D
550 !#H\!#H"    ACTUAL MOVEMENT HAS BEEN ",%6F1,T1," DEG ",C$
560 X=93
570 Y=30
580 GOSUB 830
590 !#H"   ",A$," IS ",%6F1,Q," MILES AT ",D," DEG ",C$,
600 !#H" FROM LAKE CHARLES."
610 P1=P1+3
620 FOR I=P1 TO 10\!\NEXT
630 CLOSE #1
640 IF H=0 THEN INPUT "",Z$
650 IF Q>=100 THEN 720
660 !#H\!#H\!#H
670 !#H"    **************"
680 !#H"    *  W A R N I N G  -  HURRICANE IS LESS THAN 100 MILES AWAY."
690 !#H"    **************"
700 !CHR$(7)
```

Listing 3 continued on page 132

Verbatim comments:

“Compared to the brands I've used before, Verbatim Datalife™ is the best yet!”
Sandy Tiedeman
Las Vegas, NV

“New Verbatim helped eliminate I/O errors on my Apple.”
Richard Adams
Ft. Walton Beach, FL

“I would prefer Verbatim Datalife over any brand I've ever used.”
Skip Piltz
Overland Park, KS

“My experience with Verbatim diskettes has been excellent. I've used several boxes over the past few months and they've all been error-free.”
Robert Roeder
Las Vegas, NV

“Much stronger, better centering. A definite improvement.”
Leroy LaBalle
Marrero, LA

“It has worked perfectly everytime!”
Richard Ruth
Shippensburg, PA

“I like the thicker protective cover.”
David Hendel
Lititz, PA

“Great! I have had *no* problems!”
Timothy Roscoe
Mechanicsburg, PA

“So far my Verbatim disks have been performing flawlessly. Not always so with other disks.”
Chris Otis
Hoffman Estates, IL

“Runs quieter in the disk drive.”
Richard Cannova
Los Angeles, CA

“Verbatim disks are super. They're our standard for quality.”
Bob Mills
Mission, KS

“Anything that prolongs the life of a diskette is a plus. Thank you Verbatim for an excellent improvement.”
Steve Toth
Piscataway, NJ

“Of the 130-plus Verbatim disks I have, I'm not aware of any problems. I'm sure the improvements will give your disks an even longer life.”
Gerald Janas
Warren, MI

“FANTASTIC. Not a single registration problem. Much more reliable than what I had been using.”
Gary Sandler
Playa Del Rey, CA

“Verbatim is much more reliable. I wouldn't trust anything else.”
Howard Chin
Pomona, CA

“Thank you for the improvements. Just another reason why I'll always use Verbatim.”
James Hassler
Cheyenne, WY

We introduced Verbatim Datalife mere months ago. And it's already playing to rave reviews like these.

But don't take anybody else's word for it. Try it yourself, and see if you don't agree it's the best media you've ever tried. For the name of your nearest Verbatim dealer, call (800) 538-1793, in California call (408) 737-7771 collect.

We play it back, Verbatim!

Order Dept.
Open Every Day
9 a.m. - 6 p.m.
P.S.T.

TOLL FREE ORDER LINE
800-854-6654

We honor these cards: master charge, VISA, American Express, Carte Blanche, Diners Club International

APPLE HARDWARE

TOP FIVE SELLERS

LANGUAGE SYSTEM W/PASCAL	425
SILENTYPE PRINTER W/INTERFACE	549
HAYES MICROMODEM II	319
VIDEX VIDEOTERM 80 w/graphics	335
Z-80 MICROSOFT CARD	299

APPLE COMPUTER INC.

DISK II DRIVE ONLY	445
INTEGER OR APPLESOFT II FIRMWARE CARD	155
GRAPHICS TABLET	649
PARALLEL PRINTER INTERFACE CARD	155
HI-SPEED SERIAL INTERFACE CARD	155
COMMUNICATIONS INTERFACE CARD	185
SMARTERM 80 COLUMN VIDEO CARD	335

MOUNTAIN COMPUTER INC.

MUSIC SYSTEM (16 Voices)	479
A/D + D/A INTERFACE	319
EXPANSION CHASSIS	555
INTROL/X-10 SYSTEM	249
CLOCK/CALENDAR CARD	239
SUPERTALKER SD-200	249
ROMPLUS+ CARD	135
ROMWRITER CARD	155

CALIFORNIA COMPUTER SYSTEMS

CLOCK/CALENDAR MODULE	109
GPIB IEEE-488 CARD	259
ASYNCHRONOUS SERIAL INTERFACE CARD	129
CENTRONICS PARALLEL INTERFACE CARD	99
We carry all CCS hardware.	Please call

MISC. APPLE HARDWARE

16K RAM UPGRADE (Apple, TRS-80, Exidy)	189
16K RAM CARD MICROSOFT	189
ABT NUMERIC KEYPAD (old or new kybrd)	115
ABT BAR CODE READER WAND	179
ALF 3 VOICE MUSIC CARD	229
ALF 9 VOICE MUSIC CARD	169
ALPHA SYNTAURI KEYBOARD SYSTEM	1399
BIT 3 FULL VIEW 80 CARD	349
CAT NOVATION ACOUSTIC MODEM	169
CORVUS 10MB HARD DISK	CALL
LAZER LOWER CASE PLUS	50
MICRO-SCI DISK DRIVES	CALL
PAYMAR LOWER CASE (old or new kybrd)	55
RADCOM AMATEUR RADIO INTERFACE CARD	189
SPEECHLINK 2000 HEURISTICS	229
SSM AIO SERIAL/PARALLEL CARD A&T	189
SUP-R-TERMINAL 80 COL. CARD	339
SVA 8 INCH FLOPPY DISK CONTROLLER	345
VERSAWRITER DIGITIZER PAD	229
VIDEX KEYBOARD ENHANCER	115
We stock much more than listed.	Please call.

APPLE SOFTWARE

APPLE COMPUTER INC.

DOS TOOLKIT	65
APPLEPLOT	60
TAX PLANNER	99
APPLE WRITER	65
APPLE POST	45
DOW JONES PORTFOLIO EVALUATOR	45
DOW JONES NEWS & QUOTES REPORTER	85
APPLE FORTRAN	165
APPLE PILOT	129
DOS 3.3 UPGRADE	49
MUSIC THEORY	45
THE CASHIER Retail Mngmnt & Inv.	199
THE CONTROLLER Gen. Bus. Sys	519

MISC APPLICATIONS PACKAGES

VISICALC	125
DESKTOP PLAN II	169
CCA DATA MANAGMENT DMS	85
EASYWRITER WORD PROCESSOR	225
EASYMOVER MAIL SYSTEM	225
EASYMAILER LETTER WRITER	225
ASCII EXPRESS	65
MICROSOFT FORTRAN	185
MICROSOFT COBOL	695
MICROSOFT BASIC COMPILER	375
SUPER TEXT II	139
PROGRAMMA APPLE PIE	119
THE LANDLORD Apt Mngmnt package	649
PEACHTREE BUSINESS SOFTWARE	CALL
TAX PREPARER by HowardSoft	89
APPLEBUG ASSEM/DISASSM/EDITOR	75
3-D GRAPHICS By Bill Budge	53
SUPER FORTH	49

TOP TEN GAMES

APPLE GALAXIAN	23
FLIGHT SIMULATOR	34
THE WIZARD AND THE PRINCESS	32
COSMOS MISSION (SPACE INVADERS)	24
SARGON II CHESS	32
HI-RES FOOTBALL	39
COMPUTER QUARTERBACK	39
ADVENTURE BY MICROSOFT	27
PHANTOMS FIVE	39
REVERSAL (OTHELLO)	34

CALL OR WRITE FOR A COMPLETE SOFTWARE LIST

ORDERING INFORMATION: Phone Orders invited using VISA, MASTERCARD, AMERICAN EXPRESS, DINERS CLUB, CARTE BLANCHE, or bank wire transfer. Credit cards subject to service charge: 2% for VISA & MC, 5% for AE, DC & CB. Mail Orders may send credit card account number (include expiration date), cashiers or certified check, money order or personal check (allow 10 days to clear). Please include a telephone number with all orders. Foreign orders (excluding Military PO's) add 10% for shipping, all funds must be in U.S. dollars. Shipping, handling and insurance in U.S. add 3% (minimum $4.00). California residents add 6% sales tax. We accept COD's under $500. OEM's, Institutions & Corporations please send for written quotation. All equipment is subject to price change and availability without notice. All equipment is new and complete with manufacturer warranty (usually 90 days). We cannot guarantee merchantibility of any products. We ship most orders within 2 days.

WE ARE A MEMBER OF THE BETTER BUSINESS BUREAU AND THE CHAMBER OF COMMERCE
SHOWROOM PRICES MAY DIFFER FROM MAIL ORDER PRICES.
PLEASE SEND ORDERS TO:
CONSUMER COMPUTERS MAIL ORDER 8314 PARKWAY DRIVE, GROSSMONT SHOPPING CENTER NORTH LA MESA CALIF. 92041

Circle 96 on inquiry card.

Listing 3 continued:

```
710 FOR I=1 TO 6\!#H\NEXT
720 END
730 REM  THIS SUBROUTINE COMPUTES THE DIRECTION
740 REM  AND DISTANCE BETWEEN TWO POINTS ON THE
750 REM  GLOBE.  INPUT IS -, STARTING COORDINATE
760 REM  X,Y AND ENDING COORDINAGE X1,Y1.
770 REM  OUTPUT IS - C$ CONTAINS THE HEADING
780 REM  IN WORDS, IE, NORTH OF WEST, DUE SOUTH, ETC.
790 REM  D CONTAINS THE ANGULAR HEADING IN DEGREES.
800 REM  Q CONTAINS THE DISTANCE BETWEEN THE 2 POINTS.
810 REM  USES VARIABLES A,B,Q,Q2,D,S,N,U
820 REM  X,X1,Y,Y1 ARE UNCHANGED.
830 IF X1=X AND Y1=Y THEN C$="NO MOVEMENT"
840 IF X1>X AND Y1=Y THEN C$="DUE WEST"
850 IF X1>X AND Y1>Y THEN C$="NORTH OF WEST"
860 IF X1=X AND Y1>Y THEN C$="DUE NORTH"
870 IF X1<X AND Y1>Y THEN C$="NORTH OF EAST"
880 IF X1<X AND Y1=Y THEN C$="DUE EAST"
890 IF X1<X AND Y1<Y THEN C$="SOUTH OF EAST"
900 IF X1=X AND Y1<Y THEN C$="DUE SOUTH"
910 IF X1>X AND Y1<Y THEN C$="SOUTH OF WEST"
920 REM
930 REM  SUBROUTINE MAY BE ENTERED HERE IF C$ IS NOT REQUIRED."
940 REM
950 U=57.29578
960 Q=0\D=0
970 N=ABS(X-X1)
980 B=90-Y
990 A=90-Y1
1000 S=COS(A/U)*COS(B/U)+SIN(A/U)*SIN(B/U)*COS(N/U)
1010 IF S*S>=1 THEN RETURN
1020 Q2=ATN(SQRT(1-S*S)/S)
1030 Q=Q2*U*69.5
1035 IF Y=Y1 THEN RETURN
1040 S=SIN(A/U)*SIN(N/U)/SIN(Q2)
1050 IF S*S>=1 THEN RETURN
1060 D=ATN(S/SQRT(1-S*S))*U
1070 D=90-D
1080 RETURN
```

Changes to FLOPTRAN-IV

George H Watson Jr, Physics Department
University of Delaware, Newark DE 19711

I thoroughly enjoyed Mark Zimmermann's article on compiled BASIC for the Commodore PET. (See "FLOPTRAN-IV: A Tiny Compiler," October 1980 BYTE, page 196.) His detailed documentation enabled me to translate FLOPTRAN-IV for use with version 3 PET ROMs (read-only memories). I would like to share with BYTE readers the changes needed for this translation.

• GO% is replaced by G0% in lines 50000, 58760, 58840, and 60080 as shown:

```
50000  DIMX, LN%(255),G0%(127,1),ML%(19,1):P=1025:GC=0
58760  G0%(GC,0)=PC-32766:PRINT#1,0:PRINT#1,0
       :PC=PC+3:TL=0
58840  G0%(GC,1)=TL:GC=GC+1:GOTO50260
60080  FORX=0TOGC-1:PRINT#1,G0%(X,0)+32767
       :L=G0%(X,1):Z=LN%(L)+32767
```

• Change the DATA statements for the ROM subroutines in lines 49600, 49640, and 49680 as follows:

```
49600  DATA69,219,216,219,100,219,0,0,91,210,122,210
49640  DATA94,222,127,223,246,216,218,222,216,223,223,223
49680  DATA40,224,140,224,232,214,115,215,54,215,52,217,30,
       218,104,222
```

• The pointer to the start of the variables is at hexadecimal 2A,2B, so the PEEKs in line 58180 must be changed as follows:

```
58180  PRINT#1,24:PRINT#1,144:PRINT#1,5:PC=PC+3
       :VL=256*PEEK(43)+PEEK(42)+2
```

• The BASIC buffer is now in the second page of programmable memory, so lines 59620 thru 59780 should read:

```
59620  PRINT#1,157:PRINT#1,32:PRINT#1,2:PRINT#1,232
       :PRINT#1,201:PRINT#1,13
59660  PRINT#1,208:PRINT#1,245:GOSUB59300
59680  PRINT#1,169:PRINT#1,2:PRINT#1,133:PRINT#1,32
       :PRINT#1,169:PRINT#1,32
59700  PRINT#1,133:PRINT#1,31:PRINT#1,202:PRINT#1,138
       :PRINT#1,32:PRINT#1,143
59760  PRINT#1,214:PRINT#1,162:PRINT#1,ZL:PRINT#1,160
       :PRINT#1,ZH
59780  PRINT#1,32:PRINT#1,224:PRINT#1,218:PC=PC+46
       :GOTO59500
```

• Line 59780 above and lines 49420, 50720, 51520, 55660, and 59080 require changes, as follows, due to other alterations in subroutine locations:

```
49420  PRINT#1,32:PRINT#1,174:PRINT#1,218:PC=PC+7
       :RETURN
50720  PRINT#1,32:PRINT#1,152:PRINT#1,217:PC=PC+3
       :GOTO51080
51120  PRINT#1,32:PRINT#1,224:PRINT#1,218:PC=PC+7
       :GOTO50240
55660  PRINT#1,69:PRINT#1,99:PRINT#1,133:PRINT#1,99
       :PC=PC+6:GOTO51100
59080  GOSUB49190:GOSUB49400:PRINT#1,32:PRINT#1,233
       :PRINT#1,220
```

In the new ROMs, the array dimensions are limited by the amount of memory available. The number of possible lines in the source file can be increased by changing lines 49940, 50000, and 50200, replacing 255 with the number of lines desired. ■

Circle 92 on inquiry card. ⟶

$380. TERMINAL

100's

$449. SINGLES

The Biggest Little Deal in Terminals!

The TransTerm 1 is a compact, low cost alphanumeric keyboard/display terminal designed for efficient man-computer communications. The TransTerm 1 consists of a two line 64 character liquid crystal display and a 53 key TTY style keyboard packaged in a 2″ high by 12″ wide by 7″ deep case. The terminal communicates in full duplex RS-232 serial asynchronous ASCII with 20 ma current loop or RS-422 available as options.

The TransTerm 1 is ideal for applications where low cost and minimum size or portability are desirable. The TransTerm 1 can be used on a horizontal desk-top surface or mounted on a vertical plane. Typical applications include:

Dial-up data entry/retrieval
Factory floor data collection
Portable console terminal
Microprocessor support device

TransTerm1 FEATURES

- Rugged Attractive Case
- Compact Size (11.7″ W x 6.9″ D x 1.75″ H)
- 64 Character LCD Display (5x7-0.11″ W x 0.18″ H)
- Displays 96 ASCII Characters
- 53 Key Alphanumeric Keyboard (Membrane switches)
- Audible Key-click for tactile feedback
- RS-232 Serial Asynchronous ASCII Interface
- Selectable baud rates (300, 1200, 2400, 9600)
- Data Format - 7 Data Bits, Odd Parity
- Three switch selectable operating modes:
    - Teletypewriter Emulation
    - Block Send
    - Multidrop Polled
- 20 ma Current Loop Interface (optional)
- RS-422 Compatible Party Line (optional)
- Powered by Wall Plug-in Transformer
- Low Power Consumption (less than 10 watts 115VAC)
- 25 pin RS-232 Type Female I/O Connector
- Custom Configurations Available

COMPUTERWISE INC.

4006 East 137th Terrace • Grandview MO 64030 • 816 765-3330

Multiprocessing with Motorola's MC6809E

Hunter Scales
Systems Applications Engineer
Advanced Microcomputer Components
Motorola Inc
Mail Stop L2787
3501 Ed Bluestein Blvd
Austin TX 78721

Recent years have seen microprocessors assuming applications previously targeted for minicomputers. Their cost and size advantages have spurred their inclusion in a variety of designs such as word processors, computer terminals, and cash registers. Where these functions were once implemented on minicomputers and timesharing terminals, microprocessors can now take on most of the burden in these jobs.

There are still many applications where microprocessors are too slow or are lacking in arithmetic power. However, microprocessors are so attractive from a cost standpoint that ways to use them in computation-bound problems are being intensively investigated. The sharing of resources by more than one processor spreads the cost of expensive programmable memory, mass storage, and peripheral devices. The percentage of utilization is increased, making these resources more efficient.

Multiprocessing (using more than one processor) is one way to accomplish this increase in use. The use of two or more microprocessors sharing common resources, each working on a portion of a problem, allows a microcomputer system to function where a minicomputer was needed previously—provided that the microprocessor can be used in a multiprocessor system. Motorola's new 8-bit microprocessor, the MC6809E, was designed with multiprocessing in mind.



Figure 1: *Basic hardware changes made to develop the MC6809E. Comparing the pin assignments of the original MC6809 with the "E" version's reveals that 4 pins have new functions. The MC6809E does not have an on-board clock generator. It relies on external circuitry to perform this function. This allows the control of the bus accesses in a multiprocessor application.*

Features of the MC6809E

While the MC6809E features the same instruction set as the MC6809, there are some basic hardware differences (see figure 1 for a pin description). The first difference is the clocks. The MC6809 has an on-board clock generator and inputs to control it: the MRDY (memory ready) pin causes the E and Q clocks to be stretched to allow for a longer access time (for slow memory circuits). The clock signals for the MC6809E, on the other hand, must be generated by an external circuit (see figure 2) that can also be used to stretch the clocks. On the MC6809, the DMA/BREQ input is used to stretch the clocks internally and force the address and data buses into the high-impedance state for DMA (direct memory access) operations. Since the clock generator is external to the MC6809E, this input is not present.

Figure 2 shows a simple clock-generator circuit for use with the MC6809E. The system clock is based on the signal from a crystal oscillator whose frequency is four times the desired clock frequency; the oscillator's output signal is called 4 X. The timing of the bus signals is shown in figure 3. The MRDY input is sampled on the rising edge of the 4 X signal before the falling edge of E. If MRDY is high, E falls with the next falling edge of 4 X, and Q rises one 4 X period later. If MRDY is low, E is *stretched* to remain high and Q is stretched low. Signals on the data and address buses remain valid until MRDY goes high again. E falls on the next falling edge of the 4 X signal, and E and Q continue normally from there. The MC6809E can have its clock stretched a maximum of 10 μs.

Hayes Stack™

Microcomputer Component Systems

At Hayes, we don't believe in second best. Or planned obsolescence. We believe in taking the state of the art to the limit. Our new Smartmodem, for example, is the most sophisticated 300-baud originate/answer modem you can buy. And yet, it is perhaps the easiest-to-use modem ever.

RS-232C Compatible. Smartmodem lets any RS-232C compatible computer or terminal communicate by phone with other computers and time-sharing systems located *anywhere in North America.* You get full and half-duplex operation with both Touch-Tone* *and* pulse dialing.

Auto-Answer/Dial/Repeat. Smartmodem can answer the phone, dial a number, receive and transmit data, and then hang up the phone—automatically! If desired, Smartmodem will even repeat the last command. You can depend on Smartmodem for completely unattended operation.

Completely Programmable. Smartmodem can be controlled using *any* programming language. Over 30 different commands can be written into your programs or entered directly from your keyboard.

Smartmodem also includes several switch-selectable features that let you tailor performance to your exact needs. You can "set it and forget it" for the ultimate in convenience.

Built-in Audio Monitor. Thanks to an internal speaker, you can actually listen to your connection being made. You'll know immediately if the line is busy or if you reached a wrong number—*and you don't even need a phone!*

Status at a Glance. Seven LED's indicate Smartmodem's current operating mode: auto-answer, carrier detect, off hook, receive data, send data, terminal ready and modem ready. You're never left in the dark!

Direct-Connect Design. Smartmodem is FCC registered for direct connection to any modular phone jack—there's no acoustic coupler to cause signal loss and distortion.

Smartmodem, Smart Buy. Professional quality features. Versatile performance. A full two-year limited warranty. A suggested retail price of only $279.

What more could you want? Perhaps the matching Hayes Stack Chronograph, an RS-232C compatible calendar/clock system.

Check out the Smartmodem wherever fine computer products are sold. And don't settle for anything less than Hayes.

Hayes

Smartmodem. The ultimate concept in modems is now a reality.



Hayes Microcomputer Products Inc. 5835 Peachtree Corners East, Norcross, Georgia 30092 (404) 449-8791



Figure 2: *Circuitry for generating and controlling the clock signals for the MC6809E. The MRDY line allows use of slow-access-time memory devices by controlling the "stretch" applied to the E and Q clock signals.*

In addition, the MC6809E has 4 pins dedicated to signals not used in the MC6809: TSC, AVMA, BUSY, and LIC. Asserting (placing a logical true signal on) the TSC (three-state control) pin forces the data bus, address bus, and R/$\overline{W}$ (read/write) line into a high-impedance state if the clocks are both held in the logic low state. This can be used to temporarily "remove" the processor from the bus so another bus master, such as a DMA controller, can take over.

The LIC (last instruction cycle) pin is high during the last cycle of an instruction. This signal, in conjunction with a bipolar PROM (programmable read-only memory), can be used to decode unimplemented opcodes and trigger an error condition. The error condition can be used to reset the processor to a known condition and recover. This helps to guarantee system integrity for applications needing fail-safe operation.



Figure 3: *Timing diagram for the circuit in figure 2. The MRDY and 4 X signals are used in combination to determine how long the E and Q clocks will be stretched (shaded areas).*

AVMA (advanced valid memory access) indicates that the processor will access the bus on the next cycle, whether an opcode or operand. Since the MC6809E sets all address and R/ $\overline{W}$ lines high during cycles in which it is not accessing the bus, this signal is useful to a bus arbiter in deciding which processors are granted bus access and which have to wait. (This will be discussed in more detail later, in a multiprocessor system implementation.)

The BUSY signal indicates that an indivisible memory access is taking place. This occurs during double-byte operations (such as LDX), and also during the read-modify-write instructions (such as shifts and rotates) in which a byte is fetched from memory, modified, and returned. This is also useful in a multiprocessing environment, as will be shown later.

The timing relationship of these signals is shown in figure 4. The example given is the execution of an ASR (arithmetic shift-right) operation on a memory location using the extended (16-bit) addressing mode. AVMA is high for the first three cycles, indicating that the processor is using the bus. This is the opcode fetch (hexadecimal 77) and the operand fetch (hexadecimal 10 and 00) from locations hexadecimal 100, 101, and 102. AVMA then goes false to show that the next cycle is not a

OMNI

THE NEW
FLIP/FLOPPY™ DISK
with twice the byte

OMNI is pleased to bring you a **reversible** 5¼″ mini diskette...the FLIP/FLOPPY DISK. Now you can record on both sides for twice the storage capacity of a single sided disk. And you'll be able to do it far more economically, too!

Each OMNI FLIP/FLOPPY DISK incorporates all of the quality features you'd expect from the very best single sided disk.

- Two recording surfaces
- Two sets of WRITE ENABLE notches
- Two index holes
- Reinforced Hub Rings
- Certified error-free operation at more than twice the error threshold of disk drives
- Over 12 million rated passes without disk related errors or significant wear, for extra long life operation
- Compatible with most 5¼″ disk drives including APPLE, TRS-80, PET, OHIO SCIENTIFIC, and many more.

OMNI Resources
4 Oak Pond Avenue • Millbury, MA 01527 • 617-799-0197

Call TOLL-FREE: In Mass. 1-800-252-8770
Nationwide 1-800-343-7620

INTRODUCTORY OFFER

Order the OMNI FLIP/FLOPPY DISK at this special introductory price:

Five Pack...$21.00
Equivalent to ten single-sided disks.

Ten Pack....$40.00
Equivalent to twenty single-sided disks.

OFFER EXPIRES OCTOBER 15, 1981

Please send me the following OMNI FLIP/FLOPPY DISK(s)

________ Five Packs(s) @ $21.00 each =	$ ________	
________ Ten Pack(s) @ $40.00 each =	$ ________	
Shipping and handling	$ 1.50	
Massachusetts residents add 5% sales tax	$ ________	
TOTAL	$ ________	

☐ Check made payable to OMNI RESOURCES ☐ C.O.D.
☐ Mastercard
Account Number ___ ___ ___ ___
☐ VISA/BankAmericard
Account Number ___ ___ ___ ___
Credit Card Expiration Date __ __ / __ __

Name ________________
Address ________________
City ________________
State ________ Zip ________
Phone Number ( ) ________________
Authorized Signature ________________

(Please allow approximately three weeks for delivery)
Money back guarantee if not completely satisfied

Circle 288 on inquiry card.

valid memory-access cycle; BUSY is then made true to identify the read-modify-write portion of the instruction. The value at address hexadecimal 1000 is read, shifted, and written back to memory. LIC is then made true to indicate the last cycle of the instruction. LIC, AVMA, and BUSY are all valid from the rising edge of the Q clock.

Software

The MC6809 and MC6809E have a powerful instruction set, including a variety of indexed addressing modes,



Figure 4: *Timing relationships of MC6809E signals during an ASR (arithmetic shift-right) instruction. All numbers shown are in hexadecimal.*

16-bit math functions, and versatile stack-manipulation instructions. They support position-independent reentrant code and the multiple-stack architecture required by many high-level languages, including Pascal.

The processor's architecture and programming model are shown in figure 5. There are two 16-bit stack pointers (S and U) and two 16-bit index registers (X and Y). Two 8-bit accumulators are provided, but they can be used as a single 16-bit accumulator (D) to perform double-precision additions and subtractions. The DP (direct-page register) allows a "floating" 256-byte page for direct (8-bit address) instructions. (This saves on the amount of code and time required to access frequently used variables.)

Both stack pointers also support all indexed addressing modes, and both index registers can be used as stack pointers:

```
PUSHAX  STA  0,−X   TO PUSH, PNTR IS DEC,
                    THEN STORE A

PULLAX  LDA  0,X+   TO PULL, LOAD THEN
                    INCR PNTR
```

This code implements stacks with the X and Y index registers. The X register is used as a stack pointer that always points to the last entry in the stack. The automatic "predecrement" indexed mode is used to implement a push to the stack. (The X register is first decremented by one, and the A accumulator is stored at the location pointed to by X.) In the same fashion, a pull is accomplished with the load-accumulator-indexed instruction with an automatic postincrement operation.





Figure 5: *Internal architecture and programming model of the MC6809E.*

Westico-The Software Express Service that really delivers.

The professional wants good software, wants it fast and backed by expert service — There's one answer — Westico, the Software Express Service that really delivers...



Call (203) 853-6880 for overnight delivery or... when you need expert service.

— Quality Software!
Westico constantly improves its quality software in a wide range of categories including: Accounting, Professional Time Accounting, Text Processing, Planning and Analysis, Telecommunications, Data Management, Development Tools, Language Processors.

— Your Program Overnight!
Westico knows that the speed in which you receive a program is often a key consideration in your selection. That's why Westico is the only software company to offer overnight delivery.

— Our 24-Hour Computer Hotline!
For detailed program information or for quick access ordering, just dial-up the Westico computer (300 baud) (203) 853-0816.

— The Software for a wide variety of CP/M™ and other computer systems:
TRS-80 Model II, Apple, Vector Graphic, iCom, Cromemco, North Star, Micropolis, Ohio Scientific, Altos, Dynabyte, SuperBrain and more.

— Professional Service
Westico is staffed by experts who understand your software and the equipment on which it runs. It's nice to know when you need service or advice, a Westico expert is standing by.

Send for our **NEW FREE** Catalog.

— Professional Software
Current Westico products with **new prices** for complete systems and documentation alone:

Accounting: ACCOUNTS PAYABLE 495/60 • ACCOUNTS RECEIVABLE 495/60 • CLIENT WRITE-UP 895/60 • GENERAL LEDGER 495/60 • INVENTORY CONTROL 595/60 • PAS-3 DENTAL 990/40 • PAS-3 MEDICAL 990/40 • PAYROLL 495/60 • PROPERTY MANAGEMENT 895/60.

Professional Time Accounting: DATEBOOK™ II 295/25 • ESQ-1 Legal 1495/50 • ESQ-1 Legal Demo 75/50 • PTA 595/40 • PTA Demo 75/40.

Text Processing: MAIL-MERGE™ 125/25 • MINCE 125/25 • SPELLGUARD™ 295/25 • TEXTWRITER 125/20 • WORDMASTER™ 145/40 • WORDSEARCH™ 195/40 • WORDSTAR™ 450/60.

Planning & Analysis: MILESTONE™ 295/25 • MINIMODEL 495/50 • STATPAK 500/40 • TARGET 195/25.

Telecommunications: ASCOM 175/20.



...Dial-up our 24-hour Computer Hotline (300 baud) (203) 853-0816 for program information or orders.

Data Management: CBS 395/50 • CBS Demo 75/50 • CBS LABEL OPTION 80/10 • HDBS 300/35 • MAILING ADDRESS 395/60 • MAGSAM III 145/25 • MAGSAM IV 295/25 • MDBS 900/35 • MDBS DRS 300/5 • MDBS RTL 300/5 • MDBS QRS 300/5 • PRISM/ADS 795/55 • PRISM/IMS 495/55 • SELECTOR IV 550/35 • DATASTAR™ 350/60.

Development Tools: GENERAL SUBROUTINE PAK 295/30 • APPLICATION UTILITIES 495/30 • STRING BIT™ 65/15 • STRING/80™ 95/15 • STRING/80 SOURCE 295/-.

Language Processors: LYNX Overlay loader 250/25 • BASIC COMPILER 395/25 • BASIC-80 350/25 • CBASIC-2 120/15 • NEVADA COBOL 150/25 • PASCAL/M 175/20 • PASCAL/MT+ 425/30 • PL/I-80™ 475/35 • S-BASIC™ 295/25.

Miscellaneous: SUPERSORT I 225/40 • SURVEYOR 550/60 • ULTRASORT II™ 165/15.

New from Westico

MILESTONE™: Tough Planning Jobs Made Easy

MILESTONE is a powerful new tool for managers and planners, which organizes complex projects and identifies job schedules essential to on-time completion.

MILESTONE finds the critical path through hundreds of interrelated tasks and determines where slack time can be eliminated.

Equally significant, MILESTONE computes manpower requirements and costs, allocating them to proper schedule periods and up to nine manpower skill/cost levels can be allocated to each task.

With MILESTONE, projects can be measured in hours, days, weeks, months, quarters or fiscal quarters; with provision to specify working hours, holidays, vacations and other non-productive time periods for up to 8,196 years.

Reschedule or complete tasks, revise prerequisites, play "What If" games. MILESTONE immediately displays the results on your screen or printer — either as a table or graph!

MILESTONE is easy to use and requires no programming!

System with full documentation — $295.
Documentation alone — $25.

Versions for CP/M, APPLE PASCAL and CDOS.

4 WAYS TO ORDER

- Write Westico, Inc., 25 Van Zant Street, Norwalk, CT 06855.
- Call (203) 853-6880.
- Telex 643-788.
- Dial-up our 24-hour computer (300 baud) (203) 853-0816.

MasterCard and VISA accepted.

Prices do not include shipping and are subject to change. In CT add 7½% sales tax.

Manual price may be credited toward purchase of software.

Dealer Inquiries invited.

WESTICO

The Software Express Service

25 Van Zant Street • Norwalk, Connecticut 06855
(203) 853-6880 • Telex 643-788

Listing 1: *A completely reentrant search routine for the MC6809E. Each routine in a program passes parameters on a stack and returns them on the stack.*

```
******************CHARACTER SEARCH***************
*
*         SEARCH A TABLE OF LENGTH N STARTING AT
*         LOCATION TAB TO FIND CHAR. IF THE SEARCH
*         IS SUCCESSFUL, RETURN WITH ADDRESS ON
*         THE STACK AND C=1, IF NOT THEN CLEAN THE
*         STACK AND RETURN WITH C=0
*
*         ON ENTRY CHAR, N AND TAB ARE ON STACK
*
*         REGISTER VOLATILITY: A,B,X,Y,CC
*
*
CHAR    EQU    0        OFFSET ON STACK TO CHAR
TAB     EQU    1        2 BYTE ADDR OF TABLE
N       EQU    3        NUMBER CHARS IN TABLE
*
SEARCH  LDX    TAB,S    GET ADDR OF TABLE IN X
        LDB    N,S      GET N
        LDA    CHAR,S   GET CHAR TO FIND
S1      CMPA   ,X+      CHECK FOR MATCH, INC PNTR
        BEQ    FOUND    GOT IT
        DECB            DEC COUNT
        BNE    S1       NOT FINISHED YET
NOT     ANDCC  #$FE     CLEAR CARRY
        LEAS   4,S      CLEAN STACK
        RTS             RETURN
FOUND   ORCC   #$01     SET CARRY
        LEAS   4,S      CLEAN STACK
        LDY    0,S      GET RETURN ADDR IN Y
        STX    0,S      PUT CHAR ADDR ON STACK
        JMP    0,Y      RETURN TO CALLER
```


The A accumulator is loaded with the value pointed to by X, and the X register is incremented. In any case, the stack pointer points to the last byte on the stack.

The proper use of stacks in an MC6809 machine-language program allows completely reentrant code to be written, making recursive routines easy to implement. Each routine passes parameters on a stack and returns them on the stack, as well as keeping any temporary variables there. An example of this is shown in listing 1.

The MC6809E also supports position-independent code through its relative-addressing mode and LEA (load effective address) instruction. Two types of branches are provided—short and long. The short-branch instructions have a single-byte signed offset from the current location, allowing a branch within the 256-byte page centered on the branch opcode. The long-branch instructions have a 2-byte signed offset, allowing branches to anywhere in the 16-bit address map.

A particularly useful relative-address mode is the PCR (program counter relative) mode. This allows the use of the program counter itself as an index register. Using this mode in conjunction with the LEA instruction allows the calculation of absolute addresses at run time, even though the final execution address may not be known at assembly time.

The LEA instruction loads the effective address of an operand into an index register instead of the operand itself, allowing absolute addresses to be calculated in position-independent code:

```
TABLE RMB  20             START OF DATA TABLE


      LEAX TABLE,PCR  GET ADDRESS OF TABLE
      LDA  ,X+        GET A BYTE OF DATA
```

The LEAX instruction loads the absolute (effective) address of TABLE into the X register, even though this differs if the routine is executed at different addresses.

Multiprocessor Systems

There is considerable debate about what a multiprocessor system should do and how it should be implemented. On one hand are loosely coupled systems, in which several computers communicate with one another (over a serial link, for example), each processor doing part of a larger job. Local processors can preprocess raw data into a more manageable format to be used with more comprehensive algorithms on another computer. On the other hand are tightly coupled systems, in which several processors share a common bus (of a given bandwidth), using the same memory and I/O (input/output) interfaces in a timeshared fashion. The MC6809E was designed for this latter type of system.

Two types of systems are considered here, the local/global and the global-only. In the local/global system, each processor has a *local bus* with a block of program-

Text continued on page 146

GUARANTEED RELIABLE FOR 2 FULL YEARS.

Unprecedented product reliability deserves an unprecedented warranty. IMS International provides its dealers with both.

Our commitment is real.

We are so confident that our products are the industry standard in reliability, we stand behind them for *two full years* from date-of-sale to the end user. All IMS manufactured products are covered.

The success of our dealers will insure our continued growth. That's why IMS International is committed to providing every IMS dealer with these distinct advantages in today's marketplace:

- 2 year warranty
- Low retail cost
- Best margins in the industry
- Protected territories
- Full factory technical support
- Complete system delivery in 30 days
- Comprehensive advertising and promotional support

For more information about IMS International's "Reliables" and our unique dealer plan, call 714/978-6966 or write us:

IMS INTERNATIONAL
2800 Lockheed Way
Carson City, NV 89701
Telex: 910-395-6051

Circle 179 on inquiry card.



Figure 6: *Block diagram of a global-only multiprocessor system. Each of the four microprocessors shares the system's memory and I/O resources using a round-robin priority system.*

"By expanding our potential, we help you expand yours."

"As a Vector computer, I'd like to introduce you to the newest member of the Vector computer family: me."

"I'm a Vector 5005 Multi-Share™ system, with all the intelligent, convenient characteristics of our 3005, and then some. I am a truly integrated word and data processing system, and I can stand alone or support up to a total of 5 terminals and 2 printers. I can be typing a letter, doing data entry, updating the general ledger, checking inventory, and doing a cash flow forecast on different terminals all at the same time.

"I use sophisticated, big computer error correction techniques for the security and integrity of your data. My advanced Winchester hard disk gives you 5 megabytes of storage for convenient, fast access to large amounts of information—without the inconvenience of changing floppy disks. In addition, I fit in equally well in small businesses (where the need is for perhaps 2 terminals) or in corporate environments (where I can be used as a multi-station word processor or comprehensive departmental machine)."

"For more information and your local dealer, call us at 800-423-5857. In California, call 800-382-3367. Or write to us at 31364 Via Colinas, Westlake Village, CA 91362.

"We Vector 5005s are here. Each time we get closer to our full potential, you get closer to yours."

VECTOR

Vector Graphic Inc.

COMPUTERS FOR THE ADVANCEMENT OF SOCIETY.

Circle 414 on inquiry card.



A_1 = AVMA1
A_2 = AVMA2
A_3 = AVMA3
A_4 = AVMA4
BUSY = BUSY 1+BUSY2+BUSY3+BUSY4

Figure 7: *State diagram of the bus arbiter used in a four-processor system. This resolves conflicts regarding which processor has access to the system resources.*

Text continued from page 142:
mable memory not shared by the others; a *global bus* makes available the memory and I/O that is shared. Arbitration takes place only when one processor wishes to use the global bus. In a global-only system, all processors share the same global bus and every cycle must be arbitrated.

The block diagram in figure 6 shows a global-only system in which four MC6809Es share a block of memory and some I/O interfaces. Each processor is connected to the bus via three-state bus buffers controlled by the bus arbiter. The AVMA lines of each processor are connected to the arbiter to indicate which processor is requesting access to the bus. The BUSY lines are logically ORed together to provide a single BUSY signal to the arbiter.

The arbiter's control outputs are four grant signals that control the three-state buffers of their respective processors, and four stretch signals that stretch the E and Q clocks of each processor, separately.

The function of the bus arbiter is to decide which processor will be granted access to the global bus during each cycle of the E clock. The arbiter determines access to the bus for each processor on a cycle-by-cycle basis. The clocks are stretched on the processors that are requesting the bus. Clocks are provided to the processor on the bus. This allows only one of the processors access during a given E cycle. During any given cycle, arbitration takes place for the next cycle unless BUSY is true, in which case arbitration is deferred until it becomes false. This is to ensure that data is not modified during instructions requiring indivisible accesses.

The state diagram in figure 7 shows the logical function of the arbiter. Each state represents the state of the grant outputs shown in table 1. For example, in state 1, GRANT1 is true and the remaining grant signals are false. If BUSY is true, the next state is the same as the present state and the bus continues to be granted to the same processor. BUSY remains true for a maximum of two cycles.

If no other processor requests the bus via its AVMA signal, the bus remains granted to the one currently having possession, even if it does not require it; this simplifies the logic of the arbiter.

If the processor next requesting the bus is next in line to have highest priority (ie: its number in the round-robin priority scheme is numerically next), it is granted the bus and the rest are denied access. If it does not request the bus and another processor does, the requesting unit with the highest priority is granted an access.

The stretch signals are also generated by the arbiter. If a processor requests the bus and is denied, its grant will be false and its clocks will be stretched with both E and Q held low until that unit is granted the bus and can complete its access. If a processor has not requested the bus, its grant will be false and its three-state bus buffers will be in the high-impedance state, but its clocks will *not* be stretched—to allow completion of its nonmemory access cycle. This improves system throughput markedly in programs where instructions having many internal cycles

State	Outputs $\overline{\text{GRANT1}}$	$\overline{\text{GRANT2}}$	$\overline{\text{GRANT3}}$	$\overline{\text{GRANT4}}$
0 (00)	0	1	1	1
1 (01)	1	0	1	1
2 (10)	1	1	0	1
3 (11)	1	1	1	0

Table 1: *State of the $\overline{\text{GRANT}}$ outputs of the bus arbiter, as shown in figure 7. State numbers are those shown in figure 7. The binary output of the state-register flip-flop is shown in parentheses.*

AVMA_N	$\overline{\text{GRANT}_N}$	$\overline{\text{STRETCH}_N}$
1	1	1
0	1	0
0	0	1

Table 2: *Truth table of the $\overline{\text{STRETCH}}$ outputs of the bus arbiter, as shown in figure 7. N can have the values 1, 2, 3, or 4.*

(such as a multiply instruction) are used frequently. The truth table for the stretch signals is summarized in table 2.

If a processor, having the highest priority for that cycle, were to execute the fifth cycle of an ASR or similar instruction, the BUSY signal would prevent "rearbitration" and the other processors would be held off for three cycles. If all the processors did the same thing, each would have its clocks stretched for nine cycles. With a 1 MHz E clock, this is 9 µs. Since the maximum time a clock (E or Q) can be low is 9.5 µs, a maximum of four processors can be used in a system of this type. If MC68B09Es (rated at 2 MHz) are used, eight processors can be put on the same global bus.

A circuit implementing the bus arbiter is shown in figure 8. The state machine of figure 7 is implemented using a 74S287 256 by 4-bit PROM, and a 74LS273 octal latch as the next-state latch. Since the AVMA signals change with the rising edge of Q, these signals are latched by the falling edge of E, preventing the inputs to the PROM from changing during arbitration. The outputs of the arbiter are state bits that are decoded with a 74LS139 dual 2-bit to 4-line decoder. The separate grant lines control the enable signals of the three-state buffers, and the stretch signals send the E and Q clocks to the separate processors.

The reset state presents a special problem. When the $\overline{\text{RESET}}$ line is brought low and returned high, the processors fetch their restart vectors from locations hexadecimal FFFE and FFFF. This means that all the processors would execute the same code—hardly an improvement. One way to prevent this is to designate one processor, number 1, for example, as the master. The decoding for the restart vectors would then include $\overline{\text{GRANT1}}$, so processor 1 would restart into code that would perform the I/O and set up the operating system. The other three units would restart to another location containing a SYNC instruction.

Since the interrupt masks E and I are set during reset, the SYNC instruction causes the processor to wait until it receives an interrupt to continue execution. The master processor then writes a jump instruction to the code that each processor is to execute in the location following the SYNC instruction. A PIA (programmable interface adapter integrated circuit) can be used to toggle the IRQ (interrupt request) lines to each processor, in turn, to initiate the execution of the application program.

Semaphores

Now that the processors are all executing code, how do they communicate with one another? They will possibly need to pass data from one to the other. Perhaps one will need to pass a pointer to data that has been processed to another unit, or it might need to output data and will require an I/O device. How can a resource be *allocated* to one processor and its use be made known to the others? The answer is *semaphores*.

A semaphore, in this system, is a memory location set aside by the programmer to be a flag indicating the availability of a resource, memory, I/O, or whatever. The semaphore must show a resource as being allocated or

16 BIT 8086 MICRO SYSTEM

TEC	-86W	$9990
TEC	-86	$3990
CP/M	-86™	$ 250
BASIC	-86™	$ 350
PASCAL / M86™		$ 270

- *Tec-86W includes a 31 Mbyte Winchester plus memory increase to 256K plus all the Tec-86 features below.*

- *IEEE 696 S-100* • *CPU w/Vectored Interrupts*
- *Two RS-232 Ports* • *24 Parallel I/O lines (3 ports)*
- *64K RAM (256K RAM with Tec-86W)*
- *ROM boot for CP/M-86™*
- *Dual 8-inch Shugart floppies with controller*
- *Attractive, all metal desk top enclosure*

S-100 Boards



8086 CPU with Vectored Interrupts



16 Kilobyte Static RAM
8 and 16 bit transfer



Analog to Digital Converter and Timer/Counter
16 channels expandable to 256
12, 14, or 16 bit accuracy
30,40,100,or 125 KHz
Programmable Gain



PROM and I/O
2 RS 232 - PIO
CP/M-86 ROM Boot



Real Time Video Digitizer and Display



Digital to Analog Converter
4 channels - 12 bit accuracy
3 microsecond conversion rate



Expansion Multiplexer



Analog to Digital Converter
16 channels - 12 bit accuracy
30 KHz Conversion rate



4 PIO and Timer/Counter



Digital to Analog Companion
4-20 mA output - Filters

Apple Boards





Analog to Digital Converter
16 channels
12, 14, or 16 bit accuracy
30, 40, 100, or 125 KHz



Digital to Analog Companion
4-20 mA output - Filters



Digital to Analog Converter
2 channels - 12 bit accuracy
3 microsecond conversion rate
1 parallel output port

TECMAR INC.

Data Acquisition Systems and
Video Digitization Systems Available
23600 Mercantile Rd. • Cleveland, OH 44122

TECMAR, INC.
(216) 464-7410

Basic-86™ registered tradeMark - Microsoft   Pascal/M86™ registered tradeMark - Sorcim   CP/M™ registered tradeMark - Digital Research

Circle 386 on Inquiry card.



Number	Type	+5 V	GND
IC1	74LS273	20	10
IC2	74S287	16	8
IC3	74LS139	16	8

Figure 8: *The circuitry used to implement the bus arbiter. Information based on table 1 and table 2 (stored in the PROM) is decoded to produce the states shown in figure 7.*

unallocated when read by a processor. If it was unallocated, it must show allocated the next time it is read.

Since bus accesses are performed on a cycle-by-cycle basis, there is the possibility that one processor might read the semaphore, finding it unallocated. Another processor might read it and find it still unallocated before the first processor has a chance to change the semaphore. At this point, the resource might (mistakenly) be allocated to both units.

To prevent this, the BUSY signal is used to defer bus "rearbitration." The shift instructions (which are of the read-modify-write type) can then be used to implement true semaphores:

```
CHECK  ASR   SEM      READ SEMAPHORE
       BCS   FREE     CAN NOW USE PRINTER
       BRA   CHECK    IN USE, TRY AGAIN
FREE   EQU   *        PRINTER ROUTINE HERE
```

The ASR instruction is used to allocate a printer to a processor. The location shown symbolically as SEM contains the value 0 if the printer is already in use or the value 1 if it is free. The ASR SEM instruction reads the location and shifts bit 0 into the carry bit of the processor. At the same time, a 0 is shifted into the high-order bit of the location and all other bits are shifted to the right one place. The result is the value 0. This is then written back into memory.

During the two cycles preceding the last write to memory, the BUSY line is high, preventing any other processor from accessing the bus. The BCS (branch-on-carry-set) instruction that follows will branch to FREE if the printer was free. If this is not the case, the program loops back to CHECK to try again. To reset the semaphore and make the resource available, store a 1 in the semaphore location.

The Local/Global System

One problem with the global-only type of system is that, since the processors must access the bus constantly to fetch opcodes, system efficiency suffers. One way to increase efficiency is to provide each processor with a separate, local bus with memory in which to store a program and a portion of the data as well. The only time a processor will be slowed is when it needs to access the global bus. This is called a *local/global system*.

A block diagram of a local/global system is given in figure 9. The top address bit (A15) is used to determine whether an access is local or global. Addresses hexadecimal 7FFF and below are global; 8000 and above are local. This places the restart and interrupt vectors in local address space, alleviating the restart problem mentioned earlier. The BUSY signal should also be gated with A15 to prevent the holding off of "rearbitration" when one of the processors is busy on the local bus. In the system shown, the processors are partitioned functionally. Processor 1 performs all I/O. Processor 2 executes the operating system and directs the operation of the others. Processor 3 and Processor 4 perform data manipulations.

Since it is not known whether an access as indicated by

Text continued on page 154

Say Ahh...



Our New grafixPLUS™ 80-column printer opens wide for easy servicing.

Introducing the newest members of our grafixPLUS™ family—the DP-9000 Series 80/132 column printers—built on the same tradition of quality printout, solid design and low cost of ownership established by our 132/220 column DP-9500 Series.

A Case for Serviceability

Not that is comes up often, but want to get inside? Simple. Just remove a few screws and the clam-shell case swings open exposing all major components. This easy access plus built-in self-test and minimum component count yields an MTTR of one-half hour. The 9-wire print head replacement's even simpler... two screws and it's out. Without opening the case. And without a service call.

Performance Plus

The DP-9000 Series prints the full ASCII 96 character set, including descenders and underlining, bi-directionally, at up to 200 CPS. Number of columns can go up to 80 or 132, depending on character density—switch or data source selectable from 10 to 16.7 characters per inch. And all characters can be printed double width. The print head produces razor-sharp characters and high-density graphics with dot resolutions of 72X75 dots/inch under direct data source control.

Interface Flexibility

The three ASCII compatible interfaces (parallel, RS-232-C and current loop) are standard, so connecting your computer is usually a matter of plug-it-in and print. Also standard are: a sophisticated communications interface for printer control and full point-to-point communications, DEC PROTOCOL, and a 700 character FIFO buffer. An additional 2K buffer is optional.

When you're ready for a printer (or several thousand), look into the grafixPLUS DP-9000 Series from Anadex—you'll find an open and shut case for quality. Contact us today for details, discounts and demonstrations.

Anadex®
...the plus in printers

...close please.

SALES OFFICES: San Jose, CA (408) 247-3933
Fullerton, CA (714) 871-0501 • Wakefield, MA (617) 245-9160 • Austin, TX (512) 327-5250

ANADEX, INC. • 9825 DeSoto Avenue • Chatsworth, California 91311, U.S.A. • Telephone: (213) 998-8010 • TWX 910-494-2761

ANADEX, LTD. • Dorna House, Guildford Road • West End, Woking, Surrey GU24 9PW, England • Tel: Chobham (09905) 6333 • Telex: 858762 ANADEX G



Figure 9: *Block diagram of a local/global multiprocessor system.*

COMPATIBILITY

...that's the 910

You no longer have to pay high prices for conversational terminals. Now you can get TeleVideo's new 910 terminal at a low price.



- TeleVideo engineering provides you with switchable emulations of the ADDS 25/Viewpoint, Hazeltine 1410, Lear Siegler ADM-3A, 5A. Four switchable character fonts and five independently-controlled video attributes.
- Microprocessor design offers OEM's the flexibility of code changes.
- You will get TeleVideo's high quality value and features.
- The 910 uses the same monitor, keyboard, and case as our popular 912/920. This means field-proven reliability.

TeleVideo®

TeleVideo Systems, Inc.
1170 Morse Avenue
Sunnyvale, CA 94086
408/745-7760
800/538-8725 (outside CA)
TWX 910-338-7633

Nationwide field service is available from General Electric Co Instrumentation and Communication Equipment Service Centers.

The Value Leaders

Santa Ana, CA 714/557-6095; Sunnyvale, CA 408/745-7760; Dallas, TX 214/980-9978; Atlanta, GA 404/255-9338; Bloomindale, IL 312/351-9350; Morris Plains, NJ 201/267-8805; London 44-9905-6464

Text continued from page 150:

AVMA is going to be global or local, bus arbitration cannot be accomplished until addresses for the current cycle become valid. Addresses do not become valid until t_{AD} (200 ns in a processor rated at 1 MHz) after the rising edge of E, and arbitration must be complete before the rising edge of Q to prevent BUSY from switching to the valid state for the next cycle.

The E-low-to-Q-high time (t_{EQ}) is 250 ns at 1 MHz. Arbitration must be complete in $t_{EQ} - t_{AD} =$ 250 ns − 200 ns = 50 ns. Assuming Schottky buffers for the A15 line, there will be a 7 ns delay through the buffer, a 45 ns propagation delay through the 74S287 PROM, an 8 ns propagation delay through the 74S139, and a 22 ns delay for the bus buffers to release from high impedance. This is a total of 82 ns arbitration time. Clearly, this is not sufficiently fast. One solution is to redesign the arbiter using random logic to reduce the arbitration time. Another solution is to slow the system clock to less than 1 MHz, but this reduces throughput. A better solution is to use MC68A09Es. The address delay, t_{AD}, is only 140 ns in this part. With a 1 MHz clock, this requires 250 ns − 140 ns = 110 ns to arbitrate, leaving a 28 ns margin.

This type of system can use cost-effective 16 K-bit dynamic memory devices by applying the 6809's unique method of software refresh. In this method, an oscillator is connected to the $\overline{NMI}$ line, causing a nonmaskable interrupt to be generated periodically. The interrupt routine executed with each interrupt is used to refresh the dynamic memory, and the oscillator is set at a frequency allowing all the memory to be refreshed frequently enough to retain all its information. The interrupt routine is 128 page-2 "pre-byte" opcodes (hexadecimal 10), each of which increments the program counter and fetches the next byte (each instruction takes only one machine cycle). This routine quickly cycles through all possible

COMPUTER WAREHOUSE

CALL TOLL FREE 1-800-528-1054

International Dealer & Personal Inquiries Invited, Prices May Vary. Tlx (0) 668382 (MCB)

ATARI

Special 32K 800 System 800 w/32K, recorder star raiders, joysticks	$935
800 (16K)	$744
810 Disk Drive	Call
825 Printer	$710
850 Interface	$155
410 Recorder	$70
830 Modem	$140
Star Raiders	$ 45
16K Memory	$ 75
32K Memory	$150

DISK DRIVES

Lobo

Apple 1st Drive	$490
Apple 2nd Drive	$410

MODEMS

Novation

CAT	$155
D-CAT	$155
Apple Cat II	Call
Auto Cat	Call

SOFTWARE

CBASIC	Call
CP/M	Call

VIDEO TERMINALS

Adds	
Viewpoint	Call
Soroc	
IQ 120	Call
IQ 130	Call
IQ 135	Call
IQ 140	Call
Televideo	
912 B	$699
912 C	$699
920 B	$749
920 C	$749
950	Call
Zenith - Z - 19	Call

PRINTERS

C.Itoh	
Starwriter	$1333
Datasouth	
DS180	$1365
Diablo	Call
Epson	
MX-80	Call
MX-80 F/T	Call
Fric.Feed Opt. for MX-80	$50
NEC	Call
Okidata	
Microline 80	$375
Microline 82	$515
Microline 83	$755
Qume	Call
Texas Instruments	
810 Basic	$1480
810 Loaded	$1739

COMPUTERS

Altos	Call
Northstar	Call
Intertec Data	
Superbrain 64K D/D	$2777
Commodore	
8032	$1498
8050	$1498
Zenith	
Z-89 48K	Call

DISKETTES

Memorex	Call
BASF	Call
Scotch	
5¼-0, 10, 16 Sector (Qty 100)	$250
8"-0, 32 Sector (Qty 100)	$260

MONITORS

APF - 9" Monitor	$115
Sanyo - 9" Monitor	$165

We Buy and Sell Used Equipment

Experienced Equipment

Diablo, NEC, Qume	Call
Centronics 779	$450
Hazeltine 1510	$650
Hazeltine 1420	$600
Atari 820 printer	$250
Soroc	$475
TI 810 Basic	$1100

ATARI® Novation ZENITH data systems NorthStar SOROC TECHNOLOGY, INC. TeleVideo™ 3M TEXAS INSTRUMENTS EPSON EPSON AMERICA, INC. OKIDATA MPC MICROTEK PERIPHERALS CORP.

COMPUTER WAREHOUSE

2222 E. Indian School Rd. Phoenix, Arizona 85016
(602) 954-6109 1-800-528-1054
Store Hours: Tues.- Friday 10-5 MST Saturday 10-4 MST

MasterCard VISA

Circle 85 on inquiry card.

Personal checks will delay shipping two weeks. Prices & availability subject to change without notice.

Prices reflect 3% cash discount. Product shipped in factory cartons with manufactures warranty. Add 2%, a minimum of $5, for shipping and handling.

combinations of the 8 low-address lines (A0 thru A7), which is sufficient to refresh all the 16 K-bit memory devices being used. The memory used may be very slow because the entire cycle is available to access it (since there is no hidden refresh). However, the global memory must have hardware-refresh circuits because the stretched cycles caused by the shared bus preclude efficient refresh by the above method.

Applications

The systems described earlier provide a high concentration of processing power with the ability to communicate over a high-bandwidth medium, the global bus. Appropriate applications for this type of machine include problems that can be broken into subproblems not requiring access to the full block of data; mathematical operations on matrices are an example. Adding, subtracting, multiplying, finding the inverse, and finding the determinant of a matrix are all operations that can be partitioned successfully. If each processor can perform part of the operation and later combine the subproblem solutions, the speed of the system will be substantially increased over conventional serial methods.

A different way to use a multiprocessor system is to functionally partition a problem. Using a separate processor for each task allows simplified system software but retains the cost advantage over separate, loosely coupled systems. Several users can do different tasks simultaneously without a reduction in throughput or the complication of multiple-task operating systems. In any event, multiprocessing certainly has a place wherever concentrated computing power is needed with maximum utilization of resources. Multiprocessing is the wave of the future. ■

Apple* en CASTELLANO

Tercer Medio presenta su sistema administrativo (T.M.A.) para Apple

Diseñado de acuerdo con los principios contables aceptados en todos los países de habla hispana.

APLICACIONES COMERCIALES Y CIENTIFICAS

- **CONTABILIDAD GENERAL**

  Diario General
  Resumen del Diario
  Consulta parcial al Diario
  Mayor General
  Balance de Comprobación
  Balance General
  Ganancias y Pérdidas
  Catálogos de Cuentas
  Consultas por pantalla

- **CUENTAS POR COBRAR**

  Catálogo de Cuentas
  Listado de Transacciones
  Antigüedad de Saldos
  Saldos por Vencer
  Relación de Cobranzas
  Relación de Pagos
  Estado de Cuentas
  Consultas varias por pantalla

- **INVENTARIO Y FACTURACION**
- **CONTROL DE BANCOS**
- **PERT/CPM**
- **CUENTAS A PAGAR**
- **CONTROL DE COSTO DE OBRAS**

VENTAJAS DEL SISTEMA T.M.A.

- Son completamente conversacionales.
- El chequeo de la información es instantáneo.
- Los reportes impresos o por pantalla guardan los formatos generalmente aceptados.
- Están pensados para adaptarse a cualquier empresa.
- Toda la información está instantáneamente disponible
- Precisión Expandida.
- Números de hasta ± 999.999.999,99



Circle 390 on inquiry card.

Tercer Medio
Sistema de Información C.A.

APARTADO DE CORREOS 62533
CARACAS 1060 - A - VENEZUELA
TELEX: 27.876 - CPB TH - VE.
TELEFONOS: 283.60.88 - 284.74.68

Publicidad Gráficas León, S.R.L.

*Apple es marca registrada por APPLE COMPUTER INC.

Computer Simulation of a Solar-Energy System

Daniel Doan
60 Wadsworth St #17H
Cambridge MA 02142

Energy consumption in the United States in 1979 exceeded 70 quadrillion Btus (British thermal units). That's a lot of energy. About 22% of that was consumed by residential space and water heating. If some of this energy could be supplied directly by the sun, the savings would be considerable.

This goal could be attained in part by thermal-solar-energy heating systems, but their design presents some problems. For example, what collector area would be most cost-effective? Does the building need more insulation? Can a storage tank hold enough energy to supply the building with heat thru a cold spell? A simulator program can help answer these and other important questions.

A computer program using heat-transfer equations can use numerical approximation to effectively simulate a solar-energy system. Program users can begin simulation with the parameters of their home and learn the effect of changes in these parameters on the efficiency of a hypothetical energy system. In this way, an economical system can be engineered for a particular building and location without costly experimentation.

A typical solar-heating system (figure 1) consists of a collector, storage tank, and pipes connecting these and the building. In this article, I consider only a circulating-water system, keeping in mind that the concepts are similar for a hot air system.

The flow, storage, and exchange of heat are governed by several thermodynamic equations. Heat flow in any homogeneous material is given by the equation:

$$H_f = (T_h - T_c)/R_f \quad (1)$$

where H_f = heat flow in kilojoules per hour (kJ/hr), T_h = temperature on hot side of material, in degrees Celsius, T_c = temperature on cool side of material in °C, and R_f = resistance to heat flow in the material, with units of degree-hours per kilojoule (degree-hrs/kJ). The resistance to heat flow is a constant, characteristic of the material thru which the heat transfer takes place. This equation will be used to calculate the amount of heat lost from the building. We can also calculate the amount of heat lost from the storage tank and that lost from the collector to the outside air.

The thermodynamic equation for heat storage is:

$$H_s = m\ C_v\ T_a \quad (2)$$

where H_s = heat stored in the material, in kJ, m = mass of the material in kilograms, C_v = specific heat of the material, in kJ/kg-degree, and T_a = absolute temperature of the material, in kelvins (K). (Kelvins are equivalent to degrees Celsius plus 273.15.) In this equation, H_s is the amount of absolute heat in the material. Any change in T_a will result in a storage or loss of energy.

When water is between 0° and 100°C, its specific heat, or C_v, is about 4.18 kJ/kg-degree. Since one liter of water has a mass of about 1 kilogram in this temperature range, a tank of 1900 liters (about 500 gallons) can store 7942 kilojoules of energy for each degree it is heated, according to equation (2).

Heat exchange, in this case thru water pumped in pipes, is given by the equation:

$$H_x = m_f C_v (T_s - T_d) \quad (3)$$

where H_x = amount of heat exchanged, in kJ/hr, m_f = mass flow rate of water in liters/hr, C_v = specific heat of water, T_s = temperature of heat source, and T_d = temperature of the heat's destination.

This can be restated as:

$$H_x = (T_s - T_d)/R_x$$

where $R_x = 1/(m_f \times C_v)$. In this way the piping system can be modeled as a resistance to heat flow, and our simulation will take advantage of this fact.

To increase our understanding of the simulation, we can make an analogy between a thermal system and an electrical circuit. Basically, electrical and thermodynamic systems have much in common, according to their dynamics. If we suppose that heat is analogous to electric charge, then heat flow is analogous to current. Thermal

About the Author

Daniel Doan graduated from the Massachusetts Institute of Technology in 1980 with a bachelor's degree in electrical engineering. He is continuing his education at MIT in a master of science program. During the last four years, Dan has done research on a simulation system for power electronic circuits, in which an IMSAI 8080 computer was used.

THE HARD EDGE

AND STILL THE LEADING EDGE . . .

IN SYSTEM PERFORMANCE



ADES



Hard Disk and Streaming Tape

reliability and versatility that can't be beat

OEM CONTROLLERS

- Multibus
- General Purpose
- S100





S33 ***S10*** ***SYSTEM 8***

- 31 or 62 MByte formatted
- 10.5 or 32 MByte formatted
- Lowest cost/MByte from any manufacturer
- CP/M* compatible "drop in" BIOS
- Single S100 card controller
- Fully expandable up to four drives, 8" or 14"
- Reliable high performance Priam Winchester Disks
- Immediate delivery

- 8" Winchester 10 or 32 MByte formatted
- Integrated streaming cartridge backup
- Streaming backup at 5 MB/min
- Selective file backup under CP/M
- Versatile parallel I/0 or DMA interface

ADES

ADAPTIVE DATA & ENERGY SYSTEMS

2627 Pomona Boulevard • Pomona, CA 91768

Phone: (714) 594-5858

*CP/M is a trademark of Digital Research Corp.

Figure 1: *Diagram of a water-based thermal-energy system that will provide home heat using solar energy as a source. The water tank serves as a temporary energy-storage area, which can provide heat on cloudy days.*



Figure 2: *Electrical simulation of heat flow in the solar-heating system shown in figure 1. Current source I_s simulates the solar collector. Resistors R_d and R_x represent the water-piping system connecting the collector, the storage tank, and the house. Resistors R_c, R_t, and R_h represent paths of heat loss to the environment from the three main system components. The capacitances of C_t and C_h simulate the heat-storage capacity of the water tank and the house, respectively. The switch S symbolizes the house thermostat, closing when the house temperature goes below the thermostat setting. Diode D shows that heat will be transferred to the water tank only when the collector's temperature is greater than that of the tank.*



resistance can be compared with electrical capacitance. Compare equation (1) with Ohm's law:

$$I = (V_h - V_l)/R$$

If the above analogies hold, we can see that the voltage in a circuit corresponds to the temperature in a thermal system.

For a clear illustration that capacitance is the counterpart of heat storage in our analogy, compare equation (2) with the fundamental equation for charge on a capacitor:

$$Q = CV$$

Here C is the capacitance, and V is the voltage across the dielectric. If voltage is analogous to temperature, then in our simulation, heat storage can be modeled as capacitance.

Our thermal system (figure 1) can now be described as an electrical circuit, as shown in figure 2. The piping systems from the collector to the tank and from the tank to the building are modeled by the resistances R_d and R_x, respectively. The switch S symbolizes the building thermostat, closed when building temperature is below the thermostat setting. The diode shows that heat will be transferred from the collector to the tank only when the temperature of the collector is higher than that of the tank. These heat-flow controls will be implemented in our computer simulation by IF statements and a flag in the program.

The heat-storage capacity of the building is symbolized by C_h, and R_h shows the path of heat loss to the environment. The heat-storage capacity of the water tank is shown by C_t, and R_t shows the path of heat loss from the tank. Operation of the collector is defined by the values of k and R_c. The current source at the left of the circuit is a model of the sun's energy that strikes the collector and turns into heat.

The amount of heat actually absorbed by the collector is less than the amount striking it. This is due to reflection from the cover plates and incomplete absorption by the collector surface. The ratio of heat absorbed to heat striking is referred to as k, and is given by the equation:

$$k = at^n$$

where a = absorptivity of surface (about 0.9 for most black paints), t = transmissivity of cover plate (about 0.8 for glass), and n = the number of cover plates.

Some of the absorbed heat will be lost to the environment. This heat flows thru R_c, the value of which is a parameter of the collector. The amount of heat gained from any solar collector can be described by an equation:

$$I_{out} = k\,I_s - (T_c - T_a)/R_c$$

where T_c = temperature of the collector, T_a = temperature of environment, I_{out} = amount of heat actually sent to the storage tank, and k and R_c given as parameters. Commercially built collectors will list the values of k and R_c on data sheets accompanying the units. Occasionally, this data will be given in the form of an efficiency equation:

$$\text{efficiency} = k - U(T_c - T_a)/I_s$$

with k and U given. U is merely $1/R_c$.

The hot-water-storage tank is modeled in our circuit by an RC (resistor/capacitor) network. The time constant of this RC network is R_tC_t. If the tank is large and well in-

Listing 1: *The solar-energy system simulator written in CBASIC. The author attempted to use only those BASIC statements available in other versions of BASIC, to facilitate translation.*

```
10   REM            SOLAR ENERGY
20   REM          SYSTEM SIMULATOR
30   REM     BY DANIEL DOAN     JUNE,1980
40   REM
50   REM  DEFINE FUNCTIONS
60   PI = 3.14159
70   REM  ARCCOS(X)
80   DEF FNA(X)=PI/2-ATN(X/SQR(1-X*X))
90   REM  DEGREES TO RADIANS
100  DEF FNR(Y)=Y*PI/180
110  REM
120  REM  DAYS IN MONTH
130  DATA 31,28,31,30,31,30,31,31,30,31,30,31
140  DIM M(12)
150  FOR I=1 TO 12
160  READ M(I)
170  NEXT I
180  REM
190  REM  GET PARAMETERS
200  FOR CD=1 TO 8
210  GOSUB 3260
220  NEXT CD
230  REM
240  REM  REVISE?
250  GOTO 3000
260  REM
270  REM  INPUT DATA
280  GOSUB 2000
290  IF IT<0 THEN 2500
300  REM  SETUP SUN
310  GOSUB 2200
320  REM
330  REM  LOOP ONE HOUR
340  FOR MI=DT TO 60.0 STEP DT
350  T=HR+MI/60
360  IS=B*SIN((T-(12-WS))*PI/(2*WS))
370  IS=IS*DT/60
380  IF T<12-WS OR T>12+WS THEN IS=0
390  REM  ADD TO SUM1
400  FT=FT+IS
410  IF TC<TT THEN 470
420  TC=RD*RC/(RC+RD)*(K*IS+TA/RC+TT/RD)
430  IF TC>100 THEN TC=100
440  II=(TC-TT)/RD
450  II=II*DT/60
460  GOTO 490
470  TC=K*IS*RC*60/DT+TA
480  II=0
490  REM  ADD TO SUM2
500  ST=ST+II
510  REM  CALCULATE TANK,HOUSE
520  IF TH<TS THEN F=1
530  IH=(TT-TH)/RX
540  IH=IH*DT/60
550  IL=(TT-TA)/RT
560  IL=IL*DT/60
570  REM  TANK
580  SI=II-F*IH-IL
590  TT=TT+SI/CT
600  IF TT>100 THEN TT=100
610  REM  HOUSE
620  SI=F*IH-DT*(TH-TA)/(RH*60)
630  TH=TH+SI/CH
640  REM  ADD TO SUM3
650  HT=HT+IH*F
660  F=0
670  IF OP$="S" THEN GOSUB 2400
680  NEXT MI
690  REM  SUM4
700  UT=UT+(TS-TA)/RH
710  IF TH<TS THEN 880
720  HR=HR+1
```

Listing 1 continued on page 164

sulated, it will cool off very slowly. This means that its RC time constant is large. From equation (2):

$$C_t = m\ C_v$$

Since the specific heat C_v is 4.18 kJ/kg-degree, C_t is equal to 4.18 kJ/degree multiplied by the number of liters of water in the tank. A good time constant is a week, or 168 hours, and that requires R_t to be about 0.021 degree-hrs/kJ for the 1900-liter tank.

A 1-inch thickness of common fiberglass insulation has a thermal resistance value of about 1.95 degree-m²-hrs/kJ. To convert this metric R-value or R-number to R_t, it must be divided by the area insulated. The result is in units of degree-hrs/kJ. If the 1900-liter tank has an outside area of 20 square meters, 1 inch of insulation will give $R_t = 1.95/20 = 0.098$ degree-hrs/kJ. This would be sufficient to insulate the tank, but more insulation is recommended and will decrease the amount of heat wasted.

The thermal-resistance coefficient of the building must also be calculated. This can be derived from the amount of insulation, heat loss thru windows and doors, and the heating of infiltrating air. This is complicated and beyond the scope of this article, but a guide to this calculation can be found in *Sound Control and Thermal Insulation of Buildings* by Paul Close (see reference 1). An easier way to determine R_h is to divide the number of degree-days in a year by the number of kilojoules of energy burned by the building's heating plant during that year. In this manner:

$$R_h = 24 \times N/(H_u \times eff) \times 5/9$$

where N = number of degree-Fahrenheit-days in a year, H_u = number of kilojoules burned by heating system in that year, and eff = efficiency of the furnace. The factor 5/9 converts degrees Fahrenheit to degrees Celsius.

To find H_u, the amount of fuel burned must be multiplied by its energy content. Coal contains about 6.2×10^6 kJ/metric ton, #2 heating oil contains about 39,100 kJ/liter (148,000 kJ/gallon), and natural gas contains about 19,950 kJ/m³ (565 kJ/ft³). The efficiency of a typical furnace is between 70% and 80%, but it should be measured for each individual furnace. The number of degree-days in a year for a specific geographic region can be obtained from local weather or radio stations.

The heat capacity of the building C_h cannot be easily determined from the design of the building. But the building cools down to the temperature of its environment exponentially as a function of time, with no heat source, by the equation:

$$T = (T_i - T_e)\exp(-t/R_hC_h) + T_e$$

Here, T_i = initial inside temperature, and T_e = temperature of the environment. The time it takes

Text continued on page 168

IF YOU NEED $5,000...20,000 EVEN UP TO 500,000 TO START A NEW BUSINESS OR TO EXPAND AN EXISTING FIRM—THEN READ WHY YOU TOO WILL CALL THIS INCREDIBLE MONEY RAISING MANUAL

"THE SMALL BUSINESS BORROWER'S BIBLE"

Practically prepares the loan application for you line-by-line...the "proper" way. All properly prepared applications are processed faster...no red tape! Guaranteed Loans...Direct Loans...and Immediate Loans are available now!

Most men and women seriously interested in starting their own business are eligible to apply — including those who already own a business and need capital fast for expansion...or to stay afloat...even if they've been flatly refused by banks and turned down elsewhere! Yet, too, many never qualify, simply because they do not know how to "properly" prepare the loan application...

In order to help those people applying for these guaranteed and direct loans fill out their loan applications the "right way," ICC Business Research, through its diligent compilation and research efforts, has successfully assembled and published a comprehensive, easy-to-follow seminar manual: The Money Raiser's Guaranteed and Direct Loans Manual, that will **quickly show you practically everything you'll need to know** to prepare a loan application to get federally Guaranteed and Direct Loans.

Here are just **some of the many important benefits** the Money Raiser's Guaranteed and Direct Loans Manual provides you with:

- **a completely filled in sample set of actual SBA loan application forms, all properly filled in for you to easily follow—aids you in quickly preparing your own loan application the right way. Each line on the sample application forms is explained and illustrated in easy-to-understand language.**
- **fast application preparation procedures for getting loans for both new start up business ventures and established firms.**
- **advises you on how to properly answer key questions necessary for loan approval and in order to help avoid having your application turned down—gives you advice on what you should not do under any circumstances.**
- **what simple steps you take to guarantee eligibility—no matter if you do not presently qualify.**
- **where you can file your application for fastest processing.**

At this point the most important question you want answered is: Just where is all this loan money coming from? Incredible as it may sound—these Guaranteed Loans, ...Direct Loans...and Immediate Loans are indeed available right now — from the best, and yet, the most overlooked and frequently the most ignored and sometimes outright ridiculed..."made-fun-of" source of ready money...fast capital, in America — THE UNITED STATES GOVERNMENT.

Of course, there are those who upon hearing the words "UNITED STATES GOVERNMENT" will instantly freeze up and frown and say:

"...only minorities can get small business loan money from the government!"

Yet, on the other hand (and most puzzling) others will rant on and on and on that:

"...don't even try, it's just impossible — all those Business Loans Programs are strictly for the Chryslers, the Lockheeds, the big corporations...not for the little guy or small companies." etc.

Still there are those who declare:

"...I need money right now...and small business government loans take too darn long. It's impossible to qualify. No one ever gets one of those loans."

Or you may hear these comments:

"...My accountant's junior assistant says he thinks it might be a waste of my time!" "Heck, there's too much worriesome paperwork and red tape to wade through!"

Frankly — such rantings and ravings are just a lot of "bull" without any real basis — and only serve to clearly show that lack of knowledge...misinformation...and and not quite fully understanding the UNITED STATES GOVERNMENT'S Small Business Administration's (SBA) Programs have unfortunately caused a lot of people to ignore what is without a doubt — not only the most important and generous source of financing for new business start ups and existing business expansions in this country — but of the entire world!

Now that you've heard the "bull" about the United States Government's SBA Loan Program — take a few more moments and read the following facts:

- **Only 9.6% of approved loans were actually made to minorities last year**
- **What SBA recognizes as a "small business" actually applies to 97% of all the companies in the nation**
- **Red tape comes about only when the loan application is sent back due to applicant not providing the requested information...or providing the wrong information**
- **The SBA is required by Congress to provide a minimum dollar amount in business loans each fiscal year in order to lawfully comply with strict quotas. (Almost 5 billion this year)**

Yet, despite the millions who miss out — there are still literally thousands of ambitious **men and women nationwide** who are properly applying — being approved — and **obtaining sufficient funds** to either start a new business, a franchise, or buy out or expand an existing one. Mostly, they are all just typical Americans with no fancy titles, who used essentially the **same effective know-how** to fill out their applications that you'll find in the Money Raiser's Guaranteed and Direct Loans Manual. Manual.

So don't you dare be shy about applying for and accepting these guaranteed and direct government loans. Curiously enough, the government is actually very much interested in helping you start a business that will make a lot of money. It's to their advantage — the more money you make the more they stand to collect in taxes. In fiscal 1981, our nation's good old generous "uncle" will either lend directly or guarantee **billions of dollars** in loan requests, along with technical assistance and even sales procurement assistance. Remember, **if you don't** apply for these available SBA funds **somebody else certainly will.**

Don't lose out — now is the best time to place your order for this comprehensive manual. It is **not sold in stores.** Available only by mail through this ad, directly from **ICC Business Research, the exclusive publisher,** at just a small fraction of what it would cost for the services of a private loan advisor or to attend a seminar. **For example:**

Initially, this amazing Guaranteed and Direct Loans Manual was specially designed to be the basis of a Small Business Loan Seminar — where each registrant would pay an admission fee of $450. But our company felt that since the manual's quality instructions were so ***exceptionally crystal-clear*** *that anyone who could read, could* ***successfully use its techniques*** *without having to attend a seminar or pay for costly private loan advisory assistance services.*

Therefore, for those purchasing the manual by mail, no 3 day class, no course and accommodations are required. And rather than $450 we could slash the price all the way down to just a mere $35 — a small portion of a typical seminar attendance fee — providing you promptly fill in and mail coupon below with fee while this special "seminar-in-print" manual offer is still available by mail at this relatively low price!

Remember, this most unique manual quickly provides you with actual sample copies of SBA Loan application and all other required forms—already properly filled in for you to easily use as reliably accurate step-by-step guides—thus offering you complete assurance that your application will be properly prepared...and thereby immediately putting you on the right road to obtaining fast, no red-tape loan approval.

GUARANTEE #1

Simply — look over this most effective money raising loan preparation assistance manual for 15 days — and, then, if you are not convinced that it can actually help you obtain the Business Loan you need right away — just return it for a full and prompt refund.

GUARANTEE #2

Even after 15 days — here's how you are still strongly protected — if you decide to keep the manual — and you apply for an SBA Loan anytime within 1 year...your loan must be approved and you must actually receive the funds or your money will be refunded in full.

YOU GET NOT 1 BUT 2 STRONG BINDING GUARANTEES!

YOUR LOAN MUST ACTUALLY BE APPROVED OR YOUR MONEY BACK

Of course, no one can guarantee that every request will be approved — but clearly we are firmly convinced that any sound business request properly prepared — showing a reasonable chance of repayment and submitted to SBA — will be approved. Only because we are so confident that this is a fact do we dare make such a strong binding seldom-heard-of Double Guarantee. **No stronger guarantee possible! It actually pays for you to order a copy of this remarkable manual —** ***100% tax deductible as a business expense*** **...Don't delay—send for yours right now!**

NO RISK LOAN OPPORTUNITY FORM

Detach and rush for COMPLETE PREPARATION ASSISTANCE FOR LOAN APPROVAL

Please rush me ______ copies of the "Money Raiser's Guaranteed and Direct Loans Manual," each at a $35 fee plus $2.50 handling and shipping under your 2 strong binding Guarantees.

Enclosed is full payment
☐ Check ☐ Money Order
☐ C.O.D. $5 Deposit required.
Send payment with order Save C O D Fee

Name ______________________
Please Print Clearly

Address ______________________

City ______________________

State ______________ Zip ______

My telephone is (   ) ______________
(in case we have a question about your order)

MAIL TO: **ICC Business Research**
307 Forest Hill Avenue
Winston-Salem, N.C. 27105

THE EASY NO-NONSENSE WAY TO RAISE CAPITAL FAST!

Circle 177 on inquiry card.

Listing 1 continued:

```
730  IF HR=24 THEN 770
740  IF OP$="H" THEN GOSUB 2400
750  IF IP$="H" THEN 260
760  GOTO 320
770  HR=0
780  DA=DA+1
790  IF DA>M(MO) THEN 830
800  IF OP$="D" OR OP$="H" THEN GOSUB 2400
810  IF IP$="D" OR IP$="H" THEN 260
820  GOTO 300
830  DA=1
840  MO=MO+1
850  IF MO=13 THEN MO=1
860  GOSUB 2400
870  GOTO 260
880  REM  AUX HEAT
890  IF TH>=TS-5 THEN 720
900  SA=SA+(TS-5-TH)*CH
910  TH=TS-5
920  GOTO 720
930  REM
940  REM
950  REM
960  REM  SUBROUTINES
970  REM
980  REM
990  REM
1000 REM GET LOCATION
1010 PRINT
1020 INPUT"LATITUDE(D,M,S)";LD,LM,LS
1030 LA=((LD*60+LM)*60+LS)/3600
1040 LA=FNR(LA)
1050 RETURN
1100 REM
1110 REM  GET DT
1120 PRINT
1130 PRINT"STEP SIZE, IN MINUTES"
1140 INPUT DT
1150 IF 60/DT=INT(60/DT) THEN RETURN
1160 PRINT
1170 PRINT"DT MUST BE A FACTOR OF 60."
1180 GOTO 1120
1200 REM
1210 REM  COLLECTOR DATA
1220 PRINT
1230 PRINT"COLLECTOR AREA"
1240 INPUT"(SQR. METERS)";AR
1250 PRINT
1260 INPUT"ANGLE FROM HORIZONTAL";AN
1270 AN=FNR(AN)
1280 PRINT
1290 PRINT"COLLECTOR LOSS"
1300 INPUT"COEFFICIENT";RC
1310 PRINT
1320 INPUT"# OF COVER PLATES";NP
1330 AL=0.9
1340 TR=0.8
1350 K=AL*TR^NP
1360 RETURN
1400 REM   TANK DATA
1410 PRINT
1420 INPUT"TANK VOLUME(LITERS)";CT
1430 CT=CT*4.187
1440 PRINT
1450 INPUT"TANK LOSS COEFF.";RT
1460 PRINT
1470 INPUT"FLOW TO TANK(L/MIN)";ML
1480 RD=1/(ML*4.187*60)
1490 RETURN
1500 REM  HOUSE DATA
1510 PRINT
1520 INPUT"HOUSE LOSS COEFF.";RH
1530 PRINT
1540 INPUT"HOUSE TIME CONSTANT(HRS)";HC
1550 CH=HC/RH
1560 PRINT
```

Listing 1 continued on page 166

Orange Micro

"THE COMPUTER PRINTER SPECIALISTS"

UP TO 25% DISCOUNTS! — SAME DAY SHIPMENT!

NEW CENTRONICS 739 (RADIO SHACK LINE PRINTER IV)

With Graphics and Word Processing Print Quality

• 18 x 9 dot matrix; suitable for word processing • Underlining • proportional spacing • right margin justification • serif typeface • 80/100 CPS • 9½" Pin Feed/Friction feed • Reverse Platen • 80/132 columns • Top of form

CENTRONICS 739-1 (Parallel) . . . . (List $995) $ Call
CENTRONICS 739-3 (Serial) . . . . (List $1045) $ Call

VISTA — C. ITOH

Daisy Wheel Letter Quality



• 25 CPS (Optional 45 CPS) • Typewriter quality • Centronics parallel • RS 232 Serial (Optional) • Proportional spacing • Bidirectional • Programmable VFU • Self test • Diablo compatible • Friction feed (Optional tractors) • 136 printable columns. • Manufactured by C. ITOH.

VISTA V300 (C. ITOH) . . . . (List $1895) $ Call

ANADEX

Dot Graphics, Wide Carriage

• 11 x 9 dot matrix; lower case descenders • Dot resolution graphics • Bidirectional, logic seeking • Up to 200 CPS • RS 232 Serial & Parallel • Forms control • X-ON/X-OFF • Up to 6 part copy.

ANADEX 9501 . . . . (List $1650) $1350

ANACOM

Low Cost, High Speed, Wide Carriage

• 9 x 9 dot matrix • Lower case descenders • Wide carriage • Adjustable tractors to 16" • 150 CPS, Bidirectional, Logic Seeking

ANACOM 150 . . . . (List $1350) $ Call

MALIBU 165

The Small Business Printer; Letter Quality & Speed.

• 10 x 9 dot matrix • Letter quality print; Lower case descenders • High speed; 165 CPS, Bidirectional, Logic seeking • Wide carriage • Vertical forms control • User programmable character set • Dot Resolution Graphics.

AXIOM

Dot Graphics, Low Price

• Dot addressable graphics • 70 CPS
• 12 characters per inch • 80 columns
• adjustable tractors • 3 part copies
• Manufactured by Sieko • Parallel, RS232 serial, IEEE-488 interfaces available.

AXIOM GP-80M . . . . (List $399) $349

NEC SPINWRITER

High Speed Letter Quality

• 55 CPS • Typewriter quality • Bidirectional • Plotting • proportional spacing.

5510-5 RO, Serial, w/tractors . . . . (List $2995) $2650
5530-5 RO, Parallel, w/tractors . . . . (List $2970) $2625

TELEVIDEO CRT'S

AT DISCOUNT PRICES!

TVI 912C
TVI 920C
TVI 950
} Please Call Toll Free. Prices are too low to advertise

QUANTITY PRICING AVAILABLE

IDS PAPER TIGERS

Dot Resolution Graphics, quality print, speed



• 7 wire printhead (445); 9 wire printhead (460) with lower case descenders • Over 150 CPS • bi-directional, logic seeking (460) • 8 character sizes; 80-132 columns • Adjustable tractors • High-resolution dot graphics • Proportional spacing & text justification (460).

IDS 445G 7 wire printhead, graphics . . . . . . (List $895) $ 750
IDS 460G 9 wire printhead, graphics . . . . . . (List $1394) $1150
IDS 560G 9 wire, wide carriage, graphics . . . . (List $1794) $1590

PRINTERS

MALIBU 165 wide carriage, graphics, letter quality . . (List $2495) $ 1975
QUME 5/45 typewriter quality . . . . (List $2905) $ 2559

INTERFACE EQUIPMENT

CCS APPLE PARALLEL Interface & cable . . . . $ 150
ORANGE INTERFACE for Apple II parallel interface board & cable . . . . $ 110
MICROTRONICS Atari parallel interface . . . . $ 69
ATARI 850 Interface module, serial/parallel . . . . $ 199
TRS-80 CABLES to keyboard or Exp. interface . . . . $ Call
NOVATION D-CAT direct connect modem . . . . $ Call

CALL FOR FREE CATALOG

(800) 854-8275

CA, AK, HI (714) 630-3322

At Orange Micro, we try to fit the right printer to your application. Call our printer specialists for free consultation.

TELEPHONE ORDERS: Mon.-Fri. 8:30 - 5:00
The Orange Micro Printer Store (Retail):
Mon.-Fri. 10:00 - 6:00, Sat. til 4:00

Phone orders WELCOME; same day shipment. Free use of VISA & MASTERCARD. Personal checks require 2 weeks to clear. Manufacturer's warranty included on all equipment. Prices subject to revision.

Orange Micro, Inc.
3150 E. La Palma, Suite I
Anaheim, CA 92806

Circle 290 on inquiry card.

Listing 1 continued:

```
1570 INPUT"FLOW TO HOUSE(L/MIN)";ML
1580 RX=1/(ML*4.187*60)
1590 PRINT
1600 INPUT"THERMOSTAT SETTING";TS
1610 RETURN
1620 REM
1630 REM  INITIAL TEMPS
1640 PRINT
1650 PRINT"    INITIAL"
1660 INPUT"COLLECTOR TEMP";CI
1670 INPUT"TANK      TEMP";TI
1680 INPUT"HOUSE     TEMP";HI
1690 RETURN
1700 REM
1710 REM  I/O
1720 PRINT
1730 PRINT"OUTPUT EACH MONTH, DAY,"
1740 INPUT"HOUR, OR STEP (M/D/H/S)";OP$
1750 PRINT
1760 PRINT"INPUT EACH MONTH, DAY,"
1770 INPUT"OR HOUR (M/D/H)";IP$
1780 RETURN
1800 REM
1810 REM  INIT DATE,HOUR
1820 PRINT
1830 PRINT"STARTING DATE, TIME"
1840 INPUT"MONTH(1-12)";MS
1850 INPUT"DAY  (1-21)";DS
1860 INPUT"HOUR (0-23)";HS
1870 RETURN
1900 REM
1910 REM  OUTPUT DATE,TIME
1920 PRINT
1930 PRINT"MO   DA   HR"
1940 PRINT MO;" ";DA;" ";HR
1950 RETURN
2000 REM
2010 REM  GET TEMP, INSOLATION
2020 PRINT
2030 PRINT"MEAN OUTDOOR TEMP"
2040 PRINT"FOR PERIOD BEGINNING"
2050 GOSUB 1900
2060 INPUT"(DEGREES F)";TA
2070 TA=(TA-32)*5/9
2080 PRINT
2090 PRINT"MEAN DAILY INSOLATION"
2100 PRINT"FOR SAME PERIOD"
2110 INPUT"(KJ/SQR.METER)";IT
2120 RETURN
2200 REM
2210 REM  NEW DAY OR NEW DATA
2220 REM
2230 N=MO*30+DA
2240 DE=0.40928*SIN((284+N)*2*PI/365)
2250 FA=-1*TAN(LA)*TAN(DE)
2260 WS=FNA(FA)
2270 AC=COS(LA-AN)*COS(DE)+SIN(LA-AN)*SIN(DE)
2280 AT=COS(LA)*COS(DE)+SIN(LA)*SIN(DE)
2290 IU=IT*AR*AC/AT
2300 IU=ABS(IU)
2310 WS=WS*12/PI
2320 B=(IU*PI)/(4*WS)
2330 RETURN
2400 REM
2410 REM  OUTPUT TEMPS
2420 GOSUB 1900
2430 PRINT
2440 PRINT"TH ";TH
2450 PRINT"TT ";TT
2460 PRINT"TC ";TC
2470 RETURN
2500 REM
2510 REM  OUTPUT SUMS
2520 PRINT
2530 PRINT"KJ INCIDENT  ";FT
2540 PRINT"KJ COLLECTED ";ST
2550 PRINT"KJ DELIVERED ";HT
```

Listing 1 continued on page 168

Listing 1 continued:

```
2560 PRINT"KJ REQUIRED  ";UT
2570 PRINT"AUX KJ USED  ";SA
2580 PRINT
2590 PRINT HI/UT*100;" PERCENT SOLAR"
3000 REM
3010 REM
3020 REM  MENU OF COMMANDS
3030 REM
3040 PRINT
3050 PRINT"1 - CHANGE LOCATION"
3060 PRINT"2 - CHANGE DT"
3070 PRINT"3 - CHANGE COLLECTOR DATA"
3080 PRINT"4 - CHANGE TANK DATA"
3090 PRINT"5 - CHANGE HOUSE DATA"
3100 PRINT"6 - CHANGE INITIAL TEMPS"
3110 PRINT"7 - CHANGE I/O"
3120 PRINT"8 - CHANGE DATE, HOUR"
3130 PRINT"9 - RUN"
3140 PRINT"10- CONTINUE"
3150 PRINT"11- QUIT"
3160 PRINT
3170 PRINT"TYPE THE # CORRESPONDING"
3180 PRINT"TO YOUR WISH."
3190 INPUT CD
3200 IF CD>11 OR CD<1 THEN 3000
3210 IF CD = 11 THEN STOP
3220 IF CD = 10 THEN 260
3230 IF CD = 9 THEN 3300
3240 GOSUB 3260
3250 GOTO 3000
3260 REM
3270 REM  DISPATCH
3280 ON CD GOTO 1000,1100,1200,1400,1500,1620,1700,1800
3300 REM
3310 REM  RESET INITS AND RUN
3320 TC=CI
3330 TT=TI
3340 TH=HI
3350 HT=0
3360 ST=0
3370 FT=0
3380 UT=0
3390 SA=0
3400 MO=MS
3410 DA=DS
3420 HR=HS
3430 GOTO 260
```

Text continued from page 162:

to cool down to $1/e$ or about 37% of its original temperature is one time constant R_hC_h.

If one wishes to find this time constant for a particular occupied house, certain approximations must be made. In practice all houses have many heat sources: people, appliances, lights, and pets. These can be ignored because they produce much less heat than the building's main heating system. To measure t_h (which is R_hC_h), turn off the main heating system for a few hours and fit the resulting temperatures over a period of time to the exponential equation shown above. The time constant required (in units of hours) can be divided by R_h to get C_h. For example, the R_h of a typical building might be 10^{-3} degree-hrs/kJ, and t_h might be two days, or 48 hours, so that C_h would be 48,000 kJ/degree.

About the Program

Understanding all the preceding parameters is important for understanding the simulator program. This program is designed to work easily on the data from the reference book *Input Data for Solar Systems,* distributed by the United States Department of Energy (see reference 2). This publication contains information in tables for 248 weather stations in the United States. It includes average temperature and standard degree-days (heating and cooling) in degrees Fahrenheit and mean daily solar radiation on a horizontal surface for every station each month of the year.

The simulation program (shown in listing 1) will fit in 8 K bytes of memory with lots of room for expansion. The program was written for an Ohio Scientific C1P, but only those BASIC statements available on most BASIC machines were used.

The first loop, in lines 200 to 220, calls the different subroutines to obtain values for the various heating-system parameters. The initial conditions of the system

Text continued on page 172



Introducing MuDOS.* The rest of the works for networks.

A CP/M compatible replacement for CP/NET****
MuDOS multiplies your micro capabilities with higher throughput, increased reliability and extra professional features for both single and multi-user environments. MuDOS works with any Z80-based micro, in place of CP/NET, MP/M**, or CP/M — and, of course, with MuSYS NET/80* and EXP/80* network slaves.

MuDOS works faster — MuDOS makes the most of the Z80's extra registers and instructions. Program loading is up to six times faster; file processing functions average three to five times faster than CP/M.



MuDOS works smarter — A sophisticated buffer manager, a totally re-entrant file manager, multiple print queuing, disk file support to 67MB, drive support to 2000MB and read-after-write verification of disk updates helps you make the most of your multi-user data and word processing programs. Modular design allows us to tailor the system to your configuration.

Build your network with MuSYS — MuDOS is ideal for use with our NET/80 board (64K RAM, single level interrupt, console port and parallel port for bus communication) and our EXP/80 expansion board (another serial port, Centronics port, priority interrupt control, real time clock, etc.) for S-100 based systems.

This is the year of the network — Make sure you have the works. Call or write MuSYS Corporation, 1451 E. Irvine Blvd., Suite 11, Tustin, CA 92680 (714)730-5692. TWX: 910-595-1967. CABLE: MUSYSTSTN.

MuSYS CORP.
Specialists in Multi-user Microsystems

*MuDOS, NET/80, and EXP/80 are trademarks of MuSYS Corp. **CP/M, MP/M and CP/NET are trademarks of Digital Research.

Circle 273 on inquiry card.

Listing 2: *Sample run of the solar-system simulator using actual data obtained from the author's parents' home.*

```
CRUN VER 2.03

LATITUDE(D,M,S) 41,20,0

STEP SIZE, IN MINUTES
? 60

COLLECTOR AREA
(SQR. METERS) 40

ANGLE FROM HORIZONTAL 35

COLLECTOR LOSS
COEFFICIENT .0022

# OF COVER PLATES 1

TANK VOLUME(LITERS) 1900

TANK LOSS COEFF. .098

FLOW TO TANK(L/MIN) 5

HOUSE LOSS COEFF. .00213

HOUSE TIME CONSTANT(HRS) 24

FLOW TO HOUSE(L/MIN) 5

THERMOSTAT SETTING 20

    INITIAL
COLLECTOR TEMP 10
TANK      TEMP 50
HOUSE     TEMP 20

OUTPUT EACH MONTH, DAY,
HOUR, OR STEP (M/D/H/S) m

INPUT EACH MONTH, DAY,
OR HOUR (M/D/H) m

STARTING DATE, TIME
MONTH(1-12) 1
DAY  (1-21) 1
HOUR (0-23) 0

1 - CHANGE LOCATION
2 - CHANGE DT
3 - CHANGE COLLECTOR DATA
4 - CHANGE TANK DATA
5 - CHANGE HOUSE DATA
6 - CHANGE INITIAL TEMPS
7 - CHANGE I/O
8 - CHANGE DATE, HOUR
9 - RUN
10- CONTINUE
11- QUIT

TYPE THE # CORRESPONDING
TO YOUR WISH.
? 9


MEAN OUTDOOR TEMP
FOR PERIOD BEGINNING

MO   DA   HR
 1    1    0
(DEGREES F) 26
```

```
MEAN DAILY INSOLATION
FOR SAME PERIOD
(KJ/SQR.METER) 5165

MO   DA   HR
 2    1    0

TH   15
TT   16.1120664067
TC -3.33333333333

MEAN OUTDOOR TEMP
FOR PERIOD BEGINNING

MO   DA   HR
 2    1    0
(DEGREES F) 0

MEAN DAILY INSOLATION
FOR SAME PERIOD
(KJ/SQR.METER) -1

KJ INCIDENT    10416572.1067
KJ COLLECTED   2929020.83061
KJ DELIVERED   3030684.47692
KJ REQUIRED    8150234.74177
AUX KJ USED    3404717.54754

 37.1852415659  PERCENT SOLAR

1 - CHANGE LOCATION
2 - CHANGE DT
3 - CHANGE COLLECTOR DATA
4 - CHANGE TANK DATA
5 - CHANGE HOUSE DATA
6 - CHANGE INITIAL TEMPS
7 - CHANGE I/O
8 - CHANGE DATE, HOUR
9 - RUN
10- CONTINUE
11- QUIT

TYPE THE # CORRESPONDING
TO YOUR WISH.
? 10

MEAN OUTDOOR TEMP
FOR PERIOD BEGINNING

MO   DA   HR
 2    1    0
(DEGREES F) 27.3

MEAN DAILY INSOLATION
FOR SAME PERIOD
(KJ/SQR.METER) 7815


MO   DA   HR
 3    1    0

TH   15
TT   17.1636489361
TC -2.61111111111

MEAN OUTDOOR TEMP
FOR PERIOD BEGINNING

MO   DA   HR
 3    1    0
(DEGREES F) 36
```

```
MEAN DAILY INSOLATION
FOR SAME PERIOD
(KJ/SQR.METER) 11250

MO   DA   HR
 4    1    0

TH   18.1455114873
TT   21.1256652165
TC   2.22222222222

MEAN OUTDOOR TEMP
FOR PERIOD BEGINNING

MO   DA   HR
 4    1   .0
(DEGREES F) 0

MEAN DAILY INSOLATION
FOR SAME PERIOD
(KJ/SQR.METER) -1

KJ INCIDENT    38853164.0338
KJ COLLECTED   12498479.6857
KJ DELIVERED   12236803.5069
KJ REQUIRED    21493583.7251
AUX KJ USED '  5478230.30262

 56.9323555505  PERCENT SOLAR

1 - CHANGE LOCATION
2 - CHANGE DT
3 - CHANGE COLLECTOR DATA
4 - CHANGE TANK DATA
5 - CHANGE HOUSE DATA
6 - CHANGE INITIAL TEMPS
7 - CHANGE I/O
8 - CHANGE DATE, HOUR
9 - RUN
10- CONTINUE
11- QUIT


TYPE THE # CORRESPONDING
TO YOUR WISH.
? 11
```

Wild Hare Software Systems Multiply the Capabilities of Data General's

RDOS
INFOS®
ICOS
DOS



Wild Hare gives Data General users a choice when upgrading to a multi-user environment and eliminates the need to use AOS. Wild Hare makes it easy for you. It creates a true multi-lingual, multi-user environment for your current system. No user software modifications are necessary. There is no need to install a new operating system. And, no expensive hardware upgrade is required.

Features

- Each user is totally independent of all other users.
- Each user may run all standard Data General software.
- Each user may independently edit, compile, execute and debug programs written in any language supported by RDOS, INFOS®, ICOS and DOS.
- Standard languages supported include: Fortran IV, Fortran V, COBOL, ALGOL, RPG, DG/L™, BASIC, PASCAL, MAC, etc.
- All NOVA's® and ECLIPSE's® are supported.
- Wild Hare guarantees its software systems on a money back basis.

Wild Hare's Software Gives Data General Users A Choice!

WILD HARE COMPUTER SYSTEMS INC

P.O. Box 3581, Boulder, Colorado 80307
(303)-494-0221

Circle 425 on inquiry card.

NOVA®, ECLIPSE® and INFOS® are registered trademarks of Data General Corporation.

Text continued from page 168:
are set up. These include the initial temperatures of the tank, collector, and building in degrees C. The time increment for the numerical approximation is set to a value between 1 minute and 60 minutes. This allows a very accurate simulation, if 1-minute steps are used, or a fast simulation, if 30- or 60-minute steps are used. The program is quite accurate even with long steps. Short steps could be effectively used with parameter changes to simulate how a partly cloudy day affects the system.

The subroutine beginning at line 2200 changes daily solar radiation in kilojoules to a half-wave sine approximation of the energy falling during that day. As the simulation proceeds thru the current day, the sun rises at a point in time WS hours before noon and sets WS hours after noon. WS is the hour angle of the sun, calculated from the location's latitude and the declination of the sun (lines 2230 to 2260). The sine wave is implemented in the main loop in lines 360 to 380, as the simulator time proceeds.

The user is asked if he wants output each *dt* (step size), hour, day, or month. He is also asked if changing data (outside temperature and solar radiation) should be input each hour, day, or month. The program asks the user for the initial date and hour of simulation, to calculate the angle of incidence of solar radiation. Control is then transferred to lines 3000 thru 3300, where the user is given a menu of different commands that allow him to change any parameters or run the simulation.

As the program is running, it will output the temperatures of the collector, tank, and building until data is required. When data is input, the simulation will continue. If a negative value is input for the solar radiation, the program will stop simulation and output five sums of energy:

- the amount of heat striking the collector
- the amount of heat transferred to the tank from the collector
- the amount of heat delivered to the building from the tank
- the amount of heat that would have been used by the building had its temperature stayed at 20 °C (68 °F)
- the amount of heat delivered by an auxiliary source

These sums can be compared for different parameter values to find the most efficient and effective heating system. After this output, control returns to line 3000, allowing the user to alter parameters and run the simulation again, or quit the program.

As many will note, this program is far from ideal. Much could be added. If you wish to simulate a system employing a collector with selective surfaces, lines 1320 to 1350 could be changed to allow input of different transmissivities of glass and absorptivities of the surface. If a south-facing wall of the building has many windows, a current source could be added to the electric circuit to model the heat gain from this passive source.

As an example, I calculated the t_h and R_h of my parents' home in Pennsylvania. R_h was 0.00213 degree-hrs/kJ, and t_h was 24 hours. A tank of 500 gallons with 1 inch of insulation was modeled, and the flow rates of typical water pumps were used (5 liters/minute). Other parameters were 40 square meters of collector area, a single cover plate, and an R_c of 0.0022 degree-hrs/kJ. The simulator was run for these conditions, giving the output shown in listing 2. The results were significant, since a total of 1.2×10^7 kilojoules of energy would be supplied by this system, and the house uses 2.1×10^7 kilojoules without any solar heating during January, February, and March in a typical year.

I hope that some readers will be inspired to develop further some of these ideas, which show the power of computers in engineering alternative energy sources. ■

References

1. Close, Paul D, *Sound Control and Thermal Insulation of Buildings*, New York: Van Nostrand Reinhold, 1966.
2. National Climatic Center. *Input Data for Solar Systems*. U.S. Department of Energy, 1979. Available for $3 from:

Director, National Climatic Center
Federal Building
Asheville, NC 28801
Telephone: (704) 258-2850 ext 683

For requests about receiving the same data on computer-readable magnetic tape, call extension 203.

New Products From Orange Micro

Mix APPLES and ORANGES?

. . . And you get GRAPHICS!

NEW

THE GRAPPLER™ Apple Interface and Cable

FROM ORANGE MICRO

The Grappler™ Interface is the first universal parallel interface card to provide on-board firmware for Apple high resolution dot graphics. No longer does the user need to load clumsy software routines to dump screen graphic – it's all in a chip. Actually, it's our E-PROM, and there are versions to accommodate the Anadex, Epson MX80 & MX70, IDS Paper Tigers, Centronics 739, and future graphics printers. The Grappler™ accepts 18 software commands including Hi-Res inverse, 90° rotation, double size, and much more.



$165.00 Includes Cable

Dealer/Distributor Inquiries Invited

GRAPPLER INTERFACE FEATURES

TEXT FEATURES:
Printer Bell on/off
High Bit on/off
Left Margin
Right Margin
Var. Line Length
Var. Page Length (skip over perf.)
Video on/off
Alternate Command Chars.
Text Screen Dump

Hi-RES GRAPHICS FEATURES:
Print Hi-Res Page 1 or 2
Print Inverse
Rotate Picture 90°
Single/Double Size
Variable Left Margin
Chart Recorder Mode

NEW

MX80/MX70 FRICTION FEED

FROM ORANGE MICRO

HERE AT LAST! A friction feed kit for your EPSON MX80/70. The kit allows the user to convert his Epson printer to a friction feed and pin feed mechanism.

The friction feed will accept single sheets of your letterhead, or multiple copy forms such as invoices with up to 4 part carbon copies.

The pin feed replaces the adjustable sprocket mechanism. It allows use of 9½" wide continuous fanfold paper which is an industry standard size.

No drilling required. Installation takes about 15 minutes. All parts are included with easy to follow instructions.



$75.00

Dealer/Distributor Inquiries Invited

CALL FOR FREE CATALOG

(800) 854-8275

CA, AK, HI (714) 630-3322

RETAIL PRINTER STORES:
3150 E. La Palma, #I, Anaheim, CA.
13604 Ventura Bl., Sherman Oaks, CA.
Store Hours: M-F 10-6 Sat. 10-4

Phone orders WELCOME; same day shipment. Free use of VISA & MASTERCARD. Personal checks require 2 weeks to clear. Manufacturer's warranty included on all equipment. Prices subject to revision.

Orange Micro, Inc.
3150 E. La Palma, Suite I
Anaheim, CA 92806

Circle 291 on inquiry card.

The Atari Assembler/Editor

Mark Pelczarski
1206 Kings Circle
West Chicago IL 60185

The Atari Assembler/Editor plug-in ROM (read-only memory) cartridge is finally available. Anyone who plans to use or learn 6502 assembly language on the Atari 400 or 800 computers will find it a convenient tool. It is especially nice for beginners, since some of the editing and programming features of Atari BASIC are available. The Atari people point out that this assembler is not designed for professional programmers, although they do use it for much of their in-house programming. They describe it as an experimenter's assembler designed for those people writing machine-language subroutines to supplement their BASIC programs when speed, sound, or graphics are factors.

Overview

The Assembler/Editor package includes the cartridge and a user's manual. The cartridge actually contains three programs: the Writer/Editor, the Assembler, and the Debugger/Mini-Assembler. The cartridge will operate with either a cassette-tape drive or a floppy-disk system, but the disk gives more versatility. The cartridge plugs into the left slot in the Atari 800, and it occupies the upper 8 K bytes of user-accessible memory-address space.

Although it does not make any attempt to teach the fundamental concepts of assembly-language programming, the manual does include an overview of 6502 assembly language (command format, addressing modes, types of operands, etc)—something I've not seen in other assembler/editor packages. The beginner will still want to find a good book about 6502 assembly language, however. A large part of the manual contains information explaining the use of each program and the options and procedures available. It seems complete and easy to follow and contains helpful information in the appendices, including sample programs showing how to use machine-language subroutines from BASIC.

This assembler will be used mostly for writing short subroutines that will be called from BASIC programs. Those who decide to write straight machine-language code will need more information about the Atari I/O (input/output) structure, which may be found in the *Atari Technical Manual*, now available. They will also have to consider the memory capacity of their machine. Atari estimates that the amount of object code that can be "comfortably developed" with the cartridge is about one-tenth of the memory space available. Thus a 40 K-byte system would allow about 4 K bytes of object code to be developed. (Remember that other use of the top 8 K bytes is precluded by the cartridge, so 40 K bytes is the maximum.)

Those who want to write long machine-language segments to attach to BASIC programs may find some other problems. There are only 256 bytes in memory that are guaranteed untouched by BASIC or the operating system. If you want to write a longer machine-language routine, you must incorporate it into the actual BASIC program through the use of strings. This is not an unknown practice. Programmers of Radio Shack's TRS-80 have been using this method for quite some time. The only drawback is that the code must be fully relocatable. That means the subroutine can have no JMP or JSR commands to itself, and no data tables. Some non-relocatable material may be put in the one 256-byte block that is always available, but some headaches may persist. These procedures are well documented in the appendix,

At a Glance

Product
Atari Assembler/Editor Cartridge

Manufacturer
Atari Inc,
Computer Products Division
1346 Bordeaux Dr
Sunnyvale CA 94086

Price
$59.95

Format
Plug-in ROM cartridge

Computer requirements
Atari 400 or 800, floppy-disk drive, and more than 16 K bytes of memory recommended, but not necessary

Documentation
User's manual describing operating features is included. Atari technical information and 6502 assembly-language programming information available separately

Audience
Those who want to write machine-language programs and subroutines on the Atari computers



New Hard Disk Control At Your Fingertips.

Introducing THE DAVID™ a giant step forward.

Konan, known for its innovative, versatile selection of high performance controllers, now offers THE DAVID.

THE DAVID is a series of intelligent HARD DISK CONTROLLERS for the Apple, S-100, Radio Shack, IEEE 488 and others.

Here are all the mighty things THE DAVID does:

- Error correction. 32 bit poly, 11 bit correct.
- Flaw mapping done by controller.
- Single high-speed bidirectional port.
- Fully buffered 256 and 512 byte sectors.
- Write pre-comp/data separation if required.
- Format command. Full or partial disk.
- Read next command.
- Power on diagnostics.
- Single/double density 5 1/4" and 8" floppy available in 8" hard disk products.

Hard disks currently supported include most 5 1/4's and CDC Finch. To come are all 8" hard disks with the SA1000 interface (7-81), and SMD drives (9-81). Other drive implementations available soon

These very low cost controllers are all host software and hardware compatible. That means total flexibility to change drive types or manufacturers, without rewriting software or designing new hardware.

In other words, THE DAVID is a giant in its own right...and every bit IN CONTROL. Put this powerful equipment to work for you. Give us a call on Konan's toll-free order line:

800-528-4563

Or write to: Konan Corporation
1448 N. 27th Avenue, Phoenix, AZ 85009
TWX/TELEX 9109511552

Konan offers a selection of other fine tape and disk controller products and is actively pursuing license agreements.

KONAN™ in control

Circle 201 on inquiry card.

by the way, with sample programs using calculations, sound, and graphics (a demonstration of putting 128 colors on the screen at once).

Writer/Editor

The Writer/Editor allows you to enter and edit assembly-language programs. Each line of a program is numbered, as in BASIC, and contains an optional label, an instruction, an operand, and an optional comment. These are located in predesignated fields across the line, and pressing either Tab or the space bar moves the cursor to the next field. The Editor also uses the same screen editing that Atari BASIC uses: you may move the cursor to a line, insert, delete, or change characters, then press Return and the new line is entered. The line numbering allows other BASIC-like commands, such as:

- LIST—to list all or part of a program
- DEL—to delete a line or a range of lines
- NUM—for automatic line numbering
- REN—to renumber lines

(Strangely, most of these were left out of Atari BASIC.) The Editor also has FIND and REPLACE commands, plus SAVE and LOAD commands that let you move parts of programs, allowing you to create your own library of subroutines on disk.

The Assembler

The Writer/Editor puts your program into a text buffer in memory. The Assembler takes the source program from the buffer, or from disk or cassette tape, and assembles it into an object program (true 6502 machine language) stored in a specified range of memory, on disk, or on tape. During assembly you can also specify an assembly listing to be displayed on the screen, written to disk or tape, or printed on a printer. Assembly requires two passes, which is standard. Directives to the assembler may be included in your program to control paging and titles in the assembly listing, and to insert values and character strings into the machine code. One feature not provided that would have been helpful is a symbol table that shows the values assigned to labels you've used.

Debugger/Mini-Assembler

The Debugger allows you to trace through your program step by step as it runs and make minor changes in conditions or in the code. Options provided allow for single-stepping through your program, displaying and changing register or memory values, and moving and comparing contents of memory locations. There is also the Disassembler, which will display the instruction mnemonics for any range of memory, and the Mini-Assembler, which lets you assemble single lines of code at specified locations.

Conclusions

Although there are three programs in the cartridge, transferring control back and forth between them is simple, thus creating the effect of a nicely integrated system. When you turn the power on, you are in the Editor mode. Typing ASM assembles whatever source code is in the buffer and returns you to the Editor. Typing BUG puts you in the Debugger. Typing X returns you to the Editor again. With a disk, typing DOS gives you access to the disk operating system, and you can access the Atari's built-in Memo-Pad by typing BYE.

There's nothing easier than using a cartridge-based system, even if we did have to wait for it. The designers of the Assembler/Editor programs have taken advantage of the cartridge system, and have made a nice, easy-to-use tool for both beginners and assembly-language experts. It was not designed for large-scale machine-language code development, but that shouldn't bother most people. It is much easier to write the bulk of a program in a higher-level language such as BASIC, leaving machine language for the subroutines that have requirements BASIC cannot satisfy.■

The Atari Technical Manual *is available from Atari for $27 plus $3 shipping. A documented operating-system source-code listing is available for $17 plus $3 shipping. Contact Atari Inc, Customer Service Division, 1346 Bordeaux Dr, Sunnyvale CA 94086.*

SYBEX HAS THE BASIC IDEA

PLEASE SEND ME ☐INSIDE BASIC GAMES
☐FIFTY BASIC EXERCISES

MAIL TO:
SYBEX DEPT. B71
2344 SIXTH STREET
BERKELEY, CA 94710
PHONE ORDERS:
INSIDE CA 415/848-8233
TOLL FREE OUTSIDE CA 800-227-2346

NAME ____________ ☐SEND ME YOUR FREE CATALOG
ADDRESS ____________
CITY ____________ STATE ______ ZIP ______
ADD ☐$1.50/book UPS or ☐75¢/book 4th class mail or ☐$8/book overseas airmail
(CA add tax) Total Amt. Enclosed ______ OR CHARGE MY ☐VISA ☐MC ☐AM EX.
CARD NO. ____________ EXP. DATE ______
SIGNATURE ____________

Energy Conservation with a Microcomputer

David R Jackson and John M Callahan
University of Connecticut Energy Center
POB U-139
Storrs CT 06268

Many aspects of the present energy situation are beyond the control of the individual. There are, however, a few notable actions that you can take to lessen the impact: one is to conserve conventional fuels; the other is to find economical alternatives. In this article we will present several tools that can be used in conjunction with your personal computer—tools that will allow you to understand energy-use patterns, and change these patterns with sound technical and economic decisions.

We will begin by providing a background on heat transfer and how it governs the energy consumed in a building. After this information is presented, we will outline an example that demonstrates the calculation that you must perform to determine your yearly energy requirements for space conditioning. Included in this example will be a program that you can use to simplify these calculations. We will also discuss energy conservation options available to you and how to determine the economic payback to implement these measures.

About the Authors

David R Jackson is Director of the Solar Energy Division of the University of Connecticut Energy Center and a lecturer in the School of Engineering. John M Callahan is a staff member at the Solar Energy Division and is working toward a degree in Electrical Engineering/Computer Science at the University. Both have been involved in a variety of research projects dealing with energy-systems performance analysis, as well as solar energy system design.

Basic Principles of Heat Transfer

Heat, of course, tends to flow from hot places to cold places. This observation fits right in with such other examples as water running downhill, electrical current flowing from high electrical potential (voltage) to low, and fluids moving from high-pressure areas to low-pressure areas. In these and similar phenomena there is a *flux* of something—thermal energy, matter, or electrical charge—in response to a favorable gradient in some *potential*. In the case of thermal energy in transit, which is referred to as heat, the potential is a *gradient*, or difference in temperature. The engineering discipline that attempts to quantitatively relate the flow of heat to temperature differences is called *heat transfer.*

Why do we care about this? Because the comfortable temperature of our living and work environments is often very different from the outdoor temperatures which surround these spaces. These temperature differences result in an unwanted flow of heat, either into our spaces or out of them. In the former case, which occurs in hot weather, we often "pump" the unwanted heat back outdoors with a type of heat pump called an air conditioner. In cold weather, we usually replace the escaping heat by burning some form of fuel or by operating an electrical resistance heater or a backwards air conditioner, called a heat pump.

The methods by which we cope with unwanted heat transfer all have one fact in common: they cost money to implement and operate. Alarming increases in the price

of fuel and electricity have caused the energy portion of our cost of living to challenge rent and mortgage payments for the lead item in the family budget.

Types of Heat Transfer

There are three basic types of heat transfer which must be recognized in order to understand and calculate the heating and cooling energy requirements of a building. These are *conduction, convection,* and *radiation.* A fourth contributor to the heating and cooling load related to outside air entering the structure will be dealt with separately as *infiltration.*

Conduction

The movement of thermal energy by conduction is the only mode of heat transfer that is possible within solid materials. However, it is also present and important in liquids and gases. Thermal energy can be visualized in terms of randomly directed motion among the atoms or molecules of a material. In solids, the atoms are bound together by forces so that the only possible atomic motions are various types of vibrations, as opposed to the relative freedom of motion present in liquids and gases. Picture a three-dimensional arrangement of billiard balls, all held in a regular geometrical pattern by springs. If one of the billiard balls is hit with a hammer and caused to vibrate, the vibrations will be transmitted through the springs until all of the balls are shaking. This example is a crude but easy-to-visualize model of the propagation of thermal energy through a solid by conduction.

Now that we have a conceptual idea of conduction heat transfer, we would like to be able to numerically calculate the rate of heat transfer by conduction in various materials for a given, imposed, temperature difference. This calculation is readily performed using Fourier's law of heat conduction, which states for simple steady-state one-dimensional conduction:

$$Q = KA\frac{\Delta T}{\Delta X} \qquad (1)$$

where:

- Q = the heat transfer rate in Btu/hr
- A = the cross-sectional area in square feet of the material perpendicular to the direction of heat flow
- ΔT = the temperature difference across the material in degrees Fahrenheit
- ΔX = the thickness of the material in the direction of heat flow in feet
- K = the thermal conductivity of the material in units consistent with the rest of the equation (eg: in Btu/hr ft °F)

The use of this equation is best demonstrated by an example. Suppose we have a 14½-inch-wide by 8-foot-long by 3½-inch-thick piece of fiberglass insulation, and we wish to calculate the rate of heat transfer through the



NEECO

WHY BUY FROM THE BEST?
Service... Support...
Software...

commodore

16K B (16K RAM-40 Column) - Lim. Qty	$ 995
32K B (32K RAM-40 Clm.) - Lim. Qty	$1295
4016 (16K RAM 4.0 Basic-40 Clm.)	$ 995
4032 (32K RAM 4.0 Basic-40 Clm.)	$1295
8032 (32K RAM 4.0 Basic-80 Clm.)	$1495
8050 Dual Disk (1 Meg Storage)	$1795
4040 Dual Disk (343K Storage)	$1295
8010 IEEE Modem	$ 280
C2N Cassette Drive	$ 95
CBM - IEEE Interface Cable	$ 40
IEEE - IEEE Interface Cable	$ 50
VIC 20 Home/Personal Computer	$ 295

ALTOS

ACS 8000-2 64K 1M	$ 4500
ACS 8000-15 64K 1M	$ 5990
ACS 8000-6 208K 14.5M	$10490
ACS 8000-7 208K 29.0M	$11690
ACS 8000-10 208K 10M	$ 8500
ACS 8000-10/MTU	$10990

NEC SPINWRITER PRINTERS

5530 (Parallel)	$3055
5510 (Serial)	$3055
5520 (KSR-Serial)	$3415
Tractor Option	$ 225

EPSON PRINTERS

MX-80 PRINTER	$ 645
MX-80 FT	$ 745
MX-100	$ 945
MX-70	$ 459
INTERFACE CARDS	
8141 (RS-232)	$ 75
8150 (2K Buffered RS-232)	$ 150
8161 (IEEE 488)	$ 55
8131 (Apple Card)	$ 85
8230 (Apple Card)	$ 25
8220 (TRS-80 Cable)	$ 35

APPLE

16K APPLE II+	$1330
32K APPLE II+	$1430
48K APPLE II+	$1530
APPLE DISK w/3.3 DOS	$ 650
APPLE DRIVE Only	$ 490
APPLE III 128K - In Stock! w/Monitor + Info Analystpak	$4740

DIABLO 630 PRINTER

DIABLO 630 - Serial - RS-232	$2710
Tractor Option	$ 250

AMDEK MONITORS

Video 100 12" B+W	$ 179
Video 300 12" Green	$ 249
Color I 13" Low Res	$ 449
Color II 13" High Res	$ 999

INTERTEC COMPUTERS

64K Superbrain (360 Disk Storage), CP/M™	$3495
64K QD Superbrain (700K Disk Storage), CP/M™	$3995

*CP/M is a registered trademark of Digital Research.

ATARI COMPUTERS

Atari 400 (16K RAM)	$ 399
Atari 800 (32K RAM) - good thru 8/31	$1080
Atari 410 RECORDER	$ 89.95
Atari 810 DISK DRIVE	$ 599.95

NEECO carries all available ATARI Software and Peripherals.

PROFESSIONAL SOFTWARE

WordPro 1 8K	$ 29.95
Word Pro 3 (40 Clm.)16K	$ 199.95
WordPro 3+	$ 295
WordPro 4 (80 Clm.) 32K	$ 375
WordPro 4+	$ 450

JUST A SAMPLE OF THE MANY PRODUCTS WE CARRY. CALL US FOR OUR NEW 60-PAGE CATALOG.
WE WILL MATCH ANY ADVERTISED PRICE ON PRODUCTS LISTED UNDER SIMILAR "IN STOCK" CONDITIONS.

NEECO
679 HIGHLAND AVE.
NEEDHAM, MA 02194

(617) 449-1760
Telex: 951021

MON-FRI 9:00 - 5:00
MasterCharge and VISA Accepted

Circle 277 on Inquiry card.

thickness. The warm side is at a temperature of 60°F, the cool side is at a temperature of 30°F, and the thermal conductivity of fiberglass insulation is 0.0265 Btu/hr ft °F. For this case:

$$A = \text{length} \times \text{width} = \frac{14.5 \text{ in}}{12 \text{ in/ft}} \times 8 \text{ ft} = 9.67 \text{ ft}^2$$

$$\Delta X = \frac{3.5 \text{ in}}{12 \text{ in/ft}} = 0.292 \text{ ft}$$

then:

$$Q = 0.0265 \times 9.67 \times \frac{(60 - 30)}{0.292} = 26.3 \frac{\text{Btu}}{\text{hr}}$$

Now that we have arrived at this number, how do we interpret it? Officially, a Btu is the quantity of heat required to raise the temperature of one pound of water one degree Fahrenheit. But this fact isn't much help unless we can relate heat requirements to fuel purchases. Roughly speaking, one gallon of number two fuel oil burned in a furnace of average efficiency contains about 100,000 Btu. One kilowatt-hour of electricity contains 3413 Btu. So, if we lost 26.3 Btu per hour through our piece of fiberglass insulation for a period of one month, the total amount of thermal energy lost would be:

$$26.3 \frac{\text{Btu}}{\text{hr}} \times 24 \frac{\text{hrs}}{\text{day}} \times 30 \frac{\text{days}}{\text{month}} = 18{,}936 \text{ Btu}$$

If fuel oil costs \$1.35/gal, and electricity \$.07/kWh, this corresponds to:

$$\frac{18{,}936 \text{ Btu}}{100{,}000 \text{ Btu/gal}} \times \$1.35\text{/gal} = \$0.26 \text{ for oil}$$

and:

$$\frac{18{,}936 \text{ Btu}}{3413 \text{ Btu/kWh}} \times \$.07\text{/kWh} = \$0.39 \text{ for electricity}$$

The example used for fiberglass insulation closely resembles the case of a normal American residential wall which is framed by 2-inch by 4-inch (nominal) studs placed on 16-inch centers and insulated with fiberglass batting between the studs. But how do we arrive at the thermal conductivity value used in the example? And what is the so-called "*R*-value" that is used in reference to insulation?

Actually, the *R*-value is another way of describing the thermal conductivity of insulation. Often we hear of a given thickness of insulation having a certain *R*-value. The lumber yards usually stock "R11" or "R19" fiberglass, which refers to 3½-inch thickness or 5½-inch thickness, respectively. Insulating materials also have a certain "*R*-value per inch." For instance, rigid urethane foam is frequently assigned an *R*-value of 6.5 per inch of thickness. The R11 fiberglass which is 3½ inches thick therefore has an *R*-value per inch of 11/3.5 = 3.1 per inch.

But we seem to be going in circles. Let's relate the *R*-value to the thermal conductivity. People in the building trade find the *R*-value of materials easier to deal with than thermal conductivity. The equation they use for heat transfer is:

$$Q = A \frac{\Delta T}{R} \qquad (2)$$



Figure 1: *Cross section of an insulation combination that is used to demonstrate heat-loss calculations.*

The System/48 is the outstanding office automation computing system for the 80's . . . it's so productive we call it MAGIC©. Look at these features:

- One to eight interactive users per node
- Data management system
- Report generator
- Query processor
- Screen format generator
- Automatic interface code generator
- Up to ½ Mbytes of user memory
- Winchester disk with 18-million bytes (formatted capacity)
- 15-minute mean-time-to-repair
- Built-in protection from line-voltage spikes, noise, and brownouts

And, it features MAGIC©, the Operating System that gets things done faster than you can say abracadabra because of its multi-keyed Indexed-Sequential Access Method and flexible file-organization. MAGIC© also offers high security, with password protection. MAGIC© supports global or local printers for as many users as desired.

MAGIC© also includes DataMagic II — TEI's red-hot database manager. DataMagic II has even more tricks up its sleeve — like automatic or manual record-lock protection and automatic transaction backout to protect the database. And it runs application software written for CP/M 2.X.

Take a MAGIC© leap into the future!

Arrange to attend one of our regularly scheduled System/48 workshops (RSVP).

OEM and Dealer Inquiries Invited

TEI | System/48

5075 S. LOOP EAST, HOUSTON, TX. 77033
(713) 738-2300 TWX. 910-881-3639

Today one dollar buys 6¼ readers who actually see your sales message.



As your selling dollar buys less and less, it pays more and more to advertise in McGraw-Hill magazines.

As prices keep going up and up, McGraw-Hill magazines help 10.8 million decision-makers keep costs down.

For example, *Chemical Week* told chemical processing managers and professionals how exports credits could lower their debt-servicing costs. And *Engineering News-Record* showed the construction industry how to cope with the destructive effects of the 1981 federal budget.

By helping 10.8 million readers solve their inflation problems, we help you solve yours.

Today, the price of reaching one potential customer in McGraw-Hill magazines is only 16¢.[1] This compares to a cost of $6.07 for sending a business letter,[2] over $3.50 for a business phone call,[3] and an in-person sales call which, believe it or not, now costs $137.02.[4]

In times like these, when everything costs more, you may be tempted to spend less on your advertising budget. But our Laboratory of Advertising Performance (LAP) Report #5262 demonstrates that "Industrial companies that maintained or increased their advertising expenditure during the 1974-75 recession enjoyed higher sales growth than those that cut advertising." Write 1221 Avenue of the Americas, New York, N.Y. 10020 for LAP Report #5262 today. And let us help you make your advertising more efficient, as the price of all other selling tools becomes more expensive.

[1]One reader-noted impression in the average McGraw-Hill publication. [2]The Dartnell Institute of Business Research. [3]"Telephone Marketing" by Murray Roman. P. 87. McGraw-Hill 1976. [4]Laboratory of Advertising Performance Report #8013.5. McGraw-Hill Research.

McGraw-Hill Magazines

With inflation, we're an even better buy.

"Our reputation rests on digits, decimal points, and details. We wouldn't trust them to anything less than Scotch® Brand Data Cartridges."



Bill Birkett, Vice President, Trade Graphics, Inc., Livonia, Michigan

The unique design of a data cartridge provides great reliability, high storage capacity and long tape life. And where could you possibly get better data cartridges than Scotch Brand, made by 3M, the people who invented the data cartridge system itself?

3M controls every step in manufacturing. Top quality magnetic tape and precision components are part of every Scotch Data Cartridge. Over twenty-five years of service to the computer industry assure you of the utmost reliability.

Scotch Data Cartridges are available in miniature DC 100A, the standard-size DC 300A and now, an extra-length DC 300XL with 50% more storage capacity. They are compatible with most cartridge systems including Hewlett-Packard, IBM, NCR, Tektronix and TI.

To find out where you can find Scotch Data Cartridges or virtually any other data recording medium, call toll-free: 800-328-1300. (In Minnesota, call collect: 612-736-9625.) Ask for the Data Recording Products Division.

If it's worth remembering, it's worth Scotch Data Recording Products.

3M

Circle 376 on inquiry card.

where R is the R-value. Quite often it appears in this form:

$$\frac{Q}{A} = \frac{\Delta T}{R}$$

which gives the heat-transfer rate per area of surface. If we compare equations 1 and 2, we see that $R = \Delta X/K$ for a given thickness, and the R-value per inch $= 1/12K$. The number twelve is left over from converting ΔX from feet to inches. Thermal conductivities tabulated in various reference sources may be listed in any of these three forms. References 1, 2, and 3 (given at the end of this article) are good sources for this data.

If we examine the version of Fourier's law of heat conduction that contains the R-value and compare it to Ohm's law for electrical conduction, we have the following:

$$Q = \frac{A\ \Delta T}{R} \qquad \text{(Fourier's law)}$$

$$I = \frac{V}{R_{\text{electrical}}} \qquad \text{(Ohm's law)}$$

The similarity between these laws is striking. Apparently, temperature difference and electrical potential difference are analogous, as is the R-value to electrical resistance and the heat transfer rate to electrical current. Thus, we can conceptually consider thermal circuits of various heat paths with characteristic thermal resistances. This analogy is extremely useful, as it provides the rules for dealing with complicated heat-path systems and leads to some of the more straightforward numerical schemes for solving problems involving complicated thermal networks. For our purposes, we need only the rules for combining series and parallel thermal resistances.

Looking once again at our example of the 3½-inch-thick fiberglass insulation, let's calculate the R-value:

$$R = \frac{\Delta X}{K} = \frac{3.5/12}{0.0265} = 11.0$$

R11 is, of course, much easier to remember to characterize 3½-inch fiberglass insulation than are thermal conductivity and thickness.

What happens if we sandwich our fiberglass between sheets of ½-inch-thick gypsum board and ½-inch asphalt-impregnated plywood, both having the same width and height as the piece of fiberglass? We know that the heat must pass sequentially through each of the three materials. This suggests that we should add the R-values

Material		R-Value (or Thermal Resistance) in $\frac{\text{hr ft}^2\ ^\circ\text{F}}{\text{Btu}}$
Plywood	¼ in	0.31
	⅜ in	0.47
	½ in	0.62
Particle board	⅝ in	0.82
Insulating sheathing	½ in	1.32
Soft wood	1 in	1.24
Hardwood	1 in	1.00
Gypsum board	⅜ in	0.32
	½ in	0.45
Plaster	1 in	0.20
Brick	1 in	0.15
Concrete blocks		
Three oval core	4 in	0.70
	8 in	1.12
	12 in	1.28
Poured concrete	1 in	0.25
Asbestos siding shingles		0.21
Wooden siding shingles		0.81
Asphalt roof shingles		0.44
Slate roof shingles		0.05
Wood roof shingles		0.94
Fiberglass batts	3½ in	11.00
	6 in	19.00
Urea formaldehyde	1 in	5.60
Polyurethane	1 in	6.25
Polystyrene	1 in	3.57
Inside vertical air film		0.68
Outside vertical air film (15 mph wind)		0.17
Inside horizontal air film		0.60
Dead air space attic		1.14
Air space between studs	3½ in	0.97
Single-pane glass		0.91
Double glass		1.67
Triple glass		2.50
Storm window (4 in air space)		1.78
Wooden door	1¼ in	1.56
Insulated steel door	1¾ in	1.69

Table 1: *Thermal resistances of several typical building materials.*

in the same manner that we would add the values of electrical resistances in series:

$$R_{total} = R_{gypsum} + R_{fiberglass} + R_{plywood}$$

The thermal resistances for gypsum and plywood sheathing (see table 1) are found to be 0.45 for ½ inch of gypsum and 1.32 for ½ inch of sheathing. The total R-value becomes:

$$R_{total} = 0.45 + 11.0 + 1.32 = 12.77$$

We must also consider parallel heat paths. The heat transfer through the wooden studs that form the walls of the cavities occupied by our fiberglass insulation (see figure 1) follows a parallel path to the heat passing through the fiberglass. In parallel electrical circuits, we merely add the currents. Here we add the heat transfer rates:

$$Q_{total} = \frac{A_1 \Delta T}{R_1} + \frac{A_2 \Delta T}{R_2} = \left(\frac{A_1}{R_1} + \frac{A_2}{R_2}\right)\Delta T \quad (3)$$

where the subscripts 1 and 2 refer to the wall areas associated with the studs and bays between them, respectively.

For each stud that is 1½ inches wide by 8 feet long, $A_2 = 1.0$ square feet, and the total resistance through the studs, which are also sandwiched between gypsum and plywood, is:

$$R_2 = R_{gypsum} + R_{stud} + R_{plywood} = 0.45 + 4.35 + 1.32 = 6.12$$

where R_{stud} (pine or other softwood 3½ inches thick) = 4.35. (See table 1 for the thermal resistances of several common building materials.) If the inside surface of the wall is at 62°F and the plywood is at 28°F, the heat transfer rate through the wall will be given by equation 3 as:

$$Q = \left(\frac{9.67}{12.77} + \frac{1.0}{6.12}\right)(62 - 28) = (.921)(34) = 33.3 \text{ Btu/hr}$$

An effective R-value for the stud/fiberglass parallel combination can also be determined. (This will be useful later.) Generalizing the parallel resistance analogy we have:

$$\frac{A_1 + A_2}{R_{eq}} = \left[\frac{A_1}{R_1} + \frac{A_2}{R_2}\right]$$

For our example (considering just the wood studs and fiberglass), we get the equation:

$$\frac{9.67 + 1.0}{R_{eq}} = \left[\frac{9.67}{11} + \frac{1}{4.35}\right]$$

which gives us a value of:

$$R_{eq} = 9.62$$



MEET AXIOM'S IMP — THE ONLY LOW COST IMPACT PRINTER DESIGNED FOR APPLE* COMPUTERS.

Three-Way Forms Handling

IMP is equipped with both friction and adjustable tractor feed (2-1/2 to 9-1/2 inches) to provide three-way forms handling — single sheet, roll paper, and fan fold.

The Nitty Gritty

IMP prints 80, 96 or 132 columns of crisp hardcopy at a speed of one line per second. The 7×7 dot matrix has a standard 96 ASCII character set. IMP's stylish low profile case will complement APPLE in any home or office. And, in addition to being distinctively styled, IMP is rugged, with a heavy duty mechanism, ribbon cartridge and single snap-out board for easy maintenance.

Visit your local computer store to see Axiom's IMP-APPLE in action.

*Trademark of Apple Computer, Inc.

Hardware and Software Compatible

Priced at only $699, Axiom's versatile IMP-APPLE is the only high quality impact printer specifically designed to operate with the popular APPLE computers. It's completely hardware and software compatible with APPLE. Even comes with cables and connectors for direct plug-in to the computer. No additional interface is needed.

Enhances HiRes Graphics

IMP greatly enhances HiRes graphics. While other printers can only reproduce graphics on a 1 for 1 basis, IMP provides over 20 different aspect ratios, with complete control over horizontal and vertical resolution, placement, and orientation. For example, a chart could be reduced and printed on one portion of the paper, with text added. IMP also enhances APPLE's alphanumeric capability by providing lower case. It's super simple to operate, too, with all printer commands controlled with a simple key stroke. Another plus, IMP is one of the few printers compatible with PASCAL. How is all this versatility made possible? For one thing, IMP has a 2K byte ROM in its special APPLE interface, while others have 256 bytes or less.

AXIOM

AXIOM CORPORATION

1014 Griswold Avenue • San Fernando, CA 91340
Telephone: (213) 365-9521 • TWX: 910-496-1746



Circle 222 on inquiry card.

The method outlined thus far allows us to compute conductive heat loss through walls (or ceilings) of arbitrary construction, provided we know the temperature of the inner and outermost surfaces. Unfortunately, we almost never know these temperatures, but we do have values for inside and outside *air* temperatures. If we can add additional thermal resistances to our network to account for the temperature drops across the air films separating the air temperature from the material surface temperatures, we will have a more complete picture.

Convection

Why can't we simply look up the thermal conductivity of air and add it in as a thermal resistance? There are two reasons:

- We have no way of determining a film thickness ΔX to use in the equation $R = \Delta X/12K$.
- The film of air adjacent to the wall may be mixing with air at a different temperature from outside the film as a result of turbulence.

Convection problems are classified as either *free* or *forced*, depending on whether the gas or liquid motion involved is caused by buoyancy effects (eg: cold air streaming down the interior surface of a large picture window on a cold night) or induced by wind (or mechanically by fans or blowers). We understand that raising the velocity of a gas over a solid surface improves heat transfer between the gas and solid—that's why we blow on hot food. However, determining the actual relationship between the flow characteristics and convective heat-transfer rate is a science unto itself, and amateurs are forced to use simple, empirically derived coefficients to describe convective heat transfer. The convective heat-transfer coefficient (h) relates the heat-transfer rate to the difference in temperature as follows:

$$Q_{convective} = hA(T_{air} - T_{surface})$$

The R-values given in table 1 are equivalent to the reciprocal of h; reference 1 gives the R-values of a large number of building materials.

Since we can consider $1/h$ to be an R-value, we are now in a position to add it to the resistance chain on the inside and outside walls.

Radiation

Before we conclude our discussion of heat transfer through an insulated wall, we should discuss radiation, the last of the three principal types of heat transfer. While conduction and convection involve matter as the medium of heat transfer, radiation does not. Radiative heat transfer proceeds unimpeded in a vacuum, where convection and conduction would be precluded. A type of electromagnetic radiation is emitted by all surfaces whose temperatures are above absolute zero. The amount of

Circle 223 on inquiry card. ⟶

Getting "STATIC" from our competition? . . if so, you're paying too much!

Try Ours $179

64K Static $895
assembled

16K Static $179
assembled



• STATIC RAMS • FULLY ASSEMBLED • FULLY TESTED • BURNED-IN • FULLY SOCKETED • INCREDIBLE VERSATILITY • BANK SELECTABLE • EXTENDED ADDRESSING • DELIVERY FROM STOCK • SAVE HUNDREDS OF DOLLARS • INTRODUCTORY PRICE - ORDER TODAY

The Memory Merchant Story

Why hasn't memory come down in price like it should? Here's what is being done for you.

High Performance and Low Price 16K Static Board

You want the most cost-effective, high performance memory boards that technology will allow. With that in mind we commissioned one of the top memory designers in the country. We told him to design the board with the user in mind. It had to sell for less than $200. It had to run cool and have low-power consumption. It had to have *both extended addressing capabilities and bank select capabilities at no additional cost.* You had to be able to de-select 1K blocks so the memory could accommodate memory-mapped video displays or controller cards. The board had to be fast so a user could run his processor at full speed. Finally, the board had to be reliable and easy to install. He came up with all this and more. Here's a high performance, fully *assembled, tested and burned-in,* guaranteed 16K board that we are *introducing for only $179.* Runs on any S-100 8080, 4 MHz Z-80, or 5 MHz 8085 system.

16K Ram, Model MM16K14 Specifications:

- Four independent 4K×8 byte segments
- One 4K segment equipped with 1K windows
- Compatible with both existing bank select type hardware and IEEE 696/S100 extended address protocol
- Operation guaranteed to 4 MHz with Z-80 and to 5 MHz with 8085 processors
- Low power consumption, typically 1.3 amps
- Uses low power 300 ns 2114 (1K×4)

64K Ram, Model MM65K16S Specifications:

- Operation guaranteed to 8 MHz
- Compatible with both existing bank select type hardware and IEEE 696 extended address protocol
- Fully loaded board (64K) draws 400ma. while max. current is 550 ma.
- Four independently addressable 16K submodules on one board organized as 2 pair of independent 32K banks or as 1 64K extended address page. Each 32K bank responds independently to phantom. Bank select logic is compatible with either Cromemco Cromix* or standard bank select software.
- 2716 (5V) EPROM compatibility: Programmed 2716 EPROMs may replace any or all of the Ram components on the board.
- New 16K (2K×8) Static Rams which combine extreme low power (40ma. ON; 5mo. OFF) with high speed (200ns max. access time).
- Also available partially populated to 48K or 32K.

**Cromix is a trademark of Cromemco.*

The Most Advanced 64K Static Board

The end user wants State-of-the Art when he buys a 64K board. So we had our super designer put together the 64K board of the future with tomorrow's high speed processors in mind. This board had to work with all S-100 systems, with current processors and future (up to 8 MHz) processors. It had to be ultra-low power. It had to be designed so the advanced user could *populate the board with programmed EPROMs* for special applications. This board, too, had to have *both bank select and extended addressing at no extra cost.* The board was also designed to be used as a 32K or 48K board and we are selling it that way, too. Put in additional chips when you want to increase the capacity!

OEM and dealer inquiries invited.

No Risk Free Trial

After you purchase one of our boards you may return it (intact) for any reason within 15 days after shipment and receive a full refund.

Free Six Months Memory Insurance

We will replace any board purchased from Memory Merchant that becomes defective through normal use for up to six months.

Yes! Please send me the items listed below. I understand that if I'm not fully satisfied with the product, I can get a full refund within 15 days after shipment. (Send check, money order, or use your credit card.) Note to credit card buyers: For extra fast service phone (415) 483-1008

QUANTITY	DESCRIPTION	UNIT PRICE	TOTAL
	64K	$895.00	
	48K	749.00	
	32K	569.00	
	16K	179.00	
SHIPPING & HANDLING $5.00/Board			
California Residents Add 6% Tax		TOTAL	

SEND TO:
MEMORY MERCHANT (B1)
14666 Doolittle Dr.
San Leandro, CA 94577

(NO C.O.D.'s)

☐ CHECK
☐ MONEY ORDER
☐ VISA
*☐ MASTERCHARGE
(Must also have ICA#)

CARD NO. ______________ EXP. DATE ______________

* ICA NO. ______________ SIGNATURE ______________

NAME ______________

ADDRESS ______________
Street City State Zip

Prices, terms, specifications subject to change without notice.

*14666 DOOLITTLE DR.
SAN LEANDRO,
CA 94577
(415) 483-1008*

Memory Merchant™





Figure 2: *Floor plan and elevations of a hypothetical house.*

radiation emitted per unit time is proportional to the fourth power of the absolute temperature of the emitting surface. Those surfaces which are separated by a vacuum or other transparent medium experience net heat transfer according to the following:

$$Q_{\text{radiation}} = \epsilon A \sigma (T_1^4 - T_2^4) \tag{4}$$

The emissivity, ϵ, is a number between zero and one, and it is a measure of the ability of a surface to emit (or absorb) radiant heat. The area, A, plays the usual role, and σ is a constant of proportionality. The nonlinearity exhibited by equation 4 would ruin our thermal resistance model if we attempted to explicitly include a radiation term.

Fortunately, in cases where radiation plays a significant role in building-heat transfer, convection is also present so that the radiation effect may be added into the convective R-value. For example, in the case of double-pane (insulated glass) windows, the panes may radiate to one another but this effect is taken into account in the overall window R-value listed in table 1. Similarly, radiation is included in tabulated R-values in other cases involving air gaps. Of course, when a gap between surfaces is stuffed with insulation, radiation is eliminated through the elimination of the transparency of the gap (so that we don't have to worry about it in those cases either).

Armed with some knowledge of the other two forms of heat transfer, we can complete our analysis of the insulated wall. Figure 1 gives a wall cross section showing the materials already discussed and the addition of exterior siding. Using table 1, reference 1, and our previous calculation, we add the R-values for the entire heat path from inside and to outside air:

Item	**R-value**
Inside surface (air film)	0.68
Gypsum wallboard	0.45
Insulation plus studs equivalent	9.62
Plywood sheathing	1.32
Wood siding	0.81
Outside surface, 15 mph wind	0.17

$$\text{Total } R\text{-value} = 13.05 \ \frac{°\text{F hr}}{\text{Btu}}$$

If a building had 1000 square feet of wall area constructed in this manner, the total heat loss for an interior temperature of 65°F and an exterior temperature of 25°F would be:

$$Q_{\text{wall total}} = \frac{A \Delta T}{R} = 1000 \text{ ft}^2 \times \left(\frac{(65 - 25)°\text{F}}{13.05 \text{ °F hr/Btu}}\right)$$
$$= 3065 \text{ Btu/hr}$$

If we extend this calculation to include other heat paths (doors, ceiling, windows, etc), we would add the resulting heat-transfer rates to get the total:

$$Q_{\text{total}} = \left(\sum_{\text{paths}} \frac{A}{R}\right) \Delta T \tag{5}$$

People who perform these calculations for a living have found it worthwhile to replace the R-value with its reciprocal, U, the conductance, so that equation 5 becomes:

Can your word processor pass this screen test?



WordStar™ software does*! And does it better than any other word processing system. Not only do you get all the sophisticated features you'd expect from the high-priced WP system, with WordStar you have a true screen image of what your printout will look like **before you print it!**

With WordStar, you'll erase, insert, delete and move entire blocks of copy. Page breaks are displayed and automatically revised on the screen. You can specify enhancements like underlining and boldfacing, and much more.

And WordStar's so much easier to learn because of its unique and extensive self-help menus. Every typist in your office can be an instant screen star. Call (415) 457-8990 and ask for a copy of our WordStar demonstration booklet. Remember, when you're the star, we're the star.

MicroPro™
INTERNATIONAL CORPORATION
The Star Maker

MicroPro International Corporation
1299 4th Street, San Rafael, CA 94901
(415) 457-8990 TELEX 340388
Sold through authorized dealers and distributors only. OEM inquiries invited.

*Runs on most Z80/8080/8085 microcomputers with CP/M (TM of Digital Research); 48K, and terminal with addressable cursor. Apple computer installation requires MicroSoft Softcard and 80 column video board.

Apple Computer is a registered trademark of Apple Computer, Inc.



Figure 3: *Construction of the ceiling and roof of the house shown in figure 2.*

$$Q_{total} = (\sum_{paths} UA)\Delta T \qquad (6)$$

where:

$$U = 1/R$$

The units of U are Btu/ft^2 hr °F, which are easier to remember than those of the R-value.

Infiltration

Remember that unconditioned air entering our building can impose an additional cooling or heating load. If a cubic foot of air at outdoor temperature enters a conditioned space, the heating or cooling system must adjust the temperature of that air to the conditioned temperature. The thermal energy, Q, required to accomplish this is given by:

$$Q = \text{vol of air in ft}^3 \times \text{density} \times \text{specific heat} \times (T_{inside} - T_{outside})$$

$$= \text{vol of air in ft}^3 \times 0.074 \frac{\text{lb}}{\text{ft}^3} \times 0.24 \frac{\text{Btu}}{\text{lb °F}} \times \Delta T \text{°F}$$

If the volume of infiltration air is given in cubic feet per minute (CFM), we have:

$$Q = (\text{CFM}) \times 60 \frac{\text{min}}{\text{hr}} \times 0.74 \frac{\text{lb}}{\text{ft}^3} \times 0.24 \frac{\text{Btu}}{\text{lb°F}} \times \Delta T \text{°F}$$

$$= 1.07 \times (\text{CFM}) \times \Delta T \qquad (7)$$

Meteorology

We have seen that in calculation of heating or cooling energy requirements in Btu/hr, we multiply our UA values by a temperature difference. Here our principal interest is to determine seasonal heating and cooling costs from these calculations. To this end, we need a way to modify our calculations to get this information.

The *degree-day* is a measure of the average temperature difference between our conditioned space and the outside for a given period of time. Heating degree-days are usually based on an inside temperature of 65°F. For example, if the average daily temperature on a day in February were 35°F, we would accumulate 65 − 35 = 30 degree-days on that day. Adding up all the heating and cooling degree-days for a month or an entire season provides a measure of the severity of the climate. We use degree-days in our calculations as shown in the following:

$$Q_{season} = \{\Sigma UA + \text{infiltration load}\} \times \text{degree-days} \times 24$$

Degree-day data is available for various US cities from the US Weather Service (see also references 1 thru 4).

Example Problem

To reinforce understanding of the relationship between the basic principles of heat transfer and different building components, we will present an example that outlines the calculations needed to determine the energy requirements for a residential building in Austin, Texas. If you live in the northeast, heating is the major energy consideration, and cooling is usually considered unnecessary, whereas if you live in the southwest, this situation may be reversed. Therefore, we have chosen Austin as a location where both heating and cooling functions are necessary.

First, we will outline the characteristics of the building that will serve as our example. Then we will proceed to show how to calculate the heat loss in the winter and the

heat gain in the summer. Finally, we will explain how to automate these calculations by using an interactive BASIC program that runs on a personal computer.

Two major factors determine heat loss and heat gain in any building: the climatological conditions and the building components. In Austin there are approximately 1980 heating degree-days and **2908** cooling degree-days. For the purpose of illustration, we will consider a single-story ranch-style house with 1500 square feet of floor area and a ceiling height of 8 feet. Figure **2** shows the floor plan and two elevations for our example house.

Building Description	Air Changes per Hour
House under 5 years old; new storm windows and doors; caulking and weatherstripping used around doors, windows, foundation.	0.5
House is 5 to 10 years old; old storm windows and doors; deteriorating caulking and weatherstripping.	1.0
House is 10 to 25 years old; no storm windows; no weatherstripping and caulking.	1.5
House is older than 25 years; drafty; windows rattle on windy day.	2.0

Table 2: *Guidelines for the air-changes-per-hour value of a house. Because this figure is difficult to calculate, the guidelines provide only a rough estimate.*

To simplify our calculations, we will assume no heat loss through the floor. We will also say that the walls have no insulation and the ceiling has 3½-inch fiberglass. The front and back doors are 1¼-inch-thick solid wood. There are ten windows, each measuring 3 feet by 4 feet. We will also assume that there are no storm doors or storm windows and that there are two exhaust fans, one in the kitchen and one in the bathroom. We will use the wall section shown in figure 1, but without the fiberglass insulation, and the ceiling/roof combination shown in figure 3. Based on the given configuration of our example building and the climatological conditions in Austin, we can now calculate the heat loss and heat gain. The procedure is very simple if it is approached in a logical step-by-step fashion.

First we should calculate or look up all the R-values for the different building elements (see reference 1). Table 1 is a fairly comprehensive list of the R-values of typical building materials; it can be used to determine the R-values for your own home if you are not able to obtain a copy of a standard reference.

We have already calculated the R-value for the wall with insulation and found it to be $R = 13.05$. To get the R-value without the insulation, we substitute the R-value of a 3½-inch air space from table 1 for the R11 fiberglass, and get an effective R-value of 4.4 for the wall.

We will now calculate the R-value for the ceiling on a one-square-foot basis. Referring to figure 3 and table 1, we list the ceiling and roof materials and individual R-values. The R-values for the ceiling are:

Inside still air	0.60
Gypsum board, ½ in	0.44
Fiberglass insulation, 3½ in	11.00
Still air in attic	1.14
Ceiling total	13.18

The R-values for the roof are:

Outside air	0.17
Asphalt single roof	0.44
Building paper	0.06
Plywood deck, 5/8 in	0.78
Air film	0.60
Roof total	2.05

We will assume that the resistances of the ceiling and roof are additive. This is not quite correct because there is more area associated with the roof, but the answer you obtain by simply adding the two resistances is fairly close, so we get $R_{ceiling/roof} = 15.23$. Single-pane windows are very poor insulators; therefore, they have a low R-value, which is approximately $R = 0.91$. The R-value for a 1¼-inch wooden door is $R = 1.56$ (see table 1).

Second, we must determine the total surface area for each building element. Using figure 2, we find the total wall area is 1118 ft^2, total glass area is 120 ft^2, total door

THE MOST INCREDIBLE LITTLE WORKER NEXT TO YOUR SECRETARY CAN SIT RIGHT NEXT TO YOUR SECRETARY.

The Zenith Z89 sub-compact: a dual Z80 microcomputer, a video terminal, and a floppy-disk drive . . . all in a single, desktop stand-alone.

The Z89: a subcompact microcomputer that needs about as much space on a desk as a portable TV set.

And needs about as much technical training to operate. Because the Z89 uses the industry-standard CP/M™ operating system, it accepts a vast variety of existing software. Most microcomputer programmers already know it, and anyone trained on larger systems adapts to CP/M* in a flash. The Z89 also uses standard, currently available software on both 5¼" and 8" floppy disks, yet is capable of more sophisticated operation using extended languages such as Microsoft BASIC, COBOL, FORTRAN, and PASCAL.

The keyboard follows the standard typewriter format, with every touch of a key confirmed by an audible click. Numbers are duplicated in calculator format, with up to 18 decimal-place accuracy. And the large-capacity non-glare video display is easy on the eyes.

The Z89 is a sub-compact desktop unit with a memory of up to 64K bytes of RAM—more than enough for word processing, accounts payable, accounts receivable, inventory control, and many other business, scientific, and technical applications . . . without a zillion different cords hanging out of the back.

And now, for you tech-spec freaks, some important jargon regarding standardization and flexibility:

Disk data: Choice of internal or external storage, or combination; 100K to 2.5 megabytes. 5¼" flexible drives (standard 10-sector hard-sector media, single-side single-density) for lowest media cost. 8" disk drives (double-side double-density) for greater storage; also standard IBM single-side single-density format for exchanging data with other computer systems. Available in either 48K or 64K systems.

Zenith is a boot-loaded RAM system, so it can accommodate the latest software on the market, and anything new that's likely to come along in the future. Twin serial input/output ports let you interface with just about any printer or modem on the market—handy whether you already have them now, or want to add them in the future. And with five different Zenith models, from a basic 48K no-disk-drive, to built-in 5¼" or 8" single or double disc drives, you can put together 18 different configurations . . . which means you can design a system to fit your exact job, rather than force your job to fit a system. In other words, the Z89's capabilities make the microcomputers with the cute names look like toys

Service? Available just about everywhere.

The Zenith Z89 . . . a highly reliable, highly affordable, state-of-the art microcomputer for the state of your business—whatever its size.

For the name of your nearest dealer, give us a call.

LEADING EDGE.™

Leading Edge Products, Inc., 225 Turnpike Street, Canton, Massachusetts 02021.

1-800-343-6833.

In Massachusetts, call collect (617) 828-8150. Telex 951-624.

DEALERS: For immediate delivery from our Inventory Bank,™ and some of the most attractive margins in the industry, call toll-free.

Building Element	Area (ft^2)	R-Value $\left(\frac{hr\ ^\circ F\ ft}{Btu}\right)$	U = 1/R $\left(\frac{Btu}{hr\ ^\circ F\ ft}\right)$	UA $\left(\frac{Btu}{hr\ ^\circ F}\right)$		Air Infiltration Load $\left(\frac{Btu}{hr\ ^\circ F}\right)$	Percent of Total Load
Ceiling/Roof	1500	15.23	0.066	98.5			13
Walls	1118	4.40	0.23	257.1			35
Windows	120	0.91	1.10	132.0			18
Doors	42	1.56	0.64	26.9			4
Air infiltration						213.1	29
Forced ventilation						6.6	<1
			Total conduction and infiltration:	514.5	+	219.7	
			Grand total:	734.2			100%

Table 3: *Summary of heat-transfer characteristics of a ranch-style house.*

area is 42 ft^2, and the ceiling area is 1500 ft^2. The volume of the conditioned space is 1500 $ft^2 \times 8$ ft = 12,000 ft^3.

Finally, we must consider the load imposed by air infiltration. All buildings have some unwanted infiltration, and often have some forced ventilation. A simple way to quantify unwanted infiltration is to speak of it in terms of the number of total air changes per hour (AC/hr). A well-constructed building with tight-fitting windows and doors can have an air-change rate as low as 0.5 AC/hr. On the other hand, a badly constructed building with poorly fitted doors and windows can have an air-change rate as high as 2.0 AC/hr. It is difficult to measure infiltration or to make reasonably accurate estimates, so for our example, we will assign 1.0 AC/hr. We suggest that when you perform your own calculation, you assign a number between 0.5 and 2.0 AC/hr, using the guidelines given in table 2.

We must change the number of air changes per hour to cubic feet per hour to use in our energy calculations. This is done by taking the air changes per hour and multiplying by the total volume of the house. In our example, we get 1 AC/hr $\times$ 12,000 ft^3 = 12,000 ft^3/hr.

Forced ventilation from exhaust fans must now be considered. We estimate the number of minutes each fan is on each day, along with its rated capacity, to determine how much air is exhausted by the fans. Remember that


The world's greatest strides in microsystems are in the Valley of the Sun.
Once again, Motorola is making history. The leader in Semiconductor technology is developing new microsystems at a record pace.
The opportunities have never been greater.
And Motorola Country never looked more inviting. With 300 days of sunshine each year, a casual approach to living and a lower cost of living than where you may be now, Motorola's Phoenix could be the perfect site for your next career move.
Find out about the bold new progress of the Motorola team — with innovative hardware and software designs at the "building block" and development systems level of microsystems.
Motorola is leading. Again and again and again.
• Manager, Development Systems Marketing
• Manager of Product Market Planning
• Manager, Hardware Engineering
• Manager, Software Engineering
• Hardware Section Leader
• Software Section Leader
• Applications Systems Engineer
• Product Marketing Engineer
• Software Engineers
• Hardware Engineers
• Product Engineer
• Programmers/Analysts
• Technical Writer
• Printed Circuit Board Designer
Call Ed Larsen, collect at 602-994-6821. Or send resume in confidence to Motorola, Inc., MOS Integrated Circuits Division, P.O. Box 20903, Phoenix, AZ 85036, Department M28.
Innovative systems through silicon.
MOTOROLA INC.
MOS Integrated Circuits Division
An Equal Opportunity/Affirmative Action Employer



Figure 4: *Flowchart for the energy-usage program of listing 1.*

any air exhausted by the fans must be replaced by outside air that is heated or cooled. The equation that governs forced ventilation is shown below:

$$\text{Air ventilation rate (ft}^3\text{/hr)} = \left[\text{estimated on-time}\left(\frac{\text{min}}{\text{day}}\right) \times \text{fan rating}\left(\frac{\text{ft}^3}{\text{min}}\right)\right]/24 \qquad (8)$$

For our example house we will say that each fan has a rated capacity of 100 ft^3/min, and each runs about 45 minutes per day. Substituting our numbers, we get the air-change rate for both fans combined:

$$\text{Air ventilation rate} = 90\,\frac{\text{min}}{\text{day}} \times \frac{1\text{ day}}{24\text{ hr}} \times 100\,\frac{\text{ft}^3}{\text{min}} = 375\,\frac{\text{ft}^3}{\text{hr}}$$

Now that we have determined the volume of air that is exchanged every hour and subsequently replaced by air that is unconditioned, we must determine the amount of energy needed to heat or cool this outside air. This must be calculated in two steps. The *infiltration energy load* is the amount of energy needed to bring to room temperature the air that inadvertently enters the house from outside, while the *ventilation energy load* is the amount of energy needed to bring to room temperature the air that enters the house to replace air deliberately pumped out by a house fan. These can be calculated as follows:

$$\text{Infiltration energy load} = 12{,}000\,\frac{\text{ft}^3}{\text{hr}} \times 0.24\,\frac{\text{Btu}}{\text{lbm}\,^\circ\text{F}} \times 0.074\,\frac{\text{lbm}}{\text{ft}^3} = 213.23\,\frac{\text{Btu}}{\text{hr}\,^\circ\text{F}}$$

$$\text{Ventilation energy load} = 375\,\frac{\text{ft}^3}{\text{hr}} \times 0.24\,\frac{\text{Btu}}{\text{lbm}\,^\circ\text{F}} \times 0.074\,\frac{\text{lbm}}{\text{ft}^3} = 6.66\,\frac{\text{Btu}}{\text{hr}\,^\circ\text{F}}$$

The notation "lbm" stands for pound-mass, and is a more accurate description of what we normally call one pound of weight. The constant 0.24 Btu/lbm °F is the number of Btu needed to heat one pound-mass of air one degree Fahrenheit. The constant 0.074 lbm/ft^3 is the number of pound-masses in one cubic foot of air.

So far, the calculations presented have been simplified. If you would like to try a more rigorous approach, we refer you to the references at the end of this article. You will find a number of procedures for calculating heat loss through basements, roof/ceiling combinations, solar-heat gain through windows, and you will also find a more elaborate description of air infiltration.

We have determined the *R*-value and surface area of each building component, as well as the energy load imposed by air infiltration. This information is summarized in table 3. We can proceed to calculate the yearly energy requirements for our example building. The total yearly

PHOENIX™

The next generation of business software

If you are still searching for quality software for your small business computer, search no more. *Designer Software*™ is pleased to announce *PHOENIX*™, the first line of microcomputer software to include *professional* word processing and general accounting.

WORD PROCESSING

We know word processing. A year-and-a-half ago the owners of *Designer Software*™ wrote a well-known word processor for another company. In the last 18 months we've learned about other features you want in a word processing package. *PHOENIX*™ Word Processing reflects our experience. It is more powerful and flexible than other word processing packages you can buy. And since we designed "human engineering" into *PHOENIX*™ Word Processing from the beginning, it can compete, feature for feature, with expensive dedicated word processors.

Many people have remarked that the user's manual we wrote earlier was the best ever for microcomputer software. Even so, we felt that we could have made it more accessible to the non-technical user. With *PHOENIX*™ Word Processing we have a separate Training Manual with beginning, intermediate and advanced levels. By allowing you to work at your own level, we have made the learning process easier and less intimidating.

ACCOUNTING

All five *PHOENIX*™ general accounting packages (General Ledger, Accounts Receivable and Payable, Payroll and Inventory) were designed by CPA's based on similar packages from mini and mainframe computers. The programs are COBOL with an integral assembly-language data base. They are fully integrated to allow automated posting to the General Ledger. An internal screen handler permits full-screen data entry for speed and ease of use. Although we made cosmetic enhancements prior to distribution, the basic programs have been user-tested for at least eighteen months.

PHOENIX™ Accounting also includes a growing number of specific application packages. We have completed or scheduled for completion Fixed Assets, Tenant Processing, Mail Management, Financial Projections and Time/Billing. Each package stands alone, but many also work in conjunction with other *PHOENIX*™ packages. For example, *PHOENIX*™ Mail Management will work very well by itself, but we also designed it to fit in easily with the merging capabilities of *PHOENIX*™ Word Processing.

With *PHOENIX*™ Accounting we have, as always, given special attention to documentation. Not being content to describe which buttons to push, we have taken the time to explain the accounting principles behind the programs and how each package fits into an automated office. To this end we created the fictional town of Smallville with a fictional company, Moustache Manufacturing. By seeing how Mr. Small and his employees use *PHOENIX*™ Accounting at 2M, you learn to apply it to your office as well. The Smallville sections are amusing as well as informative, and you will likely read the manual just to find out what Sidney, Mr. Small's incompetent brother-in-law, will do next.

Designer Software™
HOUSTON

If you want to know what PHOENIX™ Word Processing and accounting can do for your business, call, write, telex or use The Source to request more information.

3400 Montrose Blvd • Suite 718 • Houston, Texas 77006
(713) 520-8221 • Telex 790510 • Source TCU671

Listing 1: *Program to produce a table of conduction and ventilation loads and the yearly energy requirements for a given house. Written in PET BASIC, this program, when slightly modified, will also run on any computer that uses Microsoft BASIC. The PET-dependent features are the opening of logical files to the printer, and the printing of formatted results to the printer. Line 2030 creates logical device 2 as unformatted output to the printer. Line 2035 creates logical device 3 as formatted output to the printer (see, for example, line 8000). Line 2040 creates logical device 3 as the format that later influences formatted output (see lines 2045 and 5090).*

```
100 REM  TITLE "YEARLY ENERGY LOAD"
101 REM
105 REM
110 REM
115 REM THIS PROGRAM ALLOWS YOU TO DETERMINE YOUR YEARLY ENERGY CONSUMPTION.
120 REM YOU INPUT BUILDING INFORMATION AND WEATHER CONDITIONS.
125 REM THE PROGRAM GENERATES A SUMMARY OF BUILDING CHARACTERISTICS AND ENERGY
130 REM REQUIRERMENTS FOR EACH SEASON
465 REM
466 REM
467 REM
1000 REM
1001 REM
1005 REM DATA DEFINITION
1010 REM
1150 DIM S$(25)    :REM SURFACE NAME
1160 DIM A(25)     :REM SURFACE AREA
1165 DIM R(25)     :REM R-VALUE OF SURFACE
1170 DIM UA(25)    :REM UA FOR SURFACE
1180 T$=""         :REM TITLE
1185 AC=0          :REM INFILTRATION RATE
1190 V1=0          :REM FORCED VENTILATION
1195 RT=0          :REM ON TIME OF FANS
1200 DD(1)=0       :REM HEATING DD
1205 DD(2)=0       :REM COOLING DD
1220 V=0           :REM BUILDING VOLUME
1225 SU=0          :REM UA ACCUMULATOR
2000 REM
2005 REM
2010 REM  I/O SPECIFICATION
2020 REM
2025 REM
2030 OPEN 2,4,0  :REM UNFORMATTED DATA
2035 OPEN 3,4,1  :REM FORMATTED DATA
2040 OPEN 4,4,2  :REM FORMAT CHANNEL
2041 REM FORMAT STRINGS
2045 F1$="AAAAAAAAAAAAAAAAAA   99999.9       99.99        9999.9    999.9"
2046 F2$="AAAAAAAAAAAAAAAAAAAA    9.99       99999        9999.9       999.9"
2049 F4$="     999.99   AAAAAAAAAAAAAAAAAAAAA"
2050 REM FORMAT DELIMITER
2055 B$=CHR$(29)
2057 REM STRING CONSTANTS USED IN OUTPUT TABLE
2060 A$="AIR INFILTRATION"
2065 V$="FORCED VENTILATION"
3000 REM
3005 REM
3010 REM INPUT SECTION
3020 REM
3024 PRINT"TYPE IN TITLE OF OUTPUT TABLE"
3025 INPUT T$
3029 PRINT"WHAT IS AIR INFILTRATION RATE(A.C./HR)"
3030 INPUT AC
3034 PRINT"WHAT IS  INSTALLED FAN CAPACITY(CFM)"
3035 INPUT V1
3039 PRINT"WHAT IS ESTIMATED RUN TIME OF FANS(MIN/DAY)"
3040 INPUT RT
3044 PRINT"WHAT IS THE TOTAL # OF HEATING DEGREE DAYS "
3045 INPUT DD(1)
3049 PRINT"WHAT IS THE TOTAL # OF COOLING DEGREE DAYS "
3050 INPUT DD(2)
3064 PRINT"WHAT IS THE VOLUME OF YOUR BUILDING "
3065 INPUT V
3069 PRINT"ENTER THE NUMBER OF BUILDING ELEMENTS TO BE CONSIDERED"
3070 INPUT N
3075 FOR I=1 TO N
3080 INPUT"TYPE IN SURFACE NAME";S$(I)
3085 INPUT"WHAT IS SURFACE AREA";A(I)
3090 INPUT"WHAT IS THE R-VALUE";R(I)
3092 REM CALCULATE UA AND SUM UP
3095 UA(I)=(1/R(I))*A(I)
4000 SU=SU+UA(I)                    :REM ACCUMULATE HOURLY CONDUCTION LOADS
4010 NEXT I
4500 REM
4510 REM
4520 REM CALCULATION SECTION
4525 REM
4530 REM
4550 IL=.24*.074*V*AC               :REM HOURLY INFILTRATION LOAD
4555 V1=V1*RT/24                    :REM ADJUST VENTILATION TO FT↑3/HR
4560 VL=.24*.074*V1                 :REM HOURLY VENTILATION LOAD
4575 IN=IL+VL                       :REM COMBINED  HOURLY LOAD DUE TO AIR EXCHANGES
4580 TL=SU+IN                       :REM TOTAL HOURLY LOAD
4585 HL=(SU+IN)*24*DD(1)/10↑6       :REM YEARLY HEATING LOAD IN 10↑6 BTU
4600 CL=(SU+IN)*24*DD(2)/10↑6       :REM YEARLY COOLING LOAD IN 10↑6 BTU
5000 REM
5010 REM
5020 REM OUTPUT SECTION
5025 REM
5030 REM
5035 PRINT#2,T$
5040 PRINT#2,"":PRINT#2,""
5042 PRINT#2,"                          UA TABLE "
5045 PRINT#2,"":PRINT#2,""
5060 PRINT#2,"     SURFACE              AREA       R          UA       LOAD %"
5070 PRINT#2,"      NAME               (FT↑2)               BTU/HR DEG F "
5080 PRINT#2,"-------------------------+----------+----------+----------+----------"
5090 PRINT#4,F1$    :REM SET UP FORMAT
6000 FOR I=1 TO N
6005 PRINT#3,S$(I),B$,A(I),R(I),UA(I),UA(I)/TL*100
6010 NEXT I
7040 PRINT#2,"":PRINT#2,""
7042 PRINT#2,"                          VENTILATION TABLE"
7045 PRINT#2,"":PRINT#2,""
7060 PRINT#2,"   AIR EXCHANGE SOURCE  AC RATE   VENT RATE  ENERGY LOAD   LOAD %"
7070 PRINT#2,"                          AC/HR     FT↑3/HR   BTU/HR DEG F "
7080 PRINT#2,"-------------------------+----------+----------+-------------+-------"
7090 PRINT#4,F2$    :REM SET UP NEW FORMAT
8000 PRINT#3,A$,B$,AC,AC*V,IL,IL/TL*100
8010 PRINT#3,V$,B$,V1/V,V1,VL,VL/TL*100
8045 PRINT#2,"":PRINT#2,"":PRINT#2,""
8050 PRINT#4,F4$
8105 PRINT#2,"YEARLY HEATING REQUIRERMENT FOR";DD(1);"HEATING DEGREE DAYS"
8110 PRINT#3,HL,"MILLION BTU"
8120 PRINT#2,"":PRINT#2,"":PRINT#2,""
8125 PRI T#2,"YEARLY COOLING REQUIRERMENT FOR";DD(2);"COOLING DEGREE DAYS"
8130 PRINT#3,CL,"MILLION BTU"
9000 CLOSE 4,4
9005 CLOSE 3,4
9010 CLOSE 2,4
READY.
```

Listing 2: *Output of listing 1, based on an example that uses 3½ inches of insulation in the ceiling.*

```
EXAMPLE HOUSE IN AUSTIN TEXAS 3.5

                         UA TABLE

    SURFACE             AREA        R           UA       LOAD %
     NAME              (FT↑2)               BTU/HR DEG F
----------------------+----------+----------+----------+---------
CEILING/ROOF           1500.0      15.23        98.4     13.4
WALLS                  1118.0       4.40       254.0     34.7
WINDOWS                 120.0        .91       131.8     18.0
DOORS                    42.0       1.56        26.9      3.6

                         VENTILATION TABLE

   AIR EXCHANGE SOURCE  AC RATE   VENT RATE  ENERGY LOAD    LOAD %
                         AC/HR     FT↑3/HR   BTU/HR DEG F
-----------------------+---------+---------+-------------+-------
AIR INFILTRATION         1.00      12000        213.1        29.1
FORCED VENTILATION        .03        375          6.6          .9


YEARLY HEATING REQUIRERMENT FOR 1980 HEATING DEGREE DAYS
      34.74   MILLION BTU


YEARLY COOLING REQUIRERMENT FOR 2908 COOLING DEGREE DAYS
      51.02   MILLION BTU
```

Listing 3: *Output of listing 1, based on an example that uses 9½ inches of insulation in the ceiling.*

```
EXAMPLE HOUSE IN AUSTIN TEXAS 9.5

                         UA TABLE

    SURFACE             AREA        R           UA       LOAD %
     NAME              (FT↑2)               BTU/HR DEG F
----------------------+----------+----------+----------+---------
CEILING/ROOF           1500.0      34.28        43.7      6.4
WALLS                  1118.0       4.40       254.0     37.5
WINDOWS                 120.0        .91       131.8     19.4
DOORS                    42.0       1.56        26.9      3.9

                         VENTILATION TABLE

   AIR EXCHANGE SOURCE  AC RATE   VENT RATE  ENERGY LOAD    LOAD %
                         AC/HR     FT↑3/HR   BTU/HR DEG F
-----------------------+---------+---------+-------------+-------
AIR INFILTRATION         1.00      12000        213.1        31.5
FORCED VENTILATION        .03        375          6.6          .9


YEARLY HEATING REQUIRERMENT FOR 1980 HEATING DEGREE DAYS
      32.14   MILLION BTU


YEARLY COOLING REQUIRERMENT FOR 2908 COOLING DEGREE DAYS
      47.20   MILLION BTU
```

MEMORY Blackout!

A PROBLEM FOR YOUR PRESENT RAM?

Don't Curse the darkness. Get our non-volatile memory and watch elephants turn green with envy!



Are you looking for a reliable non-volatile memory on a rugged industrial-standard IEEE-696 S-100 card? Your search is over. Our CMOS memory modules have a battery backup that is guaranteed to keep programs and data intact for a year. We didn't sacrifice performance for non-volatility in the design of our CMEM module, so you get all the card you're looking for . . . we even supply the battery.



- ☐ 32K on a single board, 8 or 16-bit cpu compatible.
- ☐ Switch selectable addressing on 4K boundaries.
- ☐ Extended memory addressing through 24-bit lines.
- ☐ 250 nanosec access time, no wait states required.
- ☐ Runs at 4 MHz for both 8 and 16-bit S-100 systems.
- ☐ Programs developed & stored w/out disks or tapes.
- ☐ Power fail interrupts.
- ☐ Software programmable write-protect window.
- ☐ 8K bytes-$695, 16K bytes-$895, 32K bytes-$1095.

The DUAL 77 Data Acquisition and Control System is a turnkey system built to industrial standards and it comes ready to perform. As with all our systems and modules, our computer was designed with the wicked environment of the real world in mind. BASIC language makes programming easy and the built-in interface simplifies access to hundreds of sensors. The enormous expandability of the system allows its growth to meet your increasing needs, even if you enjoy learning new languages. The DUAL 77 is economical; $9995 or higher with options.

DUAL

DUAL SYSTEMS CONTROL CORPORATION
1825 Eastshore Highway, Berkeley, CA 94710
Phone (415) 549-3854 or (415) 549-3890

A/D CONVERTER

This S-100 based module is designed to withstand the rugged environment of the laboratory or in industry for general use in converting analog signals to digital information.

- ☐ 32-channel single-ended, 16-channel differential.
- ☐ 12-bit resolution and accuracy.
- ☐ 30-microsecond conversion time.
- ☐ Instrumentation amplifier on board.
- ☐ BASIC program for use provided.
- ☐ $695 or $785 w/1-1000 gain transducer amplifier.



NON-STOP CLOCK

Now you can keep time even with the main power off. Our industrial level clock module utilizes a backup battery circuit for a full year.

- ☐ Day, date, hours, minutes and seconds.
- ☐ Features new LSI CMOS chip.
- ☐ Vectored interrupt capability.
- ☐ Dip switch selectable port address.
- ☐ Simple BASIC or Assembly language program.
- ☐ Precision quartz crystal clock. ☐ $250

D/A CONVERTER

The AOM-12 analog output module is an industrial level digital-to-analog (D/A) converter which converts digital commands from the computer into analog voltages.

- ☐ 12-bit ±½ L.S.B accuracy over full 0-70°C temperature range.
- ☐ Voltage outputs of 0-10 volts, ±5 volts, or ±10 volts.
- ☐ Short circuit protection on all voltage outputs.
- ☐ Switch-programmable port base address for multiple boards.
- ☐ $575

DUAL

Dual Systems Control Corporation
Department B, 1825 Eastshore Highway
Berkeley, CA 94710 • (415) 549-3854

☐ Please send your brochure with complete details on modules.
☐ Please provide information on the DUAL 77 System.

Name ______ Title ______
Company ______
Street ______
City ______ State ______ Zip ______

DEALER AND OEM INQUIRIES INVITED

Circle 128 on inquiry card.

dBASE II

Assembly-Language Relational Database Management for CP/M

$595.

BYTE 7-81

USE OUR CLIP-OFF™ TO AVOID A RIP-OFF

Check enclosed (U.S. funds only) $______ dBASE II $595.

Name____________________________

Street___________________________

City____________ State______ Zip_______

Interactive Business Solutions

"Businessware™ for the Business Man"

Interactive Business Solutions

333 Cobalt Way, Suite 106
Sunnyvale, CA 94086
(408) 737-9618

Businessware and Clip-Off are trademarks of Interactive Business Solutions.

Circle 186 on inquiry card.

energy requirement for space conditioning is the sum of the heating and cooling loads. The governing equation is:

$$Q_{total} = Q_{heating} + Q_{cooling}$$

Heating and Cooling Requirements

The yearly heating requirement for our example house can be easily determined from the combined conduction and infiltration load shown in table 3, and the yearly heating degree-day value of 1980 °F day/year:

$$Q_{heating} = 734.2 \frac{\text{Btu}}{\text{hr}\,°\text{F}} \times 24 \frac{\text{hr}}{\text{day}} \times 1980 \frac{°\text{F day}}{\text{year}}$$

$$= 34.89 \times 10^6 \text{ Btu/year}$$

We calculate the cooling energy requirements in a similar fashion:

$$Q_{cooling} = 734.2 \frac{\text{Btu}}{\text{hr}\,°\text{F}} \times 24 \frac{\text{hr}}{\text{day}} \times 2908 \frac{°\text{F day}}{\text{year}}$$

$$= 51.24 \times 10^6 \text{ Btu/year}$$

Listing 4: *Program for calculating dollar savings based on proposed home improvements. This program uses the discounted payback method to determine when the home improvement pays for itself in decreased energy use.*

```
100 REM  TITLE "DISCOUNTED PAYBACK"
101 REM
102 REM
900 REM I/O SPECIFICATION
905 REM
1000 OPEN 2,4,0
1010 OPEN 3,4,1
1020 OPEN 4,4,2
1030 REM
1035 REM FORMAT STRING
1050 F1$="99     99999.99            99999.99            S99999.99"
1190 REM
1195 REM INPUT SECTION
1197 REM
1200 INPUT"GENERAL INFLATION(FRAC)";I
1250 INPUT"INVESTMENT YIELD(FRAC)";Y
1275 INPUT"FUEL ESCALATION RATE(FRAC)";E
1400 INPUT"RETROFIT COST($)";C
1500 INPUT"WINTER SAVINGS(10↑6BTU)";WS
1505 INPUT"COST OF HEATING ($/10↑5 BTU)";HC
1510 INPUT"SUMMER SAVINGS(10↑6BTU)";SS
1520 INPUT"COST OF COOLING ($/10↑6 BTU)";CC
1521 REM
1522 REM ECHO INPUT INFORMATION
1523 REM
1525 PRINT#2,"                DISCOUNTED PAYBACK"
1527 PRINT#2,"":PRINT#2,""
1530 PRINT#2,"GENERAL INFLATION(FRAC)";I
1531 PRINT#2,"FUEL ESCALATION RATE(FRAC)";E
1532 PRINT#2,"INVESTMENT YIELD(FRAC)";Y
1534 PRINT#2,"RETROFIT COST($)";C
1536 PRINT#2,"WINTER SAVINGS(10↑6BTU)";WS
1538 PRINT#2,"COST OF HEATING ($/10↑6 BTU)";HC
1540 PRINT#2,"SUMMER SAVINGS(10↑6BTU)";SS
1542 PRINT#2,"COST OF COOLING ($/10↑6 BTU)";CC
1545 REM
1546 REM PRINT TABLE HEADER
1547 REM
1548 REM
1555 PRINT#2,"":PRINT#2,""
1560 PRINT#2,"       WITH RETROFIT      WITHOUT RETROFIT"
1565 PRINT#2,""
1570 PRINT#2,"       PRESENT VALUE OF   PRESENT VALUE OF      PRESENT VALUE OF"
1575 PRINT#2,"YEAR     CUMULATIVE          CAPITAL             NET SAVINGS"
1580 PRINT#2,"        ENERGY SAVING       INVESTMENT "
1695 REM
1700 PRINT#4,F1$   :REM SETUP FORMAT
1705 REM
1950 REM
1960 REM  CALCULATION SECTION
1965 REM
2000 A=WS*HC+SS*CC
2010 FOR N=1TO10
2050 S=A*(1+E)/(I-E)*(1-((1+E)/(1+I))↑N)
2070 CI=C*((1+Y)/(1+I))↑N
2080 PV=S-CI
2090 PRINT#3,N,S,CI,PV  :REM PRINT TABLE ENTRIES
3000 NEXT N
5000 CLOSE4,4
5005 CLOSE3,4
5007 CLOSE2,4
READY.
```

Listing 5: *Sample output of listing 4.*

```
                 DISCOUNTED PAYBACK

GENERAL INFLATION(FRAC) .1
FUEL ESCALATION RATE(FRAC) .15
INVESTMENT YIELD(FRAC) .08
RETROFIT COST($) 450
WINTER SAVINGS(10↑6BTU) 2.6
COST OF HEATING ($/10↑6 BTU) 20.51
SUMMER SAVINGS(10↑6BTU) 3.81
COST OF COOLING ($/10↑6 BTU) 6.83

       WITH RETROFIT       WITHOUT RETROFIT

       PRESENT VALUE OF    PRESENT VALUE OF       PRESENT VALUE OF
YEAR     CUMULATIVE            CAPITAL              NET SAVINGS
         ENERGY SAVING       INVESTMENT
 1          82.95              441.81              -   358.86
 2         169.68              433.78              -   264.10
 3         260.34              425.89              -   165.54
 4         355.13              418.15              -    63.01
 5         454.23              410.55              +    43.68
 6         557.83              403.08              +   154.75
 7         666.14              395.75              +   270.39
 8         779.38              388.56              +   390.82
 9         897.76              381.49              +   516.26
10        1021.52              374.56              +   646.96
```

We have presented these calculations in considerable detail so that the reader will understand the mechanism of heat transfer. Now we would like to outline and demonstrate how to obtain these results using your personal computer. Figure 4 is a flowchart for a simple interactive program that accepts building and climate input and generates a printout (similar to table 3) and a summary of yearly energy consumption.

The program is written in Commodore (Microsoft) BASIC, and it runs on any PET with a Commodore 2022 printer. Listing 1 is the source code and listing 2 is a copy of the output from this program. Readers who are fortunate enough to have Personal Software's VisiCalc will find that the procedures performed by this program can be followed very easily. We will not go into details of the program because it simply carries out the procedures outlined earlier. We suggest that you first try these calculations by hand, then write the BASIC program after you are comfortable with the method.

Energy Conservation

At this point, you can see *how* to get your microcomputer to predict energy consumption in buildings, but you may be wondering whether you should go to the trouble.

The advantage of having a program is that it will allow you to rapidly evaluate the energy savings of such hypothetical changes as adding storm windows or insulation. To serve as an example, we have used our program to evaluate the effect of adding 6 inches of insulation to the ceiling of the example house. This change raises the *R*-value in the ceiling from 15.23 to 34.23. Listing 3 shows that the new annual ènergy consumption is 79.35 $\times$ 10[6] Btu/year, a savings of 6.41 $\times$ 10[6] Btu/year.

By themselves, annual energy savings numbers tell us very little. We still need an indicator that will help us choose from among energy conservation alternatives.

Energy Conservation Economics

Armed with our program and a "hit list" of potential conservation measures, we can compile energy savings figures for each measure or for any combination of the measures. But there are two other key pieces of information that we must stir into the recipe: the cost of material and labor for adopting the conservation scheme, and the

fuel cost information required to turn Btu saved into dollars.

Getting a cost estimate for material and labor for residential retrofit work is as easy as calling a contractor. If the labor will be your own, then you should call a local lumber yard to get material cost figures. Once we know how much the proposed modifications to the building will cost, we can turn our attention to the dollar savings associated with the energy savings.

If a fuel is burned to produce heat, we have to know the efficiency of the furnace and the heating value of the fuel. Let's assume we are burning number two fuel oil in a furnace that has an efficiency of 70%. Using 138,000 Btu per gallon as the heating value for this oil and assuming a cost of \$1.30 per gallon, we can compute:

$$\text{Cost per million Btu} = \frac{\$1.30 \text{ per gallon}}{0.7 \times 138{,}000 \text{ Btu/gallon}} \times 10^6 = \$13.46$$

All fossil fuels can be calculated in this manner.

For electric heating, we have a cost of \$0.07 per kilowatt-hour and an efficiency of 100%. We can compute:

$$\text{Cost per million Btu} = \frac{\$0.07 \text{ per kWh}}{3413 \text{ Btu/kWh}} \times 10^6 = \$20.51$$

Electric air-conditioning cost estimates require knowledge of the coefficient of performance of the air-conditioning system—a measure of the ratio of the cooling effect in Btu to the electrical energy purchased. The coefficient of performance of a good air-conditioning system is around 3.0. The cost for cooling then becomes:

$$\text{Cost per million Btu} = \frac{\$0.07 \text{ per kWh}}{3.0 \times 3413 \text{ Btu/kWh}} \times 10^6 = \$6.83$$

A time-honored method for putting all of this information together is the calculation of *simple payback*. In this easy method, we merely calculate how long it will take for the money saved each year on energy costs to "pay back" the capital we invested to carry out the building modification. We then have a simple way to rank our energy conservation options.

Let's return to the example of adding ceiling insulation. The current cost of material for R19 fiberglass is \$0.30 per square foot, which amounts to a material cost of \$450. Let's assume you install the insulation yourself. Comparing listings 2 and 3, we see an annual energy savings of 2.6 million Btu for heating and 3.81 million Btu for cooling. Using the electricity values estimated previously, our heating and cooling savings are:

$$\text{Annual heating savings} = 2.6 \text{ million Btu} \times \$20.51 = \$53.33$$

$$\text{Annual cooling savings} = 3.81 \text{ million Btu} \times 6.83 = \$26.02$$

$$\text{Total savings} = \$79.35/\text{year}$$

The simple payback period is therefore:

$$\frac{\$450}{\$79.35} = 5.67 \text{ years}$$

You probably noticed from listings 2 and 3 that the ceiling heating and cooling load is not, by any means, the predominant load. You might, for example, be tempted to assume that insulating the walls is a better approach. However, don't forget that retrofitting wall insulation is a grim proposition that, in some cases, involves drastic dismantling of the walls. Even when it is blown in loose, wall insulation will still involve a greater initial cost than do-it-yourself ceiling insulation.

Improving the Economic Model

What if we want a more sophisticated economic model to rate our conservation measures? The shortcomings of the simple payback model are that it ignores the effects of:

- Income derived from investing the capital instead of using it for energy conservation
- Escalation of fuel costs with time
- Inflation on the real value of money saved or spent in the future

NEW DISK SYSTEM POLISHES APPLE™



Plug into your Apple II or Apple II-plus with a Micro-Sci disk system, and you get Apple software compatibility, PLUS: Increased capacity, improved performance and higher reliability. And you save money, too!

COMPATIBILITY:

With thousands of programs currently available in Apple format—and many more being released every day—the ability to read and write diskettes interchangeable with the Apple disk II system is a MUST. The Micro-Sci disk subsystems offer this compatibility and more. Our disk system has a jumper-selectable boot PROM to move from DOS 3.2 to DOS 3.3, or to the language system at your fingertips.

CAPACITY:

The Micro-Sci A-40 system provides 40 tracks of storage (versus the Apple disk II system which offers only 35 tracks). The A-40's 5 extra tracks give you an additional 20,000 bytes of storage. And for even greater capacity, check out our A-70 system which offers a full 70 tracks of storage—exactly DOUBLE the storage capacity of the Apple disk II system!

PERFORMANCE:

Micro-Sci's disk systems' abbreviated track-to-track access time of 5msec (versus 15msec for the Apple disk II) means improved random disk access performance.

RELIABILITY:

Micro-Sci disk systems incorporate band-actuated head positioners for faster access and more accurate head positioning. Each disk system features Micro-Sci's improved media centering system which provides uncommonly accurate diskette registration, and virtually eliminates damage to the media centering hole.

PRICE:

The Micro-Sci A-40 drive, with controller, is priced at only $549; the second A-40 drive is only $449. The large-capacity A-70 disk drive with controller is only $699, with the second drive priced at only $599.

Call or write us today to order your new Micro-Sci disk system.

μ-SCI

17742 Irvine Boulevard, Suite 205, Tustin, California 92680 / Phone: 714/731-9461 / Telex: 910-346-6739

We will present a method here called *discounted payback*, which takes these things into account without becoming terribly complicated. We will also discuss a BASIC program that uses these concepts and gives results for our example house.

Let's assume that a quantity of capital, C, is invested at an annual yield rate, Y, with an annual inflation rate of I. In 1981 dollars, the present value of this investment after n years is given by:

$$P = C\left(\frac{1 + Y}{1 + I}\right)^n$$

The *accumulated* present value of energy saved from now to year n, while energy costs escalate at rate E and general inflation is I, is given by:

$$S = A\frac{(1+ E)}{(1 + I)}\left[1 - \left(\frac{1 + E}{1 + I}\right)^n\right]$$

where A represents the initial annual energy savings based on 1981 fuel costs.

If we compare by subtraction the accumulated present value of the energy savings for each year with the present value of the invested money, payback occurs when the difference changes sign. Using this method, the financial gains made in the years beyond payback are tangible and easy to interpret because we have discounted everything back to 1981. Reference 4 describes several more elaborate economic models.

Listing 4 shows a program written for a Commodore PET with printer. Listing 5 shows program output for our attic insulation example using an annual energy cost escalation rate of 15%, a general inflation rate of 10%, and a rate of return on investment of 8%. The program accepts input of these three rates, plus heating and cooling energy costs in year zero (1981) and the capital cost of the energy conservation measure.

Conclusions

Some readers may question the simplicity of our methodology. Please remember that we only wish to provide the basics to get you started. The material we have presented must be expanded to be truly useful, but the references cited and the vast body of available literature on the subject should help you develop the material presented here. ■

References

1. *ASHRAE Handbook, 1977 Fundamentals.* The American Society of Heating, Refrigeration, and Air Conditioning Engineers, 345 E 47th St, New York, 1971.
2. Gay, L (editor). *The Complete Book of Insulating.* Brattleboro VT: The Stephen Greene Press, 1980.
3. McQuistion F and J Parker. *Heating, Ventilating, and Air Conditioning.* New York: John Wiley & Sons, 1977.
4. Marshall H and R Ruegg (editors). *Simplified Energy Design Economics.* Washington DC: Superintendent of Documents, US Government Printing Office.

MULTI-USER OASIS HAS THE FEATURES PROS DEMAND. READ WHY.

(THEN COMPARE.)

Computer experts (the pros) usually have big computer experience. That's why when they shop system software for Z80 micros, they look for the big system features they're used to. And that's why they like Multi-User OASIS. You will too.

DATA INTEGRITY: FILE & AUTOMATIC RECORD LOCKING

The biggest challenge for any multi-user system is co-ordinating requests from several users to change the same record at the same time.

Without proper co-ordination, the confusion and problems of inaccurate or even destroyed data can be staggering.

Our File and Automatic Record Locking features solve these problems.

For example: normally all users can view a particular record at the same time. But, if that record is being updated by one user, automatic record locking will deny all other users access to the record until the up-date is completed. So records are always accurate, up-to-date and integrity is assured.

Pros demand file & automatic record locking. OASIS has it.

SYSTEM SECURITY: LOGON, PASSWORD & USER ACCOUNTING

Controlling who gets on your system and what they do once they're on it is the essence of system security.

Without this control, unauthorized users could access your programs and data and do what they like. A frightening prospect isn't it?

And multi-users can multiply the problem.

But with the Logon, Password and Privilege Level features of Multi-User OASIS, a system manager can specify for each user which programs and files may be accessed—and for what purpose.

Security is further enhanced by User Accounting—a feature that lets you keep a history of which user has been logged on, when and for how long.

Pros insist on these security features. OASIS has them.

EFFICIENCY: RE-ENTRANT BASIC

A multi-user system is often not even practical on computers limited to 64K memory.

OASIS Re-entrant BASIC makes it practical.

How?

Because all users use a single run-time BASIC module, to execute their compiled programs, less memory is needed. Even if you have more than 64K, your pay-off is cost saving and more efficient use of all the memory you have available—because it services more users.

Sound like a pro feature? It is. And OASIS has it.

AND LOTS MORE...

Multi-User OASIS supports as many as 16 terminals and can run in as little as 56K memory. Or, with bank switching, as much as 784K.

Multi-Tasking lets each user run more than one job at the same time.

And there's our BASIC—a compiler, interpreter and debugger all in one. An OASIS exclusive.

Still more: Editor; Hard & Floppy Disk Support; Keyed (ISAM), Direct & Sequential Files; Mail-Box; Scheduler; Spooler; all from OASIS.

Our documentation is recognized as some of the best, most extensive, in the industry. And, of course, there's plenty of application software.

Put it all together and it's easy to see why the real pros like OASIS. Join them. Send your order today.

OASIS

MAKES MICROS RUN LIKE MINIS

OASIS IS AVAILABLE FOR

SYSTEMS: Altos; Compucorp; Cromemco; Delta Products; Digital Group; Digital Microsystems; Dynabyte; Godbout; IBC; Index; Intersystems; North Star; Onyx; SD Systems; TRS 80 Mod II; Vector Graphic; Vorimex.

CONTROLLERS: Bell Controls; Cameo; Corvus; Konan; Micromation; Micropolis; Tarbell; Teletek; Thinkertoys; X Comp.

Write for complete, free Application Software Directory.

PLEASE SEND ME:

Product	Price with Manual	Manual Only
OPERATING SYSTEM (Includes: EXEC Language; File Management; User Accounting; Device Drivers; Print Spooler; General Text Editor; etc.) SINGLE-USER / MULTI-USER	$150 / 350	$17.50 / 17.50
BASIC COMPILER/ INTERPRETER/DEBUGGER	100	15.00
RE-ENTRANT BASIC COMPILER/INTERPRETER/ DEBUGGER	150	15.00
DEVELOPMENT PACKAGE (Macro Assembler; Linkage Editor; Debugger)	150	25.00
TEXT EDITOR & SCRIPT PROCESSOR	150	15.00
DIAGNOSTIC & CONVERSION UTILITIES (Memory Test; Assembly Language; Converters; File Recovery; Disk Test; File Copy from other OS; etc.)	100	15.00
COMMUNICATIONS PACKAGE (Terminal Emulator; File Send & Receive)	100	15.00
PACKAGE PRICE (All of Above) SINGLE-USER / MULTI-USER	500 / 850	60.00 / 60.00
FILE SORT	100	15.00
COBOL-ANSI '74	750	35.00

Order OASIS from:

Phase One Systems, Inc.
7700 Edgewater Drive, Suite 830
Oakland, CA 94621
Telephone (415) 562-8085
TWX 910-366-7139

NAME ____________
STREET (NO BOX #) ____________
CITY ____________
STATE ________ ZIP ________
AMOUNT $ ________
(Attach system description; add $3 for shipping; California residents add sales tax)
☐ Check enclosed ☐ VISA
☐ UPS C.O.D. ☐ Mastercharge
Card Number ____________
Expiration Date ____________
Signature ____________

Circle 315 on inquiry card.

Ask BYTE

Conducted by Steve Ciarcia

The VTR Blues

Dear Steve,

I want to use my Radio Shack TRS-80 for generating screen titles for videocassette training tapes, including graphs, etc. My problem is that when I plug the TRS-80's cable into the video recorder (instead of the monitor), I can't get a good recording.

I replaced the TRS-80's monitor with an industrial monitor, and modified the cassette recorder's cable to plug into the video monitor and the VTR (videotape recorder).

As long as I keep the amount of writing on the screen to a few lines, the videotape comes out fine. But if I try to put many lines on the screen, the result is sparkling, rippling letters, etc. Any more than four lines seems to drive the VTR crazy. Also, it seems that the writing has to be kept away from the right edge of the screen.

The VTR I use is a Panasonic reel-to-reel unit that has selectable video-level control. In the automatic mode, the recorder doesn't work so well. I have to keep it on a low manual setting. Even on good recordings, the playback gives a light gray background with black smears running to the right of the letters.

I use this equipment for my work, but many TRS-80 users must own VTRs. This idea is useful in schools for educational tape titling, etc, so solving this problem would benefit a lot of people.

Paul Bendorius
New York NY

The more lines of text on a screen, the greater the bandwidth required to store the information.

It sounds like you have two problems. First, using the cassette cable as you have provides no shielding and is probably very capacitive. Excess capacitance will cause high-frequency loss and probably accounts for the sparkling and rippling letters. Second, apparently your VTR needs a better signal with more defined synchronization levels. The problem is due to the difference between the standard 1- to 1½-volt peak-to-peak video signal that the recorder expects and the almost 4 V output from the TRS-80.

The video signal in this circumstance is either black or white—there are no gray tones. The synchronization level is correct, but the high white level can be confusing your VTR. The white level should be at +1.5 V, the black level at +0.5 V, and the synchronization level at 0 V.

I see no problem in directly recording this signal. My Magnavox VHS VTR has no problems even with a screen full of text. Other than opening your TRS-80 and changing the values of R23, R27, and R28, there isn't much I can suggest to you. Better cabling should help. . . . **Steve**

Chip Off the Old Program

Dear Steve,

I have some questions about PROM (programmable read-only memory) programming. Like many homebrewers, I'm strong on digital, but weak on analog. I have successfully built a 2708 EPROM programmer, but I encountered a problem when attempting to program Intel 2716s and 8755As under complete computer control. The +26/+5 V programming/verifying voltages complicated the control circuit. My circuitry came up with only +26/+4.4 V. The circuit did manage to program the PROMs and verify correctly, but obviously doesn't meet Intel specifications. The

In "Ask BYTE," Steve Ciarcia answers questions on any area of microcomputing. The most representative questions received each month will be answered and published. Do you have a nagging problem? Send your inquiry to:

Ask BYTE
c/o Steve Ciarcia
POB 582
Glastonbury CT 06033

If you are a subscriber to The Source, send your questions by electronic mail or chat with Steve (TCE317) directly. Due to the high volume of inquiries, personal replies cannot be given. Be sure to include "Ask BYTE" in the address.



Figure 1

question is: given power-supply voltages of +5, ±12, and +26 V, can a transistor circuit be designed to come within the Intel specifications?

I've wanted to use Texas Instruments' 74S-series fuse-like (transistor-transistor logic) PROMs in circuits, but had no way of programming them. I have never seen any designs for a programmer for TTL PROMs. As I see it, there are two problems. First, a controllable power-supply voltage like the one I attempted would be required (except with different voltages). Second, what kind of drive requirements are necessary to program the output bits of the PROMs? Would TTL open-collector outputs (eg: from a decoder) be sufficient, or would an active circuit with transistors be necessary?

Robert A Servis
Ann Arbor MI

I'm not exactly an analog "wizard" myself, but I have designed a few EPROM programmers. Perhaps you should look at the article I wrote in the March 1978 BYTE for examples of voltage-level switching. (See "Program Your Next EPROM in BASIC," page 84.)

Concerning your initial problem, there is nothing inherent in transistors that would preclude them from being set at +5.0 V, and it doesn't require much to do the level shifting you need. The circuit of figure 1 switches between +26 and +5 V as you require. A logic 0 input produces +26 V, and a logic 1 produces +5 V.

Finally, as you've noted, there are few fuse-link programmer schematics around. Perhaps a reader will send me one that I can forward to you. . . . **Steve**

Incomplete Interface?

Dear Steve,

I enjoy reading your interesting projects in BYTE. Your May 1980 project appeared at the right time; however, I am having some trouble adapting it to my system. (See "I/O Expansion for the Radio Shack TRS-80, Part 1," May 1980 BYTE, page 22.)

I have the Heath H-89 all-in-one computer, which has a serial interface, and a Radio



Figure 2

SPEND $62.40 TO READ THIS ADVERTISEMENT.*

A salesman generating 1.5 million dollars in sales annually for his company does so at the rate of $12.48 per minute. That's expensive time—should it really be used in rummaging through filing cabinets, writing long reports or talking to dozens of people looking for one small, crucial piece of information?

Of course not, so you hire an accounting staff, customer support personnel, and marketing people to support the business and let your salespeople sell. But the overhead takes a large slice of that $12.48.

A Delta system can do the work of a swarm of secretaries, a fleet of filers, a ton of telephones—simultaneously. It's a highly developed work processing system that can maintain files, generate reports, process orders and do all routine office work with speed and accuracy. It lets your people get on with the business of making money.

We at Delta Products have spent five years designing the most reliable, efficient Z80 based microcomputer available on the marketplace. It's fast—some models use multi processors to eliminate the delays associated with other multi user systems. It's expandable, allowing your Delta system to grow with your company's growth and change with your company's needs. And it's rugged; requiring a minimum of service or maintenance.

But the soul of any computer system is the software; therefore, having perfected the hardware techonology, Delta is now dedicated to the development of application packages designed to warm the cockles of a corporate executive's heart. Our "Uni-form", for example, will keep purchase orders, account statements, sales and shipping orders indexed, cross-indexed and filed in any manner required.

And when your Delta system has helped your business grow, it's ready to grow right along with you—every Delta System is completely expandable and configurable.

You have spent five minutes reading this advertisement, at a cost of $62.40 in potential sales. Have you calculated what a Delta system can save your company? (Hint: a Delta system can pay for itself in less than 24 hours of time saved.)

Call us today for the name of your nearest Delta distributor.

*(and save thousands later)

DELTA PRODUCTS

Delta Products
15392 Assembly Lane
Huntington Beach, CA 92649
Telephone (714) 898-1492
TELEX: 681-367 DELTMAR HTBH

Circle 113 on inquiry card.

Shack Daisy Wheel Printer II, with a letter-quality print wheel and a parallel input (eight data lines and one strobe). I need a parallel interface from my H-89 to my printer. I have tried building the parallel interface explained in your article, but can't get it to work.

I can't afford to lose the money invested in my printer, and I don't want to part with my beloved H-89. So, what can I do to complete this interface? I don't mind buying an interface off the shelf, if it's available.

Olu O Ajala
Madison TN

There are two ways to approach your problem. One is to convert the H-89 to parallel output, and the other is to enable the printer to accept serial input. Given the equipment involved, your best bet is to attach a serial-to-parallel converter to the input of the printer.

Figure 2 is a schematic of a 300 bps (bits per second) serial-to-parallel converter that should solve your problem. Set for 300 bps, no parity, and one stop bit, this circuit will allow communication between the machines. It should not be necessary to tie the printer handshaking lines back to the H-89 for the printer to operate. If you do this, however, use the input portion of the UART (universal asynchronous receiver/transmitter) IC1 to convert the parallel printer-status bits to serial.

This circuit and other variations on the subject of serial-to-parallel and parallel-to-serial conversion were covered in an article I wrote in the May 1977 BYTE entitled, "Come Upstairs and Be Respectable" (page 50). . . . **Steve**

Slow Memory Signals

Dear Steve,

The Intel 8080 microprocessor has an input intended to force the processor to wait for memory devices that have slow access times. Can you give me an example of a memory device that produces this signal?

Irv Barditch
Baltimore MD

Generally speaking, memory devices do not have output pins specifically designed to control microprocessor WAIT states. The WAIT input is controlled by separate circuitry. The usual method is to trigger a one-shot (a circuit that produces a pulse of adjustable duration) from the device-select strobe (called CS) of the memory bank in use. The one-shot holds the WAIT line low for a specific period so that the memory has time to produce valid data.

If you had a PROM (programmable read-only memory) with a 1 µs access time installed at location 0000 (to bootstrap load a system, for example), you would wire it as you would any other memory device (200 ns access time). However, the CS input on the PROM would have a one-shot attached to it that produced a 1 µs pulse. The $\overline{Q}$ *output of the one-shot is, in turn, attached to the WAIT input of the processor. Whenever data is read from this PROM, the processor is automatically delayed by the one-shot. This delay would appear essentially transparent to the user, unless it is*

Meet the HP Series 80: Hewlett-Packard's new one-on-one computing systems for professionals.



Together, you can analyze technical problems and evaluate solutions. Rapidly and accurately.

HP Series 80 personal computing systems provide the technical solutions you require. Quickly! Easily! Inexpensively! Analysis techniques that were formerly difficult and often impossible, become part of your everyday work routine. You can evaluate functional behavior, select variable alternatives, perform cost analysis... and more... all with greater accuracy and using more variables than you thought possible.

SERIES 80, VISICALC™ PLUS AND YOU

HP's VisiCalc™ PLUS is a major new software tool. It's an electronic worksheet that instantly recalculates results as you change the variables. You ask the *what-if* questions and immediately see their effects on your solution. No programming is necessary... you can become proficient with VisiCalc™ PLUS in a few hours... and then watch your horizons broaden. VisiCalc™ PLUS features many powerful functions including statistical analysis tools and the entire HP Series 80 BASIC math set. Plus graphics! Create professional presentations with curve-fitting plots, stacked or clustered bar-graphs, exploded pie-charts and line graphs, all in up to four colors, on paper or transparencies.

ONLY FROM HEWLETT-PACKARD

HP Series 80 personal computing systems are part of a forty-year tradition of electronic products built to uncompromising standards of excellence. Additionally, HP Series 80 products are serviced by HP technicians and on-site service contracts are now available. We urge you to judge for yourself with a hands-on, one-on-one demonstration at your HP dealer. For locations, call TOLL-FREE 800-547-3400, Dept. 283A, except Alaska/Hawaii. In Oregon call 758-1010. Or write Hewlett-Packard, Corvallis, Oregon 97330, Dept. 283A.

611/04

HP Series 80 Personal Computers for Professionals: HP-85 ($3250*) and HP-83 ($2250*) specifications: 16K RAM expands to 32K, 32K ROM expands to 80K; CRT with integrated graphics; (HP-85 only; built-in thermal printer, cassette tape unit); Software includes VisiCalc™ PLUS, Information Management, Graphics Presentations, Surveying, Data Communications (Spring '81), Statistics, Regression Analysis, Math, Linear Programming, Waveform & Circuit Analysis, BASIC Training. HP peripherals include floppy discs, printers and plotters.

VisiCalc is a trademark of Personal Software, Inc.

*Suggested retail price excluding applicable state and local taxes—Continental U.S.A., Alaska & Hawaii.

HEWLETT PACKARD

Circle 172 on inquiry card.

set for a long period. . . . **Steve**

'Scope Trials

Dear Steve,

I'm faced with the decision to buy an oscilloscope or to continue using a homemade logic probe. What bandwidth 'scope would you recommend: 30 MHz or 50 MHz? (The 16-bit micrprocessors are getting into the 10 MHz range, and I want my investment to last.) The problem is that the 50 MHz 'scope is twice the price of the 30 MHz one.

I'd prefer a logic analyzer, but most are designed for specific microprocessors and are just too expensive.

Mel K Schmuldt
San Jose CA

The choice of a 'scope must be a trade-off between required operating needs and price. Rarely will you have to deal with the 20 MHz clock frequencies of the new microprocessors. Most likely you will just check to see if the clock is present. A frequency counter is the better instrument to measure period.

In general, most of the signals you will be trying to observe will be at far lower frequencies. You would find very little difference between a 30 and 50 MHz 'scope when displaying a 1 MHz signal.

More important factors to be concerned about when buying a 'scope that will be used primarily on digital circuitry are the precision of the trigger and sweep electronics and a dual-trace (not dual-beam) display. Frequently, 'scopes are used to compare two signals while being triggered by a third. If the trigger circuitry is not particularly stable, the comparison of the signals is invalid and misleading (unfortunately, detecting these errors is very difficult). Also, it is often desirable to view the actual trigger signal or wait a specific time interval before starting the sweep. Trigger view and delayed sweep are expensive options.

In my opinion, the most economical choice for a computer hobbyist is a 15 to 25 MHz dual-trace 'scope that has a time-base range between 200 ns and 0.5 s (without the time-base magnifier). Vertical sensitivity should be at least 10 mV per division. Delayed sweep and trigger view are not necessary. This type of 'scope probably costs about $1200.

If you are planning to do digital design, then you must be more particular about your needs. The market is wide open, and it is not unusual to pay $5000 to $15,000 for some 'scopes. My biggest complaint about top-end 'scopes is that they have so many bells and whistles that you need a road map to find the on/off switch.

Finally, if you are determined to buy a 50 MHz 'scope, I suggest the Tektronix Model 455 (about $2200). A comprehensive list of the 'scopes on the market is available in the September 1980 Electronic Products *magazine.* . . . **Steve**

Dual-Purpose Modems

Dear Steve,

I read with interest your article "A Build-It-Yourself Modem for Under $50." (See the August 1980 BYTE page 22.) I'd like to try to adapt

Computers for people.™

"Atari graphics and sound stand in a class by themselves."

David D. Thornburg
Compute Magazine, November/December 1980

"Its superiority lies in three areas: drawing fancy pictures (in color), playing music, and printing English characters onto the screen. Though the Apple can do all these things, Atari does them better."

Russell Walter
"Underground Guide to Buying a Computer"
Published 1980,
SCELBI Publications

"The Atari machine is the most extraordinary computer graphics box ever made..."

Ted Nelson
Creative Computing Magazine, June 1980

"...so well packaged that it is the first personal computer I've used that I'm willing to set up in the living room."

Ken Skier, OnComputing, Inc. Summer 1980

"...well constructed, sleekly designed and user-friendly—expect reliable equipment, and strong maintenance and software support.

Videoplay
December, 1980

What computer people are saying about Computers for people.™

To find out about the ATARI® 800™ Computer first hand, ask your local computer dealer for a hands-on demonstration.
Or call, 800-538-8547 (In California 800-672-1404)

ATARI®
Computers for people.™

©1981, ATARI, Inc.
A Warner Communications Company

For further information write: Atari Inc., Computer Division, 1196 Borregas Avenue, Sunnyvale, CA 94086 Dept. C-11

Circle 34 on Inquiry card.

either your circuit or a commercial modem so that I can use my Apple II both for computer communication and as a deaf-communication device.

I am planning to use older model teletypewriters or special-purpose units, such as the Magsat, for the deaf communication project. From what I've been able to determine, they apparently operate at a lower transmission rate (45.5 bits per second?), and they have no carrier frequency.

What changes would be required to make a modem serve this dual purpose? Also, where can I get more information on this subject?

Jerry Black
Oshkosh WI

Remember that a modem is merely a tone generator connected to a serial-data stream. The common data rates are 110 or 300 bits per second (ie: the bit rate of the data stream). If you transmit at 45.5 bps (bits per second), the modem will operate at 45.5 bps. The modem in my article is rated to work properly from 0 to 300 bps.

If the older units you mentioned have no carrier frequency, they are probably 20 mA current-loop devices. The modem output can be converted to 20 mA with a single-transistor circuit. Such a circuit was given in my June 1980 "Circuit Cellar" article. (See "An Answer/Originate Modem," page 24.)

Finally, 45.5 bps is a function of the clock rate provided to the transmitting UART (universal asynchronous receiver/transmitter). A serial interface designed for 110 bps can be converted to 45.5 bps by lowering the clock from 1760 to 728 Hz. At 45.5 bps you would probably use 2 stop bits. . . . **Steve**

A Loaded Question

Dear Steve,

I got into computing a few months ago with a 16 K-byte Level II TRS-80, and I love it. So far I only have one problem: loading programs.

How do I load two or more programs at once? For example, I would like to combine a number of game programs into one program for my four-year-old daughter, along with a menu so I won't have

to keep loading the tape. Could you recommend a SYSTEM tape that could do this?

I tried a Radio Shack renumbering program to set the lines of each program far apart, but when I execute a CLOAD, it wipes out everything previously stored.

Dave Bower
Virginia Beach VA

CLOAD on a TRS-80 clears any previous program before it starts loading (except the memory area reserved when you answer the MEM SIZE? prompt). Every BASIC program, regardless of the line numbers, starts loading at the same point.

On a 16 K-byte Level II, you only have two alternatives. The first (what most people do) is to load the program each time you want it to run. A separate tape is required for each program. The second approach is to rewrite all the game programs to fit within 16 K bytes.

To do this, you would type in the first game to have the line numbers from 2000 to 3000, for example, the second from 3010 to 4000, the third from 4010 to 5000, and so on. Lines 0 thru 1999 would be reserved for a menu that allows you to select which of the games you want to run. If you select Game 2, for example, a GOTO statement would send the interpreter to line 3010 to start execution.

The only way to get the flexibility you want without rewriting all the programs is to add a disk system. With a disk, you can write a short menu program that loads the games you want to play exactly as you have described. If you feel adventurous, my March 1981 "Circuit Cellar" article is on how to build an Expansion Interface for the TRS-80 Model I. (See "Build the Disk-80: Memory Expansion and Floppy-Disk Control," page 36.) . . . Steve

Bus Transfers

Dear Steve,

I may buy a Compucolor II computer system because this integrated color system has most of the requirements that I am seeking. Most important is its resolution and color capability; however, its bus structure concerns me. My question is this: are there any products available that allow peripherals designed for the S-100 bus to be used on the Compucolor's S-50 bus?

For other projects that I have in mind, I have looked into boards designed for the S-100, but they, of course, would make the S-50 a liability. I can see that the same signals would not be readily available from the 8080A as from a Z80 microprocessor. For example, take the signal MWRITE: aside from the fact that this particular signal is not available from an 8080A pin, I'm not sure that it could be emulated. Has anyone accomplished this, or at least managed to change an 8080A system to a Z80-based system?

Daniel W McAndrew
Bel Air MD

I haven't seen an S-50-to S-100 bus converter, but that doesn't mean there isn't one. If that is your main consideration for buying the Compucolor II, you might want to look around.

As for the 8080, Z80, and S-100 incompatibility: there are a variety of interfaces available, and the MWRITE Z80 signal is easily synthesized with a few gates. A good book that covers all these buses (and conversions between some of them) is The S-100 and Other Micro Buses, *by Elmer C Poe and James C Goodwin (Indianapolis IN: Howard W Sams & Company). I paid $5.95 for it.* . . . Steve■

Books Received

The Architecture of Pipelined Computers, Peter M Kogge. New York: McGraw-Hill, 1981; 16 by 24.5 cm, 334 pages, hardcover, ISBN 0-07-035237-2, $27.95.

The Art of Computer Programming, Volume Two, Second Edition, Donald E Knuth. Reading MA: Addison-Wesley, 1981; 16.5 by 24.5 cm, 688 pages, hardcover, ISBN 0-201-03822-6, $25.95.

Basic Computer Logic, John R Scott. Lexington MA: D C Heath & Company, 1981; 16.5 by 23.5 cm, 233 pages, hardcover, ISBN 0-669-03706-0, $21.95.

Computer Systems Performance Modeling, C H Sauer and K M Chandy. Englewood Cliffs NJ: Prentice-Hall, 1981; 18.5 by 24.5 cm, 352 pages, hardcover, ISBN 0-13-165175-7, $18.95.

Data File Programming in BASIC: A Self-Teaching Guide, L Finkel and J R Brown. New York: John Wiley & Sons, 1981; 17.5 by 25.5 cm, 338 pages, softcover, ISBN 0-471-08333-X, $9.95.

8080/Z80 Assembly Language: Techniques for Improved Programming, Alan R Miller. New York: John Wiley & Sons, 1981; 17.5 by 25.5 cm, 318 pages, softcover, ISBN 0-471-08124-8, $9.95.

Essentials of Project Management, Clifford F Gray. Princeton NJ: Petrocelli Books, 1981; 16.5 by 24.5 cm, 241 pages, hardcover, ISBN 0-89433-101-9, $17.50.

Formal Specification of Programming Languages: A Panoramic Primer, Frank G Pagan. Englewood Cliffs NJ: Prentice-Hall, 1981; 16 by 23.5 cm, 245 pages, hardcover, ISBN 0-13-329052-2, $19.95.

How to Get the Most from Your Chess Computer, Julio Kaplan. Great Neck NY: RHM Press, 1980; 13.5 by 20.5 cm, 138 pages, softcover, ISBN 0-89058-046-4, $8.95.

Information Processing Systems, Second Edition, William S Davis. Reading MA: Addison-Wesley, 1981; 20 by 24.5 cm, 504 pages, hardcover, ISBN 0-201-03183-3, $18.95.

Inside BASIC Games, Richard Mateosian. Berkeley CA: Sybex, 1981; 18 by 23 cm, 325 pages, softcover, ISBN 089588-055-5, $13.95.

Interactive Videotex: The Domesticated Computer, Dimitris N Chorafas. Princeton NJ: Petrocelli Books, 1981; 16.5 by 24.5 cm, 263 pages, hardcover, ISBN 0-89433-127-2, $21.95.

Karel the Robot, A Gentle Introduction to the Art of Programming, Richard E Pattis. Somerset NJ: John Wiley & Sons, 1981; 16.5 by 23 cm, 106 pages, softcover, ISBN 0-471-08928-1, $5.95.

Man-Machine Systems: Information, Control, and Decision Models of Human Performance, T B Sheridan and W R Ferrell. Cambridge MA: MIT Press, 1981; 15.5 by 23 cm, 452 pages, softcover, ISBN 0-262-69072-1, $12.50.

MICRO/Apple, Ford Cavallari. Chelmsford MA: Micro Ink Inc, 1981; 16 by 23 cm, 216 pages, softcover, ISBN 0-938222-05-8, $24.95. All the programs introduced in *MICRO/Apple* are on a 5-inch floppy disk (DOS 3.2 format), which accompanies the book.

Oscilloscopes, S Prentiss. Reston VA: Reston Publishing, 1981; 16 by 23.5 cm, 161 pages, hardcover, ISBN 0-8359-5354-8, $16.95.

Pascal Primer, D Fox and M Waite. Indianapolis IN: Howard W Sams & Company, 1981; 22 by 28 cm, 208 pages; softcover, ISBN 0-672-21793-7, $16.95.

6809 Assembly Language

Programming, Lance A Leventhal. Berkeley CA: Osborne/McGraw-Hill, 1981; 16.6 by 23.5 cm, 553 pages, softcover, ISBN 0-931988-35-7, $16.99.

68000 Microprocessor Handbook, Gerry Kane. Berkeley CA: Osborne/McGraw-Hill, 1981; 18 by 23.5 cm, 113 pages, softcover, ISBN 0-931988-41-1, $6.99.

Software Maintenance Guidebook, R L Glass and R A Noiseux. Englewood Cliffs NJ: Prentice-Hall, 1981; 15.5 by 23.5 cm, 193 pages; hardcover, ISBN 0-13-821728-9, $21.95.

Stalib, A Statistical Computing Library, W M Brelsford and D A Relles. Engiewood Cliffs NJ: Prentice-Hall, 1981; 21 by 28 cm, 427 pages; softcover, ISBN 0-13-846220-8, $17.50.

Structured Requirements Definition, Ken Orr. Topeka KS: Ken Orr & Associates, 1981; 24.5 by 28 cm, 236 pages, softcover, ISBN 0-9605884-0-X, $25.

Understanding FORTRAN, Second Edition, M Boillot. St Paul MN: West Publishing, 1981; 18.5 by 25 cm, 505 pages, softcover, ISBN 0-8299-0355-0, $14.95.

Using BASIC, R Didday and R Page. St Paul MN: West Publishing, 1981; 18.5 by 25 cm, 525 pages, softcover, ISBN 0-8299-0357-7, $15.95.

When People Use Computers, Marilyn Mehlmann. Englewood Cliffs NJ: Prentice-Hall, 1981; 16 by 23.5 cm, 142 pages, hardcover, ISBN 0-13-956219-2, $15.

Why Do You Need a Personal Computer?, Lance A Leventhal and Irvin Stafford. New York: John Wiley & Sons, 1981: 17.5 by 25.5 cm, 278 pages, softcover, ISBN 0-471-04784-8, $8.95. ■



AVAILABLE FALL 1981

DIGITAL HARMONY
by John Whitney

A new synthesis of sight and sound

Digital Harmony lays the foundation for the whole new field of audio-visual art made possible by microcomputers. John Whitney, a pioneer of the special effects technology used in STAR WARS and 2001: A SPACE ODYSSEY, explains the special union of computer graphics and music. His computer-generated visual art graphically depicts the laws of harmonic motion common to all music.

Digital Harmony includes a complete description of Whitney's computer, peripherals, and film techniques. Colorful illustrations are included, as well as the program listings that generated them. The descriptions are sufficient for anyone to begin to explore this new territory as a composer and computer experimenter - transforming the small computer into an ideal instrument for creating compositions in aural and visual art.

John Whitney is on the Faculty in the Department of Art at the University of California, Los Angeles.

ISBN 0-07-070015-X
240 pages
hardcover
over 50 color photographs

$21.95

INVERSIONS: A Catalogue of Calligraphic Cartwheels
by Scott Kim
Foreword by Douglas Hofstader
Backword by Jef Raskin

Surprising symmetries in design and letterforms

Illusion . . . calligraphy . . . visual magic - Scott Kim's new book, Inversions, delights the eye and enchants the mind. Filled with intriguing designs, words that read the same right-side up and upside down, words within words, and unexpected symmetries, these compositions create a fresh way to look at the alphabet. The text includes the visual principles of symmetry, lettering, and problem solving that are basic to these images. The author also draws parallels to related exercises in perception in such diverse areas as art, music, word play, and mathematics. Scott Kim's original inversion designs first appeared in *Omni* magazine, inspiring an overwhelming reader response. An irresistable challenge, invertible writing appeals to everyone who loves beauty in mathematics and design.

Scott Kim is a doctoral student in Computer Science at Stanford University and is a concert pianist and composer.

ISBN 0-07-034546-5
128 pages
softcover
over 50 illustrations
available summer 1981

$8.95

BRAINS, BEHAVIOR, AND ROBOTICS
by James S. Albus

Robotics design and applications

This computer-oriented guide explores how the brain functions primarily as a computer device for generating and controlling behavior. The author assesses behavior as a product of three hierarchies of computing modules:

- memory modules
- behavior-generating modules
- sensory-processing modules

A section on artificial intelligence ties this hierarchical model to vital computer science techniques such as planning, problem-solving, machine vision, natural language understanding and knowledge representation. A closing section on robotics discusses the design considerations in constructing a robot control system fashioned after this model of the brain, and explores the current and potential use of robots in our environment.

Dr. James S. Albus is Project Manager with the National Bureau of Standards.

ISBN 0-07-000975-9
400 pages
hardcover
180 illustrations

$15.95

THE BRAINS OF MEN AND MACHINES
by Ernest W. Kent

Human models for computer design

When the "Brains of Men and Machines" series of articles first appeared in BYTE magazine, the response was immediate and enthusiastic. Now Ernest W. Kent has expanded his ideas about the brain into a full-length book. As researchers begin to unravel the mysteries of the brain's chemical, electrical, and synaptic circuitry, their findings are becoming immediately applicable to advances in robotic behavior and computer design. The Brains of Men and Machines "dissects" the brain to provide new insights into computer design and artificial intelligence.

It is one of the rare books that transcends disciplinary boundaries. In it the ever-increasing relationship between man and machine is freshly examined - a relationship, Professor Kent concludes, that is today being reexamined in the light of man's own neurological self-image.

Dr. Ernest W. Kent is a Professor of Physiological Psychology and Psychopharmacology at the University of Illinois at the Chicago Circle Campus.

ISBN 0-07-034123-0
304 pages
hardcover
illustrated

$15.95

The BYTE BOOK Collection

Circle 48 on inquiry card.

BASIC SCIENTIFIC SUBROUTINES, VOLUMES 1 AND 2

by Fred Ruckdeschel



Valuable programs for professional and hobbyist

Designed for the engineer, scientist, experimenter, and student, this series presents a complete scientific subroutine package in BASIC.

- Volume 1 covers plotting, complex variables, vector and matrix operation, random number generation, and series approximations.
- Volume 2 continues with least-squares approximation, special polynomial functions, approximating techniques, optimization, roots of functions, interpolation, differentiation, integration, and digital filtering.

These volumes feature routines written in both standard Microsoft and North Star BASIC, extensive appendices, and subroutine cross-referenes.

Dr. Fred Ruckdeschel is a Principal Scientist with Dynacomp, Inc.

VOLUME 1
ISBN 0-07-054201-5
336 pages
hardcover
illustrated

$19.95

VOLUME 2
ISBN 0-07-054202-3
384 pages hardcover
illustrated
available Fall 1981

$23.95



THE BYTE BOOK OF PASCAL

Blaise W. Liffick, Editor

A powerful, structured language

Based on articles, language forums, and letters from BYTE magazine, this work is a valuable software resource. Pascal continues to be popular as a structured programming language. Written for both potential and established users, this book introduces the Pascal language and examines its merits and possible implementations. Featured are two versions of a Pascal compiler, one written in BASIC and the other in 8080 assembly language; a p-code interpreter written in both Pascal and 8080 assembly language; a chess-playing program; and an APL interpreter.

ISBN 0-07-037823-1
334 pages
hardcover

$25.00

THREADED INTERPRETIVE LANGUAGES

by Ronald Loeliger



How to implement FORTH on your Z80

Threaded languages (such as FORTH) are compact, giving the speed of assembly language with the programming ease of BASIC. They combine features found in no other programming languages. This book develops an interactive, extensible language with specific routines for the Zilog Z80 microprocessor. With the core interpreter, assembler, and data type defining words covered in the text, it is possible to design and implement programs for almost any application and equivalent routines for different processors.

Ron Loeliger is a Senior Analyst with Intermetrics, Inc.

ISBN 0-07-038360-X
272 pages
hardcover
illustrated

$18.95



BEGINNER'S GUIDE FOR THE UCSD PASCAL SYSTEM

by Kenneth L. Bowles

The most popular Pascal version explained by its creator

Written by the originator of UCSD Pascal System, this informative book is an orientation guide to the UCSD Pascal System. For the novice, this book steps through the System, bringing the user to a sophisticated level of expertise. Once familiar with the System, the reader will find the guide an invaluable reference tool for creating advanced applications. The package offers programs which may be run without alteration on:

- DEC PDP-11 or General Automation minicomputers
- Western Digital Microengines
- 8080, 8085, Z80, 6502, 6800, 9900 or AM-100 based microcomputers (including the popular Apple II and Radio Shack TRS-80 microcomputers)

Dr. Kenneth L. Bowles is Director of the Institute for Information Systems, University of California, San Diego.

ISBN 0-07-006745-7
204 pages
softcover

$11.95

YOU JUST BOUGHT A PERSONAL *WHAT?*



by Thomas Dwyer and Margot Critchfield

A Structured Approach to Creative Programming

Intended for both the novice programmer and the experienced computer enthusiast. this book presents practical ideas for personal computer use at home or at work.

Its approach is especially suitable for educational purposes. Written by the leading contributors of computer education material, this book is an entertaining and resourceful tool. There are over 60 ready-to-use programs written in Microsoft and Level II BASIC for the TRS-80 in the areas of educational games, financial record keeping, business transactions, disk-based files, and word processing.

Dr. Thomas Dwyer is a Professor of Computer Science at the University of Pittsburgh.

Margot Critchfield is a doctoral student in Foundations in Education at the University of Pittsburgh.

ISBN 0-07-018492-5
343 pages
softcover
78 illustrations

$11.95

BEYOND GAMES: SYSTEM SOFTWARE FOR YOUR 6502 PERSONAL COMPUTER

by Kenneth Skier

Creating programs for the Apple, Atari, Challenger and PET computers

At last, a complete programming guidebook for owners of personal computers utilizing the 6502 microprocessor. A self-contained course in structures programming and top-down design, this book presents a powerful set of tools for building an extended monitor, disassembler, hexadecimal dump routine, and text editor programs. Programs are thoroughly explained, with clear instructions for modifications.

Kenneth Skier is a Systems Programmer for Wang Laboratories, Inc., and a Lecturer at MIT.

ISBN 0-07-057860-5
440 pages
softcover
illustrated

$14.95

stimulating, provocative, problem-solving

Circle 49 on Inquiry card.

CIARCIA'S CIRCUIT CELLAR
by Steve Ciarcia

Practical uses for home computers

Imaginative and practical, Ciarcia's Circuit Cellar details a variety of microcomputer projects. A collection of the best articles from the popular series in BYTE magazine, this volume includes
- D/A conversion
- Programming EPROMS
- AC remote-controlled appliances
- digitized speech
- touch input video display

Complete instructions are given on how to construct each project. With amusing anecdotes and an easy-going style, Ciarcia presents his material in such a manner that even a neophyte need not be afraid of it.

ISBN 0-07-010960-5
125 pages
softcover
color photographs and diagrams

$8.00

CIARCIA'S CIRCUIT CELLAR, VOLUME II
by Steve Ciarcia



More practical uses for home computers

Composed of popular articles from BYTE magazine, this volume tells how microcomputers can be uniquely interfaced to our environment. Projects include
- building a computer controlled home-security system
- computerizing appliances
- transmitting digital information over a beam of light
- building the Intel 8086 microprocessor system design kit
- input-output expansion for the TRS-80

ISBN 0-07-010963-X
224 pages
softcover
photographs and diagrams

$12.95

MICRO-COMPUTER STRUCTURES
by Henry D'Angelo

Digital Electronics, Logic Design, and Computer Architecture

Today, there is an increasing demand for computer users who are not only well-versed in software, but who can also maintain, modify, and design their own hardware systems.

This text introduces computer users with little or no background in digital hardware to the basic computer structures used in microcomputer design and microcomputer interfacing. Helpful examples and end-of-chapter exercises further illustrate the various concepts presented, and a detailed bibliography provides additional reading opportunities. As a resource and textbook, it will assist
- programmers and systems analysts
- engineers and scientists
- managers
- students

Detailed Instructor's Manual also available.

Dr. Henry D'Angelo is the Associate Dean of the College of Engineering and Professor of Manufacturing Engineering at Boston University.

ISBN 0-07-015294-2
288 pages
hardcover
314 illustrations
available spring 1981

$18.95

Instructor's Manual
ISBN 0-07-015298-5
softcover

$8.95

BUILD YOUR OWN Z80 COMPUTER
by Steve Ciarcia



Every step spelled out for do-it-yourself buffs

For the engineer, computer technician, student, and anyone interested in building a computer rather than buying one, this practical guide shows how to build a working computer based on the Zilog Z80 microprocessor. Each computer subsystem is fully explained and supported by proven design and testing information. The description focuses on a basic single-board microcomputer containing
- easy expansion to include a video terminal
- a 1 K-byte operating system
- serial and parallel ports
- hexadecimal display
- audio cassette mass storage

Readers can modify the system to meet personal needs.

Steve Ciarcia is a Computer Consultant, Electrical Engineer, and author of "Ask Byte" and "Ciarcia's Circuit Cellar" columns in BYTE magazine.

ISBN 0-07-010962-1
330 pages
softcover
available summer 1981

$15.95

BYTE Books' reputation is based on providing technically accurate, useful, and timely information. Established on the same principle as *BYTE* magazine, BYTE Book's evolved in response to the rapidly expanding audience of home and business computer users. Computer professionals and enthusiastic newcomers need to keep pace with this unabated growth. This selection of BYTE books can expand your library of knowledge and expertise.

TO ORDER, CALL TOLL FREE 800-258-5420, OR FILL OUT YOUR CHOICES IN THIS COUPON and return it with check, money order, or charge card number to:

BYTE BOOKS
70 Main Street
Peterborough,
New Hampshire 03458

BYTE BOOKS
70 Main Street
Peterborough, New Hampshire 03458

Name ______________________

Address ______________________

City __________ State __________ Zip __________

- Check enclosed in the amount of __________
- Bill Visa. Card Number __________
- Bill Master Charge. Card Number __________
- Expiration Date __________

Include 75c per book to cover postage and handling.

TITLE	PRICE	QUANTITY	AMOUNT

SHIPPING ______
TOTAL ______

order now . . . !

McGraw Hill

Circle 50 on inquiry card.

Collector Edition

BYTE COVERS

The Byte covers shown below are available as beautiful Collector Edition Prints. Each full color print is 11" × 14", including a 1½" border, and is part of an edition strictly limited to 500 prints. (Print numbers 2, 4, 6, 7 and 8 are editions of only 100 prints, and some quantities are very low.) The artist, Robert Tinney, has personally inspected, signed and numbered each print. A Certificate of Authenticity accompanies each print guaranteeing its quality and limited number.

Collector Edition Prints are carefully packaged flat to avoid bending, and are shipped first class. The price of each print is $20, plus $3 per shipment for postage and handling ($6 overseas). Collector Prints 9-12 are available as a set of 4 for $70. Because certain prints have sold out, Sets 1-4 and Sets 5-8 are no longer available as sets.

To order your own beautiful Collector Edition Byte Cover use the convenient coupon below. Visa or MasterCard orders may call Toll Free.



#9 SOFTWARE PIRACY $20



#10 THE PROGRAMMING ROUTE $20



#11 FORTH $20



#12 FUTURE PAST $20



#2 FUN AND GAMES $20



#4 SOFTWARE MIRAGE $20

#6 TOTAL ECLIPSE $20



#7 COMPUTER HARDWARE $20



#8 PERSPECTIVES $20

COMPUTER CHESS
Oct. 1978
$7.95



THROUGH THE TRAP DOOR
Mar. 1979
$35.00



BREAKING THE SOUND BARRIER
Sept. 1977
$35.00

ALSO AVAILABLE are the prints shown at left. "Computer Chess" is an 18" X 22" full color poster.

"Through the Trap Door" and "Breaking the Sound Barrier" are limited editions of 750 prints each, signed and numbered by the artist. Each print is 18" X 22", and is accompanied by its own Certificate of Authenticity. **If both "Door" and "Barrier" are ordered, a special price of $55 applies.**

All three prints shown at left are shipped first class in heavy duty mailing tubes.

Please send me the following Prints:

QTY	TITLE	AMOUNT
____	____________	$____
____	____________	$____
____	____________	$____
____	____________	$____
____	____________	$____
____	____________	$____
____	**Set 9-12**	$70
____	**Both "Trap Door" & "Barrier"**	$55
Post. & Hand. ($3 U.S., $6 overseas)		$____
	TOTAL	$

☐ I have enclosed check or money order.
☐ Visa ☐ MasterCard

Card # ____________

Expiration Date ____________

SHIP MY PRINTS TO:

Name ____________

Address ____________

City ____________

State ________ Zip ________

Mail this coupon to:

robert tinney graphics
1864 N. Pamela Drive
Baton Rouge, LA
70815

For VISA OR MASTERCARD ORDERS
CALL TOLL FREE!
1-800-854-0562 / Ext. 910
Calif: 1-800-432-7257 / Ext. 910
24 HOURS A DAY! 7 DAYS A WEEK!

Circle 438 on inquiry card.

Kalman Mileage Predictor-Monitor

Jerry Lobdill
6708 Beckett Rd
Austin TX 78749

Have you ever wondered how a heat-seeking missile homes in on its prey? How lunar landings are accomplished without dashing the lunar module to bits? Or how satellite orbits are predicted and adjusted? These and other complex problems have been solved through the powerful techniques of optimal estimation theory.

The roots of this discipline can be traced back to Karl F Gauss, who first used the technique of deterministic least squares in an orbit-measurement problem—circa 1800. Although Gauss recognized and discussed many aspects of the general problem of estimating the state of a dynamic system based on "noisy" measurements of observable quantities, it remained impractical to address the real-time statistical problem until 1960 when R E Kalman proposed optimal *recursive* techniques which can be easily implemented on digital computers. Today "Kalman filtering" problems involving ten to twenty variables are routinely solved in real time using microprocessor-based systems.

A complete understanding of the theory of Kalman filtering requires considerable familiarity with the theory of random processes, but the intuitive concept can be easily grasped by any interested person with some background in university-level mathematics. This article provides insight into the workings of a Kalman filter and at the same time it presents a useful algorithm that can be implemented on any personal computer. The problem addressed is simple to solve with Kalman techniques in that only one variable is involved—the gasoline mileage of your automobile.

About the Author

Jerry Lobdill is a sonar systems scientist at Tracor Inc in Austin, Texas. As a personal computer hobbyist he has written numerous programs for the HP 67/97, with applications that range from accounting to music.

A Practical Application

As the price of gasoline spirals, it becomes increasingly important to conserve fuel. Certain driving habits result in poor fuel economy; consequently more of us are suppressing our desire to experience the thrill of acceleration. The EPA ratings have made us aware that even the gas mileage of a properly tuned car will vary substantially depending upon whether it is driven in town or on the highway. This variation tends to obscure the inevitable aspect of gradual deterioration in performance due to aging spark plugs and points, a clogging air filter, and slowly deflating tires. Early detection of this downward trend in the average mileage can save a considerable amount of fuel and money if promptly followed by maintenance.

The problem is that even if we buy an expensive special-purpose onboard computer to monitor and display instantaneous and average mileage, or simply compute and plot mileage on a tank-to-tank basis, we still have to decide when this gradual deterioration is occurring. Although a record of the mileage the car is getting at any instant contains too much random variation (noise), a plot of average mileage versus time can be eyed judiciously or subjected to regression analysis in order to extract the required information. This is comforting to know, of course, but the idea of studying a graph is aesthetically revolting to a personal computer enthusiast, and to store all previous data for display or regression analysis seems like a brute-force approach. Isn't there an elegant recursive algorithm that will monitor the fuel economy performance? The answer is yes.

This article presents an algorithm for the recursive optimal estimation of a car's mileage performance, a flow chart for implementing the algorithm, a program written for the Hewlett-Packard HP-67/97, and an example that illustrates the program's use. I have monitored the performances of a 1973 MGB and a 1971 Mercury Monterey for several months and have found the program to be convenient and useful.

The program, based on optimal estimation theory, implements a single-state linear Kalman filter which recursively predicts the gasoline mileage at each successive fill-up, compares the measured mileage with the prediction, monitors the trend of the data, and sums the miles traveled and cost of the gasoline used since initializing the Kalman filter. The HP-67/97 program also provides alerts when the difference between the predicted and measured mileage exceeds a given threshold, when a trend toward degraded (or improved) performance is established, and when it is time to change the oil. The program and the data for the next update (fill-up) can be stored on just one of the calculator's magnetic cards.

Optimal Estimation

Optimal estimation theory is

applied to navigation systems, satellite orbit estimation, and rocket guidance. Most of the mechanizations are based on Kalman filtering theory (see references).

An overview of the Kalman filter is shown in figure 1. The Kalman filter recursively estimates a parameter (or set of parameters), x, called a state vector, based on discrete samples of a noisy measurement vector, z, and gives a prediction of the state vector, $\hat{x}_k(+)$, based on previous measurements. The measurement vector is considered to be linearly related to the state vector, although it need not contain the same number of elements as the state vector. If it contains fewer elements, the system is underdetermined; if it contains more, the system is overdetermined. (In the case at hand, both the measurement vector and the state vector are one dimensional.) The Kalman filter is designed to produce an estimate of the state vector which is optimum in a least-squares sense. Theoretically, no other estimator can produce a better estimate if the actual process and the model of the process incorporated into the filter are in accord. The Kalman filter provides not only an estimate of the current state vector, $\hat{x}_k(+)$, but also a prediction of the next state vector, $\hat{x}_{k+1}(-)$.

System and Measurement Models

In the Kalman mileage predictor-monitor, we assume that when the car is operating properly the true mileage is a constant perturbed by additive zero-mean Gaussian noise. Thus, our system model is defined by a single state with the following simple- state transition equation:

$$x_{k+1} = x_k + w_k \qquad (1)$$

where x_k is the mileage on the kth fill-up, and w_k is a sample from a zero-mean Gaussian process with variance given by q. Changes in the mileage due to different driving conditions encountered on different tanks (not errors in our measurements) are represented by *plant noise*, w_k.

Our kth measurement of the mileage, which we denote by z_k, is corrupted by another zero-mean Gaussian noise process, v_k, so that in the Kalman filter we assume that the measurement is related to the actual mileage, x_k, by the equation:

$$z_k = x_k + v_k \qquad (2)$$

where v_k has a variance denoted by r. The quantity v_k is called *measurement noise*, and it represents the uncertainty in our measurement procedure.

The program computes the mileage measurement, z_k, using the total cost of the fill-up, C_k, and the price per gallon, CG_k. This yields a more accurate measure of the number of



Figure 1: *The discrete linear Kalman filter computes the optimal estimate of the state vector, x, from a noisy measurement vector, z, and a prediction of the state vector, $\hat{x}_{k+1}(-)$, based on the available k previous measurements. After the kth measurement, the optimal estimate of the state vector is $\hat{x}_k(+)$. The system and measurement model boxes represent mathematical descriptions of the filter designer's concept of the processes which produce the observables, z_k. To the extent that these models coincide with reality, the filter is optimal.*

LEADER OF THE PACK

You'll see a lot of confusing claims for disk packs and storage modules, but here are a few tips that can help you make the right choice when you're specifying your next pack:

- BASF products represent BASF technology and quality, because, unlike many suppliers, we make them ourselves.
- We polish our uncoated metal disks to a mirror finish for optimum headflight characteristics and virtually no possibility of media-induced headcrash.
- We coat, polish, and burnish each disk by our own process, assuring you of long-lasting, trouble-free operation.
- We magnetically orient all oxide particles in the disk coating for greater packing density.
- We drive-test each pack before it leaves the factory, for top performance with no surprises.
- BASF has your configuration and format*...at a competitive price, ready for immediate delivery.
- For the name of your nearest supplier, write BASF Systems Corporation, Crosby Drive, Bedford, MA 01730, or call 800-343-4600.

*For Burroughs: Front-load single disk cartridges, 80MB Tridents.
For CDC: 80 and 300 MB storage modules, Phoenix single disk cartridges.
For Data General: 50, 100, 200, and 300 MB disk packs, top-load single disk cartridges.
For DEC: 100 and 200MB 12-high packs, front-load single disk cartridges, 80 and 300 MB storage modules.
For Honeywell: Phoenix single disk cartridges, 80 and 300MB storage modules, 100MB packs.
For IBM: 100 and 200MB 12-high packs, top and front-load single disk cartridges.
For Wang: Phoenix single disk cartridges, 80 and 300 MB storage modules, top-load single disk cartridges.

BASF

BASF Systems Corporation
Attn.: Marketing Services, Computer Division
Crosby Drive, Bedford, MA 01730

Please send me information on BASF disk packs.

Name/Title ______________________

Company ______________________

Address ______________________

City ____________ State ________ Zip ______

Telephone ______________________

BYTE-7

Circle 41 on inquiry card.

gallons used than that obtained by using the gas pump reading. Thus:

$$z_k = \frac{(O_k - O_{k-1})\,(CG_k)}{C_k} \qquad (3)$$

where $O_k - O_{k-1}$ is the difference between odometer readings on the $(k-1)$th and the kth fill-up.

Recursive Estimation

The optimal estimate of x after the kth fill-up is given by the following equation:

$$\hat{x}_k(+) = \hat{x}_k(-) + K_k(z_k - \hat{x}_k(-)) \qquad (4)$$

where the ∧ caret denotes an estimate of the state, and the $(-)$ or $(+)$ denotes the estimate before or after the kth fill-up, respectively. A prediction of the kth value of x based on the $k-1$ previous measurements (but not including the kth measurement) is expressed as $\hat{x}_k(-)$. K_k is called the *Kalman gain,* and the quantity $(z_k - \hat{x}_k(-))$ is called the *residual,* denoted hereafter by R_k.

The Kalman gain is a measure of the confidence the filter places in the current measurement. It is related to the *error covariance,* $P_k(-)$, by the equation:

$$K_k = \frac{P_k(-)}{P_k(-) + r} \qquad (5)$$

The error covariance is an estimate of



Figure 2: *Flowchart of the Kalman mileage-predictor program. MNOC is a constant with a value that means "miles since filter initialization."*

```
001  *LBLE     21 15
002   CLRG     16-53
003   STO4     35 04
004    R↓        -31
005   STOA     35 11
006    R↓        -31
007   STOB     35 12
008    R↓        -31
009   STOD     35 14
010      0        00
011   STOI     35 46
012    R/S        51
013   STOC     35 13
014    R↓        -31
015   STO3     35 03
016    R↓        -31
017   STO5     35 05
018   WDTA     16-61
019    RTN        24
020  *LBLA     21 11
021    R↓        -31
022   STO2     35 02
023    R↓        -31
024   STO0     35 00
025   ST+8  35-55 08
026    R↑      16-31
027      ÷       -24
028   RCLB     36 12
029    R↑      16-31
030   STOB     35 12
031    X⇄Y       -41
032      -       -45
033   ST+7  35-55 07
034    X⇄Y       -41
035   ENT↑       -21
036    R↓        -31
037      ÷       -24
038   STO1     35 01
039      .       -62
040      4        04
041   RCL5     36 05
042      +       -55
043    1/X        52
044   RCL5     36 05
045      ×       -35
046   STO6     35 06
047      0        00
048   RCLA     36 11
049   RCL1     36 01
050   RCL3     36 03
051      -       -45
052   STOE     35 15
053    ABS     16 31
054   X>Y?     16-34
055   GSB0     23 00
056   RCLI     36 46
057      3        03
058   X≤Y?     16-35
059   GSB1     23 01
060   GSBC     23 13
061    RTN        24
062  *LBL1     21 01
063   RCLE     36 15
064   ST+9  35-55 09
065      1        01
066   RCL4     36 04
067   RCL9     36 09
068    ABS     16 31
069   X>Y?     16-34
070   GSB0     23 00
071    RTN        24
072  *LBL0     21 00
073    SPC     16-11
074   PRTX       -14
075    R↓        -31
076   PRTX       -14
077    R↓        -31
078   PRTX       -14
079    RTN        24
080  *LBLC     21 13
081   RCL9     36 09
082   RCLE     36 15
083   RCL3     36 03
084   RCL1     36 01
085   GSB0     23 00
086    R↓        -31
087   PRTX       -14
088    R↑      16-31
089   RCL6     36 06
090      ×       -35
091   RCL3     36 03
092      +       -55
093   STO3     35 03
094   ISZI  16 26 46
095      1        01
096   RCL6     36 06
097      -       -45
098   RCL5     36 05
099      ×       -35
100   RCLD     36 14
101      +       -55
102   STO5     35 05
103      2        02
104   RCLC     36 13
105   RCL7     36 07
106   X≤Y?     16-35
107   GTO2     22 02
108   GSB0     23 00
109  *LBL2     21 02
110   WDTA     16-61
111    RTN        24
```

Listing 1: *Program to predict automobile mileage using the Kalman filtering technique. Written for the Hewlett-Packard HP-67 (or HP-97), the program uses a recursive routine that compares the actual fuel economy with the predicted economy and provides a warning if the discrepancy is above a threshold level.*

the variance of the error in the filter's estimate of x. When the filter is updated, the error covariance is updated according to the equation:

$$P_{k+1}(-) = (1-K_k)P_k(-) + q \quad (6)$$

By virtue of our state transition model, equation 1, we have:

$$\hat{x}_{k+1}(-) = \hat{x}_k(+) \quad (7)$$

because the Gaussian noise term, w_k, has a zero-mean value. Note in equation 5 that the Kalman gain cannot exceed unity since r, the measurement noise variance, is non-negative. (If r were zero, our measurements would be error free.) When the gain is small, the filter places more confidence in the prediction than in the new data; when the gain is large, the filter is less skeptical of the new data. After the filter is initialized, the Kalman gain decreases monotonically from the initial value to a steady-state value as the filter is updated. This decrease in the gain is a result of the fact that as more data is accumulated, the error in the estimate of the state decreases (ie: P_k decreases). If r is small, the Kalman gain approaches unity, in which case it disregards new data. In this instance, the error in the estimate of the state would be entirely due to the plant noise, as can be seen by examination of equation 6 with $K_k = 1$. Plant noise prevents the filter from deciding that it knows everything, in a sense causing it to behave like a finite memory filter that always responds to new data. The recursive feature of the Kalman filter is evident in that only the present measurement value, z_k, is required in equations 4 thru 7.

Filter Design Considerations

It is desirable that the filter respond slowly to changes in the mean value

32 PROVEN SOLUTIONS.

proven solutions that create expandable, modular, fast, exceptionally reliable, and truly professional level machines that conform fully to the IEEE 696/S-100 standards.

When you depend on your computer, choose a computer on which you can depend: **S-100 from CompuPro.**

18 **8088/8086 MONITOR-DEBUGGER SOFTWARE.** Ideal for use with CPU 8085/88. Supplied on single sided, single density, soft sectored 8" disk. CP/M-80 compatible. Great development tool; mnemonics used in debug conform as closely as possible to current CP/M DDT mnemonics. (Also included in CP/M-86 package.) $35.

19 **8 BIT CPU 8085.** Same as CPU 8085/88, but without 8088. May be easily upgraded to 16 bit operation. $235 Unkit, $325 A/T, $425 CSC.

20 **INTERFACER 1.** Two RS-232 serial ports, with full handshaking and independently selectable Baud rates, connect your computer to serial peripherals. $199 Unkit, $249 A/T, $324 CSC.

21 **INTERFACER 2.** Adds three full duplex parallel ports, and one serial port with all the features of an Interfacer 1 serial port, to your computer. $199 Unkit, $249 A/T, $324 CSC.

22 **INTERFACER 3-5.** Includes five RS-232 serial ports (2 synchronous/asynchronous, 3 asynchronous) with handshaking. Includes software programmable Baud rates and many other convenience features. $599 A/T, $699 CSC.

23 **INTERFACER 3-8.** Same as above, but with eight full RS-232 serial ports (2 synchronous/asynchronous, 6 asynchronous). Ideal for multi-user/multi-terminal systems. $699 A/T, $849 CSC.

24 **SPECTRUM COLOR GRAPHICS BOARD.** With 8K of IEEE-compatible static RAM, full duplex bidirectional I/O port for keyboard or joystick interface, and 6847-based graphics generator that can display all 64 ASCII characters. 10 modes of operation, from alphanumerics/semi-graphics in 8 colors to ultra-dense 256 x 192 full graphics. $299 Unkit, $399 A/T, $449 CSC.

25 **6 SLOT HIGH SPEED MOTHERBOARD.** With all edge connectors, Faraday shielding, extensive bypassing, and split active termination. $89 Unkit, $129 A/T.

26 **12 SLOT HIGH SPEED MOTHERBOARD.** Same as above, but with 12 slots. $129 Unkit, $169 A/T.

27 **20 SLOT HIGH SPEED MOTHERBOARD.** Same as above, but with 20 slots. $174 Unkit, $214 A/T.

28 **MEMORY MANAGER.** Extends the addressing of older S-100 machines beyond 64K Bytes to allow for greatly expanded memory capacity. $59 Unkit, $85 A/T, $100 CSC.

29 **ACTIVE TERMINATOR.** Promotes reliable and accurate data transfer in older machines by properly terminating bus lines, thereby minimizing ringing, crosstalk, overshoot, noise, and other gremlins associated with unterminated lines. $34.50 Unkit, $59.50 A/T.

30 **2708 EPROM BOARD.** This board is the way to store often used routines or pieces of software. $85 Unkit, $135 A/T, $195 CSC (2708s not included).

31 **BIG 8 SPECIAL PACKAGE.** You don't need to compromise anymore: CompuPro's advanced S-100 engineering is now cost-competitive with mass market 8 bit computers that do a whole lot less. The Big 8 package includes CPU-Z, Disk 1, 32K of fast static RAM with 24 bit extended addressing, Interfacer 1 or 2 (your choice), CP/M-80 2.2, and all documentation and manuals. Plus, if you purchase a Big 8 package before August 1, you'll receive an extra 32K of free static RAM. **Total value? $2712 with the free RAM- but Big 8's list price is only $1995!** This package not only saves you $700, but provides the nucleus of one of the most advanced 8 bit systems available–regardless of cost.

32 **DOCUMENTATION.** User manuals are available for all products for $5, with the following exceptions: Interfacer 3, $10; Disk Controller, $25; System Support 1, $20. Also available: "CompuPro Product User Manuals: 1975 - 1980". This 250+ page book includes data on all older Godbout/CompuPro products, as well as many newer products such as the Spectrum Color Graphics board, Interfacers 1 and 2, CPU 8085/88, motherboards, CPU Z, and more. Whether you want to evaluate the innovative engineering behind CompuPro products, or study the nuts and bolts of high speed computer operation, this is the books for you. $20 plus shipping.

FUTURE SOLUTIONS: In the months ahead, we'll be introducing an ultra-fast, true **DMA Hard Disk Controller; Parity check board;** and much more in our continuing commitment to professional level computing.

TERMS: Prices shown do not include dealer installation and support services. Cal res add tax. Allow at least 5% shipping; excess refunded. Orders under $15 add $2 handling. VISA® and Mastercard® orders ($25 min) call our 24 hour order desk at **(415) 562-0636.** Include street address for UPS delivery. Prices are subject to change without notice.

world-wide ...call **(415) 562-0636** for the store nearest you.

division of GODBOUT ELECTRONICS

MEMBER MITA

*LEGAL CORNER: Z80A is a registered trademark of Zilog CP/M is a registered trademark of Digital Research

Circle 159 on Inquiry card.

of the mileage data. This allows the residuals to be monitored for the purpose of detecting changes in mileage that exceed the expected variation for a properly operating automobile. We generate an alarm if the residual exceeds twice the expected standard deviation of the steady-state estimation error (the alarm detects sudden changes in mileage). We also sum the residuals and generate an alarm if the magnitude of the sum exceeds four times the expected standard deviation of the steady-state estimation error (this alarm detects a gradual trend, either upward or downward). In order to allow the filter to converge, we do not begin to sum the residuals until the third update after initialization.

Flow Diagram

The flow diagram for the Kalman mileage predictor-monitor is shown in figure 2. Note that a number of inputs are required upon initialization. The following guidelines and the example contain a discussion of how to select values for these inputs.

Figure 2 shows optional computations that aid in monitoring automobile performance and assure timely maintenance. Specifically, sums of all gasoline costs and total miles traveled since filter initialization are computed and a test is performed to determine whether or not the total miles traveled exceeds the desired oil change interval. If it is time for an oil change, the program outputs an alarm. The user can compute gasoline cost per mile traveled at any time by recalling the summed data and computing the ratio of costs to miles traveled. Other optional computations can be added if you are willing to use more than one HP-67/97 magnetic card for program and data storage or if the program is implemented on a larger machine.

The optional manual action, set $\Sigma R = 0$, has been shown in figure 2 to emphasize a point about ΣR, the sum of the residuals computed for $k \geq 3$. Since the mean value of the residuals is zero, you might expect that the sum of the residuals will remain near zero. However, there is a theorem in probability theory (the theorem of long leads) that states, in effect, that the farther this sum departs from zero, the longer it will be before it returns to zero. This is a result of the fact that a significant departure from zero requires an improbable sequence of events—the occurrence of residuals of improbably large magnitude and/or a sequence of residuals of the same sign. Once such an improbable event occurs, an equally improbable event must occur to return the sum to zero. Therefore, the user may wish to set $\Sigma R = 0$ whenever $|\Sigma R|$ reaches or crosses the threshold, $|\Sigma R|_{max}$, in order to prevent this alarm from repeating erroneously after the car has been repaired. The flow diagram shows that the program does not output the filter's estimate of the mileage based on all k measurements, $\hat{x}_k(+)$.

Register	Contents	Units
P0	Cost of current fill-up, C_k	\$
P1	Measured miles per gallon at current fill-up, z_k	mpg
P2	Cost per gallon, CG_k	\$
P3	Predicted miles per gallon for next fill-up, $\hat{x}_{k+1}(-)$	mpg
P4	Threshold for magnitude of the sum of residuals, $\lvert\Sigma R\rvert_{max}$	mpg
P5	Error covariance for next fill-up, $P_{k+1}(-)$	$(mpg)^2$
P6	Kalman gain for current fill-up, K_k	none
P7	Total miles traveled since initialization, $\Sigma(O_k - O_{k-1})$	mi
P8	Total cost of gasoline since initialization, ΣC_k	\$
P9	Sum of the residuals, ΣR_k $(k \geq 3)$	mpg
A	Threshold for magnitude of a residual, R_{max}	mpg
B	Odometer reading at current fill-up, O_k	mi
C	Total miles between initialization and next oil change, MNOC	mi
D	Variance of plant noise, q	$(mpg)^2$
E	Residual, current fill-up, R_k	mpg
I	Number of fill-ups since initialization, including current fill-up, k	none

Table 1: *Data-register contents for the mileage-predictor program. P0 thru P9 represent primary registers.*

WE DID IT, AGAIN!!

Microcomputer Workstations from $7,995.00



CI-MWS03-SB — LSI 11/2 computer workstation. LSI 11/2 CPU, 64KB Memory, power supply, KEV 11, in 16 slot rack mountable chassis. 2 port serial I/O. CRT terminal. 1 Megabyte floppy disk system. Desktop workstation **$7,995.00**

CI-MWS23-MB — LSI 11/23 computer workstation. LSI 11/23 CPU, MMU, 256KB Memory, power supply, in 16 slot rack mountable chassis. CRT terminal. 10 megabyte cartridge disk system. 4 port serial I/O. Desktop workstation **$11,995.00**

CI-1103LK — LSI 11/2 CPU, 64KB Memory, power supply, KEV 11 in 16 slot rack mountable chassis **$2,450.00**

PDP 1103SE — LSI 11/2 CPU, 64KB Memory, power supply, KEV 11 in 8 slot rack mountable chassis **$2,695.00**

CI-11/23 AC — LSI 11/23 CPU, MMU, 256KB Memory, power supply, in 16 slot rack mountable chassis **$4,995.00**



DON'T ASK WHY WE CHARGE SO LITTLE, ASK WHY THEY CHARGE SO MUCH.

Chrislin Industries, Inc.

31352 Via Colinas • Westlake Village, CA 91362
Telephone: 213-991-2254 • TWX 910-494-1253

Instead, the filter's prediction is based on $k-1$ measurements, $\hat{x}_k(-)$. This quantity is more useful because the user is interested in what the mileage *should* have been on the kth fill-up.

Alarms are indicated by a code number on the printer. A zero indicates that the magnitude of the residual has exceeded the threshold, a one indicates that the magnitude of the sum of the residuals has exceeded the threshold, and a two indicates that it is time for an oil change.

HP-67/97 Program Listing

The HP-67/97 program listing is shown in listing 1. Since it requires 111 steps, the program can be recorded on side 1 of a magnetic card. A value of $r = 0.4$ has been incorporated in the program at steps 039 and 040. This choice is explained in the next section and in the example. Data storage requires primary registers 0 thru 9 and registers A, B, C, D, E, and I. The contents of these data registers can be recorded on side 2 of the card. Table 1 identifies data register contents, and table 2 gives instructions for the use of the program.

Program Calibration

When the filter is initialized, it is necessary to specify the initial values of the error covariance, $P_1(-)$, an estimate of your car's mileage, $\hat{x}_1(-)$, the plant noise variance, q, and the measurement noise variance, r. A reasonable initial guess at the quantities will cause the filter to converge to a good estimate within three updates. The two parameters which affect the filter's steady-state performance are r and q. It is recommended that you select $q = 0.02$ and $r = 0.4$ when you first begin to use the program. These values work well for both of my cars (which perform quite differently). The procedure used to select these quantities requires that you keep a record of mileage data for a number of updates. Try plotting z_k versus O_k for a few fill-ups. By virtue of equation 2, the variance of the measurements, σ_z^2, is r, provided the data does not contain a trend. If the plot appears to contain a trend, try

If you need M68000, Z8000, or 8086 Software, take it off our shelf.

Why wait up to 6 months for high quality 16-bit resident system software, when you can get it now?

Hemenway Associates can give you the software tools you need to get the most out of your 16-bit hardware. Because 8086, Z8000 and 68000 Systems Software is sitting on our shelves right now.

Single user operating systems, macro assemblers, text editors, floating point packages, multi-tasking operating systems, linking loaders and PASCAL compilers are all ready for immediate delivery.

You've heard about Hemenway Associates' system designs in the pages of EDN. But now you can have Hemenway-designed software for your 16-bit microprocessor. Our software is easily adaptable to any hardware configuration. From manufacturers evaluation boards to full-blown microcomputers. It's efficient, easy-to-use and backed by ongoing support.

So whether you're a microcomputer manufacturer, software developer or individual microcomputer owner, Hemenway has the software for you.

For the hard facts on Hemenway software, write or call: Hemenway Associates, 101 Tremont Street, Boston, Massachusetts 02108. Phone: 617-426-1931. TWX 710 321 1203. TELEX 921735.

Circle 170 on inquiry card.

HEMENWAY ASSOCIATES, INC.

When it comes to software, come to Hemenway.

Step	Instructions	Input Data/Units	Keys	Output Data/Units
1	Load side 1, magnetic card			
2	If updating GO TO 5, otherwise continue			
3	INITIALIZE: Enter plant noise, q	q/(mpg)^2	ENT	
	Beginning odometer reading, O_o	O_o/mi	ENT	
	Threshold for residual alarm, R_m	R_m/mpg	ENT	
	Threshold for sum of residuals alarm, $\|\Sigma R\|_m$	$\|\Sigma R\|$/mpg	E	
	Initial guess at the error covariance, $P_1(-)$	$P_1(-)$/(mpg)^2	ENT	
	Initial guess at the mileage, $\hat{x}_1(-)$	$\hat{x}_1(-)$/mpg	ENT	
	Value of $\Sigma(O_k - O_{k-1})$ at next oil change	MNOC/mi	R/S	Crd
4	Record data on side 2 of card END			
5	Load side 2 of card			
6	Enter total price of gasoline at fill-up	C_k/\$	ENT	
	Enter price per gallon	CG_k/\$	ENT	
	Enter odometer reading	O_k/mi	A	
	OUTPUTS: If $\|R_k\| > R_m$:			$\|R_k\|$/mpg
				R_m/mpg
				0.0000
	If $\|\Sigma R_k\| > \|\Sigma R\|_m$:			$\|\Sigma R_k\|$/mpg
				$\|\Sigma R\|_m$/mpg
				1.0000
	Actual mileage measured, z_k			z_k/mpg
	Predicted mileage, $\hat{x}_k(-)$			$x_k(-)$/mpg
	Residual, $R_k = z_k - \hat{x}_k(-)$			R_k/mpg
	Sum of residuals for $k \geq 3$			ΣR_k/mpg
	If time for oil change:			
	Elapsed mileage since initialization			$\Sigma(O_k - O_{k-1})$/mi
	Elapsed mileage at oil change interval			MNOC/mi
	(When this happens, change the oil, add the desired oil change interval to the contents of register P7 to get the new value of MNOC, and DO:	MNOC/mi	STO C	2.0000
7	Record data on side 2 of card END OPTIONAL:		f WDTA	Crd
8	When something causes $\|\Sigma R_k\| > \|\Sigma R\|_m$ to occur it is best to set P9 = 0 before recording data for next update: 0		STO 9	
9	You can compute your gasoline costs per mile traveled over the total miles traveled by:		RCL 8 RCL 7 ÷	\$/mile

Table 2: *Instructions and keypresses necessary for use with the mileage-predictor program.*

When you can't afford to buy wrong…

"Sorry, Hawkins, we simply can't keep you ***and*** *replace that non-expandable computer you bought. . . ."*

…you need Novell's NEXUS,™ the starter-priced computer system designed to grow with you.

BUYING A COMPUTER is a big decision. How much can you afford to spend? Will the system you're considering do the job? And what happens when your needs outgrow that first computer? Can it expand to handle increasingly larger workloads, or will you have to spend a fortune replacing it? Expandable computer systems are strictly big-league. They've *been* very expensive, and unless you've had *at least* $40,000 to spend they've been out of reach.

But, now, there's Novell's new NEXUS Series—an incredibly versatile, surprisingly inexpensive computer that expands into a multiple terminal-computer network system just by adding components as your growth requires. You can begin using your NEXUS computer the day it arrives, because it works with the widest assortment of proven software available in the industry today. Exclusive RAM-GUARD™ protection detects and corrects memory errors automatically as they occur—a feature no other comparably priced computer offers. NEXUS is the one starter-priced computer system you'll never have to replace!

If you're in the market for *any* computer, you can afford the NEXUS I. Since you *can't* afford to buy wrong, you can't afford to miss seeing, trying and learning all about NEXUS.

Call us toll-free and we'll set up a hands-on demonstration. We'll prove how NEXUS will take you all the way to the top. 800-453-1188

NOVELL
DATA SYSTEMS, INC.

1170 No. Industrial Park Drive, Orem, Utah 84057
Telephone: (801) 226-8202

Circle 279 on inquiry card.

Alarm Type	k	C_k	CG_k	O_k	z_k	$\hat{x}_k(-)$
—	0	9.91	0.889	77406.6*	—	—
0	1	8.77	0.889	77645.2	24.1865	28.0000*
—	2	5.06	0.879	77784.0	24.1117	24.4690
—	3	9.45	0.879	78045.0	24.2771	24.2925
—	4	8.40	0.899	78273.1	24.4121	24.2871
—	5	9.25	0.899	78519.6	23.9571	24.3230
—	6	8.10	0.899	78742.6	24.7502	24.2308
0,1**	7	9.00	0.919	78942.6	20.4222	24.3513
0	8	10.20	0.919	79182.8	21.6415	23.4871
—	9	8.26	0.929	79389.0	23.1913	23.0948
1,2**	10	10.35	0.949	79627.0	21.8224	23.1149
0,1**	11	11.32	0.949	79866.1	20.0447	22.8449
—	12	10.42	0.969	80108.4	22.5325	22.2798
0	13	9.89	0.979	80352.5	24.1632	22.3308
—	14	10.30	0.999	80580.4	22.1041	22.6997
—	15	10.70	0.999	80820.5	22.4168	22.5801
—	16	9.25	1.05	81021.3	22.7935	22.5473
0,1**	17	5.05	1.05	81098.3	16.0099	22.5967
0	18	11.80	1.07	81367.0	24.3652	21.2779

* Initialization values. Since the $\hat{x}_1(-)$ guess was wrong, a type-0 alarm occurred on the first fill-up ($k=1$). Other initialization data were: $q=0.02$, $P_1(-)=5$, $R_{max}=1.26$, $|\Sigma R|_{max}=2.53$, MNOC = 2000.

** When type-1 alarms occurred, ΣR_k was set to zero as suggested in the text.

Table 3: *Program input data and results (also see figure 3).*



Figure 3: *Plots of actual data provided to Kalman mileage predictor (see table 3) and the resulting mileage estimates. The filter program provided alarms that resulted in the following repairs:*

A: faulty vacuum hose replaced on carburetor
B: valve job
C: loose spark plug wire

Other interesting points on these plots are marked as follows:

0: indicates that the residual magnitude exceeds the alarm threshold
1: indicates that the magnitude of the sum of the residuals exceeds the alarm threshold
2: indicates that oil-change mileage has been reached or exceeded

Mileage measurements are indicated by a circle; mileage predictions are indicated by a cross.

linear regression to obtain a proper value of r.

Once a value of r is obtained, you must make a choice of q. The choice can be made either analytically or heuristically, but remember that the function of plant noise in the Kalman mileage predictor-monitor is to keep the filter from ignoring new data. At steady state (the value of k large) the effect of q on the error covariance and Kalman gain are given by the relations:

$$\lim_{k \to \infty} P_k(\pm) = \sqrt{rq} \qquad (8)$$

and:

$$\lim_{k \to \infty} K_k = \sqrt{q/r} \qquad (9)$$

respectively. The variance of the residuals is given by:

$$\sigma^2_{R_k} = \sqrt{rq} + r \qquad (10)$$

Equations 4 and 9 demonstrate that the larger the value of q, the more responsive the filter is to new data. However, equations 1 and 10 imply that the predictions, $\hat{x}_k(-)$, also become noisier as q increases. In addition, the ability of the filter to detect trends in the mileage data decreases, as indicated in equation 8.

Obviously, an optimization problem could be defined here. An elaborate simulation experiment could be designed to select a value of q that would cause the filter to adapt its estimate to track a step function change in the mean value of the measurements within so many updates while still producing an alarm on measurements containing a trend of so many miles per gallon per fill-up.

I prefer the heuristic approach. The idea is to select a sufficiently small q so that $\hat{x}_k(-)$ varies slowly with k when the car is operating properly and when driving conditions are similar. A value of $q = 0.02$ works well for both of my cars and my driving pattern. If I took my car on an extended trip where highway driving would predominate I would probably increase the value of q by, say, a factor of 10 for one or two fill-ups in

commodore

MEETING THE NEEDS OF BUSINESS AND PROFESSIONALS

COMMODORE 8032 COMPUTER

The Commodore 8032 Computer with 32K RAM offers a wide screen display to show you up to 80-character lines of information. Text editing and report formatting are faster and easier with the new wide-screen display. The 8032 features a typewriter styled keyboard with a separate numeric pad and BASIC 4.0 Operating System.

Call Toll Free For Price

COMMODORE 4040 DISK DRIVE

The CBM 4040 Dual Drive Floppy Disk is an intelligent 5¼" mini-floppy disk system with 343K net user storage capacity with 2.1 DOS

Call Toll Free For Price

The VIC-20 Personal Computer

The New VIC-20, which connects to any TV set, rivals the features of existing microcomputers selling at 4 or 5 times the price. The features include:

- color
- sound
- programmable function keys
- 5K memory expandable to 32K
- standard PETBASIC
- full-size typewriter keyboard
- graphics character set
- plug-in program/memory cartridges
- low-priced peripherals
- joystick/paddles/lightpen
- self-teaching materials



Call Toll Free For Price



COMMODORE 4022 TRACTOR PRINTER

The CBM 4022 80-Column Dot Matrix Tractor Printer enhances your business system by enabling you to print mailing lists, checks, invoices, and standard or customized business forms at 65 characters per second. The printer has full PET graphics, variable line spacing, programmable character and character enhancement with a 6 x 7 dot matrix.

Call Toll Free For Price

COMMODORE 8050 DISK DRIVE

The CBM 8050 Dual Drive Floppy Disk is an enhanced version of the intelligent CBM 4040 Disk Drive. The CBM 8050 has all the features of the 4040 as well as providing more powerful software capabilities and nearly one megabyte of online storage capacity. Like the 4040, the 8050 2.1 DOS is incorporated in the drive as opposed to using valuable memory.

Call Toll Free For Price

No Risk, No Deposit On Phone Orders, COD or Credit Card, Shipped Same Day You Call*

* on all in stock units

(800) 233-8950

VISA master charge

Computer Mail Order (717) 323-7921
501 E. Third St., Williamsport, PA 17701

Circle 76 on inquiry card.

Glossary

The following glossary of terms is provided to clarify the meaning of some of the specialized terms used in this article. Definitions have been simplified to avoid the introduction of additional terms.

Convergence: *A Kalman filter may be said to converge when the magnitude of the envelope of the residuals is a monotonically decreasing function of the number of filter updates.*

Error covariance: *In intuitive terms, a statistical estimate of the error in the state vector.*

Gaussian noise: *Random errors that add algebraically to quantities of interest, such as measurements (z_k), are frequently considered to have a Gaussian probability density with a zero-mean value. For example, the expression:*

$$f(v_k) = \frac{1}{\sqrt{2\pi r}} \exp\left(\frac{-v_k^2}{2r}\right)$$

is the probability density for v_k, the measurement noise term of equation 2, which has a variance of r and a mean value of zero. Zero-mean random variables are said to be unbiased. A probability density equation gives the probability that a random variable (v_k in the above equation) assumes a particular value.

Kalman gain: *A function of the error covariance (the measurement matrix which relates the measurement vector to the state vector) and the measurement noise covariance (or variance in the case of a filter with a single element measurement vector). It is a measure of the confidence the filter places in the current measurement. The smaller the gain, the less confidence the filter has in the measurement.*

Least-squares sense optimum estimator: *An algorithm that produces estimates for which the sum of the squares of the errors in the estimates is minimum.*

Linear Kalman filter: *A filter in which the equations expressing the measurements in terms of the elements of the state vector are linear equations.*

Measurement noise: *A random unbiased error which corrupts the measurements.*

Overdetermination/underdetermination: *If there are more elements in the measurement vector than in the state vector, the Kalman filter is overdetermined. If there are fewer elements in the measurement vector than in the state vector, the Kalman filter is underdetermined.*

Plant noise: *An additive unbiased random quantity representing some actual physical process which causes the state vector to have statistical variability. Plant noise has the effect of preventing the Kalman gain from approaching zero as the number of updates increases. Kalman filter designers sometimes use this effect to implement an adaptive filter. In such filters, the sequence of residuals is tested for bias. When bias is detected, artificial plant noise is introduced into the filter. This increases the Kalman gain, which in turn causes the filter to increase its confidence in the incoming measurements when compared to its predictions. When the residuals are again unbiased, the plant noise is reduced.*

Regression analysis: *A process by which a least-squares optimum curve is fit to a set of data points. When the curve is a straight line, the process is called linear regression analysis.*

Residual: *A Kalman filtering term that denotes the difference between the actual measurement vector and the predicted measurement vector.*

Standard deviation: *A statistical term that is a measure of the expected or observed spread of data points about the mean value. Quantitatively, two thirds of the data points are within one standard deviation, plus or minus, of the mean value.*

State vector: *Any set of quantities sufficient to completely specify the unforced motion of a dynamic system.*

Variance: *The variance of a set of n measurements, x_i (i = 1 to n), is given by the formula:*

$$\text{variance} = \sum_{i=1}^{n} \frac{[(x_i - \bar{x})^2]}{(n-1)!}$$

where $\bar{x}$ is the mean value of the set. The *square root of the variance is called the standard deviation.*

**Though the filter's output is based upon all data entered since initialization, and data is not saved. Thus, the amount of memory required to produce successive estimates is minimal and constant — an essential feature of algorithms implemented on the HP67/97.*

MODEL II

26-4002
64K 1 Drive
$3440.00

26-4160 1 Drive Exp	$1034.00
26-4161 2 Drive Exp	1574.00
26-4162 3 Drive Exp	2114.00
26-4530 Scripsit II	265.00
26-4512 Profile II	162.00
26-4511 Visicalc II	265.00
26-4501 Gen Ledger	180.00
26-4506 Mail List	72.00

$ DISCOUNT $

TRS-80®

DEALER A301

COMPUTER SPECIALISTS

CALL US. . .

SAVE MONEY

We carry the full line of TRS-80 Computers. All other R.S. software, furniture, and accessories at discount from catalog price. We stock most items to assure you fast delivery and save you money.

26-1140 Expansion Interface	$249.00
26-1141 16K Exp. Interface	359.00
26-1142 32K Exp. INterface	469.00
26-1145 RS232C Board	84.00
26-1160/1 Mini Disk Drive	419.00
26-1563 Scripsit-Disk	79.00
26-1566 Visicalc	83.00

* * * * * ***PRINTERS*** * * * * *

26-1155 Quick Printer	187.00
26-1167 9½ Dot Matrix Printer	360.00
26-1166 Line Printer VI	1080.00
26-1158 Daisy Wheel II	1799.00
26-1165 Line Printer V	1710.00

MODEL III



26-1061 4K I	$629.00
26-1062 16K III	865.00
26-1063 32K III W/2 Drives, RS232	2225.00

COLOR



26-3001 4K	$353.00
26-3002 16K Ext. Basic	533.00
26-3008 Joysticks	22.50
26-3010 Color Video	353.00
26-1206 Recorder	54.00

PRINTERS

CENTRONICS

BEST PRICES

Fast 100 CPS Centronics 730-1A Printer	$577.00
Text Quality Centronics 737-1 Printer	$737.00

Pocket Computer



26-3501 1.9K P.C	$221.00
26-3503 Cassette IF	45.00
14-812 Recorder	72.00

commodore

AUTHORIZED DEALER
CALL FOR PRICES

ALL POCKET AND COLOR COMPUTER SOFTWARE SOLD AT DISCOUNT

WRITE US FOR A
FREE CATALOG

1-800-841-0860 Toll Free Order Entry

MICRO MANAGEMENT SYSTEMS, INC.

No Taxes on Out Of State Shipments

Immediate Shipment From Stock on Most Items

DOWNTOWN PLAZA SHOPPING CENTER
115 C. SECOND AVE. S.W.
CAIRO, GEORGIA 31728
(912) 377-7120 Ga. Phone No. & Export

TRS-80 is a registered trademark of the Tandy Corp.

R.S. 90 Day Limited Warranty
F-48 Form Provided

Largest Inventory In The S.E. U.S.A.

Circle 236 on inquiry card.

order to allow the filter to adapt its estimate to the anticipated improvement in gasoline mileage.

Example

Figure 3 shows the measurement data, z_k, as a function of k for my 1973 MGB. Also shown are significant maintenance events during the time period covered by the data. Until the thirteenth fill-up, I did not rely on the Kalman mileage predictor-monitor because all initialization data was based on speculation. On the twelfth fill-up, I calibrated the filter using the data from $k = 5$ through $k = 12$. Since this data contains a trend, I used linear regression to obtain a value of $r = 0.4$ mpg². I then reprocessed the data using $r = 0.4$, $q = 0.02$, $P_1(-) = 5$ mpg², $x_1(-) = 28$ mpg, $R_{max} = 2\sqrt{0.4}$, and $|\Sigma R|_{max} = 4\sqrt{0.4}$.

Figure 3 indicates the occurrence of each type of alarm and superimposes the predictions, $x_k(-)$, on the plot of z_k versus k. The filter alarms will indicate the need for maintenance at the proper time. The history of input and output data for the MGB are given in table 3.

One powerful feature of the Kalman filtering technique lies in its use of a recursive algorithm. Though the filter's output is based upon all data entered since initialization, the data is not saved. Thus, the amount of memory required to produce successive estimates is minimal and constant—an essential feature of algorithms implemented on the HP-67/97. The filter program monitors gradual degradation of fuel economy, despite the action of noise and variations due to external sources. While other methods (plotting a graph or regression analysis) could be used, the Kalman technique is elegantly simple. ■

References

1. Kalman, R E. "A New Approach to Linear Filtering and Prediction Problems." *J Basic Engineering*, March 1960, pages 35 thru 46.
2. Gelb, Arthur et al. *Applied Optimal Estimation*. Cambridge MA: MIT Press, 1974. (This text is recommended as a practical introduction to Kalman filtering theory.)

PERIPHERALS
FOR ATARI 400 & 800

16K MEMORY BOARD: AT-16
- 16K 4116 RAM (200NS)
- Assembled and tested
- No modifications - hardware or software
- Compatible with Atari 800
- One year warranty
- Price: $119.50

32K MEMORY BOARD: AT-32
- 32K 4116 RAM (200NS)
- Assembled and tested
- No modifications - hardware or software
- Compatible with Atari 400/800
- One year warranty
- Price: $199.50

PARALLEL PRINTER CABLE: ATC-1
- Pre-tested
- 3′ length
- Centronics compatible
- DB15 to Amphenol 57-30360
- Price: $39.50

SERIAL (RS-232) PRINTER CABLE: ATC-2
- Pre-tested
- 3′ length
- DB15 to DB25 connectors
- Price: $39.50

EXTENDER BOARD: ATB-1
- Raises board 3 inches
- Ideal for prototype boards
- Price: $39.50



Available
at your local computer dealer
or direct from Microtek Peripherals.

MPC
MICROTEK PERIPHERALS CORP.
9514 CHESAPEAKE DR., SAN DIEGO, CA 92123
(714)278-0630 TWX-910-335-1269

Atari, Atari 400 and Atari 800 are trademarks of Atari, Inc.

Circle 253 on inquiry card.

Circle 287 on inquiry card.

Circle 287 on inquiry card.

The Infamous Traveling-Salesman Problem

A Practical Approach

Richard R Parry
38 W 255 Deerpath Rd
Batavia IL 60510

Howard Pfeffer
4610 Lake Trail Dr
Lisle IL 60532

You may not need a computer to tell you the shortest distance between two points, but you may need one if you are trying to find the shortest route from city to city when many are involved.

This problem is commonly known as the traveling-salesman problem and is referred to by mathematicians and computer scientists as an NP-complete (nondeterministic polynomial) problem.

The difficulty lies in the number of different routes a salesman can take from city to city. If only five cities are involved, the number of different routes is a manageable 4! (4 factorial or 24). But the number of routes increases exponentially. So with nine cities, for example, the number of routes jumps to 8! (5040). And with 12 cities, the number of possibilities for the trip reaches a staggering 40 million. That's a lot of calculations—even for a computer. In fact, it is not too hard to imagine a traveling-salesman problem that would take the world's most powerful computer centuries to solve.

The fact that NP-complete problems take so long to solve is both a burden and a blessing. The obvious disadvantage is that it is difficult or impossible to solve some very useful problems. But it is a blessing as well since it lends itself to the design of systems to encode information for security purposes. This fact comes at a time when computer fraud is increasing.

Interestingly, the traveling-salesman problem was discussed in an article entitled, "What Computers Cannot Do " (BYTE, January 1980, page 100). Indeed, there is no known way, at present, to solve all traveling-salesman problems in a simple and elegant manner or in a relatively short time. Even the recent breakthrough by the Russian mathematician Leonid G Khachiyan, which solves the linear-programming class of problems, leaves the traveling-salesman problem unsolved. (See "Khachiyan's Algorithm, Part 1: A New Solution to Linear Programming Problems," BYTE, August 1980, page 198, and "Khachiyan's Algorithm, Part 2: Problems with the Algorithm," BYTE, September 1980, page 242, by G C Berresford, A M Rockett, and J C Stevenson.) However, with a limited number of towns, the traveling-salesman problem is most certainly solvable.

In this article, we discuss a BASIC program that can solve a 12-city problem in less than an hour—not bad, considering that there are 40 million possibilities and that the program was written in BASIC on an 8-bit microcomputer. (Unless otherwise noted, execution times stated are based on a SwTPC [Southwest Technical Products Corporation] 6800 computer system with a 1 MHz system clock using TSC [Technical Systems Consultants] BASIC.)

We loaded the program into a Control Data Cyber 175 large-scale computer to see what it could do with the traveling-salesman problem. The 12-city problem, which requires 47 minutes on the microcomputer, was solved by the Cyber in less than four seconds. When a 16-city problem was given to the Cyber, the execution time was 41 seconds. This is truly astounding, considering that there are 1.3 trillion possibilities for this trip.

Several characteristics of the Cyber account for its speed. Perhaps the greatest gain comes from the fact that it uses a BASIC *compiler* instead of an interpreter. Its 60-bit word length, hardware arithmetic manipulation,

and faster cycle rate are other factors that increase its speed. But such a powerful computer is not the ultimate answer to solving NP-complete problems. Even the Cyber would be hard-pressed to solve a 50-city problem in our lifetime.

About the Program

We wanted to develop a program that would be useful in many ordinary situations. For example, while it's possible that you might have to visit 100 or more points in one trip, it's not very likely. It seemed that if we could develop a program that would compute the shortest trip for an 11- or 12-city problem in less than an hour, then the program could solve a large number of real-life situations. Also, we wanted to write a program that could be used on virtually every computer system. (This meant that we had to use BASIC.) But this hampered our goal of fast execution time because BASIC is ordinarily interpreted and, therefore, slow. As previously noted, execution time would be much faster if the program could be compiled.

We first tried to solve the traveling-salesman problem by using a sampling technique in which only a few of the possibilities are calculated. From this sample, the best route for the trip is the answer. Sampling seemed a viable solution; it would certainly reduce the total execution time because all possibilities are not evaluated. The technique does not yield the best route for a trip (at least not normally), but we hoped it would give a good solution.

We were disappointed by the results of this approach, however. Looking back, it is easy to see why: if only a small percentage of the possibilities are examined, on the average, the probability of finding the best route is also very small. In addition, even if only 1% of the possibilities of a 12-city trip are examined, the total that must be tried is still very large (400,000). The weaknesses of sampling were further illustrated by a simple experiment with friends, which showed that a

dBASE™ II vs. the Bilge Pumps.

by Hal Pawluk

We all know that bilge pumps suck.

And by now, we've found out—the hard way—that a lot of software seems to work the same way.



So I got pretty excited when I ran across **dBASE II**, an assembly-language relational Database Management System for CP/M. It works! And even a rank beginner like myself got it up and running the first time I sat down with it.

If you're looking for software to deal with your data, too, here are some tips that will help:

Tip #1: Database Management vs. File Handling:

Any list or collection of data is, loosely, a data base, but most of those "data base management" articles in the buzzbooks are really about file handling programs for specific applications. A real Database Management System gives you data and program independence (no reprogramming when data changes), eliminates data duplication and makes it easy to turn data into information.

Tip #2: Assembly Language vs. BASIC:

This one's easy: if you're setting up a DBMS, you're going to be doing a lot of sorting, and Basic sorts are s-l-o-w. Run a benchmark on a Basic system like S*-IV against a relational DBMS like **dBASE II** and you'll see what I mean. (But watch it: I've also seen one extremely slow assembly-language file management system.)

Tip #3: Relational vs. Hierarchal & Network DBMS.

CODASYL-like hierarchal and network systems, around since the 1960's, are being phased out on the big machines so why get stuck with an old-fashioned system for your micro? A relational DBMS like **dBASE II** eliminates the predefined sets, pointers and complex data structures of a CODASYL-type DBMS. And you don't need to be a programmer to use it.

dBASE II vs. everything else.

dBASE II really impressed me.

Written in assembly language (with no need for a host language), it handles up to 65,000 records (up to 32 fields and 1000 bytes each), stores numeric data as packed strings so there are no round-off errors, has a super-fast multiple-key sort, and supports ISAM based on B* trees.

You can use it interactively with English-like commands (DISPLAY 10 PRODUCTS), or program it (so when you've set up the formats, your secretary can do the work). Its report generator and user-definable full screen operations mean that you can even use your existing forms.

And if all this makes your mouth water, but you've already got all your data on a disk, that's okay: **dBASE II** reads your ASCII files and adds the data to its own database.

Right now, I'm using **dBASE II** with my word processor for budgeting, scheduling and preparing reports for my clients.

Next come job costing, time billing and accounting.

An Unheard-of Money-Back Guarantee.

dBASE II is the first software I've seen with a full money-back guarantee.

To check it out, just send $700 (plus tax in California) to Ashton-Tate, 3600 Wilshire Blvd., Suite 1510, Los Angeles, CA 90010. (213) 666-4409. Test **dBASE II** doing your jobs on your computer for 30 days. If, for some strange reason, you don't want to keep it, send it back and they'll refund your money.

No questions asked.

They know you don't need your bilge pumped.

Ashton-Tate

person could easily outperform the computer.

We were convinced that an exhaustive search of all possible routes was necessary. This meant that in the 12-city problem all 40 million routes would have to be evaluated. Extrapolation from a simple 5-city problem that was run using an exhaustive-search program indicated that the SwTPC computer would require 40 days to solve the 12-city problem. This falls far short of our original goal of solving it in less than an hour.

The solution to reducing the execution time lies in a technique similar to that used in computer chess programs. It is basically a *decision-tree-pruning* method. In the case of the traveling-salesman problem, the idea is to skip over newly examined routes that are poorer than the best route found up to that point.

For example, assume a 6-city problem, with city 1 the starting and ending point. Also, assume that the path thru cities 1, 2, 3, 4, 5, 6, and back to 1 has been calculated to require 400 miles. (This may or may not be the shortest route; it merely represents the shortest path found thus far.) The program must now generate another path and evaluate it.

Assume the new path is 1, 4, 2, 3, 5, 6, 1. If after evaluating the distance from 1 to 4 to 2 to 3, the accumulated distance is found to be greater than 400 miles, there is no need to continue the evaluation. Continuing would only prove what we already know—that this path is not the shortest. More important, it means we can skip the permutation 1, 4, 2, 3, 6, 5, 1.

Now suppose we know that the shortest possible route involving *any three cities* then ending at city 1 covers 150 miles. We could then say that if the distance from 1 to 4 to 2 to 3 is greater than 250 miles, there is no point in calculating further. The distance from 3 thru two cities to 1, regardless of the choice of the intermediate cities, will add at least 150 miles to the 250 miles already calculated. The total trip must be at least 400 miles, so it cannot be shorter than a route we already know.

Discover

the most organized (and inexpensive) way to keep up with what's new in computer techniques and management—

The Library of Computer and Information Sciences

(Publishers' Prices shown)

70230. PRINCIPLES OF SOFTWARE ENGINEERING AND DESIGN. *Marvin V. Zelkowitz et al.* $22.95

41785. DEBUGGING SYSTEM 360/370 PROGRAMS USING OS AND VS STORAGE DUMPS. *D.H. Rindfleisch.* $24.95

60385. MANAGING THE SYSTEMS DEVELOPMENT PROCESS. *Charles L. Biggs et al.* Provides every computer professional with all the management tools and procedures necessary to keep the systems development process under control, on budget, and on time. $24.95

79240. SOFTWARE PSYCHOLOGY: Human Factors in Computer and Information Systems. *Ben Shneiderman.* $24.95

81845. SYSTEM/370 JOB CONTROL LANGUAGE. *Gary DeWard Brown.* Softcover. $13.50

84238. 370/360 ASSEMBLER LANGUAGE PROGRAMMING. *Nancy Stern et al.* A step-by-step guide from the basics through efficient sophisticated coding. 516 pages. 8¼" x 11" format. Softbound. $19.50

70745. A PROGRAMMER'S GUIDE TO COBOL. *William J. Harrison.* $18.95

70725-2. THE PROGRAMMER'S ANSI COBOL REFERENCE MANUAL. *Donald A. Sordillo. Counts as 2 of your 3 books.* $27.95

40010. COMPUTER POWER FOR THE SMALL BUSINESS. *Sippl and Dahl.* A complete guide to micro and mini computers. $15.95

80847. STRUCTURED MICROPROCESSOR PROGRAMMING. *Morris Krieger et al.* How to use the 8080/8085 microprocessor instruction set and more. $20.00

42213. DICTIONARY OF BUSINESS AND MANAGEMENT. *Jerry M. Rosenberg.* Over 8000 entries. $24.95

59920. MANAGEMENT: Tasks, Responsibilities, Practices. *Peter F. Drucker.* The skills, techniques and tools a good executive needs to stay effective in modern management. 839 pages. $17.50

41625. DATABASE: A PROFESSIONAL'S PRIMER. *David Kroenke.* Covers every aspect of data base concepts, systems and applications. $24.95

79155. SOFTWARE INTERPRETERS FOR MICROCOMPUTERS. *Thomas C. McIntire.* $23.95

34130. THE APPLICATION DESIGN HANDBOOK FOR DISTRIBUTED SYSTEMS. *Robert L. Patrick.* With 186 specific design hints. $19.95

Take any 3 books for only $1.00 each (values to $74.90)

You simply agree to buy 3 more books—at handsome discounts—within the next 12 months.

63187. MOVING ON UP: ADVANCE YOUR CAREER BY CONTROLLING YOUR OWN PROMOTIONS. *Ted Pollock.* $9.35

56360. INTRODUCTION TO PASCAL. *Welsh and Elder.* $14.95

79167. SOFTWARE RELIABILITY GUIDEBOOK. *Robert L. Glass.* Analysis of technical tools available for software design and implementation. $18.95

51955-2. A GUIDE TO THE SUCCESSFUL MANAGEMENT OF COMPUTER PROJECTS. *Hamish Donaldson. Counts as 2 of your 3 books.* $34.95

38968. THE COBOL ENVIRONMENT. *Grauer and Crawford.* $20.95

43735. THE EFFECTIVE EDP MANAGER. *Michael R. Frank.* A sound blueprint to help every EDP manager cope with today's changing environment. $17.95

49295-2. FUNCTIONAL PROGRAMMING: Application and Implementation. *Peter Henderson.* Rigorous and comprehensive. *Counts as 2 of your 3 books.* $28.00

80155. STANDARDIZED DEVELOPMENT OF COMPUTER SOFTWARE, Part II. *Robert C. Tausworthe.* A detailed set of rules for software implementation. Contains extensive appendices. $21.95

37206. THE C PROGRAMMING LANGUAGE. *Kernighan and Ritchie.* Softcover. $11.95

79150-2. SOFTWARE ENGINEERING. *Jensen and Tonies.* All phases of software engineering with the emphasis on real applications in industry. *Counts as 2 of your 3 books.* $27.50

42053-2. DESIGNING A DISTRIBUTED PROCESSING SYSTEM. *Hamish Donaldson.* Includes file strategy, communication networks and workflow design. *Counts as 2 of your 3 books.* $34.95

65730. 1001 THINGS TO DO WITH YOUR PERSONAL COMPUTER. *Mark Sawusch.* With possible applications, sample programs, ideas for simulating other electronic devices and much more. $12.95

50045-2. GAME THEORY: Mathematical Models of Conflict. *A.J. Jones.* A brilliant introduction to the science. *Counts as 2 of your 3 books.* $45.00

62641. MICROPROCESSORS: From Chips to Systems. *Rodnay Zaks.* $25.00

—EXTRAORDINARY— VALUE!



44900-3. THE ENCYCLOPEDIA OF COMPUTER SCIENCE. *Edited by Ralston and Meek.* Monumental 1,550-page volume covers software, hardware, languages, programs, systems, mathematics and much more. Over 1,000 charts, tables and illustrations. *Counts as 3 of your 3 books.* $60.00

If the reply card has been removed, please write to **The Library of Computer and Information Sciences Dept. 7-AP5, Riverside, N.J. 08075** to obtain membership information and application

In fact, if we knew that the shortest possible route involving any *five* cities, then ending at city 1, covers 300 miles, we would first ask if the distance from 1 to 4 is greater than 100 miles (400 − 300). If it is, we need not bother with the 24 permutations:

1,4,(2,3,5,6),1
1,4,(2,3,6,5),1
1,4,(2,5,3,6),1
.
.
.

Of course these shortest-possible-trip values (stored in an array called M in the program) are not obvious and must be calculated. Indeed, their calculation forms the solution to the problem. We first calculate M(2), which is the shortest possible trip touching any city other than city 1 and ending at city 1. Next we calculate M(3), the shortest route involving *two* cities then ending at city 1, using M(2) to reduce the number of permutations. Then M(2) and M(3) help in calculating M(4), and so on. Calculating each successive element, M(N), is approximately N times as complex as calculating the previous element. Because of powerful pruning, the time that is saved in calculating the higher-order elements of M more than makes up for the time spent in earlier M-element calculations.

In the 6-city problem, after calculating M(2) thru M(5), we slightly modify the routine to account for a fixed starting point. The resulting answer is the best route for the traveling salesman.

It is largely thru use of this technique that the 12-city problem requires less than one hour; it would normally require 40 days if all routes were fully evaluated. Put another way, of the 40 million possibilities, perhaps only several thousand need to be completely evaluated.

The execution time can be reduced further by converting specific numeric variables to intergers. The program is shown in listing 1 using standard floating-point variables (to allow it to be applicable to most

DEALERS: By now you know that it takes . . . . .

SOFTWARE
TO SELL
COMPUTERS

and International Micro Systems can provide you with the largest selection of quality business applications ever developed for the microcomputer industry.

If you are just looking for a G.L., A/P, and Payroll, you can find them in a dozen ads in this magazine. But thers's a much bigger market for micros out there than that. Where can you find a fully interfaced Wholesale/Retail Distribution System? How about Manufacturing Inventory Control including Production Scheduling & Control. See that one anywhere else? Maybe your market is Medical/Dental and IMS has the full systems there too. You can't sell computers without software and IMS has the finest selection of software available for you. Each system has been developed by the IMS professional staff and we support what we sell.

But thats not all. International Micro Systems has the strongest dealer marketing plan in the industry. With our . . . . .

$245 Dealer Demo System.

we put all the software shown below in your office or store ready to demo to your prospects and we include the promotional material and our unique video sales presentation to help you move systems. Give us a call or drop us a card and let us show you what selling business systems should be all about.

Financial Systems
- GL, A/P, A/R
- Payroll
- Cash Receipts/Disb.
- Job Costing
- Mailing List Mgmt.

Medical/Dental
- Office.Scheduler
- Patient Billing & A/R
- Insurance Forms

Governmental/Educational
- Student Record Keeping and Scheduling
- Fund Accounting

Wholesale Distribution System
- Purchasing & Receiving
- Inventory Control
- Invoicing & Receivables
- Salesman Comm. Reporting
- Backorder Management

Manufacturing Inventory Control
- Finished Goods Inventory Mgmt.
- Parts Inventory Mgmt.
- Parts Purchasing & Receiving
- Bill of Material
- Production Scheduling

INTERNATIONAL
MICRO
SYSTEMS

For details on our demo special, contact us at:
8425 Quivira Road, Lenexa, Kansas 66215
Phone: (913) 888-8330

Circle 188 on inquiry card.

readers' systems). Those with a version of BASIC supporting integer variables (eg: TRS-80 Level II and TSC Extended BASIC) may wish to alter the program to decrease the execution time by about 15%. All numeric variables may be changed to integers except the arrays R and A, and the scalar variables X1, Y1, X2, Y2, XT, YT, ZT, and TP. The percent sign (%) is the standard symbol used to indicate an integer variable in BASIC. Therefore, all references to elements of T may be changed to T%, and, in like manner, all references to elements of K may be changed to K%.

How to Use the Program

In this section we discuss two examples. Each illustrates certain features of the program and how they are used. In listing 2, we assume that a traveling salesman is responsible for visiting 12 cities in Illinois, in no particular order.

The program begins by prompting the user to supply the number of destinations to be visited, in this case 12. The program then gives the user three methods for entering the location of the cities. The first method allows the user to supply the location of the cities in rough polar coordinates, using a distance from a reference location and an angle in the form of a map heading (ie: N, S, NNW, etc).

The second method allows the user to supply the location of the cities' polar coordinates, using a distance from a reference location and an angle from a reference direction expressed in degrees.

Both of these methods force the user to supply the location data with respect to a reference. In listing 2, the reference is the city of Chicago. Any point may be a reference. In fact, the reference point need not be one of the cities in the problem. However, there must be only one reference point. With the data supplied exclusively thru these methods, the program constructs an "inter-destination" table, which gives the distance from every city to every other city. All computed

Text continued on page 284

Listing 1: *The source listing for the traveling-salesman program in TSC BASIC. All variables are shown as floating-point variables. However, changing specific variables to integer-type will decrease the execution time by about 15%. A copy of the program is available on a 5-inch floppy disk for those using a compatible computer system.*

```
 10 INPUT "HOW MANY DESTINATIONS "; N
 20 IF N<4 THEN PRINT "TOO FEW TOWNS, DO IT YOURSELF!" : GOTO 10
 30 DIM D(N,N), T(N+1 ), C(N+1 ), K(N+1 )
 40 DIM N$(N), R(N), A(N), A$(N), M(N)
 50 REM *******************************************
 60 REM * INSTRUCTIONS FOR SELECTING INPUT METHOD *
 70 REM *******************************************
 80 PRINT:PRINT
 90 PRINT "TYPE 1   IF YOU WANT TO INPUT THE ANGLE AS MAP DIRECTIONS"
100 PRINT TAB(9);"(E.G. SW, NNW, E, ENE ETC.)"
110 PRINT
120 PRINT "TYPE 2   IF YOU WISH TO INPUT THE ANGLE USING POLAR COORDINATES"
130 PRINT TAB(9);"(E.G. 0 DEGREES=EAST, 270 DEGREES=SOUTH ETC.)"
140 PRINT : PRINT "TYPE 3   IF YOU WISH TO INPUT ALL DATA VIA THE"
150 PRINT TAB(9);"INTER-DESTINATION TABLE."
160 PRINT : INPUT "METHOD 1, 2, OR 3 "; IM
170 IF IM<>1 AND IM<>2 AND IM<>3 THEN 160
180 IF IM=3 THEN 590
190 REM **** CONSTRUCT INPUT TABLE
200 FOR M=1 TO N
210 GOSUB 2490
220 NEXT M
230 REM **** DISPLAY INPUT DATA TABLE
240 PRINT : PRINT
250 PRINT TAB(15); "INPUT DATA TO BE USED"
260 PRINT TAB(8); "DESTINATION             DISTANCE         BEARING"
270 FOR M=1 TO N
280 IF IM=1 THEN 300
290 PRINT M; ". "; N$(M); TAB(32); R(M); TAB(49); A(M) : GOTO 310
300 PRINT M; ". "; N$(M); TAB(32); R(M); TAB(49); A$(M)
310 NEXT M
320 REM ************************************
330 REM * EDIT MODE FOR EDITING INPUT DATA *
340 REM ************************************
350 INPUT "DO YOU WANT TO EDIT ANY (Y/N) "; Q$
360 IF LEFT$(Q$,1)="N" THEN 430
370 PRINT : PRINT "TYPE 0 TO END EDITING WHEN ASKED 'WHICH ONE'. " : PRINT
380 PRINT : INPUT "WHICH ONE "; M
390 IF M=0 THEN 230
400 IF M<1 OR M>N THEN 380 ELSE GOSUB 2490
410 GOTO 380
420 REM *************************************
430 REM * CONSTRUCT INTER-DESTINATION TABLE *
440 REM *************************************
450 FOR M=1 TO N-1
460 Y1=R(M) * SIN(A(M)*.01745329)
470 X1=R(M) * COS(A(M)*.01745329)
480 FOR L=M+1 TO N
490 Y2=R(L) * SIN(A(L)*.01745329)
500 X2=R(L) * COS(A(L)*.01745329)
510 IF X1>X2 THEN XT=X1-X2 ELSE XT=X2-X1
520 IF Y1>Y2 THEN YT=Y1-Y2 ELSE YT=Y2-Y1
530 ZT=SQR(XT*XT + YT*YT)
540 D(M,L)=ZT : D(L,M)=ZT
550 NEXT L
560 NEXT M
570 GOTO 680
580 REM ************************************************************
```

Listing 1 continued on page 264

BASIC∅9™
has a dual personality.

One craves meat-and-potatoes BASIC.

The other prefers Programme ala Pascal.

Some people say BASIC∅9 is really a PASCAL in disguise, others say it's still BASIC. You'll understand this delightful dilemma when you look at both versions of the "bubble sort" program shown below: both can be run by BASIC∅9. The program on top is unstructured and hard to understand, but it's traditional BASIC. The program on the bottom is well-structured and easy to follow, a virtue of PASCAL. With BASIC∅9 you can program either way, or mix the best of both. It's like getting two languages for the price of one.

SORT AN ARRAY
IN ASCENDING SEQUENCE

```
90   DIM A(5)
100  I=5
110  IF I=1 THEN 200
120  FOR J=1 TO I-1
130  IF A(J)<=A(J+1) THEN 170
140  T=A(J+1)
150  A(J+1)=A(J)
160  A(J)=T
170  NEXT J
180  I=I-1
190  GOTO 110
200  RETURN
```

```
DIM array(5)
outer=5
WHILE outer> 1 DO
  outer=outer-1
  FOR inner=1 TO outer
    IF array(inner)>=array(inner+1) THEN
      temp=array(inner+1)
      array(inner+1)=array(inner)
      array(inner)=temp
    ENDIF
  NEXT inner
ENDWHILE
RETURN
```

Makes programs better

BASIC∅9 has five kinds of loop structures: WHILE . . DO, REPEAT . . UNTIL, LOOP . . ENDLOOP, FOR . . NEXT and IF . .THEN . . ELSE. If one of the five built-in data types (byte, integer, real, string, and boolean) doesn't suit the problem, you can make a new one of your liking with the TYPE statement. Need a tree, linked list, or symbol table? Complex non-rectangular data structures using any combination of data types are easy to define. Modular programming breaks down large programs to smaller, more manageable elements. BASIC∅9 lets you create independent program modules called "procedures" with local variables for recursion plus parameter passing to any other BASIC∅9 or machine language procedure. There is a complete set of statements for device-independent sequential or random I/O, plus a superlative PRINT USING system.

Makes programs faster

No full-feature BASIC for any 8-bit microprocessor is faster than BASIC∅9, because it is an interactive compiler. As each program line is entered, it is instantly compiled to a smaller, faster form. Because BASIC∅9 automatically converts programs back to original "source" form for listing, it is as friendly and easy-to-use as traditional interpreter BASICs. Each procedure can be independently compiled to position-independent, reentrant, ROMable format. Microware® developed a new ultra-fast 9-digit-accuracy floating point math system just for BASIC∅9. And if that's still not fast enough, there's BYTE and INTEGER arithmetic.

Features that make programs easier to write

The compiler is integrated with a full-feature string AND line-number oriented text editor. If you make a mistake, BASIC∅9 tells you instantly. String-oriented commands such as search, change, change all occurances, delete, and insert can be used on programs with or without line numbers. There's an automatic line renumbering function too.

Features that make programs easy to test

Debugging often takes longer than writing a program. That's why BASIC∅9's integral high-level debugger sets it apart from all other compiled OR interpretive languages. The TRACE command shows you each statement executed in BASIC form, plus the result of any expression evaluation. STEP lets you run one or more statements at a time. LET and PRINT allow you to examine or change the values of variables, by name. STATE lists procedure calling order. And there are nine other debug commands. If you need to correct a program, you can edit, recompile, and rerun it in seconds.

Microware® software is available for most popular 6809 computer systems. Source listings and yearly maintenance update service are sold separately for most programs.

Write or call for our free catalog. We accept phone orders and MasterCard and VISA orders.

MICROWARE®
Microware Systems Corporation
5835 Grand, Des Moines, Ia 50312
(515) 279-8844 TWX 910-520-2535

For compatible hardware see **GIMIX** ad on page 56.

Circle 254 on inquiry card.

Listing 1 continued:

```
590 REM * INPUT VIA INTER-DESTINATION TABLE, GET DESTINATION NAMES *
600 REM ************************************************************
610 FOR M=1 TO N
620 PRINT M; ", NAME OF DESTINATION ";
630 INPUT N$
640 N$(M)=N$
650 NEXT M
660 PRINT : GOTO 730
670 REM ***********************************
680 REM * DISPLAY INTER-DESTINATION TABLE *
690 REM ***********************************
700 INPUT "DO YOU WANT TO EDIT OR EXAMINE THE INTER-DESTINATION TABLE "; Q$
710 IF LEFT$(Q$,1)="N" THEN 1080
720 PRINT : PRINT
730 PRINT TAB(15); "**** INTER-DESTINATION TABLE ****"
740 PRINT TAB(14); "(VALUES ROUNDED TO NEAREST INTEGER)"
750 FOR M=1 TO N
760 PRINT TAB(5*M-1); M;
770 NEXT M
780 FOR M=1 TO N
790 PRINT:PRINT M; "."; TAB(5);
800 FOR L=1 TO N
810 PRINT INT(D(M,L)+.5); TAB(5*L+4);
820 NEXT L
830 NEXT M
840 PRINT
850 REM ************************************************
860 REM * EDIT MODE FOR EDITING INTER-DESTINATION TABLE *
870 REM ************************************************
880 INPUT "DO YOU WISH TO EDIT ANY VALUES (Y/N) "; Q$
890 IF LEFT$(Q$,1)="N" THEN 1080
900 PRINT:PRINT
910 PRINT "TO ALTER, USE FORMAT : FROM,TO,NEW DISTANCE."
920 PRINT "FOR EXAMPLE,  2,4,512 ALTERS THE DISTANCE FROM DESTINATION 1"
930 PRINT "TO DESTINATION 2 TO 512.  DISTANCE FROM DESTINATION 2 TO"
940 PRINT "DESTINATION 1 IS ALSO CHANGED."
950 PRINT "INPUT 0,0,0 TO LEAVE EDIT MODE."
960 PRINT:PRINT
970 I=1
980 PRINT I; ". "; "FROM,TO,DIS=";
990 INPUT M,L,DI
1000 IF M=0 THEN 680
1010 IF M=L THEN PRINT "ILLEGAL INPUT" : GOTO 980
1020 IF M<1 OR M>N OR L<1 OR L>N THEN PRINT "ILLEGAL INPUT" : GOTO 980
1030 D(M,L)=DI
1040 D(L,M)=DI
1050 I=I+1
1060 GOTO 980
1070 REM ***************************************
1080 REM * GET STARTING AND ENDING DESTINATIONS *
1090 REM ***************************************
1100 INPUT "WHAT IS YOUR BEGINNING LOCATION "; BL
1110 IF BL<1 OR BL>N THEN 1100
1120 INPUT "WHAT IS YOUR ENDING LOCATION "; EL
1130 IF EL<1 OR EL>N THEN 1120
1140 IF BL=EL THEN K=N ELSE K=N-1
1150 IF K<4 THEN PRINT "TOO FEW TOWNS, DO IT YOURSELF!" : GOTO 1080
1160 IF BL<>EL THEN T(1)=BL : C(1)=BL : T(K+1)=EL : C(K+1)=EL : GOTO 1290
1170 REM **** BEGINNING AND ENDING POINT IS SAME, FIND OPTIMUM POINT
1180 SV=0
1190 FOR M=1 TO N
```

Listing 1 continued on page 266

we carry it all....

everything for Commodore
and Atari

Atari® Software

VisiCalc	149
CX4101 Invitation to Programming 1	17
CX4104 Mailing List	17
CX4102 Kingdom	13
CX4103 Statistics	17
CX4105 Blackjack	13
CX4106 Invitation to Programming 2	20
CX4107 Biorhythm	13
CX4108 Hangman	13
CX4109 Graph It	17
CX4111 Space Invader	17
CX4110 Touch Typing	20
CX4115 Mortgage & Loan Analysis	13
CX4116 Personal Fitness Program	13
CX4117 Invitation to Programming 3	20
CX4118 Conversational French	45
CX4119 Conversational German	45
CX4120 Conversational Spanish	45
CX4121 Energy Czar	13
CX4125 Conversational Italian	45
CX8108 Stock Charting	20
CXL4001 Educational System Master	21
CXL4002 Basic Computing Language	46
CXL4003 Assembler Editor	46
CXL4004 Basketball	30
CXL4005 Video Easel	30
CXL4006 Super Breakout	30
CXL4007 Music Composer	45
CXL4009 Chess	30
CXL4010 3-D Tic-Tac-Toe	30
CXL4011 Star Raiders	33
CXL4015 TeleLink	20
Talk & Teach Courseware: CX6001 to CX6017	23

Atari® Peripherals:

400 16K	$349
410 Recorder	59
810 Disk	469
815 Disk	1199
822 Printer	359
825 Printer	629
830 Modem	159
850 Interface Module	139

Atari® Accessories

CX853 16K RAM	89
CX70 Light Pen	64
CX30 Paddle	18
CX40 Joystick	18
CX86 Printer Cable	42
CO16345 822 Thermal Printer Paper	5
CAO16087 825 80-col. Printer Ribbon (3/box)	17
Microtek 16K RAM	79
Microtek 32K RAM	179

commodore

VIC-20	$ 279
4032 N	1080
8032	1499
CBM 4022 Printer	669
CBM 4040 Drive	1039
CBM 8050 Drive	1449
CBM C2N Drive	87
PET-IEEE Cable	37
IEEE-IEEE Cable	46

ATARI 800™
with 32K RAM only $759

Disks

Maxell Disks	10 for $36
Syncom Disks	10 for 29
Atari Disks	5 for 22

Software

EBS Accounts Receivable Inventory System	$595
OZZ Information System	329
BPI General Ledger	329
Tax Package	399
Dow Jones Portfolio Management	129
Pascal	239
WordPro 3 (40 col.)	186
Word Pro 4 (80 col.)	279
WordPro 4 Plus (80 col.)	339
Wordcraft 80	319

Printers

NEC 5530	2495
Diablo 630	2195
Trendcom 100	299
Starwriter	$1495
Trendcom 200	489
Paper Tiger 445G	769
Paper Tiger 460G	1219
Epson MX-80	499
Tally 8024	1699

Please Call Between 11AM & 6PM (Eastern Standard Time)

No Risk - No Deposit On Phone Orders - COD or Credit Card - Shipped Same Day You Call*

(800) 233-8950

Prepaid Orders Receive Free Shipping

* on all in stock units

VISA · master charge

Computer Mail Order **501 E. Third St., Williamsport, PA 17701 (717) 323-7921**

Circle 77 on inquiry card.

Listing 1 continued:

```
1200 SU=0
1210 FOR L=1 TO N
1220 SU=SU + D(L,M)
1230 NEXT L
1240 IF SU>SV THEN OL=M : SV=SU
1250 NEXT M
1260 IF K<4 THEN PRINT "TOO FEW TOWNS, DO IT YOURSELF!" : GOTO 1080
1270 T(1)=OL : C(1)=OL : T(K+1)=OL : C(K+1)=OL
1280 REM ******************************************
1290 REM * CALCULATE TOTAL POSSIBILITIES FOR TRIP *
1300 REM ******************************************
1310 TP=1
1320 FOR M=1 TO K-2
1330 TP=TP*(M+1)
1340 NEXT M
1350 PRINT "TOTAL POSSIBILITIES FOR TRIP "; TP
1360 REM ********************************************
1370 REM * CALCULATE POSSIBLE DESTINATIONS TO VISIT *
1380 REM ********************************************
1390 FOR PP=2 TO K
1400 FOR M=1 TO N
1410 FOR L=1 TO K+1
1420 IF M=T(L) THEN 1450
1430 NEXT L
1440 T(PP)=M
1450 NEXT M
1460 NEXT PP
1470 REM *****************************************************
1480 REM * PREPARATION COMPLETE, NOW CALCULATE SHORTEST TRIP.*
1490 REM * HOWEVER, BEFORE EXECUTING GENERAL TRIP ROUTINE    *
1500 REM * FIRST COMPUTE SPECIAL CASE OF P=2.                *
1510 REM *****************************************************
1520 M(2)=32000
1530 FOR L=2 TO K
1540 S=D(T(L),T(K+1))
1550 IF S<M(2) THEN M(2)=S : C(2)=T(L)
1560 NEXT L
1570 REM *************************
1580 REM * GENERAL CASE FOR P>2  *
1590 REM *************************
1600 LL=2 : LU=4
1610 SW=32000 : F=0
1620 FOR PP=3 TO K+1
1630 IF PP<>K+1 THEN P=PP ELSE P=K : LL=1 : LU=3
1640 FOR L=1 TO K
1650 K(L)=L
1660 NEXT L
1670 H=LL+1
1680 IF H<>P THEN 1920
1690 REM **** CALCULATE TOTAL DISTANCE FROM TOWN 2 THROUGH P + P TO K+1
1700 S=0
1710 IF H<4 THEN 1750
1720 FOR M=LL TO H-2
1730 S=S + D(T(M),T(M+1))
1740 NEXT M
1750 SD=S + D(T(H-1),T(H)) + D(T(H),T(K+1))
1760 REM **** SAVE DISTANCE AND TOWNS OF TRIP IF IT IS A BETTER ROUTE
1770 IF SD>SW THEN 1820
1780 SA=SD : SW=SD
1790 FOR L=2 TO K
1800 C(L)=T(L)
1810 NEXT L
```

Listing 1 continued on page 270



THE HARD DISK YOU'VE BEEN WAITING FOR

XCOMP introduces a complete micro-size disk subsystem with more...

- **MORE STORAGE**
- **MORE SPEED**
- **MORE VALUE**
- **MORE SUPPORT**

S100 users . . . The XCOMP subsystem is now available with 10 megabytes of storage; 5 megabytes also available at $2,898.00. Compare the price and features of any other 5¼-inch — or even 8-inch system, and you'll agree that XCOMP's value is unbeatable.

OUTPERFORMS OTHER HARD DISKS
Floppy disk and larger, more expensive hard disks are no match for this powerful little system. More data is available on every seek: 64K on 10MB and 32K on 5MB. Faster seek time too — an average of 70MS. It provides solid performance anywhere with only 20 watts of power. Data is protected in the sealed enclosure, and the landing zone for heads provides another margin of safety. The optional power board plugs directly into the S100 bus and provides power for the drive.

FAST CONTROLLER
The XCOMP controller is the key to this system's high efficiency operation. Speed-up features include interleave without table lookup, block-deblock with controller buffer, and read lookahead. OEMs worldwide have already proven the outstanding performance of the XCOMP controller.

MORE SOFTWARE
Included with the system is software for testing, formatting, I/O drivers for CP/M® , plus an automatic CP/M driver attach program. Support software and drivers for MP/M® and Oasis® are also available. The sophisticated formatting program assigns alternate sectors for any weak sectors detected during formatting, assuring the lowest possible error rate — at least ten times better than floppies.

WARRANTY
The system has a full one-year warranty on parts and workmanship.

ALSO AVAILABLE FROM XCOMP

- General Purpose controllers (8 bit interface), with easy interface to microprocessor-based systems.
- GP controller adapter that plugs directly into most Z80 computers.
- ST/R GP controller for the 5MB and 10MB drive above, with ST506 type interface.
- SG/R GP controller for SA1000 interface.
- SM/R GP controller for storage module drives.
- ST/S, SG/S, and SM/S, same as above, for the S100 bus.

Quantity discounts available. Distributor, Dealer, and OEM inquiries invited.

See your local Dealer, or call:

XCOMP

XCOMP, Inc.
7566 Trade Street
San Diego, CA 92121
Tel: (714) 271-8730
Telex: 182786

Circle 430 on inquiry card.

Key Variable Definitions

Variable	Description
A()	This array is used to store the polar coordinate angle of the destination. If map headings (N,SW,...) are used as input data, they are converted to an angle before they are stored in this array.
A$()	This array is used to store map headings for the destinations if the user enters the data using this method.
BL	User-specified beginning location of the trip.
C()	This array contains the route of the shortest trip found thus far. Each time the shortest-trip-search routine finds a path shorter than that previously encountered, the cities that make up this newly found shortest route must be saved to expedite the searching of subsequent routes. When the program ends, the C array contains the answer to the problem.
D()	This two-dimensional array contains the inter-destination table.
EL	User-specified ending location of the trip.
F	This flag variable is used in evaluating trip distances. When the last city in a sequence is changed, the new distance is calculated by merely correcting the previous distance for the change in the last city. However, some changes require a change in the next-to-last city as well. The flag alerts the distance-calculation routine that such a change has been made. This forces the routine to calculate the entire distance of the sequence from the beginning.
H, K(H)	The combinatorial algorithm used requires that destinations be changed and evaluated for a possible shortest route. Given a sequence of cities (stored in array T), these two variables tell the program to exchange the Hth city in that sequence with the city whose position in the sequence is K(H).
IM	Three input methods are available to input the location data to the program. This variable is equal to 1, 2, or 3, depending on the input method the user chooses.
L	A variable used to control a FOR...NEXT loop.
LL, LU	After all of the elements of M are calculated, limits LL and LU are changed from 2 to 1 and from 4 to 2 respectively: then the last M-element calculation is repeated. Changing these limits brings the fixed starting city into the calculation, and the resulting minimum path is the solution to the traveling-salesman problem.
OL	Optimum location to start and end the trip. If the user requests that the starting and ending point be the same, the program calculates the optimum location to begin and end, for greatest efficiency in calculating the routes. When the shortest trip has been found by the program, the point used in the calculation is rotated back to the point requested by the user if the optimum location differs from that specified by the user. This step substantially reduces the total execution time by making optimum use of decision-tree pruning.
M	A variable used to control a FOR...NEXT loop.
M()	The shortest-trip-search routine begins by searching for the minimum distance from a single city to the ending location specified by the user. The program then searches for the minimum distance from any two cities ending the route in the location specified by the user. This process continues until the shortest route is found. This array is used to store the minimum distance found for a particular number of cities. It is used extensively to reduce the search time by preventing obviously poor routes from being evaluated.
N, K	The variable N represents the number of destinations specified by the user at the beginning of the program. The variable K may or may not be equal to N. If the user wishes to start and end in the same location, K=N. However, if the starting and ending point differ, K=N−1.
N$()	This character-string array is used to store the names of the destinations specified by the user (ie: New York, Chicago, etc).
P	This variable indexes the M-element calculations. As P sequences from 2 thru K, each of the elements of M is calculated in turn.
PP	A variable to control a FOR...NEXT loop.
R()	This array is used to store the distances from the reference location to all destination points. The value is supplied by the user for each of the destinations.
S, SA, SD, ST, SW	These variables are all used in the shortest-trip-search routine. They represent the results of various partial or complete distance calculations.
SU, SV	These variables are used to calculate the optimum location to begin and end a trip. The optimum location may or may not coincide with the location specified by the user. See the definition of variable OL.
TP	This variable equals the total number of possible combinations for a trip. It is not used by the program; it is calculated to give the user an appreciation of the number of possible routes.
T	Each of the destinations supplied by the user is represented by a number stored in this array. This array is permuted many times before the final result is found and stored in the array C.
X1, X2, XT, Y1, Y2, YT, ZT	All of these variables are used to calculate the distance between cities. They serve as the basis for the construction of the inter-destination table. The variable pair X1, Y1 and the pair X2, Y2 represent the x and y components of two cities with respect to the reference location. The variable pair XT and YT are the x and y components of the absolute distance between the two cities, irrespective of the reference. These two variables are used to compute the line-of-sight distance ZT between the two cities.

LOWEST PRICE - BEST QUALITY

NORTH STAR



North Star Horizon 2

2-5¼ Disk Drives
32K Double Den
Factory assem. & tested
Factory guaranteed
List $3695
only **$2697**

POWERFUL NORTH STAR BASIC FREE
SUPERB FOR BUSINESS & SCIENCE

FACTORY ASSEMBLED & TESTED		LIST	ONLY
HORIZON-2-64K-DOUBLE DEN		$4195	$3062
HORIZON-2-32K-QUAD DENSITY		$3995	$2916
HORIZON-2-64K-QUAD		$4495	$3281
HORIZON RAM ASSM	16K = $279		32K = $479
HORIZON RAM ASSM	48K = $679		64K = $879
HORIZON DISK DRIVE SALE			
DOUB DEN		SAVE!	$ 445
NORTH STAR HARD DISK 18 Mb		$5375	$3923
NORTH STAR TIME SHARING MULTI-USER			CALL

SUPERBRAIN
ZENITH



SUPERBRAIN QD 64K
List $3995 only $2995

Z-89 48K
List $2895 only $2299

TERMINALS Z-19 $725
INTERTUBE III only $725

DYNABYTE COMPUTER—SAVE—PHONE
EPSON MX-80—PHONE
ANADEX 9501 $1349
NEC PRINTER $2639
TRACTOR,
THIMBLE,
RIBBON

DIP-81 $395
TEC LETTER QUAL $1599

InterSystems

ITHACA INTERSYSTEMS 2A



Z-80A CPU 4 MHz
64K Dynamic RAM
Front panel
V I/O—with interrupts
FDCII Disk Controller
20 slot motherboard

CALL FOR PRICE—
TOO LOW TO ADVERTISE!

PASCAL/Z + THE FASTEST PASCAL $375
Z-8000 & CACHE BIOS—POWERFUL—PHONE
8086 16 BIT CPU & SUPPORT CARD SEATTLE $695
CALIFORNIA COMPUTER 2210A ONLY $1795

MORROW 8" DISK

DISCUS 2D + CP/M® 600K ONLY $929
DISCUS 2 + 2 + CP/M® 1.2 MEGA B. $1240
ADD DRIVES 2D = $650 2 + 2 = $975
2D-DUAL + CP/M® ONLY $1540
FREE MBASIC FROM MORROW!!

MORROW HARD DISK
26,000,000 BYTES!!
LIST $4995 ONLY $3919
CP/M® IS INCLUDED!

SAVE ON MEMORY AND PROGRAMS

SYSTEMS MEMORY 64K A & T 4mHz	$590
SYSTEM MEMORY 64K BANK SELECT	$740
ITHACA MEMORY 8/16-bit 64K	$845
SEATTLE MEMORY 8/16 BIT 16K	$249
SSM KITS Z-80 CPU	$221
VIDEO BRD V83 4Mhz	$412
ANADEX PRINTER DP-9500-1	$1349
CATNOVATION MODEM	$169
ECONORAM 2A 8K ASSM	$179
NSSE 1-22 & P01 TERRIFIC PROGRAMS	ONLY $10. EACH
NORTHWORD $329 MAILMAN $246	
INFOMAN	$411
WORD STAR	$315
SPECTRUM	$269
COMPUPRO	SAVE
EZ-CODER Translates English to BASIC	$71
ECOSOFT FULL ACCOUNTING PKG	$355
BOX OF DISKETTES	$29
SECRETARY WORD PROCESSOR The Best!	$99
GOFAST NORTH STAR BASIC OPTIMIZER—FAST	$71
Which Computers are BEST? BROCHURE	FREE
North Star Documentation refundable w/HRZ	$35

TARBELL COMPUTER-PHONE
AMERICAN SQUARE COMPUTERS BEATS ADV. PRICES

American square Computers

919-889-4577 KIVETT DR. JAMESTOWN N.C. 27282 919-883-1105

® CP/M is a registered trademark of Digital Research, Inc.

Circle 22 on inquiry card.

Listing 1 continued:

```
1820 IF K(H)=K THEN 1850
1830 K(H)=K(H)+1
1840 EX=T(H) : T(H)=T(K(H)) : T(K(H))=EX : GOTO 1750
1850 IF H=K THEN 1900
1860 REM **** RETURN TOWNS BETWEEN H AND K TO ORIGINAL ORDER
1870 FOR L=H TO K-1
1880 EX=T(L) : T(L)=T(L+1) : T(L+1)=EX
1890 NEXT L
1900 K(H)=H : H=H-1 : F=1 : GOTO 2060
1910 REM **** GENERAL ALPHA-BETA CHECK
1920 IF H=LL THEN H=H+1 : GOTO 1680
1930 S=0
1940 IF H<LU THEN 1980
1950 FOR L=LL TO H-2
1960 S=S+D(T(L),T(L+1))
1970 NEXT L
1980 ST=S + D(T(H-1),T(H))
1990 IF ST + M(P-H+2) >SW THEN 2060
2000 REM **** CONTINUE ROUTE EVALUATION
2010 H=H+1
2020 IF H=P THEN 1700
2030 ST=ST + D(T(H-1),T(H))
2040 F=1 : GOTO 1990
2050 REM **** PATH ALREADY TOO LONG, TRY NEXT PERMUTATION
2060 IF K(H)=K THEN 2100
2070 K(H)=K(H)+1
2080 EX=T(H) : T(H)=T(K(H)) : T(K(H))=EX
2090 IF F=0 THEN 1980 ELSE F=0 : GOTO 1920
2100 FOR L=H TO K-1
2110 EX=T(L) : T(L)=T(L+1) : T(L+1)=EX
2120 NEXT L
2130 K(H)=H : H=H-1
2140 IF H<>1 THEN F=1 : GOTO 2060
2150 IF LL=1 THEN 2260
2160 M(P)=SA
2170 IF P=K THEN SW=D(T(1),C(2)) + M(P) : GOTO2240
2180 SW=32000
2190 FOR L=P+1 TO K
2200 S=D(C(2),C(L))
2210 IF S<SW THEN SW=S
2220 NEXT L
2230 SW=SW+M(P)+.01
2240 NEXT PP
2250 REM ****************************************************************
2260 REM * PERMUTATION COMPLETE, DISPLAY RESULTS.  HOWEVER, IF OPTIMUM *
2270 REM * BEGINNING AND ENDING POINT WAS USED INSTEAD OF POINT        *
2280 REM * REQUESTED BY USER, ROTATE BACK.                             *
2290 REM ****************************************************************
2300 IF BL<>EL THEN 2380
2310 IF C(1)=BL AND C(K+1)=EL THEN 2380
2320 C(K+1)=EL
2330 REM **** ROTATE ONE CITY
2340 FOR L=1 TO K-1
2350 EX=C(L) : C(L)=C(L+1) : C(L+1)=EX
2360 NEXT L
2370 GOTO 2310
2380 PRINT : PRINT : M=1
2390 IF M=K+1 THEN D=0 ELSE D=(INT((D(C(M),C(M+1))+.05)*10))/10
2400 PRINT M; "."; TAB(6); N$(C(M)); TAB(24); D;
2410 M=M+1 : IF M>K+1 THEN 2450
```

Listing 1 continued on page 272

High resolution, dot addressable graphics with vertical resolution of 72 dots per inch and up to 82 dots per inch horizontal resolution.

"Q.T." cover reduces noise to an office comfort level. This is an optional feature to our standard sound deadening case.

Single sheet feeder is very simple to use. The only front load feeder available on the market today.*

1K standard buffer permits the 88G to print while receiving data. The optional 2K buffer allows a 1920 character dump to the printer freeing the CRT.



The Features Leader

Integrated Paper Handling System
Dual tractor/friction feed allows use of pin feed, roll or single sheet paper.

Versatile Interface
Data input from most computers can be supported by the 88G. RS232C serial and Centronics® type parallel is standard. Options can be added for current loop, IEEE 488 and high speed serial inputs.

Letter Quality Capability
The 88G provides a selectable 11 x 7 serif style dot matrix for correspondence printing.

Cost Effective
The 88G has more features than any other impact printer in its price class. First compare the quality of the 88G, then compare the price —the 88G wins! Single unit price is less than $800.

*Optional

mpi Micro Peripherals, Inc. 4426 South Century Drive Salt Lake City, Utah 84107 (801) 263-3081

The Printer People

California VITEK (714) 744-8305 **Colorado** PLS Associates (303) 773-1218 **Florida** GMI Distributors (305) 894-3354 **Illinois** Coombs & Associates (312) 298-4830 **Massachusetts** Eastmark (617) 449-0050 **Minnesota** Bohlig & Associates (612) 922-7011 **New Jersey** Hansen & Hughes (201) 652-7055 **Oregon** Microwave (503) 620-8150 **Utah** PLS Associates (801) 466-8729 Type-A-Line (801) 521-5310
International England Russet Instruments, Ltd. (0734) 868147 Telex: 849721 **Phoenix** Sigma International (602) 994-3435 Telex: 165-745 Sigma **France** IER Tel. 333.67.81 Telex: 620-289 **Canada** Norango (416) 449-2761

Circle 270 on inquiry card.

Listing 1 continued:

```
2420 IF M=K+1 THEN D=0 ELSE D=(INT((D(C(M),C(M+1))+.05)*10))/10
2430 PRINT TAB(32); M; "."; TAB(36); N$(C(M)); TAB(55); D
2440 M=M+1 : IF M<=K+1 THEN 2390
2450 PRINT
2460 PRINT "THE SHORTEST TRIP IS ";(INT((SA+.05)*10))/10
2470 END
2480 REM ******************************************************************
2490 REM * SUBROUTINE FOR INPUTTING DESTINATION NAME, DISTANCE, AND ANGLE *
2500 REM ******************************************************************
2510 PRINT : PRINT M; ".";
2520 PRINT TAB(5); "NAME OF DESTINATION ";
2530 INPUT N$(M)
2540 PRINT TAB(5); "DISTANCE FROM REFERENCE ";
2550 INPUT R(M)
2560 IF IM=1 THEN 2600
2570 PRINT TAB(5); "ANGLE (0 DEGREES=EAST) ";
2580 INPUT A(M)
2590 RETURN
2600 PRINT TAB(5); "MAP HEADING ";
2610 INPUT A$(M)
2620 IF A$(M)="E" THEN A(M)=0 : RETURN
2630 IF A$(M)="ENE" THEN A(M)=22.5 : RETURN
2640 IF A$(M)="NE" THEN A(M)=45   : RETURN
2650 IF A$(M)="NNE" THEN A(M)=67.5 : RETURN
2660 IF A$(M)="N" THEN A(M)=90 : RETURN
2670 IF A$(M)="NNW" THEN A(M)=112.5 : RETURN
2680 IF A$(M)="NW" THEN A(M)=135 : RETURN
2690 IF A$(M)="WNW" THEN A(M)=157.5 : RETURN
2700 IF A$(M)="W" THEN A(M)=180 : RETURN
2710 IF A$(M)="WSW" THEN A(M)=202.5 : RETURN
2720 IF A$(M)="SW" THEN A(M)=225 : RETURN
2730 IF A$(M)="SSW" THEN A(M)=247.5 : RETURN
2740 IF A$(M)="S" THEN A(M)=270 : RETURN
2750 IF A$(M)="SSE" THEN A(M)=292.5 : RETURN
2760 IF A$(M)="SE" THEN A(M)=315 : RETURN
2770 IF A$(M)<>"ESE" THEN 2600 ELSE A(M)=337.5 : RETURN
```

A machine-readable copy of the program is available from co-author Richard Parry for $9 on a 5-inch disk. The disk is formatted for TSC's FLEX Version 2.0 for 6800-based systems.

Listing 2: *Sample run of the traveling-salesman program. The results of this run are shown in figure 1. The problem here is to find the shortest path that will allow a salesman to visit each city only once, beginning from and returning to Peoria. The execution time is 47 minutes on a SwTPC 6800 system.*

```
HOW MANY DESTINATIONS ? 12


TYPE 1    IF YOU WANT TO INPUT THE ANGLE AS MAP DIRECTIONS
          (E.G. SW, NNW, E, ENE ETC.)

TYPE 2    IF YOU WISH TO INPUT THE ANGLE USING POLAR COORDINATES
          (E.G. 0 DEGREES=EAST, 270 DEGREES=SOUTH ETC.)

TYPE 3    IF YOU WISH TO INPUT ALL DATA VIA THE
          INTER-DESTINATION TABLE.

METHOD 1, 2, OR 3 ? 2

 1 . NAME OF DESTINATION ? PEORIA
     DISTANCE FROM REFERENCE ? 128
     ANGLE (0 DEGREES=EAST) ? 223

 2 . NAME OF DESTINATION ? CHICAGO
     DISTANCE FROM REFERENCE ? 0
     ANGLE (0 DEGREES=EAST) ? 0

 3 . NAME OF DESTINATION ? BELLEVILLE
     DISTANCE FROM REFERENCE ? 261
     ANGLE (0 DEGREES=EAST) ? 244

 4 . NAME OF DESTINATION ? CARBONDALE
     DISTANCE FROM REFERENCE ? 297
     ANGLE (0 DEGREES=EAST) ? 255

 5 . NAME OF DESTINATION ? ROCKFORD
     DISTANCE FROM REFERENCE ? 70
     ANGLE (0 DEGREES=EAST) ? 163

 6 . NAME OF DESTINATION ? DECATUR
     DISTANCE FROM REFERENCE ? 158
     ANGLE (0 DEGREES=EAST) ? 247

 7 . NAME OF DESTINATION ? WAUKEGAN
     DISTANCE FROM REFERENCE ? 27
     ANGLE (0 DEGREES=EAST) ? 104

 8 . NAME OF DESTINATION ? CHAMPAIGN
     DISTANCE FROM REFERENCE ? 126
     ANGLE (0 DEGREES=EAST) ? 261

 9 . NAME OF DESTINATION ? DEKALB
     DISTANCE FROM REFERENCE ? 58
     ANGLE (0 DEGREES=EAST) ? 184

 10 .NAME OF DESTINATION ? SPRINGFIELD
     DISTANCE FROM REFERENCE ? 178
     ANGLE (0 DEGREES=EAST) ? 238

 11 .NAME OF DESTINATION ? KANKAKEE
     DISTANCE FROM REFERENCE ? 59
     ANGLE (0 DEGREES=EAST) ? 266
```

Listing 2 continued on page 276

Listing 2 continued:

```
12 .NAME OF DESTINATION ? AURORA
    DISTANCE FROM REFERENCE ? 34
    ANGLE (0 DEGREES=EAST) ? 204


                 INPUT DATA TO BE USED
          DESTINATION                 DISTANCE         BEARING
 1 . PEORIA                            128              223
 2 . CHICAGO                           0                0
 3 . BELLEVILLE                        261              244
 4 . CARBONDALE                        297              255
 5 . ROCKFORD                          70               163
 6 . DECATUR                           158              247
 7 . WAUKEGAN                          27               104
 8 . CHAMPAIGN                         126              261
 9 . DEKALB                            58               184
 10 . SPRINGFIELD                      178              238
 11 . KANKAKEE                         59               266
 12 . AURORA                           34               204
DO YOU WANT TO EDIT ANY (Y/N) ? N
DO YOU WANT TO EDIT OR EXAMINE THE INTER-DESTINATION TABLE ? N
WHAT IS YOUR BEGINNING LOCATION ? 1
WHAT IS YOUR ENDING LOCATION ? 1
TOTAL POSSIBILITIES FOR TRIP  3.99168E+07


 1 .   PEORIA               90.6     2 .DEKALB              26.1
 3 .   ROCKFORD             60.7     4 .WAUKEGAN            27
 5 .   CHICAGO              34       6 .AURORA              52.5
 7 .   KANKAKEE             67.4     8 .CHAMPAIGN           47
 9 .   DECATUR              142.2    10 .CARBONDALE         64.4
 11 .  BELLEVILLE           86       12 .SPRINGFIELD        63.7
 13 .  PEORIA               0
THE SHORTEST TRIP IS  761.6


READY
```

Listing 3: *An everyday application of the traveling- salesman program. This particular program will chart the best route for someone who must do eight errands at eight different locations and then pick up the baby-sitter. Execution time is 17 minutes on a SwTPC 6800 system.*

```
HOW MANY DESTINATIONS ? 10


TYPE 1    IF YOU WANT TO INPUT THE ANGLE AS MAP DIRECTIONS
          (E.G. SW, NNW, E, ENE ETC.)

TYPE 2    IF YOU WISH TO INPUT THE ANGLE USING POLAR COORDINATES
          (E.G. 0 DEGREES=EAST, 270 DEGREES=SOUTH ETC.)

TYPE 3    IF YOU WISH TO INPUT ALL DATA VIA THE
          INTER-DESTINATION TABLE.

METHOD 1, 2, OR 3 ? 1

 1 . NAME OF DESTINATION ? HOME
     DISTANCE FROM REFERENCE ? 0
     MAP HEADING ? E
```

Listing 3 continued on page 278

☆☆

4MHZ, DOUBLE DENSITY, COLOR & B/W GRAPHICS . . THE LNW80 COMPUTER

COMPARE THE FEATURES AND PERFORMANCE

FEATURES	LNW80	PMC-80**	TRS-80* MODEL III
PROCESSOR	4.0 MHZ	1,8 MHZ	2.0 MHZ
LEVEL II BASIC INTERP.	YES	YES	LEVEL III BASIC
TRS80 MODEL 1 LEVEL II COMPATIBLE	YES	YES	NO
48K BYTES RAM	YES	YES	YES
CASSETTE BAUD RATE	500/1000	500	500/1500
FLOPPY DISK CONTROLLER	SINGLE/ DOUBLE	SINGLE	SINGLE/ DOUBLE
SERIAL RS232 PORT	YES	YES	YES
PRINTER PORT	YES	YES	YES
REAL TIME CLOCK	YES	YES	YES
24 X 80 CHARACTERS	YES	NO	NO
VIDEO MONITOR	YES	YES	YES
UPPER AND LOWER CASE	YES	OPTIONAL	YES
REVERSE VIDEO	YES	NO	NO
KEYBOARD	63 KEY	53 KEY	53 KEY
NUMERIC KEY PAD	YES	NO	YES
B/W GRAPHICS, 128 X 48	YES	YES	YES
HI-RESOLUTION B/W GRAPHICS, 480 X 192	YES	NO	NO
HI-RESOLUTION COLOR GRAPHICS (NTSC), 128 X 192 IN 8 COLORS	YES	NO	NO
HI-RESOLUTION COLOR GRAPHICS (RGB), 384 X 192 IN 8 COLORS	OPTIONAL	NO	NO
WARRANTY	6 MONTHS	90 DAYS	90 DAYS
TOTAL SYSTEM PRICE	$1,915.00	$1,840.00	$2,187.00
LESS MONITOR AND DISK DRIVE	$1,450.00	$1,375.00	---

When you've compared the features of an LNW80 Computer, you'll quickly understand why the LNW80 is the ultimate TRS80 software compatible system. LNW RESEARCH offers the most complete microcomputer system at an outstanding low price.
We back up our product with an unconventional 6 month warranty and a 10 days full refund policy, less shipping charges.

LNW80 Computer $1,450.00
LNW80 Computer w/B&W Monitor & one 5" Drive $1,915.00
All orders must be prepaid, CA residents please include 6% sales tax.
Contact us for shipping charges

* TRS80 Product of Tandy Corporation.
** PMC Product of Personal Microcomputer, Inc.

LNW80

- BARE PRINTED CIRCUIT BOARD & MANUAL $89.95

The LNW80 - A high-speed color computer totally compatible with the TRS-80*. The LNW80 gives you the edge in satisfying your computation needs in business, scientific and personal computation. With performance of 4 MHz, Z80A CPU, you'll achieve performance of over twice the processing speed of a TRS-80*. This means you'll get the performance that is comparable to the most expensive microcomputer with the compatibility to the world's most popular computer (TRS-80*) resulting in the widest software base.

FEATURES:
- . TRS-80 Model 1 Level II Software Compatible
- . High Resolution Graphics
  - . RGB Output - 384 x 192 in 8 Colors
  - . NTSC Video or RF MOD - 128 x 192 in 8 Colors
  - . Black and White - 480 x 192
- . 4 MHz CPU
- . 500/1000 Baud Cassette
- . Upper and Lower Case
- . 16K Bytes RAM, 12K Bytes ROM
- . Solder Masked and Silkscreened

LNW SYSTEM EXPANSION

- BARE PRINTED CIRCUIT BOARD AND MANUAL $69.95
WITH GOLD CONNECTORS $84.95

The System Expansion will allow you to expand your LNW80, TRS-80*, or PMC-80** to a complete computer system that is still totally software compatible with the TRS-80* Model 1 Level II.

FEATURES:
- . 32K Bytes Memory
- . 5" Floppy Controller
- . Serial RS232 20ma I/O
- . Parallel Printer
- . Real Time Clock
- . Screen Printer Bus
- . On Board Power Supply
- . Solder Masked and Silkscreened

LNDoubler & DOS PLUS 3.3D

- Assembled and Tested W/DOS PLUS 3.3D. $175.00

Double-density disk storage for the LNW Research's "System Expansion" or the Tandy's "Expansion Interface". The LNDoubler™ is totally software compatible with any double density software generated for the Percom's Doubler***. The LNDoubler™ provides the following outstanding features.

- . Store up to 350K bytes on a single 5" disk
- . Single and double density data separation
- . Precision write precompensation circuit
- . Software switch between single and double density
- . Easy plug in installation requiring no etch cuts, jumpers or soldering
- . 35, 40, 77, 80 track 5" disk operation
- . 120 day parts and labor Warranty

*** Doubler is a product of Percom Data Company, Inc.

DOS PLUS 3.3D

Micro Systems software's double density disk operating system. This operating system contains all the outstanding features of a well developed DOS, with ease in useability.

KEYBOARD

LNW80 KEYBOARD KIT $84.95

The Keyboard Kit contains a 63 key plus a 10 key, P.C. board, and remaining components.

CASE

LNW80 CASE $84.95

The streamline design of this metal case will house the LNW80, LWN System Expansion, LNW80 Keyboard, power supply and fan, LNDoubler™, or LNW Data Separator. This kit includes all the hardware to mount all of the above. Add $12.00 for shipping

PARTS AVAILABLE FROM LNW RESEARCH
- . 4116 - 200ns RAM
  - 6 chip set $26.00
  - 8 chip set $33.50
  - 16 chip set $64.00
  - 24 chip set $94.00
  - 32 chip set $124.00

- . LNW80 "Start up parts set" LNW80-1 . . . . $82.00
- . LNW80 "Video parts set" LNW80-2 . . . . $31.00
- . LNW80 Transformer LNW80-3 . . . . $18.00
- . LNW80 Keyboard cable LNW80-4 . . . . $16.00
- . 40 Pin computer to expansion cable $15.00
- . System Expansion Transformer $19.00
- . Floppy Controller (FD1771) and UART (TR1602) . . . $30.00

LNW RESEARCH
C O R P O R A T I O N

2620 WALNUT ST.
TUSTIN CA. 92680

ORDERS & INFO. NO. 714-544-5744
SERVICE NO. 714-641-8850

Circle 207 on inquiry card.

VISA MASTER CHARGE ACCEPTED

UNLESS NOTED ADD $3 FOR SHIPPING

Listing 3 continued:

```
2 . NAME OF DESTINATION ? QUILT SHOP
    DISTANCE FROM REFERENCE ? 3
    MAP HEADING ? NE

3 . NAME OF DESTINATION ? HARDWARE STORE
    DISTANCE FROM REFERENCE ? 4
    MAP HEADING ? N

4 . NAME OF DESTINATION ? SCHOOL
    DISTANCE FROM REFERENCE ? 10
    MAP HEADING ? NW

5 . NAME OF DESTINATION ? AUTO SHOP
    DISTANCE FROM REFERENCE ? 4
    MAP HEADING ? NW

6 . NAME OF DESTINATION ? GROCERY STORE
    DISTANCE FROM REFERENCE ? 5
    MAP HEADING ? W

7 . NAME OF DESTINATION ? BIKE SHOP
    DISTANCE FROM REFERENCE ? 6
    MAP HEADING ? SSW

8 . NAME OF DESTINATION ? BAKERY
    DISTANCE FROM REFERENCE ? 3
    MAP HEADING ? S

9 . NAME OF DESTINATION ? SHOE STORE
    DISTANCE FROM REFERENCE ? 5
    MAP HEADING ? S

10 .NAME OF DESTINATION ? BABYSITTER
    DISTANCE FROM REFERENCE ? 4
    MAP HEADING ? SE


              INPUT DATA TO BE USED
        DESTINATION                 DISTANCE        BEARING


 1 . HOME                             0              E
 2 . QUILT SHOP                       3              NE
 3 . HARDWARE STORE                   4              N
 4 . SCHOOL                           10             NW
 5 . AUTO SHOP                        4              NW
 6 . GROCERY STORE                    5              W
 7 . BIKE SHOP                        6              SSW
 8 . BAKERY                           3              S
 9 . SHOE STORE                       5              S
 10 . BABYSITTER                      4              SE
DO YOU WANT TO EDIT ANY (Y/N) ? Y

TYPE 0 TO END EDITING WHEN ASKED 'WHICH ONE'.


WHICH ONE ? 4

 4 . NAME OF DESTINATION ? SCHOOL
     DISTANCE FROM REFERENCE ? 1
     MAP HEADING ? NW
```

Listing 3 continued on page 281

ALL THESE FEATURES... IN THIS SMALL SPACE... AT THIS LOW PRICE!

4,695

Greater computer power . . . fewer separate components . . . larger capability . . . simpler to operate . . .. modular maintenance . . .

These are the unique benefits of the Quasar Data QPD-100 Floppy Disk Computer . . . plus unsurpassed reliability...plus 12-month warranty on all PC boards.

Its highly reliable, double density drive is compact. Accepts both single AND double-sided disks.

Upgradeable from the Z-80™ microprocessor-based system to our 16 BIT microprocessor-based system by simply plugging in extra PC cards. Hard disk and multi-user systems available.

As your requirements grow, your QDP-100 can grow to fit them.

The Quasar Data QDP-100H is a larger version with 6-megabyte capacity; includes one double-sided floppy and one 5¼ microwinchester hard disk.

Both the Quasar Data QDP-100 and QDP-100H are fully compatible with all standard terminals.

Phone or write for descriptive bulletin and specifications. And ask for a demonstration. Dealer inquiries invited.

QUASAR DATA'S QDP-100 COMPUTER SYSTEM.

FEATURES

- Z-80, 4-MhZ CPU
- 64K memory, bank selectable
- Two (2) double-sided, double-density 8" floppies, 2 megabytes
- Four (4) ports...2 serial, 2 parallel
- Double-sided, double-density disk controller, to 4 MB
- CP/M 2.2 DOS. MP/M multi-user operating system. (Optional)
- S-100 (IEEE) motherboard
- BASIC LANGUAGE . . . CBASIC compiler
- Real-time clock
- Monitor in PROM
- Manuals supplied: All documentation and schematics, including "CP/M Handbook" by Sybex.
- Accounting systems: G/L, A/R, A/P, P/R, included.

18" wide
16⅞" deep
11" high

Complete systems available

Z-80 is a trademark of Zilog Corp.

CP/M and MP/M are trademarks of Digital Research Corp.

CBASIC Is a trademark of Compiler Systems Inc.

Quasar Data Products

10330 Brecksville Road, Brecksville (Cleveland), Ohio 44141
Phone: 216/526-0838 / 526-0839
Telex: 241596

Circle 330 on inquiry card.

When Eight Is Not Enough: CP/M-86™ and CBASIC/86™



"In 1977 Compiler Systems, Inc. introduced CBASIC™ as a CP/M® programming language. It quickly became the most widely used BASIC dialect. Since then CBASIC has been adapted for use on systems supporting MP/M™ and TRSDOS."

"At Compiler Systems we learned the lessons of the past well. So well, that in the relatively short time we've been in the software business, we managed to make history ourselves. In fact, CBASIC is the standard for CP/M-based business systems."

— Gordon Eubanks, CSI president

Today CSI offers CBASIC/86 designed for 16-bit microcomputer-based systems running under CP/M-86. CBASIC/86, now available worldwide, is based on concepts first used by CBASIC including such business-oriented features as: BCD arithmetic with fourteen-digit precision; full format control of printed reports; random and sequential records of any length (not limited to 256 bytes); aids to structured design, i.e. multiple line functions and control structures as well as excellent file-handling and stringing capabilities.

But perhaps the best of CBASIC/86 becomes clear when you're using it. To learn more about CSI's commitment to support CBASIC/86 and CP/M-86 call (213) 355-1063 and discuss putting CBASIC/86 on your system.

Send this coupon today, we'll send details that go a long way toward answering your questions.

Name/Date ____________________

Company ____________________

Address ____________________

City/State/Zip ____________________

OEMs contact us for pricing

CBASIC/86

WORLDWIDE DISTRIBUTION FROM CSI

Compiler Systems, Inc., 37 N. Auburn Ave., P.O. Box 145
Sierra Madre, CA 91024, (213) 355-1063

Circle 65 on inquiry card.

Listing 3 continued:

```
WHICH ONE ? 7

 7 . NAME OF DESTINATION ? BIKE SHOP
     DISTANCE FROM REFERENCE ? 6
     MAP HEADING ? SW

WHICH ONE ? 0


                 INPUT DATA TO BE USED
          DESTINATION                  DISTANCE          BEARING
 1 . HOME                              0                 E
 2 . QUILT SHOP                        3                 NE
 3 . HARDWARE STORE                    4                 N
 4 . SCHOOL                            1                 NW
 5 . AUTO SHOP                         4                 NW
 6 . GROCERY STORE                     5                 W
 7 . BIKE SHOP                         6                 SW
 8 . BAKERY                            3                 S
 9 . SHOE STORE                        5                 S
 10 . BABYSITTER                       4                 SE
DO YOU WANT TO EDIT ANY (Y/N) ? N
DO YOU WANT TO EDIT OR EXAMINE THE INTER-DESTINATION TABLE ? Y


                  **** INTER-DESTINATION TABLE ****
                 (VALUES ROUNDED TO NEAREST INTEGER)
        1    2    3    4    5    6    7    8    9    10
 1 .    0    3    4    1    4    5    6    3    5    4
 2 .    3    0    3    3    5    7    9    6    7    5
 3 .    4    3    0    3    3    6    9    7    9    7
 4 .    1    3    3    0    3    4    6    4    6    5
 5 .    4    5    3    3    0    4    7    6    8    8
 6 .    5    7    6    4    4    0    4    6    7    8
 7 .    6    9    9    6    7    4    0    4    4    7
 8 .    3    6    7    4    6    6    4    0    2    3
 9 .    5    7    9    6    8    7    4    2    0    4
 10 .   4    5    7    5    8    8    7    3    4    0
DO YOU WISH TO EDIT ANY VALUES (Y/N) ? Y


 TO ALTER, USE FORMAT : FROM,TO,NEW DISTANCE.
 FOR EXAMPLE,  2,4,512 ALTERS THE DISTANCE FROM DESTINATION 1
 TO DESTINATION 2 TO 512.  DISTANCE FROM DESTINATION 2 TO
 DESTINATION 1 IS ALSO CHANGED.
 INPUT 0,0,0 TO LEAVE EDIT MODE.


  1 . FROM,TO,DIS=? 1,4,4.2
  2 . FROM,TO,DIS=? 2,3,5.4
  3 . FROM,TO,DIS=? 4,5,5.1
  4 . FROM,TO,DIS=? 5,6,6.1
  5 . FROM,TO,DIS=? 8,9,5.1
  6 . FROM,TO,DIS=? 8,10,4.5
  7 . FROM,TO,DIS=? 9,10,5.4
  8 . FROM,TO,DIS=? 3,5,5.5
  9 . FROM,TO,DIS=? 6,7,7.1
  10 . FROM,TO,DIS=? 5,6,6.6
  11 . FROM,TO,DIS=? 0,0,0
 DO YOU WANT TO EDIT OR EXAMINE THE INTER-DESTINATION TABLE ? Y
```

Listing 3 continued on page 282

Listing 3 continued:

```
                    **** INTER-DESTINATION TABLE ****
                   (VALUES ROUNDED TO NEAREST INTEGER)
        1    2     3    4     5    6     7    8     9    10
 1 .  0    3     4    4     4    5     6    3     5    4
 2 .  3    0     5    3     5    7     9    6     7    5
 3 .  4    5     0    3     6    6     9    7     9    7
 4 .  4    3     3    0     5    4     6    4     6    5
 5 .  4    5     6    5     0    7     7    6     8    8
 6 .  5    7     6    4     7    0     7    6     7    8
 7 .  6    9     9    6     7    7     0    4     4    7
 8 .  3    6     7    4     6    6     4    0     5    5
 9 .  5    7     9    6     8    7     4    5     0    5
 10 . 4    5     7    5     8    8     7    5     5    0
DO YOU WISH TO EDIT ANY VALUES (Y/N) ? N
WHAT IS YOUR BEGINNING LOCATION ? 1
WHAT IS YOUR ENDING LOCATION ? 10
TOTAL POSSIBILITIES FOR TRIP  40320


 1 .  HOME            3        2 .QUILT SHOP          5
 3 .  AUTO SHOP       5.5      4 .HARDWARE STORE      3.4
 5 .  SCHOOL          4.4      6 .GROCERY STORE       5.8
 7 .  BAKERY          4.4      8 .BIKE SHOP           4.3
 9 .  SHOE STORE      5.4      10 .BABYSITTER         0

THE SHORTEST TRIP IS  41.2


READY
```

WHEN YOUR NUMBER IS UP, CALL OURS.

FREE.

1-800-321-META

IN OHIO, (216) 289-META

When you are weary of the "NEVER UNDERSOLD" dealers, when you are tired of corresponding with a post office box number, when you are fed up with paying for long distance phone calls because you haven't received your merchandise, when your number is up, call ours.

We don't think any company can be everything to everybody, so we don't try to be. While each of our companies is an independent legal and financial entity, we share a common bond. The one thing we will never undersell you on is service.

With almost 20,000 square feet of facilities, knowledgeable, professional staffs, and solid experience in the industry, we intend to be around for a long time. Our level of automation within our companies (centered around our $200,000 data processing/communications network) may be unsurpassed in the business. Bigger can mean better . . . and we're out to prove it.

Whether you need a $20 box of diskettes or a $250,000 timesharing system, help may be a phone call away. So, when your number is up, call ours.

The META Companies

26111 Brush Avenue, Euclid, Ohio 44132

META TECHNOLOGIES CORPORATION
Software/Supplies

META RESOURCES CORPORATION
Management/Services

META LOGIX CORPORATION
"the computer company company"
Wholesale/Dealer's Supply

META VIDEO CORPORATION
Video Tapes & Supplies

METATRONICS CORPORATION
Hardware/Supplies

Meta Media Productions, Inc.
Advertising

Circle 224 on inquiry card.



Figure 1: *The shortest route for visiting all 12 cities. The sample run from which this data was calculated is shown in listing 2. The total distance for the trip is 761.1 miles. While the results may seem simple, the total number of possible paths thru these 12 cities is 40 million. The program must evaluate each path to determine the shortest route.*

Text continued from page 260:

distances are line-of-sight distances. For the present example, these distances are fairly accurate because major highways run between most of the Illinois cities mentioned. In other examples, such as those involving travel thru a city, the line-of-sight distances may be grossly inaccurate because of one-way streets which dictate roundabout routes.

The third method for entering data allows the user to insert all distances directly in the inter-destination table. For this method to be used, the user must know the distance between every possible pair of points. In practice, a traveler will not have this information. But, over a period of time it is possible to get it. This input method is the most accurate, since true distances are used instead of line-of-sight distances.

In most situations, the user will start with one of the first two methods and then *edit* the inter-destination table by inserting known distances. Listing 3 shows how the inter-destination table can be edited.

In listing 2 polar coordinates are used to input the data. The program prompts the user to supply the name, distance, and angle of each of the 12 cities. When this step is completed, the program displays the input data in neat tabular form—this lets the user easily check the accuracy of the information. If an error is discovered, the user may edit the data before it is used.

THE ULTIMATE REFINEMENT.
PL/I FOR YOUR MICRO.

It's standard, it's structured, and it's perfect for commercial applications.

PL/I Subset G. Designed expressly for minicomputers by an ANSI committee of PL/I experts. All the best application programming features, refined to match contemporary programming practices. Supported by the major minicomputer manufacturers, there's no better way to protect your software investment.

PL/I-80™ for Microcomputers. Based on Subset G, PL/I-80 runs under our CP/M© and MP/M™ operating systems on Z-80, 8080 and 8085 based microcomputers.

PL/I-80 Features. Save design time, minimize debugging and maintenance problems, and design high-quality output with picture specifications, structures, arrays, based and pointer variables, and exception processing.

BT-80™. A Record Retrieval System for PL/I-80 applications is available separately to help you manage your large files.

PL/I-80 from Digital Research. Fast. Economical. Refined. With the programming power of minicomputer PL/I. The package includes compiler, run-time library, linkage editor and relocating macro-assembler, plus three comprehensive manuals. All for only $500.
(Domestic USA price only)

Interested in Refinement?
Call or write Digital Research. Experts in refinement.

DIGITAL RESEARCH®

U.S.A.
DIGITAL RESEARCH
P.O. Box 579
801 Lighthouse Avenue
Pacific Grove, CA 93950
TWX 910 360 5001

EUROPE
VECTOR INTERNATIONAL
Research Park
B-3030 Leuven
Belgium
32 (16) 20-24-96
Telex 26202 VECTOR

FAR EAST
MICROSOFTWARE ASSOCIATES
102 Plasada
3-16-14 Minami Aoyama
Minato-ku
Tokyo 107, Japan
03-403-2120 Telex 2426875 MSA

Circle 123 on inquiry card.

The program then constructs the inter-destination table and gives the user the option to have it displayed. The user must now supply the starting and ending locations for the trip. In this example, Peoria (city 1) is the point from which the salesman starts and to which he returns. The program then executes the search algorithm and finds the shortest route. The time required for this calculation is 47 minutes.

All 12-city problems do not require this amount of time. The input data plays a major role in determining the execution time. In fact, our studies have shown that a 10-city problem can require more time to solve than an 11-city problem because of the tendency of the decision-tree-pruning method to use certain data more efficiently.

The program ends by displaying the shortest route as well as the distance between the cities and the total distance for the trip. For the sample run, the total distance is 761.6 miles. The results are shown in figure 1. In this particular example, we referred to an Illinois road map and changed 45 of the 132 line-of-sight distances to true traveling distances. With this more accurate data, the path was identical. Only the total distance changed.

Figure 2 illustrates an everyday application of the traveling-salesman problem. It will pick the most efficient route for someone who must, for example, do eight errands at eight different locations and then pick up the baby-sitter. The sample run in listing 3 shows how the data is supplied to the program using map headings. Note that two errors were made while supplying the data. The example shows how the edit mode is called to correct the errors. Both the school's distance and the bike shop's map heading are altered.

When all the location data has been supplied, the program constructs the inter-destination table. We now want to edit the table, because we know that several of the line-of-sight distances are inaccurate. Of the 90 distances in the table, 10 distances are

COMPUTERS—TERMINALS—MODEMS!

MODEMS AND COUPLERS

Connect your Apple, TRS—80 or any other computer or terminal to the phone lines!

Penril

Penril 300/1200

Penril 300/1200—Bell 212A style $799
Bell 212A style. 1200 baud and 300 baud. Manual originate, auto-answer. Full duplex. RS232. Direct connect to phone lines via RJ11C standard extension phone voice jack. 1 year warranty.

U.S. Robotics
USR-330A
Bell 103/113 style
USR-330D
Bell 103/113 style

USR-330D $339
Bell 103/113 style. 330 baud. Manual originate, auto-answer. Half/full duplex. RS232. 1 year warranty. Direct connect to phone lines via RJ11C standard extension phone voice jack.

USR-330A $399
Same as USR-330D but includes auto-dial capability.

U.S. Robotics
The Phone Link Acoustic Modem

Bell 103/113 style $179
300 baud. Sleek, low profile. Originate and answer capability. Half/full duplex. Self-test. RS232. Light displays for On, Carrier, Test, Send Data, Receive Data. 15 oz.

Digital Equipment Corporation

DEC VT100

DEC VT100 ... $1668
Detachable keyboard. Separate numeric keypad with function keys. Business forms character set. Reverse video. Selectable double-size characters. Bidirectional smooth-scrolling. 80 cols or 132 cols. Split screen. Settable tabs. Line drawing graphic characters. Status line. Key-Click.

CRT's

Perkin-Elmer Corporation

Superowl 1251

Perkin-Elmer Superowl 1251 .... $1564
Intelligent, editing CRT. Detachable keyboard. 32 fully programmable function keys. Intelligent printer part. Business forms character set. Block mode. Protected fields. Blinking fields. Numeric fields. Reverse video. Half intensity. Polling. Down line loading of options. Remote control of all options by host computer. Settable tabs. Status line. Separate numeric keypad. Transparent mode.

Perkin-Elmer Corporation

Bantam 550B $694
Compact. Silent. Upper/lower case. 80th col. wrap-around. Bell. Integrated numeric pad. Printer port. Transparent mode. Editing features. Tabbing.

Bantam 550E ... $755
Same as 550B plus separate numeric keypad and cursor direction keys.

Bantam 550S $879
Same as 550E plus block mode. 8 function keys, and protected fields, reverse video fields, half intensity fields, blinking fields.

550 Options
- 20mA Current Loop Interface $70
- Non-Glare Screen $25
- 2nd page of memory (550S only) .. $100

HARDCOPY TERMINALS & PRINTERS



Teletype Model 43

Teletype Corporation

Teletype Model 43 KSR with RS232 and Connector Cable $999
30 CPS. Dot matrix. 132 cols. True descenders on lower case. Excellent print quality for dot matrix printer. Pin feed.



DEC LA120

Digital Equipment Corporation

DEC LA120 ... $2388
180 CPS. Dot matrix. Upper/lower case. 1K buffer. Designed for 1200 baud communications. 30 character answerback message. Adjustable line spacing. Adjustable character sizes including double sized characters. Settable horizontal and vertical tabs. Top-of-form capability. RS232.

Digital Equipment Corp.

DEC LA34DA ... $939
30 CPS. Dot matrix. Upper/lower case. 4 character sizes. Up to 217 cols per line. 6 lines per inch settings. Friction feed. Settable tabs. RS232.

DEC LA34AA $1095
30 CPS. Dot matrix. Upper/lower case. 8 character sizes including double size characters. 6 lines per inch settings. Up to 217 cols per line. Friction feed. Settable horizontal and vertical tabs. Top-of-form capability.

Options for LA34AA and LA34DA
- Tractor Feed Mechanism $114
- Numeric Keypad w/ Function Keys .. $69
- Pedestal................................. $100
- Paper Out Sensor $25
- APL Capability with APL Keycaps .. $499
- 2K Buffer with Text Editor and 1200 Baud Communications Capability $499

NEC Corporation
NEC Spinwriter 5510 & 5520

5520 KSR Spinwriter $3088
55 CPS. Impact printer. Selectric print quality. Changeable print fonts. 110, 300 and 1200 baud data rate. Numeric keypad. Friction and tractor feed.

5510 Spinwriter $2754
55 CPS. Impact printer. Selectric print quality. Changeable print fonts. 110, 300 and 1200 baud data rate. Friction and tractor feed.



Perkin-Elmer Corporation

Pussycat 650/655 CRT Screen Printer

650/655 Pussycat CRT Screen Printer. $899
100 CPS. Extremely compact and quiet. 110 to 9600 baud rate. 2K buffer. Ideal for producing rapid, reliable hardcopy of your CRT screen display. Can be added to any CRT with our interface option.

Circle 408 on inquiry card.

Leasing rates and lease/purchase plan information is available on request.
All equipment is shipped with a 10 day money back guarantee.
We offer full service, on site maintenance plans on all equipment.
All equipment in stock.

U.S. ROBOTICS INC.
203 N. WABASH SUITE 1718 CHICAGO, ILL 60601

SALES (312) 346-5650
GENERAL OFFICES (312) 346-5651
SERVICE (312) 733-0497

The A2-3D1 Graphics Family...

professional 3D and 2D graphics for the Apple II

Now for non-programmers!

The **A2-3D1** is the graphics utility you can depend on whether you're mapping a town, presenting charts at a business meeting, or animating games.

Now this versatility is available for the non-programmer with the **A2-GE1** graphics editor and programmer. Create images as you view them. Scan them, animate them, combine them, or add text or labels. With a minimum of fuss, you can prepare all sorts of scientific, business, or educational presentations.

Add the **A2-3D2** enhancement package for color, and as a bonus you'll also be able to manipulate images independently of each other—as many different objects at once as your memory will accommodate.

When it's time for some challenging and educational entertainment, run the **A2-3D/A** Saturn Navigator. You'll enjoy an adventurous flight to Saturn, enter its orbit, and rendezvous with an orbital space station that awaits your arrival.

We've reached our goal of giving you the most sophisticated graphics utilities in the market-place . . .

see them now at your dealer!

Running on the Apple II:
A2-3D/A Saturn Navigator

A2-3D1 Graphics Package
$59.95 on disk (32K required)
$49.95 on cassette (16K required)

A2-3D2 Enhancement
$24.95 on disk (48K and A2-3D1 required)
$19.95 on cassette (32K and A2-3D1 required)

A2-GE1 Graphics Editor
$34.95 on disk (48K and A2-3D1 required)

A2-3D/A Saturn Navigator
$24.95 on disk (48K and A2-3D1 required)

For direct order, include $3 for UPS or $5 for first class mail delivery. Illinois residents add 5% sales tax. Visa and Master Card accepted.

subLOGIC
Communications Corp.
Box V, Savoy, IL 61874
(217) 359-8482
Telex: 206995

Circle 370 on inquiry card.



Figure 2: *The results of the sample run shown in listing 3. The black line indicates the best route to take if line-of-sight distances (distances as they appear on the map) are assumed. The dotted line is the true best route because it is developed from the input data as altered to reflect actual traveling distances between specific points. (A person would be hard-pressed to solve this type of problem visually.)*

altered. When editing is complete, the table is displayed again to show that it has been modified correctly.

The user must supply the starting and ending points, in this case his home. With this input, however, it is possible that the shortest route computed would require that the baby-sitter be picked up first, which means that the baby-sitter would be forced to tag along on all the errands. To eliminate that problem, the baby-sitter's house is supplied to the program as the end point. In this way the user can place some constraints on the route.

Before the program searches for the shortest route, the total number of possibilities for the trip is calculated and displayed. In this case, there are 40,320 possible paths.

When the search is completed, the best route is displayed as well as the distance between each point and the next point in the path. The total distance of 41.2 miles is also displayed. Figure 2 shows this path as a dotted line. The solid line is the route that would have been calculated if only the line-of-sight distances had been used. The figure vividly shows the need to supply the program with accurate distances.

In preparing this article, I gave maps to friends to see just how well they could do compared to the computer. In general, my friends did well. In fact, in some cases a person calculated the correct solution or near-correct solution more quickly than the computer. However, this apparent case of a person outperform-

ing a computer quickly decays when the line-of-sight distances are quite different from the true distances.

An examination of figure 2 shows the drastic path change that occurs when true distances are used instead of line-of-sight distances. This stems from the fact that it is difficult or perhaps impossible for a person to visualize many points in which the true traveling distances have no relationship to the proximity of the points on a map.

Conclusion

Getting from one place to another efficiently is becoming increasingly important as the price of energy keeps climbing. This is true for anyone who travels, but it is particularly true for those who travel a great deal, such as salesmen. The need to plan trips in advance is obvious. However, planning a trip even when the number of destinations is relatively small is a hard task for a human as well as for a computer. By using a decision-tree-pruning method, the program execution time can be drastically reduced.

The BASIC program described here has its limits, but it should be of help in solving many practical problems. Until a major breakthrough is made, solving this NP-complete problem will remain difficult and time-consuming. ■

References

1. Berresford, G C, A M Rocket, and J C Stevenson. "Khachiyan's Algorithm, Part 1: A New Solution to Linear Programming Problems," BYTE, August 1980, page 198, and "Khachiyan's Algorithm, Part 2: Problems with the Algorithm," BYTE, September 1980, page 242.
2. Frey, Peter W and Larry R Atkin. "Creating a Chess Player," BYTE, October 1978, page 182.
3. Kolata, Gina Bari. "Trial-and-Error Game that Puzzles Fast Computers," *Smithsonian*, Volume 10, Number 7, October 1979, page 90.
4. Lewis, T G. "What Computers Cannot Do," BYTE, January 1980, page 100.
5. Maurer, W D. "Alpha-Beta Pruning," BYTE, November 1979, page 84.
6. Steen, Lynn Arthur. "Linear Programming: Solid New Algorithm," *Science News*, Volume 116, October 6, 1979, page 234.
7. Whaland, Norman D. "A Computer Chess Player Tutorial," BYTE, October 1978, page 168.

STATE OF THE ART MEMORY SYSTEMS



256KB LSI 11/23® SINGLE DUAL WIDTH BOARD

The First and Only 256KB Memory on a Single Dual Board.

4 MEGABYTE ADDRESS FIELD — Most memories available for the DEC PDP 11/23 are only addressable to 256K bytes (18 address lines). The CI-1123 is addressable to 4 mega bytes (22 address lines) so there is no need to worry about obsolescence.

FAST ACCESS AND CYCLE TIME — With an access time of 240 NSEC and cycle time of 400 NSEC one is insured the best throughput on the PDP 11/23 system.

PARITY — The CI-1123 generates and checks parity for each byte of memory. Totally DEC compatible.

BATTERY BACKUP POWER CONSUMPTION — Power requirement for the module is only 1.2 AMP from the 5 volt supply. The CI-1123 is easily configured for battery back-up mode of operation requiring only 300MA from a single 5 V back-up supply for 256KB memory in the down state.

SINGLE QTY. PRICE: 32K x 18 **$575.** 128K x 18 **$1925.**

512KB SINGLE BOARD MULTIBUS® MEMORY

State of the Art Multibus Memory Design.
First to Offer 512KB on One Board.

The CI-8086 module is compatible with both 8 or 16 bit Multibus Systems.

PARITY — The CI-8086 generates and checks even parity with selectable interrupt on parity error.

FAST ACCESS AND CYCLE TIME — Data access is 270 NSEC and cycle time is 375 NSEC.

16 MEGA BYTE ADDRESSING — The memory is addressable in 16K increments up to 16 mega bytes.

LOW POWER CONSUMPTION — Total power consumption is under 8 watts.

SINGLE QTY. PRICE: 128K x 9 **$1350.** 512K x 9 **$2995.**





64K x 9 EXORCISER® I SINGLE BOARD MEMORY

For Exorciser I, Exorciser II and Rockwell System 65.

FAST ACCESS AND CYCLE TIME — Data access time is 225 NSEC and cycle time is 400 NSEC, allowing the unit to work as a static RAM at clock rates in excess of 1.5 mega hertz. For 2 mega hertz operation the board can be easily configured to utilize a cycle stealing refresh operation.

ADDRESSING — On-board memory select is available in 4K increments up to 64K words of memory on either the VUA or VXA control inputs.

PARITY — On board even parity with output jumper select to the system bus as a parity error or non-maskable interrupt.

Complete board power consumption is under 7 watts.

SINGLE QTY. PRICE: 64K x 9 **$575.**

Tested and burned in. Full year warranty.

DON'T ASK WHY WE CHARGE SO LITTLE, ASK WHY THEY CHARGE SO MUCH.

Chrislin Industries, Inc.

31352 Via Colinas • Westlake Village, CA 91362 • 213-991-2254

Multibus is a trademark of the Intel Corp. LSI II is a trademark of Digital Equipment Corp. EXORciser is a trademark of Motorola

Circle 61 on inquiry card.

asap computer products, inc.

NEW LOCATION
1198 E. Willow Street
Signal Hill, CA 90806

Toll Free **(800) 421-7701** Outside Calif.
(213) 595-6431 Inside Calif.

ORDERING INFO

Name, address, phone
Ship by UPS or Mail
Shipping Chrg. Add $2.50 up to 1 lb.-Call for larger shipments
Freight, U.S. Mail Add $1.50
U.S. Only up to 2 lbs.

TERMS

We Accept Cash, Check, Money Orders, Visa & Master Charge
(U.S. Funds Only)
Tax: 6% Calif. Res.
COD's & Terms Available on Approval (School PO's Accepted)
($25.00 Minimum Order)

MICROBYTE S-100 BOARDS



Z-80A/I-O $349.00
Assembled & Tested
Optional Monitor Program $50.00

- A complete single board Z-80A CPU with serial/parallel interface
- Fully compatible with the proposed IEEE S-100 Bus Standard
- Z-80A CPU (4MHz version of the Z-80)
- 158 instructions—superset of and upwardcompatible from the 8080's 78instructions
- Up to 4Kof on board Eprom with optional Z-80 monitor program — 1K(2708), 2K(2716) or 4K(2732)
- Full vectored interrupt capability — 8 bit with MNI(1 bit)
- 2MHz or 4MHz operation is jumper selectable
- Selectable auto-wait state insertion for extending M1*, MREQ*, IORQ* and/or on board ROM
- Dual RS-232 serial I/Oportsusing the Z80A-DART with individual baud rateselection (from50-19,200baud)
- Upto 24 bit parallel I/O port—fully programmable Intel 8255A



64K RAM Board
Assembled & Tested *Call for Price*

MICROBYTE
- Fully S100 bus compatible
- 64K x 8 bit dynamic RAM
- Low power:
  - + 8VDC @ 700ma
  - + 16VDC @ 100ma
  - – 16VDC @ 25ma
- Built-in-parity with LED indicator and vector interrupt
- Memory addressable in four 16K banks
- Hidden refresh
- Gold contacts for high reliability
- 72-hour Burn-in
- Memory mapped via DIP switch
- Built-in programmable write-protect
- Programmable control port for parity and bank control
- Alpha-Micro Compatible



Disc Controller $389.00
Assembled & Tested
CPM Available (Optional)

MICROBYTE
- DMA to within 16M byte of memory
- State-of-the-art NEC765LSI Controller
- IEEE-S100compatible
- DMA arbitration allows useof multiple boards within a system
- PLL data recovery fortotally reliable operation
- Write pre-comp switched atmid-disc forreliable double density operation
- Supports upto four(4) drives
- Power On, Power Off or Reset de-selectsdrivesto avoiddamaging files
- Drive deselect Time Out, deselect drives not in use
- Singleor double sided operation
- Single density/double density operation
- 8" standarddrives
- Separate V_{CC} supply fordata recovery to eliminate possible noise problems



I/O Board $289.00
Assembled & Tested
Cables Available (Optional)

MICROBYTE
- Quad RS-232C Serial Ports, One 20mA Current Loop Port
- Fully IEEE S-100Bus Compatible
- Asynchronous Communications with Z80A-Dart(TM) or Synchronous Communications with Z80A-SIO/0(TM)
- Full Set of Modem Control Signals, Including RI (Ring Indicator)
- Easily Configurable to Any Type of Terminal Interface
- I/O Servicing Environments (1) Polled; (2) Bus Vector; (3)Z80 Mode 2 Vector
- Off-Board Interrupt Daisy Chain Capability
- Special Receive Conditions: (1) Framing Error; (2)Parity Error; (3) Receiver Overrun Error
- BaudRates Selected Individually from 50 Baud to 300K Baud
- 72 Hour Burn-In

CALIFORNIA COMPUTER®

2032	32K STATIC RAM BRD.
2065	64K DYNAMIC RAM BOARD
2116	16K STATIC RAM BRD.
2200	MAINFRAME
2422	DISK CONTROLLER
2501	MOTHERBOARD
2710	4-PORT SERIAL I/O
2718	2 SER. PORT & 2 PAR.
2720	4-PORT PARALLEL I/O
2802	6502 CPU BOARD
2810	Z-80 CPU BOARD
7114A	12K ROM/PROM BRD.
7424A	CALENDAR CLOCK BD.
7440A	PROGRAMMABLE TIMER
7470	A/D CONVERTER
7710A	SERIAL SYNCH. BRD.
7712A	SERIAL SYNCH. BRD.
7720A	PARALLEL INTERFACE
7728A	CENTRONICS INTERFACE

CALL FOR PRICE & DELIVERY

SD SYSTEM / S-100 BOARDS

EXPANDORAM I	16K	$240.00
2 MHz DYNAMIC	32K	$258.00
RAM BOARD	48K	$276.00
KITS	64K	$294.00
EXPANDORAM II	16K	$250.00
4 MHz DYNAMIC	32K	$268.00
RAM BOARD	48K	$286.00
KITS	64K	$304.00

SBC-100 KIT
2.5 MHz/Z80 CPU with Serial I/O Ports & SBC 100 Monitor of your choice at No Chrg.
$299.00

SBC-200 KIT
4 MHz/Z80A CPU with Serial & Parallel I/O Ports & SBC 200 Monitor of your choice at No Chrg.
$325.00

VERSAFLOPPY I KIT
Disk Controller for 5¼" & 8" Drives, Single or Double Sided/Single Density, S-100 Compatible
$250.00

VERSAFLOPPY II KIT
Disk Controller for 5¼" or 8" Drives, Single or Double Sided/Single or Double Density, S-100 Compatible
$300.00

PROM 100 KIT
S-100/EPROM PROGRAMMER for 2708, 2716, 2732 & (TI) 2516
$210.00

ALL BOARDS ARE AVAILABLE ASSEMBLED & TESTED CALL FOR PRICES

ATARI 800
(16K) PERSONAL/BUSINESS COMPUTER

- Computer Console
- Operators Manual
- Atari 8K Basic
- RF Modulator
- 57 Full Stroke Alpha-numeric keys & (4) Function Keys
- Power Supply

CALL FOR PRICE

★*Add'l 16K RAM FREE* w/Purchase of System

ATARI OPTIONAL ACCESSORIES

MODEL #	DESCRIPTION	PRICE
810	Disk Drive System	$ 475.00
815	Disk Drive System	$1199.00
820	40-col. Dot Matrix Printer	$ 279.00
822	40-col. Thermal Printer	$ 349.00
825	80-col. Dot Matrix Printer	$ 625.00
830	Acoustic Modem	$ 159.00
850	Interface Module	$ 139.00
410	Cassette Recorder	$ 60.00

ATARI SOFTWARE

Description	Price
Basketball	$30.00
Super Breakout	$30.00
Chess	$30.00
Video Easel	$30.00
3-D Tic Tac Toe	$30.00
Star Raiders	$34.00
Music Composer	$42.00
Educational System ROM	$19.95
Assembler/Editor	$45.00
Telelink I	$19.95
Space Invaders	$15.95
Kingdom	$12.95
Blackjack	$12.95
Biorhythm	$12.95
Graph It	$15.95
Energy Czar	$12.95
Mailing List	$16.95
Statistics I	$16.95
Paddle Controls	$17.95
Joysticks (pair)	$17.95
Touch Typing	$19.95
Stock Charting	$19.95
Stock Analysis	$19.95
Bond Analysis	$19.95

MANY MORE AVAILABLE

MAIN/FRAME & DISK DRIVE CABINETS from INTEGRAND

MODEL X5 — Desktop Mainframe - 5 Cards - Small Power Supply **$200**
Cabinet size: 9.4"w x 16"d x 7.5"h. Cabinet painted dove grey, front panel is black. **No optional colors!** 5-position motherboard, 5 connectors installed, card cage with all guides. Reset switch on front panel. Power switch, 4 DB25 cutouts, 1 BNC mounting hole, 70CFM fan, EMI filter, 6' power cord, line fuse, and clamped flat cable exit on rear panel. PX/5 power supply (+8@10A, +16@1.5A, -16@1.5A). Power supply is a removable module.

MODEL 700D — Horizontal Desktop Disk/Cover - 2 Eight Inch Drives - Drives Horizontal **$250**
Cabinet size: 20"w x 23"d x 7.5"h. Cabinet painted dove grey, front panel is black. Mounting for 2 eight-inch Shugart SA801R Floppy Disk Drives (or mechanical equivalent). Drive mounting brackets supplied. Drives not supplied. 70CFM fan, 6' three-wire line cord, power switch, line fuse, EMI filter and clamped flat cable exit on rear panel. P794 power supply: +5@4A, +24@5A—6A peak, -5@.75A. All voltages regulated. Power supply is a removable module.

MODEL 8000 — Desktop Main/Frame - 15 Cards - Standard Power Supply **$255**
Cabinet size: 17"w x 20.5"d x 7.5"h. Cabinet painted dove grey, front panel is black (other color schemes optional). 15-position IEEE compatible motherboard (will accept T801 terminator kit, optional), card cage with all guides. Reset switch on front panel. Power switch, 8'DB25 cutouts, 2 BNC mounting holes, 70CFM fan, EMI filter, 6' power cord, line fuse, and clamped flat cable exit on rear panel. P800 power supply (+8@15A, +16@3A, -16@3A). Power supply is a removable module. Motherboard connectors optional.

MODEL 7000S — Vertical Desktop Disk/Cover - 2 Eight Inch Drives - Drives Vertical **$250**
Cabinet size: 13.5"w x 23"d x 11"h. Cabinet painted dove grey, front panel is black. Mounting for 2 eight-inch Shugart SA801R Floppy Disk Drives (or mechanical equivalent). Drive mounting brackets supplied. Drives not supplied. 70CFM fan, 6' three-wire line cord, power switch, line fuse, EMI filter and clamped flat cable exit on rear panel. P794 power supply: +5@4A, +24@5A—6A peak, -5@.75A. All voltages regulated. Power supply is a removable module.

PRINTERS

MFG./MODEL #	PRICE
ANACOM-150	$ 995.00
ANADEX-9501	$1300.00
BASE 2-800B	$ 650.00
DIABLO-630R0	$2225.00
INTEGRAL-460	CALL
C. ITOH-Starwriter 45	$1925.00
TEXAS INSTR.-810	$1650.00

MONITORS

MFG.	MODEL #	PRICE
Amdek	100/12" B&W	$139.00
Amdek	100-80	$169.00
Amdek	100G/12" Grn.	$169.00
APF	TVM-10/10" B&W	$149.00
Hitachi	VM910/9" B&W	$210.00
Hitachi	VM129/12" B&W	$340.00
Sanyo	DM5012/12" B&W	$260.00
Sanyo	DM5112ex/12" Grn.	$280.00
Sanyo	DMC6013/13" Color	$450.00

MODEMS

MFG.	MODEL #	PRICE
Novation	CAT	$149.00
Novation	D-CAT	$169.00
Novation	Auto-CAT	$229.00
Lexicon	Lex-11	$139.00
Livermore	LIV-Star 20M	$149.00
UDS	UDS 103	$189.00
UDS	UDS 202	$295.00

TERMINALS

MFG.	MODEL #	PRICE
Ampex	Dialogue 80	$ 945.00
Soroc	IQ120	$ 750.00
Soroc	IQ140	$1250.00
Televideo	TVI 912C	$ 725.00
Televideo	TVI 920C	$ 775.00
Televideo	TVI 950C	$ 975.00

QUME DT-8 DISK DRIVE



Specifications
- Double-sided Sgle-Dble Density
- IBM-compatible 1.2 Mbytes/Disk
- Fast—3 ms. Track to Track
- 154 Tracks/Daisy Chain 4 Drives
- ISO Standard Write Protect
- Programmable Door Lock

CALL FOR PRICE & DELIVERY
O.E.M. Pricing Available on Request
120 Day Factory Warranty

WAMECO INC. Bare Boards & Kits

KITS

PART #	DESCRIPTION	PRICE
EPM-1	4K EPROM	$ 59.95
EPM-2	16K or 32K EPROM	$ 74.95
MEM-1	8K Static	$ 71.95
MEM-2	16K Static	$ 80.95
FPB-1	Front Panel	$159.95
CPU-1	8080A CPU	$119.95
RTC-1	Real Time Clock	$ 75.95
QMB-9	9 Slot Motherboard	$ 99.95
QMB-12	12 Slot Motherbrd.	$109.95

KITS LESS EPROM OR RAM CHIPS

BARE BOARDS

PART #	DESCRIPTION	PRICE
EPM-1	4K EPROM	$29.95
EPM-2	16K or 32K EPROM	$29.95
MEM-1	8K Static	$29.95
MEM-2	16K Static	$31.95
MEM-3	32K Static	$35.95
FPB-1	Front Panel	$49.95
FDC-1	Disk Controller	$44.95
CPU-1	8080A CPU	$31.95

BARE BOARDS

PART #	DESCRIPTION	PRICE
CPU-2	Z80 CPU	$39.95
RTC-1	Real Time Clock	$27.95
QMB-9	9 Slot Motherboard	$34.95
QMB-12	12 Slot Motherbrd.	$39.95
CRT-1	80 x 24 Video	CALL
IOB-1	2 Par. & 1 Ser. I/O	CALL
IOB-2	8-Parallel I/O Ports	$35.95
IOB-5	4-Serial I/O Ports	$35.95

Circle 32 on inquiry card.

COMPONENTS

4116's (200 ns.)
Apple, TRS-80, Heath
8 for $18.80

16-49	$2.25 ea.
50-99	$2.15 ea.
100 Up	$2.05 ea.

2114 L-2/200 NS

Lo-Power 1Kx4 Static RAM

1-16	$3.05 ea.
17-49	$2.95 ea.
50-99	$2.85 ea.
100 Up	$2.70 ea.

74LS240	$1.25 ea.
74LS241	$1.10 ea.
74LS244	$1.25 ea.
74LS373	$1.25 ea.
74LS374	$1.25 ea.
8T245	$1.50 ea.

2708/450 NS

1K x 8 EPROM
$4.25 ea.
or
8/$32.00

2716/5 VOLT

2K x 8 EPROM
$6.95 ea.
1 YR. WARRANTY

8080A-CPU	$ 2.50
Z80A-CPU	$ 8.95
Z80A-CTC	$ 8.95
Z80A-DART	$13.95
Z80A-SIO	$22.00
8255AC5	$ 6.95
8257AC5	$15.00

320T5	.80	320T12	.80
340T5	.70	340T12	.75

	1-9	10-24	25 Up
DB25P	2.80	2.65	2.50
DB25S	3.80	3.70	3.40
DB25C	1.05	.95	.85

100 PIN IMSAI

Gold / S-100
Soldertail
Connectors
$2.40 each
OR
10/$2.25 each

CAPACITORS

.1 @ 12 Volt
Ceramic
8¢ ea.
or
100/$7.00

DISKETTES FROM asap

VERBATIM

5¼" DISKETTES

PART #	SECTORING	PRICE
MD525-01	SOFT SECTOR	10/2750
MD525-10	HARD 10 SECTOR	10/2950
MD525-16	HARD 16 SECTOR	10/2950

8" DISKETTES

PART #	SECTORING	PRICE
FD32-1000	HARD SECTOR	10/3500
FD34-1000	SOFT SECTOR	10/3500

MEMOREX

5¼" DISKETTES

PART #	SIDES/DENSITY	SECTORING	PRICE
MEM 3401	1/SINGLE	SOFT SECTOR	10/2500
MEM 3403	1/SINGLE	HARD 10 SECTOR	10/25.00
MEM 3405	1/SINGLE	HARD 16 SECTOR	10/2500

8" DISKETTES

PART #	SIDES/DENSITY	SECTORING	PRICE
MEM 3060	1/SINGLE	SOFT SECTOR	10/3500
MEM3101	2/SINGLE	SOFT SECTOR	10/4500
MEM 3090	1/DOUBLE	SOFT SECTOR	10/4500
MEM3102	2/DOUBLE	SOFT SECTOR	10/5500

DYSAN

5¼" DISKETTES

PART #	SIDES/DENSITY	SECTORING	PRICE
D-0130	1/SINGLE	SOFT SECTOR	10/5000
D-0226	1/DOUBLE	SOFT SECTOR	10/53 00
D.0235	2/DOUBLE	SOFT SECTOR	10/6500

8" DISKETTES

PART #	SIDES/DENSITY	SECTORING	PRICE
D-0506	1/SINGLE	SOFT SECTOR	10/5900
D-0605	2/DOUBLE	SOFT SECTOR	10/75.00

SCOTCH 3M

5¼" DISKETTES

PART #	SIDES/DENSITY	SECTORING	PRICE
744-0	1/SINGLE	SOFT SECTOR	10/3000
744-10	1/SINGLE	HARD 10 SECTOR	10/3000
744-16	1/SINGLE	HARD 16 SECTOR	10/30 00
745-0	2/DOUBLE	SOFT SECTOR	10/59 00
745-10	2/DOUBLE	HARD 10 SECTOR	10/59.00
745-16	2/DOUBLE	HARD 16 SECTOR	10/59.00

MAXELL

5¼" DISKETTES

PART #	SIDES/DENSITY	SECTORING	PRICE
MD1	1/SINGLE	SOFT SECTOR	10/39.00
MD2D	2/DOUBLE	SOFT SECTOR	10/65.00
MH1	1/SINGLE	HARD 16 SECTOR	10/3900
MH2D	2/DOUBLE	HARD 16 SECTOR	10/6500

8" DISKETTES

PART #	SIDES/DENSITY	SECTORING	PRICE
FD1-128	1/SINGLE	SOFT SECTOR	10/45.00
FH1-32	1/SINGLE	SOFT32SECTOR	10/45.00
FD2-XD	2/DOUBLE	SOFT SECTOR	10/65.00

SRW

MEDIA STORAGE CASES

PART #	SIZE	PRICE
SRW-5	5¼"	$2.50ea
SRW-8	8"	$3.25ea

DIP SOCKETS/LOW PROFILE TIN SOLDERTAIL

DESCRIPTION	1-9	10-49	50-99	100 Up
14 PIN TIN ST	.15	.13	.12	.11
16 PIN TIN ST	.16	.14	.13	.12
18 PIN TIN ST	.19	.18	.16	.14
20 PIN TIN ST	.25	.23	.21	.20
24 PIN TIN ST	.26	.24	.22	.20
28 PIN TIN ST	.32	.30	.29	.27
40 PIN TIN ST	.42	.40	.38	.34

INTRODUCING
asap's Atari 800

Computer System • 16K RAM Module
$79.95
1 YEAR WARRANTY PARTS AND LABOR

PERSONAL SOFTWARE for APPLE, TRS80, PET, & ATARI

DESCRIPTION	PRICE
VISICALC APPLE DISK	125.00
DESKTOP PLAN APPLE DISK	79.95
MICROCHESS 2.0 APPLE DISK	21.95
MICROCHESS 2.0 APPLE	17.95
CHECKER KING APPLE DISK	21.95
CHECK KING APPLE	17.95
GAMMON GAMBLER APPLESOFT DISK	21.95
GAMMON GAMBLER APPLE	17.95
BRIDGE PARTNER APPLESOFT DISK	21.95
BRIDGE PARTNER APPLE	17.95
CCA DATA MGMT SYS APPLE DISK	79.95
MICROCHESS 2.0 8-32K PET	17.95
CHECKER KING PET	17.95
GAMMON GAMBLER PET	17.95
BRIDGE PARTNER PET	13.95
VISICALC - PET	175.00
CCA DATA MGMT SYS TRS80 DISK	65.00
MICROCHESS 1.5 TRS80	17.95
CHECKER KING TRS80	17.95
BRIDGE PARTNER TRS80	13.95
TIME TREK TRS80	13.95
VITAFACTS PKG/6 PET APPLE TRS	100.00
VISICALC - ATARI	175.00

APPLE SOFTWARE by EDU-WARE

DESCRIPTION	PRICE
COMPU-MATH (FRACTIONS)	29.95
COMPU-MATH (DECIMALS)	29.95
COMPU-READ	19.95
EDU-PAK I	35.00
TERRORIST	24.95
WINDFALL	16.95
NETWORK	16.95
SPACE	24.95
PRISONER	24.95

(ALL SOFTWARE ON DISK)

PANAVISE

BASES, HEADS, MTS. & COMBINATIONS

PART #	DESCRIPTION	PRICES
300	STANDARD BASE	11.95
301	STANDARD PANAVISE	24.95
303	STANDARD HEAD	14.49
304	LOW PROFILE HEAD	15.25
305	LOW PROFILE BASE	11.95
308	WEIGHTED BASE	14.25
310	SURFACE PLATE	33.95
311	BENCH CLAMP	14.49
315	CIRCUIT BOARD HOLDER	16.95
333	RAPID ASSEMBLY	30.95
350	WORK CENTER STATION	38.95
366	WIDE OPEN HEAD	13.95
376	SELF-CENTERING HEAD	16.95
380	VACUUM BASE	16.95

ACCESSORIES

PART #	DESCRIPTION	PRICE
316	EXTRA ARMS	9.50
318	12" BAR	3.49
343	NYLON JAWS (PAIR)	2.00
344	GROOVED NYLON JAWS	2.00
346	NEOPRENE JAWS	2.50
353	STEEL JAWS	2.95
359	UNIVERSAL HOLDER	6.95

SHUGART 801R DISK DRIVE

Capacity	Single Density	Double Density
Unformatted		
Per Disk	400K	800K
Per Track	5.2K	10.4K
IBM Format		
Per Disk	256K	512K
Per Track	3328	6656
Transfer Rate	250 kilobit/sec	500 kilobits/sec
Latency (avg.)	83 ms	83 ms
Access Time		
Track to Track	8 ms	8 ms
Average	260 ms	260 ms
Settling Time	8 ms	8 ms
Head Load Time	35 ms	35 ms

Model 801 .... $400.00
Case & Power Supply $265.00

ZIP DIP II®

Zero Insertion Pressure Test Socket

PART #	PINS	1-9	10-24	25 UP
ZD1116	16	5.35	5.15	4.95
ZD1124	24	7.35	7.10	6.85
ZD1140	40	9.75	9.50	9.25

DIP SWITCHES®

PART #	POSITIONS	1-9	10-24	25 UP
DS4P	4	1.25	1.20	1.15
DS5P	5	1.30	1.20	1.10
DS6P	6	1.35	1.25	1.10
DS7P	7	1.40	1.25	1.10
DS8P	8	1.40	1.20	1.05

IDS SOCKET CONNECTORS
Crimp-On Type

Contacts	1-9	10-24	25 Up
20 PINS	2.95	2.75	2.50
26 PINS	3.25	2.95	2.75
34 PINS	4.45	4.25	3.95
40 PINS	5.65	5.35	4.95
50 PINS	5.95	5.65	5.25

IDS CARD-EDGE CONNECTORS
Crimp-On Type

Contacts	1-9	10-24	25 Up
20 PINS	3.95	3.75	3.50
26 PINS	4.95	4.55	4.25
34 PINS	5.25	4.95	4.75
40 PINS	6.25	5.85	5.50
50 PINS	6.95	6.35	5.95

The Epson MX-80

80 COLUMN DOT MATRIX PRINTER



SPECIFICATIONS
Print method - serial impact dot matrix
Print rate - 80 CPS
Print direction - bidirectional
Number of pins in head - 9
Matrix - 9 x 9
Line spacings - 1/8", 1/6", 7/72" + programmable
Throughput at 10 CPI - logical seeking function - 105 LPM, 20 character line; 73 LPM, 43 char. line; 48 LPM, 80 char. line

PRINTING CHARACTERISTICS
Character set - full 96-character ASCII with descenders
Graphics characters - 64 block characters

INTERFACES
Standard - Centronics-style 8-bit parallel
Optional - RS232, IEEE488.
Buffer size - 1 line

New MX80FT Available
CALL FOR PRICE & DELIVERY

MICROBYTE 32K STATIC RAM BOARD



- 2 MHz or 4 MHz operation
- 4K hardware or software selectable
- Will operate with or without front panel
- Low power consumption 800mA
- Fully warranted for 120 days from date of shipment
- Uses Intel low-power 2141L-4 4Kx1 Static RAM
- Each 4K bank addressable to any 4K slot within a 64K boundary

$500.00

- Fully S100 bus compatible IMSAI, SOL, ALTAIR, ALPHA MICRO

GODBOUT 32K ECONORAM XX
Static S-100 Memory

32K Bank Select. IEEE S-100 compatible. One 32K block can be addressed on 4K boundaries. Compatible with IEEE proposed standard of 24 address lines and all currently used bank select configurations. Disable any or all of the eight 4K blocks to create as many windows in memory to avoid system memory conflicts.

PART #	DESCRIPTION	PRICE
GB ER XX 16K	16K A & T	$339.00
GB ER XX 24K	24K A & T	$449.00
GB ER XX 32K	32K A & T	$579.00

asap DISK DRIVE CABLE ASSEMBLY

PART # CA832PT

DESCRIPTION: CONNECTS (2) 8" DISK DRIVES (Shugart Qume, etc.) TO STANDARD DISK CONTROLLER BOARD

$25.95 ea.

CATALOG REQUEST

Please send me your
1981 asap
Full Line Catalog

Name ____________________
Address ____________________
City ____________________
State ________ Zip ________

asap computer products, inc.

NEW LOCATION
1198 E. Willow Street
Signal Hill, CA 90806
Toll Free (800) 421-7701 Outside Calif.
(213) 595-6431 Inside Calif.

ORDERING INFO

Name, address, phone
Ship by UPS or Mail
Shipping Chrg. Add $2.50 up to 1 lb.-Call for larger shipments
Freight, U.S. Mail Add $1.50
U.S. Only up to 2 lbs.

TERMS

We Accept Cash, Check, Money Orders, Visa & Master Charge (U.S. Funds Only)
Tax: 6% Calif. Res.
COD's & Terms Available on Approval (School PO's Accepted)
($25.00 Minimum Order)

Circle 32 on inquiry card.

Energy Measurement with the Apple II

William H Murray, Engineering Science Department
Boome Community College, Binghamton NY 13902

Anyone who has tried to make medium- to long-term electrical-energy measurements on a wind-driven generator or a bank of solar cells has found it difficult, *if* not impossible, to obtain the proper monitoring equipment. There are two good reasons for this: there is no real commercial demand for a direct-current kWh (kilowatt-hour) meter, and it is difficult to build a meter that will work on a system where both voltage and current can vary widely during the course of the monitoring period.

California Computer Systems came to my rescue when I tried to tackle this problem. It makes a 3¾-digit A/D (analog-to-digital) converter and a clock/calendar

Text continued on page 299

(1a)



(1b)



Figure 1: *Resistor networks used to ensure that input signals are within the proper range for use with A/D converter boards. The component values specified in figure 1a will divide the input voltage by a factor of 50. The circuit shown in figure 1b provides current division by a factor of 5. Both factors are taken into account by the Applesoft BASIC program in listing 1.*

Listing 1: *This Apple BASIC program performs data-logging functions. The A/D converters and the clock/calendar are initialized with the routines in listings 1b thru 1d.*

(1a)

```
]LIST

10  REM : LOAD MACHINE LANGUAGE
     CONTROL PROGRAMS
20 D$ =  CHR$ (4)
30  PRINT D$;"BLOAD ENERGY A/D5.O
    BJO"
40  PRINT D$;"BLOAD ENERGY A/D7.O
    BJO"
50  PRINT D$;"BLOAD ENERGY.OBJO"
60  REM : RUN MACHINE LANGUAGE
     PROGRAMS
70  CALL 50374
80  REM : CLEAR SPLIT SCREEN
90  CALL  - 936
100  REM : SET CONSTANTS FOR LEFT
     PORTION OF SCREEN
110 P1 = 0:TP = 0:BOTTM = 24
120 LEFTEDGE = 0:WIDTH = 25
130  POKE 32,LEFTEDGE: POKE 33,WI
    DTH
140  POKE 34,TP: POKE 35,BOTTM
150  VTAB 2: PRINT "          ENERGY
     DATA FOR"
160  VTAB 5: PRINT "   THE PRESEN
    T TIME IS"
170  VTAB 6: PRINT "THE PRESENT V
    OLTAGE IS"
180  VTAB 7: PRINT "THE PRESENT C
    URRENT IS"
190  VTAB 8: PRINT "THE PRESENT W
    ATTAGE IS"
200  VTAB 10: PRINT "THE AVERAGE
    WATTAGE IS"
210  VTAB 13: PRINT "   THE PEAK
    WATTAGE IS"
220  VTAB 15: PRINT "   THE TIME
    OF MAXIMUM"
230  VTAB 17: PRINT " NUMBER OF K
    W-HOURS IS"
240  VTAB 18: PRINT "  NUMBER OF
    SAMPLES IS"
260  REM : CHECK FOR COMPLETED
     CONVERSION
270 MM =  PEEK (774):MN =  PEEK (
    779)
280  IF MN > 0 THEN  GOTO 270
290  REM : STORAGE LOCATIONS: 757
    ($2F5) TO 778($30A)
300 Z = 768
310  REM : VOLTAGE
320 VA = ( PEEK (Z + 2))
330 VB = ( PEEK (Z + 3)) / 10
340 VC = ( PEEK (Z + 4)) / 100
350 VD = ( PEEK (Z + 5)) / 1000
360  REM : CURRENT
370 CA = ( PEEK (Z + 7))
380 CB = ( PEEK (Z + 8)) / 10
390 CC = ( PEEK (Z + 9)) / 100
400 CD = ( PEEK (Z + 10)) / 1000
410  REM : TIME AND DATE
420 TA =  PEEK (Z)
430 TB =  PEEK (Z - 1)
440 TC =  PEEK (Z - 2)
450 TD =  PEEK (Z - 3)
460 TE =  PEEK (Z - 4)
470 TF =  PEEK (Z - 5)
480 TG =  PEEK (Z - 6)
490 TH =  PEEK (Z - 7)
500 TI =  PEEK (Z - 8)
510 TJ =  PEEK (Z - 9)
520 TK =  PEEK (Z - 10)
530 TL =  PEEK (Z - 11)
540  REM : GET VOLTAGE DATA
550 VT = VA + VB + VC + VD
560 V = VT * 50
570  REM : GET CURRENT DATA
580 CT = CA + CB + CC + CD
590 C = CT * 5
600  IF V > 300 THEN  GOTO 270
610  REM : SET RIGHT PORTION OF
     SCREEN FOR TIME UPDATE
620 LEFTEDGE = 28:WIDTH = 10
630  POKE 32,LEFTEDGE: POKE 33,WI
    DTH
640  POKE 34,TP: POKE 35,BOTTM
650  REM : UPDATE TIME ONCE PER
     SECOND
660  VTAB 5: PRINT TF;TE;":";TD;T
    C;":";TB;TA
670  REM : AFTER ONE MINUTE,
     SAMPLE A/D'S FOR NEW DATA
680 X = (TB * 10) + TA
690  IF X = 0 THEN  GOSUB 750
700  POKE 7,4: POKE 7,4: POKE 7,4

710  GOTO 270
720  END
730  REM : SUBROUTINE FOR DATA UP
    DATE
740  REM : N=NUMBER OF SAMPLES
750 N = N + 1
760  REM : PC=PRESENT POWER
      READING
770 PC = C * V
780  REM : ACCUMULATED NUMBER OF
    K.W.H.
790 KWH = KWH + (PC / 60000)
800 TT = TT + PC
810  REM : PA=AVERAGE POWER
820 PA = TT / N
830  REM : SUBROUTINE TO GET PEAK
     POWER
840  IF RR < PC THEN  GOSUB 1080
850 V =  INT (V * 10 + .5) / 10
860 C =  INT (C * 10 + .5) / 10
870 PC =  INT (PC * 10 + .5) / 10

880 PA =  INT (PA * 10 + .5) / 10

890 RR =  INT (RR * 10 + .5) / 10

900 KWH =  INT (KWH * 1000 + .5) /
    1000
910  REM : CLEAR RIGHT PORTION OF
     SCREEN
920  VTAB 1: CALL  - 958
930  VTAB 2: PRINT TJ;TI;"/";TH;T
    G;"/";TL;TK
940  VTAB 5: PRINT TF;TE;":";TD;T
    C;":";TB;TA
950  VTAB 6: PRINT V;""
960  VTAB 7: PRINT C;""
970  VTAB 8: PRINT PC;""
980  VTAB 10: PRINT PA;""
990  VTAB 13: PRINT RR;""
1000  VTAB 15: PRINT T6;T5;":";T4
    ;T3;":";T2;T1
1010  VTAB 17: PRINT KWH;""
1020  VTAB 18: PRINT N;""
1030 X = 0
1040  REM : CHECK SEC. COUNT, GO
    TO MAIN STREAM AFTER A 1 SEC
    . DELAY
1050 TA =  PEEK (768)
1060  IF TA = 0 THEN  GOTO 1050
1070  RETURN
1080 RR = PC
1090 T1 = TA:T2 = TB:T3 = TC
1100 T4 = TD:T5 = TE:T6 = TF
1110  RETURN
```

(1b)

```
:                                   CTRL-

SOURCE FILE: ENERGY A/D5
----- NEXT OBJECT FILE NAME IS ENERGY A/D5.OBJO
C500:                1          ORG   $C500      ;SLOT FOR CURRENT A/D
C500:A9 80           2          LDA   #$80       ;STOP CONV. TO SAMPLE
C502:A9 80           3          LDA   #$80
C504:8D D0 C0        4          STA   $C0D0
C507:8D D0 C0        5          STA   $C0D0
C50A:AD D3 C0        6          LDA   $C0D3      ;BIT 1
C50D:AD D3 C0        7          LDA   $C0D3
C510:29 0F           8          AND   #$0F       ;USE LOWER BITS
C512:8D 02 03        9          STA   $302       ;STORE BIT 1
C515:AD D2 C0       10          LDA   $C0D2      ;BIT 2
C518:AD D2 C0       11          LDA   $C0D2
C51B:29 0F          12          AND   #$0F
```

Listing 1 continued on page 296

Listing 1 continued:

```
C51D:8D 03 03     STA  $303      ;STORE BIT 2
C520:AD D1 C0     LDA  $C0D1     ;BIT 3
C523:AD D1 C0     LDA  $C0D1
C526:29 0F        AND  #$0F
C528:8D 04 03     STA  $304      ;STORE BIT 3
C52B:AD D0 C0     LDA  $C0D0     ;BIT 4
C52E:AD D0 C0     LDA  $C0D0
C531:29 0F        AND  #$0F
C533:8D 05 03     STA  $305      ;STORE BIT 4
C536:A9 00        LDA  #$00      ;LOAD A WITH 00
C538:A9 00        LDA  #$00
C53A:8D D0 C0     STA  $C0D0     ;START CONVERSIONS
C53D:8D D0 C0     STA  $C0D0
C540:8D 06 03     STA  $306      ;SIGNAL SAMPLE DONE
C543:8D 06 03     STA  $306
C546:60           RTS
```

(1c)

```
                                  CTRL-
SOURCE FILE: ENERGY A/D7
----- NEXT OBJECT FILE NAME IS ENERGY A/D7.OBJ0
C700:             ORG  $C700     ;SLOT FOR VOLTAGE A/D
C700:A9 80        LDA  #$80      ;STOP CONV. TO SAMPLE

C702:A9 80        LDA  #$80
C704:8D F0 C0     STA  $C0F0
C707:8D F0 C0     STA  $C0F0
C70A:AD F3 C0     LDA  $C0F3     ;BIT 1
C70D:AD F3 C0     LDA  $C0F3
C710:29 0F        AND  #$0F      ;USE LOWER BITS
C712:8D 07 03     STA  $307      ;STORE BIT 1
C715:AD F2 C0     LDA  $C0F2     ;BIT 2
C718:AD F2 C0     LDA  $C0F2
C71B:29 0F        AND  #$0F
C71D:8D 08 03     STA  $308      ;STORE BIT 2
C720:AD F1 C0     LDA  $C0F1     ;BIT 3
C723:AD F1 C0     LDA  $C0F1
C726:29 0F        AND  #$0F
C728:8D 09 03     STA  $309      ;STORE BIT 3
C72B:AD F0 C0     LDA  $C0F0     ;BIT 4
C72E:AD F0 C0     LDA  $C0F0
C731:29 0F        AND  #$0F
C733:8D 0A 03     STA  $30A      ;STORE BIT 4
C736:A9 00        LDA  #$00      ;LOAD A WITH 00
C738:A9 00        LDA  #$00
C73A:8D F0 C0     STA  $C0F0     ;START CONVERSION
C73D:8D F0 C0     STA  $C0F0
C740:8D 0B 03     STA  $30B      ;SIGNAL SAMPLE DONE
C743:8D 0B 03     STA  $30B
C746:60           RTS
```

(1d)

```
                                  CTRL-
SOURCE FILE: ENERGY1
----- NEXT OBJECT FILE NAME IS ENERGY1.OBJ0
C400:             ORG  $C400      LOAD AT SLOT 4
C400:A5 45        LDA  $45
C402:20 4A FF     JSR  $FF4A      SAVE REGISTERS
C405:BA           TSX
C406:BD 00 01     LDA  $0100,X
C409:0A           ASL  A          MULT BY 2
C40A:0A           ASL  A          MULT BY 2
C40B:0A           ASL  A          MULT BY 2
C40C:0A           ASL  A          MULT BY 2
C40D:A8           TAY              PUT IN Y
C40E:A2 40        LDX  #$40       PUT 40 IN X
C410:A9 20        LDA  #$20
C412:99 81 C0     STA  $C081,Y    GET SEC
C415:B9 80 C0     LDA  $C080,Y
C418:29 0F        AND  #$0F
C41A:9D C0 02     STA  $02C0,X
C41D:CA           DEX
C41E:A9 21        LDA  #$21
C420:99 81 C0     STA  $C081,Y    GET SEC
C423:B9 80 C0     LDA  $C080,Y
C426:29 0F        AND  #$0F
C428:9D C0 02     STA  $02C0,X
C42B:CA           DEX
C42C:A9 22        LDA  #$22
C42E:99 81 C0     STA  $C081,Y    GET MIN
C431:B9 80 C0     LDA  $C080,Y
C434:29 0F        AND  #$0F
C436:9D C0 02     STA  $02C0,X
C439:CA           DEX
C43A:A9 23        LDA  #$23
C43C:99 81 C0     STA  $C081,Y    GET MIN
C43F:B9 80 C0     LDA  $C080,Y
C442:29 0F        AND  #$0F
C444:9D C0 02     STA  $02C0,X
C447:CA           DEX
C448:A9 24        LDA  #$24
C44A:99 81 C0     STA  $C081,Y    GET HOUR
C44D:B9 80 C0     LDA  $C080,Y
C450:29 0F        AND  #$0F
C452:9D C0 02     STA  $02C0,X
C455:CA           DEX
C456:A9 25        LDA  #$25
C458:99 81 C0     STA  $C081,Y    GET HOUR
```

Listing 1 continued:

```
C45B:B9 80 C0        LDA   $C080,Y
C45E:29 03           AND   #$03
C460:9D C0 02        STA   $02C0,X
C463:CA              DEX
C464:A9 27           LDA   #$27
C466:99 81 C0        STA   $C081,Y    GET DAY
C469:B9 80 C0        LDA   $C080,Y
C46C:29 0F           AND   #$0F
C46E:9D C0 02        STA   $02C0,X


C471:CA              DEX
C472:A9 28           LDA   #$28
C474:99 81 C0        STA   $C081,Y    GET DAY

C477:B9 80 C0        LDA   $C080,Y
C47A:29 0F           AND   #$0F
C47C:9D C0 02        STA   $02C0,X
C47F:CA              DEX
C480:A9 29           LDA   #$29
C482:99 81 C0        STA   $C081,Y    GET MONTH
C485:B9 80 C0        LDA   $C080,Y
C488:29 0F           AND   #$0F
C48A:9D C0 02        STA   $02C0,X
C48D:CA              DEX
C48E:A9 2A           LDA   #$2A
C490:99 81 C0        STA   $C081,Y    GET MONTH
C493:B9 80 C0        LDA   $C080,Y
C496:29 0F           AND   #$0F
C498:9D C0 02        STA   $02C0,X
C49B:CA              DEX
C49C:A9 2B           LDA   #$2B
C49E:99 81 C0        STA   $C081,Y    GET YEAR
C4A1:B9 80 C0        LDA   $C080,Y
C4A4:29 0F           AND   #$0F
C4A6:9D C0 02        STA   $02C0,X
C4A9:CA              DEX
C4AA:A9 2C           LDA   #$2C
C4AC:99 81 C0        STA   $C081,Y    GET YEAR
C4AF:B9 80 C0        LDA   $C080,Y
C4B2:29 0F           AND   #$0F
C4B4:9D C0 02        STA   $02C0,X
C4B7:20 00 C5        JSR   $C500      SLOT 5 A/D
C4BA:20 00 C7        JSR   $C700      SLOT 7 A/D
C4BD:A9 6F           LDA   #$6F
C4BF:99 81 C0        STA   $C081,Y
C4C2:20 3F FF        JSR   $FF3F
C4C5:40              RTI
C4C6:08              PHP               ;CALL THIS LOC.
C4C7:48              PHA               ;TO START PROG.
C4C8:8A              TXA
C4C9:48              PHA
C4CA:20 CB FF        JSR   $FFCB
C4CD:BA              TSX
C4CE:BD 00 01        LDA   $0100,X    ;INTER. ADDRES
C4D1:8D FF 03        STA   $03FF      ;HI-INTER VEC.
C4D4:0A              ASL   A          MULT BY 2
C4D5:0A              ASL   A          MULT BY 2
C4D6:0A              ASL   A          MULT BY 2
C4D7:0A              ASL   A          MULT BY 2
C4D8:AA              TAX
C4D9:A9 00           LDA   #$00
C4DB:8D FE 03        STA   $03FE      ;LO-INTER VEC.
C4DE:A9 6F           LDA   #$6F
C4E0:9D 81 C0        STA   $C081,X
C4E3:68              PLA


C4E4:AA              TAX
C4E5:68              PLA
C4E6:28              PLP
C4E7:58              CLI
C4E8:60              RTS
C4E9:78              SEI
C4EA:60              RTS
```

MAROT ANNOUNCES THE FIRST COMPUTERS POWERFUL ENOUGH TO RELIEVE GROWING PAINS.



Sooner or later, your small business will look for a so-called "first" computer. And sooner or later, your small business will grow larger and need more computer capacity.

Fortunately, Marot Systems has anticipated your needs and offers two "first" computers that have the capacity to grow as large as you do.

Altos: upgradeable, portable and affordable.

Start out with a low cost multiuser Altos dual floppy based system with 208 K of RAM. It's perfect for inexpensive work stations or applications like accounting, word processing, mailing lists and more.

If you're already in need of more storage and greatly enhanced access speed, then look into the Altos 10Mb-58Mb hard disk systems. When combined with the standard 208 K of RAM, 6 serial I/O and 2 parallel ports, they become unusually fast and powerful 4-user business or scientific systems.

All Altos systems are packaged with single board Z80 CPU, quality Shugart 8-inch disk drives, and options such as DMA (required for OASIS) floating point processors, and a cartridge tape back-up subsystem.

So as you grow, you just add onto your system. Without suffering the growing pains of eating the costs of your "first" computer.

Onyx: maximum integration in one sleek box.

The Onyx represents a new standard of quality and cost effectiveness in small business computers.

The 8-bit C8001/MU is an ideal multi-user system for business or word processing applications. It combines Z80 high speed processors, standard 128 K RAM, (expandable to 256 K), Winchester disk and integral cartridge tape drive in an efficient, compact package. And using reentrant BASIC application programs, it allows up to 5 simultaneous operators.

When you need the power of a 16 bit computer, you want the C8002. It uses a special edition of Bell Laboratories UNIX operating system to accommodate up to 8 users involved in product development or executing application programs in C, COBOL, PASCAL or C-BASIC II.

You can also expand the RAM of the C8002 to 1 Mb and its disk capacity to over 300 Mb. So you get all the growing power you need. With none of the growing pains.

Marot: looking for good dealers for 2 great systems.

Marot, East Coast Distributor for Altos and Onyx, needs a few qualified dealers for these two hot items. If you're the great dealer we need, please contact us.

MAROT SYSTEMS INC.
310 Madison Avenue, New York, NY 10017

I am a ☐ computer consultant
☐ computer dealer ☐ computer user
Please send me more information on:
☐ Altos ☐ Onyx

Name____________________

Title ____________________

Company ____________________

Address ____________________

City/State/Zip ____________________

Phone(   )____________________

Z80 is a trademark of Zilog, Inc.
C-BASIC II is a trademark of Compiler Systems
UNIX is a trademark of Western Electric Corporation

marot

MAROT SYSTEMS, INC.
310 Madison Avenue, Suite 408,
New York, N.Y. 10017
(212) 661-8550 TWX: 710-581-2477
Circle 218 on inquiry card.

Text continued from page 294:

module that can be directly interfaced with the Apple II computer to give accurate energy measurements.

The module's principle of operation is fairly simple. The clock calls for an interrupt once each second. Data is sampled and placed in a memory location where an Applesoft BASIC program assembles it into voltage, current, power, and energy readings. The clock/calendar card and the A/D cards must be fitted with 2112-type programmable memories to hold the machine-language programs shown in listing 1 (two devices per card). The machine-language programs were written to be "slot dependent," and unless they are modified, the clock/calendar must reside in slot 4, the voltage A/D card in slot 5, and the current A/D card in slot 7.

The Applesoft program in listing 1 uses a split screen to display the data. Because a clock/calendar module is used, you have the ability to record the date when the samples are taken, along with the time of *maximum* readings (often extremely important to solar- and wind-generator experimenters). The program displays the present voltage, current, and power being produced by the source, along with average and peak power, number of kilowatt-hours, number of samples, and time of maximum readings. The date and time are updated once per second, with the remainder of the data being updated once each minute.

If the power is being fed into a constant load, only one A/D converter will be necessary because you'll be able to calculate power from the equation:

$$P = \frac{E^2}{R}$$

where P is power in watts, E is voltage, and R is the load resistance in ohms. If this is the case, delete lines 40, 360, 370, 380, 390, 400, 570, and 580 from listing 1. Modify line 770 to read PC = (V↑2)/R and line 590 to read C = V/R, where R is the resistance of your load.

The A/D converter has a full-scale reading of 3.999 V, but the range can be extended with the use of a voltage divider. For example, the wind-driven generator I work with produces a maximum of +200 V DC. Figure 1a shows the voltage-divider network used in that application. The voltage-divider network reduces 200 V to 4 V, which is a 50-to-1 reduction. (Note that 50 is the multiplier constant in line 560 of the program.) The 50 k-megohm potentiometer permits calibration, while the two 1-megohm resistors and the fuses protect the Apple and the converter boards from trouble.

Current can be measured indirectly by sampling the voltage drop across a series resistance. (See figure 1b.) In my work application, currents of up to 20 A can be expected, so a shunt resistance of 0.25 ohms was made from a piece of 30 gauge wire, $2\frac{9}{10}$ inches long. Again, the 50 k-ohm potentiometer permits calibration and the two 1-megohm resistors and the fuses provide protection. This current divider produces a 5-to-1 division (note the multiplier in line 590 of listing 1).■

Further product information can be obtained from California Computer Systems, Santa Clara CA 95050. I will try to answer correspondence concerning the software if a self-addressed, stamped envelope is enclosed. Address correspondence to Dr William H Murray, Engineering Science Department, Broome Community College, Binghamton NY 13902.

Programming Quickies

Computing Inflation With the Consumer Price Index

Joe Haldeman
c/o BYTE
POB 372
Hancock NH 03449

Every now and then someone comes along who refuses to be impressed by your computer. He thinks the games are silly. He sees better graphics on television. The really interesting programs he can't understand. Try this one on him. But don't let the tears fall on the keyboard.

In this simple program we ask the computer the age-old question "What does the future hold for me?"—and it answers, "Trade in your wallet for a wheelbarrow."

The BASIC program INFLATION (see listing 1) reads in the United States' CPI (Consumer Price Index) from 1945 to the present as a one-dimensional array. It computes how much a certain amount in the past would buy today, or how much a current sum would be worth in yesterday's dollars. Within limits, it extrapolates inflationary trends into the future. (The limit being the assumption that inflation will continue at a steady, predictable rate. If you believe that, boy, do I have a bridge for you!)

The program helps when you are making a decision to buy something—check the item against an old catalog and see how much of a price increase is justified by inflation. You can also find out how much of a pay raise you actually got last time, or how to set the price of a piece of real estate. My own use for it has been in the preparation of a book on the space program, trying to get a realistic perspective on how much a few billion dollars is *really* worth, from Eisenhower to Reagan. (Answer: $10 billion 1952 = $36 billion 1981.)

One technical point is that there are now two Consumer Price Indices, our government having discovered that a dollar is worth more to a poor person than to a rich one. The CPI-W index is based on the purchasing patterns of urban wage-earners and clerical workers; the CPI-U index is weighted toward the needs of the retired and unemployed. I've used the former index, figuring that rather few people buy their computers with food stamps. ■

C ~~or~~ AND Pascal

Efficiency ~~or~~ AND Portability

Flexibility ~~or~~ AND Strong Typing

Now you don't have to compromise!

Whitesmiths Ltd. now offers portable language development systems for four families of computers. Approximately one thousand installations use our software.

We support complete versions of both C and Pascal, as compilers and cross-compilers. You get C automatically when you license Pascal, and you get native support with each cross-compiler. Test the software on your VAX before burning PROMs for your 68000 or 8080.

Whitesmiths Ltd. offers a variety of licensing arrangements, the simplest being a binary license for use on a single CPU. The full source code is available with internal documentation. Maintenance, training and sublicensing rights may also be obtained.

Call or write for more information.

Source Operating Systems	Target Machines			
	8080/Z80	LSI-11/PDP-11	VAX-11	M68000
8080/Z80 CP/M	C: $630 Pascal: $880	*	*	*
LSI-11/PDP-11: Idris, Unix, RT11, RSX-11/M, RSTS/E, IAS	C: $1130 Pascal: $1380	C: $630 Pascal: $880	*	C: $1130 Pascal: $1380
VAX-11 Unix/V32 VMS	C: $1130 Pascal: $1380	*	C: $630 Pascal: $880	C: $1130 Pascal: $1380
M68000 VERSAdos	*	*	*	C: $630 Pascal: $880

Idris is a trademark of Whitesmiths, Ltd. ■ Unix is a trademark of Bell Laboratories ■ CP/M is a trademark of Digital Research Company ■ VMS, RSX-11/M, RSTS/E, LSI-11, VAX, are trademarks of Digital Equipment Corporation ■ VERSAdos is a trademark of Motorola Corporation

* Special Order

Protect your software investment.

Whitesmiths, Ltd.

P.O. Box 1132 Ansonia Station New York, N.Y. 10023
(212) 799-1200

Listing 1: *This Applesoft BASIC program, using Consumer Price Indices for past years, can calculate the current value of $50 from the year 1956, or help determine the increase in value of a piece of property due to inflation. Lines 190 and 210 must be updated every year.*

```
10  REM   ***************
20  REM   ** INFLATION **
30  REM   ***************
40  REM
50  REM    **. A PROGRAM GIVING
60  REM   DOLLAR EQUIVALENTS FOR
70  REM   ANY TWO YEARS BETWEEN
80  REM  1945 AND THE NEAR FUTURE

90  REM
100  REM   (NOTE THAT STATEMENTS
110  REM   190 AND 210 MUST BE
120  REM   ANNUALLY UPDATED.)
130  REM
140  DIM X(2000)
150  REM
160  REM      ** READ IN CONSUMER
170  REM      PRICE INDEX
180  REM
190  FOR I = 1945 TO 1981
200  READ X(I)
210  DATA  1.855,1.709,1.495,1.38
     7,1.401,1.387,1.285,1.258,1.
     248,1.242,1.247,1.229,1.186,
     1.155,1.145,1.127,1.116,1.10
     4,1.091,1.076,1.058,1.029,1,
     .96,.911,.86,.824,.799,.752,
     .678,.621,.587,.551,.493,.46
     1,.404,.35
220  NEXT
230 YEAR = I - 1
240  REM
250  REM   ** (FIGURE FOR 1981
260  REM   IS A CONSERVATIVE
270  REM   EXTRAPOLATION ... )
280  REM
290  PRINT : PRINT : PRINT "WHAT
     IS THE AMOUNT?"
300  INPUT P1
310  PRINT : PRINT : PRINT "IN WH
     AT YEAR?"
320  INPUT Y1
330  PRINT : PRINT : PRINT "FOR W
     HAT YEAR WOULD"
340  PRINT "YOU LIKE THE EQUI-"
350  PRINT "VALENT PRICE?"
360  INPUT Y2
370  IF Y2 > YEAR GOTO 510
380 P2 = P1 * X(Y1) / X(Y2)
390  REM
400  REM    ** PUT ANSWER INTO
410  REM       "DOLLAR" FORMAT
420  REM
430  IF P2 =  INT (P2) THEN P$ =
     "$" +  STR$ (P2): GOTO 450
440 P$ = "$" +  STR$ ( INT (P2)) +
      LEFT$ ( STR$ (P2 -  INT (P2
     )),3)
450  PRINT : PRINT : PRINT "IF IT
      COST $";P1;" IN ";Y1
460  PRINT "THEN IT WOULD COST ";
     P$;" IN ";Y2;"."
470  PRINT : PRINT : PRINT "ANOTH
     ER COMPUTATION? (Y OR N)": PRINT

480  INPUT Q$
490  IF Q$ = "Y" GOTO 290
500  END
510  PRINT : PRINT : PRINT "WHAT
     RATE OF INFLATION"
520  PRINT "DO YOU PREDICT?"
530  PRINT "(EXPRESS AS DECIMAL)"

540  INPUT R
550 P2 = P1 * X(Y1) / X(YEAR)
560 P2 = P2 * (1 + R) ^ (Y2 - YEA
     R)
570  GOTO 440
```

CSC Logic Probe Kit.

$17.95 Complete, easy-to-follow instructions help make this a one-night project.

BUY 5 FOR $16.15 each

$124.95 apple clock/calendar

- Seconds, minutes, hours, day-of-week, month, date, & year.
- On board batteries with one year life.
- Uses MSM5832-crystal controlled.

APPLE CARDS

- SERIAL CARD → $159.00
- PARALLEL CARD → $99.00
- INTEGER or APPLESOFT CARD → $189.00
- PASCAL SYSTEM → $425.00
- PROTO BOARD → $25.00

"APPLE II Plus"

48k–$1199.00
64k–$1399.00

W/PURCHASE OF APPLE RECEIVE SPECIAL PRICING:

- BASE II PRINTER → $619.00
- DISK II w/cont. → $595.00
- DISK II w/o cont. → $495.00
- SUP'R'MOD II → $23.00
- MONITOR: B&W 12"–12MHz. → $125.00
- INTEGER BASIC CARD → $169.00

HOME STUDY COURSE ON CASSETTE

Each course below includes a special course book plus two cassettes for a total course length of 2½ hours. The lecture is completely coordinated to the pages of the book and cassettes can be played on any standard cassette player.

S1·INTRODUCTION TO MICROPROCESSORS

For Non-Specialists. Course contains: Definitions • Application • Evaluation Terms • System Components • 2.5 hrs.

$29.95

S2·PROGRAMMING MICROPROCESSORS

For the student who has completed S-1. GOAL: To provide an over-all and practical understanding of the concepts of Micro Computer Programming. 2.5 hours.

$29.95

• NO TECHNICAL BACKGROUND ASSUMED •

78H05 $5.95 TO-3 case 5 AMPS 5 VOLTS

MSM5832 MICROPROCESSOR REAL-TIME CLOCK/CALENDAR

XTAL. $3.85

GENERAL DESCRIPTION

The MSM5832 is a monolithic metal-gate CMOS integrated circuit that functions as a real time clock calendar for use in bus-oriented microprocessor applications. The on chip 32 768 Hz crystal controlled oscillator time base is counted down to provide addressable 4 bit I O data of SECONDS MINUTES HOURS DAY OF WEEK DATE MONTH and YEAR. Data access is controlled by 4 bit address chip select read write and hold inputs. Other functions include 12H 24H format selection leap year identification and manual 30 second correction.

The MSM5832 normally operates from a 5 volt 5% supply. Battery back up operation down to 2 2 volts allows continuation of time keeping when main power is off. One test input facilitates rapid testing of the time keeping operations. The MSM5832 is offered in an 18-lead dual in line plastic (RS suffix) package.

$7.45

FEATURES

- Microprocessor bus oriented
- TIME 23 59 59 · MONTH 12 · DATE 31 · YEAR 99 · DAY OF WEEK 7
- 4 BIT DATA BUS
- 4 BIT ADDRESS
- Read Write Hold Chip select inputs
- Interrupt signal outputs – 1024 1 1 60 1 3600 Hz
- 32 768 KHz crystal controlled operation
- Leap year register bit
- 12 or 24 hour format
- 30 second error correction
- Single 5 volt power supply
- Back up battery operation to Vcc 2 2 V
- Low Power Dissipation 90 uw Max at Vcc 3 V, 2 5 mw Max at Vcc 5 V
- High Density 300 mil 18 Pin Package

video 100 $129.00 ~~$130.00~~ Leedex Corp 12" BLACK & WHITE LOW COST VIDEO MONITOR

COLOR $365.00 13"

Green Phos 12 inch. $155.00

SOROC TECHNOLOGY INC



IQ120 $689.00

No "Glitches", Surges Or Interference

Marway's MPD 117 turns an ordinary outlet into a controlled power source for up to 8 devices

The MPD 117 is the low-cost solution to your power distribution problems

$79.50

Global Specialties Logic Probes



LP1 $40



LP3 $60

2716 5V 450NS	7.25ea	8 for 6.50ea
2708 450NS	4.25ea	8 for 4.00ea
2732	24.50ea	4 for 19.50ea
4116 300NS	3.00ea	8 for 17.50
4116 200NS	3.75ea	8 for 19.50
2114L 300NS	3.50ea	4 for 13.75
2114L 200NS	3.75ea	4 for 14.25

MODEL 800B



IMPACT PRINTER

- Dot resolution graphics in six densities
- 1920 character buffer
- Fully adjustable tractors to 9-1/2"

$649.00

base 2 inc.

UNIBOX ENCLOSURES SIX SIZES → NEW

Attractive grain finish high-impact ABS thermoplastic enclosures. Molded-in card guides & mounting bosses provide maximum versatility. Supplied with assembly hardware.

ENCLOSURES

PART NUMBER	DIMENSIONS X		Y		Z	PRICE
110 *	1.25"	x	2.07"	x	2.77"	$2.85
120 *	1.50"	x	2.65"	x	3.75"	3.51
130 *	1.50	x	3.25"	x	4.38"	3.84
133 *	2.00"	x	3.25"	x	4.38"	4.28
140 *	1.50"	x	4.00"	x	5.30"	4.72
144 *	2.00"	x	4.00"	x	5.30"	5.16

* SPECIFY COLOR: GRAY BROWN ORANGE

MATERIAL: ABS

IC SOCKETS

PIN	
8	10/1.20
14	10/1.40
16	10/1.60
18	10/1.90
20	10/2.80
22	10/2.80
24	10/2.80
28	10/3.80
40	10/4.75

CPUs

Z-80	8.95
Z-80A CTC	12.50
Z-80A CPU	12.50
Z-80 002 16-64K	129.00
8085A	11.50
2901A	12.50
MC6800	9.50

New for the APPLE → MICROSOFT 16K RAM CARD $159.95

S·100 MEMORY BOARD

SUPER SALE!!

16K STATIC RAM

FULLY STATIC OPERATION 4K BANK ADDRESSABLE EXTENDED MEMORY MGMT MEETS IEEE PROPOSED S-100 SIGNAL STANDARDS 4 MHZ OPERATION

ASSEMBLED & TESTED $269.

California Computer Systems

Apple Expansion Kit 16K Memory Add-On Includes Instructions $25.95

TRS80 16K Add-On Instructions & Dip Switches $25.95

ATARI® 800™ COMPUTER SYSTEM



- 400 Computer 8K → $419.00
- 800 Computer 16K → $779.00
- *800 COMPUTER w/48K → $989.00

*Best Buy

ATARI PERIPHERALS:

Printer ("825")	$775.00	Printer ("822")	$379.00
Recorder	$65.00	Disk Drive	$565.00
Interface (850)	$175.00	Modem	$169.00
Paddles	$17.00	Joysticks	$17.00
Star Raiders	$49.00	Assembler Editor	$49.00
Space Invaders	$17.00	Music Composer	$49.00
Chess	$32.00	Mailing List	$17.00
Kingdom	$12.00	TV Switch Box	$8.95
Hangman	$12.00	16K RAM	$155.00
Blackjack	$12.00	8K RAM	$119.00

Circle 79 on inquiry card.

VISICALC APPLE → 129. ATARI → 154.

"1981" I.C. Master $59.95

EPSON MX-80 $560.00

MB8264–20 64K RAM w/SPEC's → $29.50

ER2051 EAROM → $4.50

P8155 → $19.50

"ALLOW 2 WKS. DEL'Y IF PERSONAL CHECK IS SENT."

74LS00	.26	74LS155	1.15
74LS02	.26	74LS158	.75
74LS03	.26	74LS160	.95
74LS04	.26	74LS161	.85
74LS08	.28	74LS162	.95
74LS09	.26	74LS163	1.60
74LS10	.26	74LS164	.65
74LS20	.26	74LS165	.65
74LS21	.28	74LS170	1.75
74LS22	.26	74LS174	.75
74LS26	.49	74LS175	.75
74LS27	.26	74LS190	.75
74LS30	.28	74LS193	.95
74LS32	.32	74LS195	.95
74LS38	.32	74LS196	.85
74LS42	.65	74LS221	1.40
74LS48	.78	74LS240	1.65
74LS51	.25	74LS241	1.65
74LS54	.35	74LS243	1.45
74LS74	.38	74LS244	1.45
74LS75	.60	74LS245	2.25
74LS83	.44	74LS253	.95
74LS85	.95	74LS257	.95
74LS86	.95	74LS258	.95
74LS90	.69	74LS259	2.85
74LS93	.69	74LS279	.44
74LS107	.45	74LS283	1.00
74LS112	.38	74LS293	1.85
74LS113	.48	74LS298	1.20
74LS122	.48	74LS366	.95
74LS123	.95	74LS367	.55
74LS126	.69	74LS368	.55
74LS138	.69	74LS373	1.39
74LS151	.44	74LS374	1.39
74LS153	.44	74LS386	.65



5712 Panel W 1½ H 5¼ — 5722 Shelf W 3½ H 5¼



Connector Layout

$145.00 $155.00

Description

The RS-232C Compatible Digital Transfer Switch is designed to switch modems between front end processors. All 24 pins of the connector are switched, with Pin 1 wired to ground.

T-bar INCORPORATED

CONCORD COMPUTER PRODUCTS

1971 SO. STATE COLLEGE
ANAHEIM, CALIF. 92806
(714) 937-0637

☆send $1.00 for "81" catalog☆

VISA · master charge · CHECK — M/O · NO COD

$10. MIN ORDER / CA. RES. ADD 6%

FRT.

10-49$	2.00$	250-499$	8.00
50-99	4.00	500-999	10.00
100-24	7.00	1000-Up	Inquire

BYTELINES

News and Speculation About Personal Computing

Conducted by Sol Libes

CSNET Approved: The National Science Foundation has approved the establishment of CSNET (computer science network), a cooperative effort of computer scientists to establish a computer-based communications network that will interconnect research groups in universities, industry, and government. Based on recent advances in computer-networking technology, including international protocol standards and the availability of commercial packet networks, CSNET will provide a means for collaborative work at the forefront of computer-science research. CSNET will initially link host computers on a number of other communications networks, including ARPANET, Telenet, and Tymnet. Later, it may be expanded to include other networks.

Computer Sales Up: The Department of Commerce (DOC) estimates that this year US computer makers will ship $32.8 billion worth of computers, up from $26 billion last year. This is an increase of 15% after inflation. 1980 saw a 24% increase over 1979. DOC estimates that personal-computer sales in 1980 exceeded $1 billion, a 100% increase over 1979. US computer exports are four times that of the Japanese, five times that of the French, seven times that of the West Germans, and almost ten times that of the British. DOC notes, however, that the Japanese are moving aggressively into the US and are expected to capture 30% to 40% of the personal-computer market.

Videodisk Players And Microcomputers Combined: The newest rage in DBS (data-base systems) and CAI (computer-aided instruction) is the combination of a videodisk player and microcomputer system. This allows large, highly intelligent, and low-cost CAI or DBS programs to be created. The videodisk player (VDP) is usually hooked up to the computer system via an RS-232C serial interface or IEEE-488 bus channel.

A user can interrogate and directly access any part of the information on the VDP in a fully interactive manner, with a typical response time of 1 second. For example, the DiscoVision VDP can store up to 100,000 megabytes on either side of a VDP disk. That's roughly the contents of 180 volumes of 300 pages each or about fifteen years' worth of BYTEs. With this approach, an immense library of information is instantly accessible to the user. Doctors, lawyers, engineers, and any other professionals constantly accessing reference material can have a complete library at their fingertips.

In CAI, the VDP/microcomputer combination makes high-fidelity mono- or multiple-channel audio, color video, and data available. If voice-input equipment matures, it's conceivable that the microcomputer keyboard may not even be needed.

SSM Microcomputer Products demonstrated a VDP/microcomputer system this past April at the San Francisco Computer Faire. The system used a DiscoVision Associates VDP (which is a joint venture of IBM and MCA) and an Apple II.

Peddle and Paivenen Back In Business: In 1975, a small outfit by the name of MOS Technology introduced a microprocessor called the 6502. Nobody paid much attention to it with heavyweights like Intel's 8080 and Motorola's 6800 around. Yet, the 6502 presented some unique features, and a few smart designers latched on to it (eg: Apple Computer Inc). Then in 1976, MOS Technology introduced a single-board computer called the KIM. Before the KIM, few had ever conceived of a whole computer on a single printed-circuit board; and, in 1977, MOS Technology shook everybody with the first "totally integrated personal computer"—the PET.

The 6502 went on to surpass the 8080 and 6800 in sales. The KIM and PET were copied by many companies and spearheaded the rocket-like growth of the personal-computer market.

The two fellows who started and led MOS Technology through its pioneering projects were John O Paivenen (founder) and Chuck Peddle (the technical guru). In late 1976, the company was bought by Commodore International, and John and Chuck lingered there for awhile, then left. They have now started a new venture called Sirius Systems Technology, Scotts Valley, California. Their first product will be a computer system to compete in the small-business-computer field. Strangely enough, it will use an Intel 8085 microprocessor.

Amateur Data Net Urged: A data-communications network for amateurs is being developed by AMRAD (Amateur Radio Research and Development Corporation). A formal proposal for funding of the AMNET (amateur network) project has been submitted to ARRL (American Radio Relay League). In it, AMRAD calls for a North American computer-communications network composed of seven HF (high-frequency) nodes (packet radio stations) tied into local VHF (very high frequency) message systems. (See the July 1981 "BYTELINES," page 214.) A portable node may be added later.

If approved, ARRL will serve as the network manager, AMRAD as the developer, and the VADCG (Vancouver Amateur Digital Communications Group) as the system designer. AMRAD hopes to have its link in operation soon. Different message formats are being developed for electronic mail, information conversations, and file transfer.

Two data-communications networks are already on air, one in Vancouver, British Columbia, and the other in San Francisco. Both systems use the VADCG packet-node-controller boards.

In other data-communications news, Kelly Smith, one

PLAN80
A powerful tool for planning and analysis
bpc
business planning systems
PLAN80

of the leading developers of CP/M remote-network systems, is now publishing the *CP/M-Net News*. The newsletter has up-to-the-minute reports for CP/M developers and users. It costs $18. For details, write to *CP/M-Net News*, 3055 Waco St, Simi Valley CA 93063.

On another front, Novation Inc, the maker of low-cost modems, has set up a free computer-accessible information number. The system is available 24 hours a day. The data rate is 300 bps (bits per second). To gain access, dial (213) 881-6880 and type CAT followed by Return. You'll be given an eighteen-item menu of the information files (eg: there are modem and printer tests). The files are updated monthly.

Another UNIX Users Group Formed: Uni-ops is a new organization for UNIX fans. It intends to publish a monthly journal and a members' directory. Uni-ops will hold a convention the third week of October in San Francisco. Membership is $24. For details, write to Uni-ops, POB 5182, Walnut Creek CA 94596, or call (415) 933-8564.

Rockwell Casts Off Bubble Memories: Rockwell International, one of the earliest entrants in the bubble-memory market, is abandoning the race. Company sources concede that the bubble-memory market refused to develop as expected. The company will continue making the 256 K-bit bubble-memory devices for military applications. Rockwell had been working on a 1-megabit bubble device. Intel, Texas Instruments, and National Semiconductor are still making bubble-memory devices, and Motorola is expected to enter the market.

Maximum IC Density Predicted: Stanford University's James D Meindl has predicted that the maximum number of transistors fabricated on a single integrated-circuit chip will be 1 billion and that this density will be reached by the turn of the century. That's a big leap from current 8-bit microprocessors, which have about 30,000 transistors, or Intel's new iAPX432 32-bit microprocessor, which has approximately 150,000 transistors on each of the integrated circuits in its three-chip set.

OSI and Montgomery Ward To Open Computer Stores: For more than a year, Ohio Scientific and Montgomery Ward (MW) have been experimentally marketing personal computers in selected MW stores. Now the two companies have reached an agreement whereby OSI will site computer stores within MW outlets. Six such stores will be opened soon. The computer stores will be owned and operated by OSI dealers with a percentage of the income going to the Montgomery Ward store.

Memory Fixes Itself On-the-Fly: National Semiconductor has made public details of its new ECC (error-correcting code) memory. The ECC has sixteen spare programmable-memory integrated circuits per megabyte and substitutes a good memory for a faulty one on-the-fly. The error-checking and replacement are transparent to the main computer. While the technique is not new, applying it on the integrated-circuit level is.

Here's how it works: all data written is automatically read back and verified to determine if there is a memory error. If there is, a new integrated circuit is switched with the defective chip by "blowing" off fusible links. The system keeps track of the number of replacement circuits and gives a warning when the number of spares gets low.

Intel also has a self-correcting memory system. It switches memory banks into and out of a system.

Random News Bits: Atari will "private-label" microcomputer systems for Sears Roebuck. . . . Tandy will go into the OEM (original equipment manufacturing) computer business. Incidentally, Tandy reported net sales for January 1981 of $141.3 million, up from $112.3 million last year, a 26% gain. . . . Venture Development Corporation, Wellesley, Massachusetts, is predicting that shipments of personal computers will increase from fewer than 400,000 units in 1980 to almost two million in 1985. That's an effective growth rate of 37% per year. . . . RCA has been selected to design and install the Postal Service's first electronic mail system. It's projected to be operating by 1982. . . . Intel Corporation has reduced the price of the plastic-package version of the 8088 microprocessor to $14.10, in quantities over 100. The 8088 is instruction-set-compatible with the 16-bit 8086 microprocessor, but uses an 8-bit data bus. . . .

Random Rumors: It's rumored that Fujitsu is working on a large-capacity Winchester-technology disk drive for the micro/minicomputer market. The "Eagle" will supposedly have a capacity of 464 megabytes, using a 12-inch platter. It is expected to sell for $8000-$8500, in original equipment manufacturers quantities. . . . Apple Computer Inc may soon offer a modem card that operates at up to 1200 bps. It may be made by Novation. . . . Expect Hewlett-Packard (HP) to unveil a new color-video terminal at a substantially reduced price. It could be out by late summer. HP's current color terminal costs $40,000. . . . It's rumored that the Japanese Ministry of International Trade and Industry may fund the development of a "fifth generation" computer with a new architecture far beyond semiconductors. The funding could be as much as $2.1 billion. The undertaking could involve five large Japanese component manufacturers over a seven-year period. . . .

Quote Of The Month: "More than a million computers are churning out 220 billion pages of information every working day" . . . Robert M Price, President, Control Data Corporation.

MAIL: I receive a large number of letters each month as a result of this column. If you write to me and wish a response, please include a self-addressed, stamped envelope.

Sol Libes
POB 1192
Mountainside NJ 07081

If you can't find the right program in our new catalog, it probably hasn't been written.

As the world's largest publisher of professional software for microcomputers, Lifeboat Associates offers the largest selection of state-of-the-art programs. And our new catalog has more to offer than ever. We also add the crucial dimension of after-sales service and full support to everything we sell. Order your free catalog today.

For a free catalog, mail coupon to Lifeboat Associates, 1651 Third Avenue, New York, NY 10028.
Or call (212) 860-0300. Telex 640693 (LBSOFT NYK)

CB781

Name________ Title________

Company________

Street________

City________ State________ Zip________

Our catalog contains full descriptions and specifications of the following:

DISK OPERATING SYSTEMS

CP/M CONFIGURED FOR:
- APPLE II
- DATAPOINT 1550/2150
- ICOM MICRO DISK
- ICOM 3712
- ICOM 3812
- ICOM 4511/PERTEC D3000
- INTEL MDS
- MICROPOLIS FLOPPY DISK
- MITS/ALTAIR
- MOSTEK MDX
- NORTH STAR
- OSI C3
- OSI C3B
- OSI C3C Prime
- TRS-80 MODEL II

MP/M FOR INTEL MDS

HARD DISK INTEGRATION MODULES

CORVUS WITH APPLE II SOFTCARD
CORVUS WITH S100 AND TRS-80 MODEL II
ICOM 4511/PERTEC D3000
KONAN PLUS CDC PHOENIX
XCOMP SM/S PLUS CDC PHOENIX
XCOMP OFC10 FOR PERTEC D3000

SYSTEMS TOOLS

BUG AND uBUG
DESPOOL
DISILOG
DISTEL
EDIT
EDIT-80
FILETRAN
IBM/CPM
MAC
MACRO-80
PASM
PLINK
PMATE
RAID
RECLAIM
SID
TRS-80 MODEL II CP/M CUSTOMIZATION
UNLOCK
WORD-MASTER
XASM-18
XASM-48
XASM-65
XASM-68
XMACRD-86
ZDT
Z80 DEVELOPMENT PACKAGE
ZSID

TELECOMMUNICATIONS

BSTAM
BSTMS

LANGUAGES

ALGOL-80
APL/V80
BASIC-80 (COMPILER)
BASIC-80 (INTERPRETER)
BOS C COMPILER
CBASIC-2
CIS COBOL
COBOL-80
FORTRAN-80
JRT PASCAL
muLISP
muSIMP
NEVADA COBOL
PASCAL/M
PASCAL/MT
PASCAL/MT+
PASCAL/Z
PL/I-80
S-BASIC
TINY C
TINY-C TWO
W'SMITHS C COMPILER
XYBASIC

LANGUAGE AND APPLICATIONS TOOLS

BASIC UTILITY DISK
DATASTAR
FABS
FORMS 1 FOR CIS COBOL
FORMS 2 FOR CIS COBOL
MAGSAM III
MAGSAM IV
MOBS.DRS
MDBS.RTL
M/SORT FOR COBOL-80
PEARL
PSORT
QSORT
STRING BIT
STRING /80
SUPER-SORT
ULTRASORT II

WORD PROCESSING SYSTEMS AND AIDS

MAGIC WAND
LETTERIGHT
MICROSPELL
SPELLGUARD
TEX
TEXTWRITER III
WORDSTAR
WORDINDEX

DATA MANAGEMENT PACKAGES

CONDOR
HDBS
MOBS
MDBS.QRS

GENERAL PURPOSE APPLICATIONS

CBS
SELECTOR III-C2
SELECTOR IV

MAIL LIST APPLICATIONS

MAILING ADDRESS (PTREE)
MAILMERGE FOR WORDSTAR
NAD
POSTMASTER

BUSINESS APPLICATIONS

ACCOUNTS PAYABLE (PTREE)
ACCOUNTS PAYABLE (SSG)
ACCOUNTS RECEIVABLE (PTREE)
ACCOUNTS RECEIVABLE (SSG)
GENERAL LEDGER II (CPAIDS)
GENERAL LEDGER (PTREE)
GENERAL LEDGER (SSG)
GLECTOR FOR SELECTOR III-C2
INVENTORY (PTREE)
INVENTORY (SSG)
PAYROLL (PTREE)
PAYROLL (SSG)

NUMERICAL PROBLEM-SOLVING TOOLS

ANALYST
FPL
muMATH
STATPAK
T/MAKER

OTHER SPECIALIZED APPLICATIONS

DATEBOOK
ESQ-1
PAS-3 DENTAL
PAS-3 MEDICAL
PROPERTY MANAGEMENT (PTREE)

BOOKS AND PERIODICALS

APL—AN INTERACTIVE APPROACH
ACCOUNTS PAYABLE & ACCOUNTS RECEIVABLE-CBASIC
8080/Z80 ASSEMBLY LANGUAGE
THE CP/M HANDBOOK
THE C PROGRAMMING LANGUAGE
CRASH COURSE IN MICROCOMPUTERS
FIFTY BASIC EXERCISES
GENERAL LEDGER-CBASIC
INTRODUCTION TO PASCAL
LIFELINES
THE PASCAL HANDBOOK
PASCAL USER MANUAL AND REPORT
PAYROLL WITH COST ACCOUNTING-CBASIC
STRUCTURED MICROPROCESSOR PROGRAMMING
USING CP/M-A SELF-TEACHING GUIDE

ACCESSORIES

DC 300 DATA CARTRIDGE
HEAD CLEANING DISKETTE
FLIPPY DISK KIT
FLOPPY SAVER

Program names and computer names are generally trademarks or service marks of the author or manufacturing company.

All software products have specific requirements for hardware and additional associated software (e.g. operating system or language).

All products are subject to terms and conditions of sale.

Prices and specifications are subject to change without notice.

All Lifeboat software requires CP/M unless otherwise stated.

ORDERING INFORMATION. COMPUTERS SUPPORTED INCLUDE:

Computer	Code
ADOS Multivision	RT
AVL Eagle	RB
Altair 8800	B1
Altos	A1
Apple CP/M 13 Sector	RG
Apple CP/M 16 Sector	RR
BASF System 7100	RD
Blackhawk Micropolis Mod II	Q2
CDS Versatile 3B	Q1
CDS Versatile 4	Q2
Columbia Data Products	A1
COMPAL-80	Q2
CSSN Backup	T1
Cromenco System 3	A1
Cromenco System 2 SDSS	R6
Cromenco System 2 DOSS	RX
Cromenco System 2 ODDS	RY
Datapoint 1550/2150 Single Sided	AA
Datapoint 1550/2150 Double Sided	AB
Delta Systems	A1
Digi-Log Microterm II	RD
Digital Microsystems	A1
Durango F-85	RL
Oynabyte DB8/2	R1
Oynabyte OB8/4	A1
Exidy Sorcerer + Lifeboat CP/M	Q2
Exidy Sorcerer + Exidy CP/M	RW
Heath H8 + H17/H27 disk	P4
Heath H89 + Lifeboat CP/M	P4
Heath H89 + Magnolia CP/M	P7
Heath H89 + Heath CP/M	P7
Helios II	B2
ICOM 2411 Micro Floppy	R3
ICOM 3712	A1
ICOM 3812	A1
ICOM 4511 5440 Cartridge CP/M 1.4	01
ICOM 4511 5440 Cartridge CP/M 2.2	D2
IMS 5000	RA
IMS 8000	A1
IMSAI VOP-40	R4
IMSAI VOP-42	R4
IMSAI VDP-44	R5
IMSAI VOP-80	A1
ISC Intecolor 8063/8360/8963	A1
Intertec Superbrain DOS 0.1	R7
Intertec Superbrain DOS 0.5	RJ
Intertec Superbrain DOS 3.x	RK
Intertec Superbrain QD	RS
Kontron PSI-80	RF
MITS 3200-3202	B1
MSO 5.25 in	RC
Meca Delta-1 5.25 in.	P6
Micromation	A1
Micropolis Mod I	Q1
Micro polis Mod II	Q2
Morrow Discus	A1
Mostek	A1
NEC PC-8001	RV
North Star Single Density	P1
North Star Double Density	P2
North Star Quad Density	P3
Nytac Micropolis Mod II	Q2
Ohio Scientific C3	A3
OKI IF-800	RZ
Onyx C8001	T2
Pertec PCC 2000	A1
Processor Technology Helios II	B2
Quay 500	RO
Quay 520	RP
RAIR Single Density	R9
RAIR Double Density	RE
Research Machines 5.25 in.	RH
Research Machines 8 in.	A1
SO Systems 5.25 in.	R3
SO Systems 8 in.	A1
Sanco 7000 5.25 in.	RQ
Spacebyte	A1
TEI 5.25 in.	R3
TEI 8 in.	A1
TIP	T3
TRS-80 Model I STANDARD	R2
TRS-80 Model I + FEC Freedom	RN
TRS-80 Model I + Micromation	A4
TRS-80 Model I + Omikron 5.25 in.	RM
TRS-80 Model I + Omikron 8 in.	A1
TRS-80 Model I + Shuffleboard 8 in.	A1
TRS-80 Model II	A1
TRS-80 Model III	RU
Vector MZ	Q2
Vector System 2800	A1
Vector System B	Q2
Vector VIP	Q2
Vista V-80 5.25 in. Single Density	R8
Vista V200 5.25 in. Double Density	P6
Zenith Z89 + Zenith CP/M	P7
Zenith Z89 + Lifeboat CP/M	P4
Zenith Z89 + Magnolia CP/M	P7

SS = single sided
DO = double sided
SO = single density
DO = double density

The list of available formats is subject to change without notice. In case of uncertainty, call to confirm the format code for any particular equipment.

LIFEBOAT WORLDWIDE

Lifeboat Inc.
3-23-8 Nishi-shinbashi
Minato-ku, Tokyo, 105 Japan
Tel: 03-437-3901
Telex: 2422723 (ASRTYOJ)

Lifeboat Associates, Ltd.
PO Box 125
London WC2H 9LU, England
Tel: 01-836-9028
Telex: 893709 (LBSOFTG)

Lifeboat Associates GmbH
PO Box 168, Aegeristrasse 35
CH 6340 Baar, Switzerland
Tel: 042-31-2931
Telex: 865265 (MICO CH)

Intersoft GmbH
Schlossgartenweg 5
D-8045 Ismaning, W. Germany
Tel: 089-966-444
Telex: 5213643 (ISOFO)

Lifeboat Associates, SARL
10, Grande Rue Charles de Gaulle
92600 Asnieres, France
Tel: 1-733-08-04
Telex: 250303 (PUBLIC X PARIS)

Lifeboat Associates

Software with full support.

Micromodem Support in Apple Pascal

Scott G Robinson
120 Upland Rd
Marlboro MA 01752

When I added Apple Pascal to my Apple II Plus system, I discovered that a few of my peripheral-device cards not made by Apple Computer Inc didn't work under the system. One was the Hayes Microcomputer Products Micromodem II direct-connect modem. Although the Pascal BIOS (basic input/output system) recognizes the Micromodem as a communication card, the BIOS does not contain the software necessary to control the modem's operations.

In BASIC, I could easily call and communicate with other modem-equipped systems, or have them call me. In Pascal, my system can't answer the phone even though the REMIN: and REMOUT: device names are associated with the Micromodem I/O card. This happens because BIOS doesn't use the Hayes modem's on-card firmware as Apple's DOS (disk operating system) and monitor ROM (read-only memory) do.

Various solutions were possible. In the February 1981 issue of BYTE, Thomas H Woteki described an Apple Pascal support procedure for the Hayes modem. (See "A Pascal Library Unit for the Micromodem II," page 106.) His method included modifying the BIOS routines in the SYSTEM.APPLE disk file and using a fair amount of machine-language routines. I decided against modification of the BIOS to maintain program compatibility with other Apple Pascal users. By using a programming trick that permits direct examination and modification of memory locations from Pascal, I knew I could reduce the amount of machine-language code needed. The final solution was to write a set of Pascal routines to supply some of the original Hayes modem firmware's services and use them in programs as needed.

I have several programs that would use these routines, so I wanted to have them compiled separately from the calling programs. Apple Pascal offers separately compiled routines through the "unit" option. A program gains access to the contents of the unit during compilation through inclusion of a "uses" statement. The object-code file from the compilation is linked with the unit's object-code file to make an executable program. Basically, a unit consists of three parts:

Accessing memory locations directly from Pascal reduces the amount of machine-language code required.

- the unit header, which specifies the name of the unit just as the program header does for normal programs. The name chosen is included in the USES statement of calling programs
- the "interface" portion, which specifies usable items to the calling program. These items could be procedures or functions, and include global data declarations
- the "implementation" portion, which specifies actual routines and functions that implement this unit and its interfaces

The code included in the interface portion of the Micromodem unit was determined by functions I needed. The BIOS didn't support dialing other systems, answering incoming calls, or hanging up the phone. Additionally, I thought that a function to determine if new data is available (similar to the APPLESTUFF "keypress" routine) would be useful because Apple Pascal is not interrupt-driven. Thus the Pascal routines to be coded were:

```
function MM_DIALER
   (NUMBER: string):
   boolean;
function MM_ANSWER
   (TIMING_ENABLED:
   boolean): boolean;
function MM_KEYPRESS:
   boolean;
procedure MM_HANGUP;
```

Before programming the implementation portion, I had to solve the fundamental problem of accessing the Control and Status registers on the Micromodem card. Actually, I needed to fool Pascal into allowing access to the contents of actual memory locations. This was accomplished through the infamous Pascal TRIX record, shown in listing 1, which sets up a relation between the variables ADDRESS and MEMORY like that produced by the EQUIVALENCE statement in FORTRAN.

To use the TRIX record, an assignment to the variable ADDRESS (the address field) is done followed by a read or write using the MEMORY

MEMOREX

WHEN YOU ADD IT UP, MEMOREX FLEXIBLE DISCS FROM PACIFIC EXCHANGES ARE YOUR BEST BUY.



For Data Reliability—
Memorex
Flexible
Discs

CALL FREE FOR PRICES & INFORMATION

(800)235-4137

In California, (805)543-1037



PACIFIC
EXCHANGES
100 Foothill Blvd.
San Luis Obispo, CA
93401

DEALER INQUIRIES INVITED VISA master charge C.O.D.'s ACCEPTED

Listing 1: *The TRIX record structure in Apple Pascal produces a relation between the variables ADDRESS and MEMORY like that produced by the EQUIVALENCE statement in FORTRAN.*

```
type TRIX =
  record
   case boolean of
    false:(ADDRESS:integer);
    true:(MEMORY:^char);
   end;
```

Listing 2: *The BTRIX record structure is a modification of TRIX for operation on individual bits. Due to the 16-bit operation of the packed-array type, some care must be taken during its use.*

```
type
  BBITS = packed array[0..7] of boolean ;
  BTRIX =
    record
     case boolean of
      false:(ADDRESS:integer);
      true:(BITS:^BBITS);
     end;
```

Listing 3: *This short Pascal program demonstrates the use of the TRIX record.*

```
type TRIX =
  record
   case boolean of
    false:(ADDRESS:integer);
    true:(MEMORY:^char);
   end;
procedure MM_SET_MODEM (CBYTE:char);
var MMII:TRIX;
begin
   MMII.ADDRESS := -16251+32;
   MMII.MEMORY^ := CBYTE;
end;

begin
(*   Just Hangup the Modem   *)
   MM_SET_MODEM(chr(0));
end.
```

field. The "record" structure makes the integer field into a character pointer.

The TRIX record is adequate except for operations on individual bits in a character. It is common to test bits in I/O interfaces to determine the current status and service required (such as reading a character). For the Micromodem, bit testing is used to determine whether the phone is ringing or if a carrier tone has been detected on the phone line. The bit-operation TRIX record is shown in listing 2. Using the BTRIX record does have its side effects, however. A packed-array type causes the ADDRESS field to point at a word (16 bits or 2 bytes) not just a character (8 bits or 1 byte). When a reference to the MEMORY field is done, 2 bytes are read or written. This is normally not a problem because Pascal allocates data structures of that type in a word.

Reading 2 bytes can be a problem for the Micromodem because the Status and Data registers are adjacent bytes in the address space. A test of the Data Ready status bit will cause the character to be read and thrown away. (The MM_KEYPRESS function in the unit MICROMODEM was written in assembly language to circumvent the double-byte reference.) The example program in listing 3 demonstrates the use of the TRIX-type records.

Text continued on page 324

APPLE ACCESSORIES

LOBO Disk II/Controller	$499.
LOBO Disk II	419.
SUPERTERM 80 Col. Card	329.
Z80 Soft Card	295.
H.S. Serial Card	179.
COMM. Card	179.
CLOCK Calendar Card	225.
ROM Plus Card/KB Filter	175.
HAYES Micromodem	319.
SUPERTalker	249.
PARALLEL Printer Card	149.
16K Ram Card	189.
GPIB IEEEE-488 Card	259.

SOFTWARE

VISICALC	119.00
DESKTOP Plan II	169.00
PERS Filing Syst	80.00
ADDRESS Book	40.00
SUPER Text II	125.00
CCA Data Mgmt	85.00

MODEMS

UDS 103 LP, *direct*	$169.
103 JLP *Auto Answer*	219.
NOVATION CAT, *acoustic*	159.
D-CAT, *direct*	169.
Auto Cat	219.
Apple Cat	309.
LEXICON LX—11, *acoustic*	147.
HAYES Micromodem, S100	349.

VIDEO MONITORS

Sanyo 9" B/W	$169.
NEC 12" Green	229.
Amdek 12" B/W (Leedex)	135.
Amdek 13" Color	399.

VIDEO TERMINALS

Ampex Dialog 80	$995.
Ampex Dialog 30	795.
Televideo 920C	845.
Televideo 950	995.
Soroc IQ 120	795.
Soroc IQ 140	1,195.

FLOPPY DRIVES

1—SA 400 Case, power	$399.
1—SA 800/801 Case, power	995.
2—SA 800/801 Case, power	1,495.
2-SA 850/851 Case, power	1,995.

PRINTER SALE

Diablo 630 RO	$2,395.
Diablo 1640 RO	2,795.
Diablo 1650 RO	3,095.
Qume 3/45 RO	2,195.
Qume 3/55 RO	2,295.
Qume 5/45 RO	2,595.
Qume 5/55 RO	2,795.
C.Itoh Starwriter RO	1,695.
TI 810 RO	1,695.
TI 820 RO	1,795.
Anadex DP9500/9501	1,345.

EPSONS TOO!

NEW! NOVELL IMAGE 800

150 CPS Heavy Duty Matrix

15" wide carriage, expanded, compressed and double density "correspondence quality" printing at 80, 96 and 136 columns, true descenders, underlining, superscripts, subscripts. Up to 3K Buffer, optional character set and graphics option.

List $1,395. .... $1,295.00

PRINT ELEMENTS

NEC Thimbles	$14.95
Plastic Daisy Wheels *for Qume, Diablo, Starwriter*	6.00
Metal Daisy Wheels	59.00
IBM Selectric Elements	19.00

RIBBONS

NEC	$77.00/Doz.
QUME	45.00/Doz.
DIABLO	66.00/Doz.
ANADEX	135.00/6 ea.
TRITEL	95.00/Doz.
TI/DEC/TTY	45.00/Doz.
EPSON	13.95/ea.
MPI/Axiom/Base 2	10.00/ea.



MAGNETIC MEDIA

Premium Quality At Bargain Prices

5¼" Diskettes, all Formats, 100% Certified with hub rings, box of 10

Single sided, single density	26.50
Single sided, double density	29.50
Double sided, double density	38.50

8" DISKETTES, ALL FORMATS 100% CERTIFIED

Single sided, single density	29.50
SSSD Error Free	34.50
Single sided, double density	39.50
Double sided, double density	49.50



MPI 88 G Matrix

High resolution dot-addressable graphics for Apple. Enhanced "correspondence quality" printing. Tractor and Friction feed. Serial and Parallel Input. 100 cps Bidirectional printing, 80, 96, and 132 column widths!

List $799.00 .... $599.00

Apple II I/O Card	$110.00
PET/IEEE I/O Card	55.00
Single Sheet Feeder	25.00
QT Cover	25.00



NEC SPINWRITERS

5510 RO	$2,595.
5520 KSR	2,895.

NEW!



OLYMPIA ES100

Letter quality, Daisy wheel printer/typewriter interfaces to Apple, Atari, NEC, TRS80 and RS232 Serial ports. A truly cost effective letter quality printer that functions as a typewriter.

List $1,495. .... $1,295.00

TO PLACE YOUR ORDER CALL:

TELEPHONE (714) 744-7314 — *TELEX* 697120

or write to:

PALOMAR
Computer Products

910-105 W. San Marcos Blvd., San Marcos, CA 92069

TERMS OF SALE: Cash, check, money order, bank wire transfer, credit card or purchase orders from qualified firms and institutions. Please include telephone number with order and expiration date on credit card orders. California residents add 6% sales tax. Advertised prices are for prepaid orders F.O.B. shipping point. Add 3% for shipping in U.S. Pricing and availability subject to change without notice.

SuperBuys!!!!

. . . on computers, peripherals, accessories and supplies!

Circle 302 on inquiry card.

Listing 4: *Apple Pascal support "unit" for the Hayes Microcomputer Products Micromodem II. Since the Pascal language system does not use the on-board firmware included with this peripheral card, functions to support dialing, answering calls, and automatic hang-up are provided in this procedure. Note that the "_" (underline, ASCII decimal 95) character is used to make the listing more readable, and that the "{ }" braces often replace the "(* *)" comment delimiters.*

```
MICROMODEM.TEXT          (c) 1980 Scott G. Robinson     Sept. 14, 1980     Page 1
{D.C. Hayes Micromodem II Support Unit}
--------------------------------------------------------------------------------

(*$S+*)
unit MICROMODEM;
{---------------------------------------------}
{ M I C R O M O D E M   II   S U P P O R T    }
{                                             }
{ Author: Scott G. Robinson                   }
{         120 Upland Rd.                      }
{         Marlboro, Ma.                       }
{                                             }
{ Version: 1.0                                }
{ Creation Date: August 27, 1980              }
{                                             }
{ (c) 1980 by Scott G. Robinson               }
{ All Commercial Rights Reserved              }
{---------------------------------------------}

interface
   function MM_KEYPRESS : boolean;
   function MM_DIALER(NUMBER:string) : boolean;
   function MM_ANSWER(TIMING_ENABLED: boolean) : boolean;
   procedure MM_HANGUP;

implementation
   const
{     These ensure Phone Co. standards          }
      DIAL_PULSE = 120;
      DIAL_PAUSE = 60;
      DIGIT_DELAY = 1200;
      A_2_SEC_DELAY = 3400;

{     These describe the Micromodem Registers }
      SLOT_X_16 = 32;
      MODEM = -16251;
         M_OFFHOOK = 128;
         M_INIT    = 8;
         M_ORIG    = 4;
         M_XMTE    = 2;
         M_300BAUD = 1;
      STATUS = -16250;
         S_PE      = 64;
         S_OVRN    = 32;
         S_FE      = 16;
         S_RESET   = 8;
         S_CD      = 4;
         S_XRDY    = 2;
         S_RRDY    = 1;
      CONTROL = -16250;
         C_INIT    = 3;
         C_8BITS   = 21;
      DATA  = -16249;

   type
      TRIX = record
              case boolean of
               false:(ADDRESS:integer);
               true:(MEMORY:^char);
              end;
      BBITS = packed array[0..7] of boolean;

      BTRIX = record
```

Listing 4 continued on page 314

Listing 4 continued:

```
                  case boolean of
                   false:(ADDRESS:integer);
                   true:(BITS:^BBITS);
                  end;

     var
       DIGIT : integer;      { Holds digit while dialing }
       I,J : integer;        { Misc loop control vars     }
       CD,RI : boolean;      { Indicates carrier or ring }

procedure WAIT(HOWLONG:integer);
{
  Delay for specified amount
}
var DELAY : integer;
begin
   for DELAY := 1 to HOWLONG do ;
end {WAIT};

function MM_GET_STATUS(BIT_NUMBER:integer): boolean;
{
  Test STATUS BIT_NUMBER and return true if set

  WARNING! An assembly language routine should
           be used in data transfer usage
           because PASCAL may read the DATA reg
           along with the STATUS reg thus
           causing lost characters or worse.
}
var MMII: BTRIX;
begin
   MMII.ADDRESS := STATUS+SLOT_X_16;
   MM_GET_STATUS:=MMII.BITS^[BIT_NUMBER];
end {MM_GET_STATUS};

function MM_GET_MODEM(BIT_NUMBER:integer): boolean;
{
  Test MODEM BIT_NUMBER and return true if set
}
var MMII: BTRIX;
begin
   MMII.ADDRESS := MODEM+SLOT_X_16;
   MM_GET_MODEM:=MMII.BITS^[BIT_NUMBER];
end {MM_GET_MODEM};

function MM_GET_DATA: char;
{
  Return copy of DATA reg as char

  NOTE: PASCAL's unitread should normally
        be used for this function.
}
var MMII: TRIX;
begin
   MMII.ADDRESS := DATA+SLOT_X_16;
   MM_GET_DATA:=MMII.MEMORY^;
end {MM_GET_DATA};

procedure MM_SET_CONTROL(CBYTE:char);
{
  Set CONTROL reg with CBYTE
}
var MMII: TRIX;
begin
   MMII.ADDRESS := CONTROL+SLOT_X_16;
   MMII.MEMORY^ := CBYTE;
end {MM_SET_CONTROL};
```

Listing 4 continued on page 316

NEW YORK COMPUTER EXPO

Albert Hall, Sheraton Centre, 52nd St. & 7th Ave., New York, NY • Aug. 12-15, 1981

All the excitement of "hands-on" experience with the newest small computers returns to New York City in August.

SPECIAL "BUSY EXECUTIVE" SESSION

New York Computer Expo presents an ancillary opportunity for the busy executvie who feels it's time to become familiar with computers and the world of data processing, quickly, efficiently and at a low cost.

The aim of this special session is to show the busy executive how to approach data processing technology, how to cope with it on an administrative basis, how to keep ahead of it, and how to put this knowledge to immediate use.

The tutorial covers about five hours, and will be given once each day, Aug. 11 through Aug. 15. Each tutorial has limited registration. Hours are 9 a.m. to about 3 p.m., with time for lunch and a coffee break.

Each registrant will receive an original workbook and computer language dictionary. Four-day registration for the New York Computer Expo also is included. Total fee for the session is $200.

EXECUTIVE TUTORIAL OUTLINE

SECTION 1. COMPUTER FUNDAMENTALS

In this section of the course you'll learn what a computer is, how it's put together and how you make it do the things you want it to do.

A. ABC's of Computers
-What a computer actually is and what it's not.
-How a computer works. The in's and out's of number systems.

B. Computer Hardware
-The basic parts of a computer.
-CPUs--An introduction to the different types.
-Memory--RAM, ROM, EPROM, ETC.
-Peripherals.

C. Computer Software
-The anatomy of a simple computer language--BASIC.
-Software buzzwords.
-An overview of the major computer languages--Assembler, FORTRAN, COBOL, PASCAL, PL/1, APL, ADA, C, FORTH, LISP and more.
-Packaged software--why you may need it.
-Specialized software--Data base/data management systems, etc.

D. Computer Configurations
Putting computers, terminals, etc., together in more complicated ways to improve efficiency.
-Time sharing
-Data communications
-Distributed processing.

E. A look at the People Side of Data Processing
What are all those people *really* doing? Functions of various types of computer personnel: programmers, systems analyst, data entry personnel, operators, etc.

F. An Overview of Computer Applications
An introduction to some of the things computers are being used for.

SECTION 2. HOW TO CHOOSE, INSTALL AND OPERATE A COMPUTER

A. Defining Your Needs
-The feasibility study. How to cost out the obvious computer applications.
-Setting up a computerization timetable.
-Long-range computer and office automation planning.

B. Finding Out What's Available to Fit Your Needs
A comprehensive overview of the current state of the are in computers, peripherals and software. We'll even give you a peek into the future at what might be available in the years to come.

C. How Much Work to Do In-House and How Much to Contract Out
An information-packed discussion of the available sources of outside help: computer stores, systems houses, contract programmers, service bureaus.

D. How To Handle A Vendor
-How to solicit bids and pick the best one.
-Computer contracts--picking your way through the minefield.

E. Conversion
How to get from your current systems to your new system.

F. The Care And Feeding Of Computer People
How to find and *keep* the right personnel in a *very* tight market.

SECTION 3. WHERE TO GET MORE INFORMATION

—Introduction to computer organizaitons.
-Finding other companies and executives in similar circumstances.
-A complete, annotated bibliography of the best and *clearest* books in the field.

ABOUT THE INSTRUCTOR

The instructor for the course is Barbara Schwartz. The course lecture and workbook is all original material created by her. She is a consultant to major corporations and small businesses and is a writer on computer and data processing topics. She has taught courses for companies and schools in simple clear English.

Minis • Micros • Software • Peripherals
Services • Free Lectures

Once again, the fascinating world of computers is presented in the heart of New York City for business, science, education, professionals and personal users.

It's the greatest opportunity on the east coast to get an up-date education on what's new by visiting 15,000 square feet of exhibits and attending lectures given by expert computer scientists and educators.

FREE LECTURE SCHEDULE

	August
Introduction to Small Systems for Business	12 & 13
Introduction to Personal Computing	12 & 15
Selecting a Small Computer for Business for the First-Time user	12 & 14
Computer Performance in an Accounting Environment	12 & 14
Survey of Graphic Packages Available for Micros	12 & 13
All About Printers for Business	12
Understanding the Cost of Business Software	12 & 13
The Computer as a Scientific research Tool	12 & 14
CP/M Update	14
Interfacing to the Real World	13 & 15
The Multi-Lingual Microcomputer	13
Introduction to COBOL for Microcomputers	13 & 15
Using a Microcomputer for Technical Analysis of Stocks & Commodities	13 & 14
Survey of Computer-Assisted Instruction	13 & 15
All About Printers for Personal Use	13
The Next Five Years in Small Computers	14 & 15
Applying PASCAL	14
Microcomputers and Medicine	14
The Beauty of FORTRAN for Small Computers	14 & 15
The Future of the Home Terminal	15
Selecting a Small Computer for Personal Use	15
Uses of the Microcomputer in Education: New Directions	15

(Subject to Change)

Show Registration Fee: $10 per day — Show Hours: 11 a.m. to 6 p.m. Daily

NEW YORK COMPUTER EXPO

Please register me for the New York Computer Expo

NAME ______________________

COMPANY (If Any) ______________________

ADDRESS ______________________

______________________ ZIP __________

BUSINESS TITLE (If Any) ______________________

☐ *One Day $10* ☐ *Two Days $20* ☐ *Three Days $30* ☐ *Four Days $40*

EXECUTIVE SESSION ($200):

☐ AUG. 11 ☐ AUG. 12 ☐ Aug. 13 ☐ Aug. 14 ☐ Aug. 15

Mail with applicable payment. Use one form per person. Registration badge will be sent by mail in early August. Check or money order only.

Your company's primary business. Check one.

1 ☐ Accounting firm	9 ☐ Engineering	18 ☐ Personnel Agency
2 ☐ Advertising/Marketing	10 ☐ Entertainment/News	19 ☐ Professional Services
3 ☐ Banking/Insurance/ Real Estate/Credit/Securities	11 ☐ Government/Military	20 ☐ Research/Development
4 ☐ Communications	12 ☐ Hospital	21 ☐ Transportation (All)
5 ☐ Computer Consultant	13 ☐ Hotel	22 ☐ Utility
6 ☐ Computer Dealer/Dist	14 ☐ Industrial Design	23 ☐ Wholesale/Retail Sales
7 ☐ Construction/Architecture	15 ☐ Law Office	24 ☐ Other (Please Specify)
8 ☐ Education	16 ☐ Management Consultant	__________
	17 ☐ Manufacturing	

Check your primary job function.

1 ☐ Account Executive	9 ☐ Designer (All)	17 ☐ Salesperson (All)
2 ☐ Administrator	10 ☐ DP/WP Manager/Operator	18 ☐ Scientist
3 ☐ Bookkeeper	11 ☐ Doctor	19 ☐ Skilled Laborer
4 ☐ Chemist/Pharm	12 ☐ Engineer (All)	20 ☐ Student
5 ☐ Consultant	13 ☐ Lawyer	21 ☐ Teacher
6 ☐ Corporate Officer	14 ☐ Office Manager	22 ☐ Technician
7 ☐ CPA	15 ☐ Programmer	23 ☐ Other (Please Specify)
8 ☐ Creative Arts (All)	16 ☐ Purchasing	__________

Your primary interest in computers (check only one) 1 ☐ Business 2 ☐ Personal 3 ☐ Both

Mail prior to July 24, 1981. No foreign mail orders. New York Computer Expo. 110 Charlotte Place, Englewood Cliffs, NJ 07632 (201) 569-8542

Listing 4 continued:

```
procedure MM_SET_MODEM(CBYTE:char);
{                              }
{  Set MODEM reg with CBYTE    }
{                              }
var MMII: TRIX;
begin
   MMII.ADDRESS := MODEM+SLOT_X_16;
   MMII.MEMORY^ := CBYTE;
end {MM_SET_MODEM};

procedure MM_SETUP;
{                                      }
{  Initialize ACIA chip to 8-bits/char }
{                                      }
begin
   MM_SET_CONTROL(chr(C_INIT));
   MM_SET_CONTROL(chr(C_8BITS));
end {MM_SETUP};

(*$P*)

function MM_KEYPRESS;
{                                                  }
{  MM_KEYPRESS returns true if a character is      }
{  ready for input from the micromodem             }
{                                                  }
external;

function MM_DIALER;
{                                                       }
{  MM_DIALER attempts to establish communication        }
{  with a modem after dialing NUMBER. If successful     }
{  the function is 'true' otherwise 'false'.            }
{                                                       }
   begin
{  Start by taking the phone line 'off-hook' }
   MM_SET_MODEM(chr(M_OFFHOOK));
   WAIT(A_2_SEC_DELAY);
{  Then dial NUMBER requested. }
   for I := 1 to length(NUMBER) do
      case NUMBER[I] of
         '0','1','2','3','4','5','6','7','8','9':
            begin
            DIGIT := ord(NUMBER[I])-ord('0');
            if DIGIT = 0 then DIGIT := 10;
            repeat
               WAIT(DIAL_PAUSE);
               MM_SET_MODEM(chr(0));
               WAIT(DIAL_PULSE);

               MM_SET_MODEM(chr(M_OFFHOOK));
               DIGIT := DIGIT - 1;
            until DIGIT = 0;
            WAIT(DIGIT_DELAY);
            end;
         '*': WAIT(A_2_SEC_DELAY);
      end {case};
{  Set Originate Mode and wait for the carrier }
   MM_SET_MODEM(chr(M_OFFHOOK + M_ORIG));
   I := ord(MM_GET_DATA); {Ensure Valid CD bit}
   CD := false;
   J := 8;
   repeat
     WAIT(A_2_SEC_DELAY);
     CD := not(MM_GET_STATUS(2));
     J := J-1;
   until (J=0) or CD;
{  Finish up by either hanging up or enabling transmitter }
```

Listing 4 continued on page 318

QUALITY DISK SOFTWARE

BACKED BY ON-GOING APPLICATIONS SUPPORT

***APPLE II* (A) *TRS•80* (T)**

HOME FINANCE PAK I: Entire Series $49.95 (A) (T)

CHECK REGISTER AND BUDGET: This comprehensive **CHECKING ACCOUNT MANAGEMENT SYSTEM** not only keeps complete records, it also gives you the analysis and control tools you need to actively manage your account. The system provides routines for **BUDGETING INCOME AND EXPENSE, AUTOMATIC CHECK SEARCH,** and **BANK STATEMENT RECONCILING. CRT** or printer reports are produced for **ACTUAL EXPENSE vs BUDGET, CHECK SEARCH DISPLAY RECONCILIATION REPORT** and **CHECK REGISTER DISPLAY** by month. Check entry is prompted by user-defined menus of standard purposes and recipient codes, speeding data entry and reducing disk storage and retrieval time. Six fields of data are stored for each check: amount, check no., date, purpose, recipient and **TAX DEDUCTIBLE REMINDER. CHECK SEARCH** routines allow searching on any of these data fields. Up to 100 checks/mo. storage $39.95

SAVINGS: Account management system for up to 20 separate Savings accounts. Organizes, files and displays deposits, withdrawals and interest earned for each account. $14.95

CREDIT CARD: Get Control of your credit cards with this program. Organizes, stores and displays purchases, payments and service charges for up to 20 separate cards or bank loans. $14.95

UNIVERSAL COMPUTING MACHINE: $49.95 (A)

A user programmable computing system structured around a 50 row x 50 column table. User defines row and column names and equations forming a unique computing machine. Table elements can be multiplied, divided, subtracted or added to any other element. Hundreds of unique computing machines can be defined, used, stored, and recalled, for later use. Excellent for sales forecasts, budgets, inventory lists, income statements, production planning, project cost estimates-in short for any planning, analysis or reporting problem that can by solved with a table.

COLOR CALENDAR: $29.95 (A)

Got a busy calendar? Organize it with Color Calendar. Whether it's birthdays, appointments, business meetings or a regular office schedule, this program is the perfect way to schedule your activities.
The calendar display is a beautiful **HI-RES** color graphics calendar of the selected month with each scheduled day highlighted in color. Using the daily schedule, you can review any day of the month and schedule an event or activity in any one of 20 time slots from 8:00 A.M. to 5:30 P.M.

BUSINESS SOFTWARE: Entire Series $159.95 (A) (T)

MICROACCOUNTANT: The ideal accounting system for small businesses. Based on classic T-accounts and double-entry booking, this efficient program provides a journal for recording posting and reviewing up to 1,000 transactions per month to any one of 300 accounts. The program produces **CRT** and printer reports covering:

TRANSACTION JOURNAL	BALANCE SHEET
ACCOUNT LEDGERS	INCOME AND EXPENSE STATEMENT

Includes a short primer on Financial Accounting. (48K) $49.95

UNIVERSAL BUSINESS MACHINE: This program is designed to **SIMPLIFY** and **SAVE TIME** for the serious businessman who must periodically Analyze, Plan and Estimate. The program was created using our Universal Computing Machine and it is programmed to provide the following planning and forecasting tools.

CASH FLOW ANALYSIS	SALES FORECASTER
PROFORMA PROFIT & LOSS	SOURCE AND USE OF FUNDS
PROFORMA BALANCE SHEET	JOB COST ESTIMATOR
REAL ESTATE INVESTMENT	INVENTORY ANALYSIS

Price, including a copy of the Universal Computing Machine $89.95

BUSINESS CHECK REGISTER AND BUDGET: Our Check Register and Budget programs expanded to include up to 50 budgetable items and up to 400 checks per month. Includes bank statement reconciling and automatic check search (48K) $49.95

ELECTRONICS SERIES VOL I & II: Entire Series $259.95

LOGIC SIMULATOR: SAVE TIME AND MONEY. Simulate your digital logic circuits before you build them. **CMOS, TTL,** or whatever, if it's digital logic, this program can handle it. The program is an interactive, menu driven, full-fledged logic simulator capable of simulating the bit-time response of a logic network to user-specified input patterns. It will handle up to 1000 gates, including **NANDS, NORS, INVERTERS, FLIP-FLOPS, SHIFT REGISTERS, COUNTERS** and user-defined **MACROS.** up to 40 user-defined random, or binary input patterns. Accepts network descriptions from keyboard or from **LOGIC DESIGNER** for simulation . . . . $159.95 (A) (T)

LOGIC DESIGNER: Interactive **HI-RES** graphics program for designing digital logic systems. Draw directly on the screen up to 10 different gate types, including **NAND, NOR, INVERTER, EX-OR, T-FLOP, JK-FLOP, D-FLOP, RS-FLOP, 4 BIT COUNTER** and **N-BIT SHIFT REGISTER.** User interconnects gates using line graphics commands. Network descriptions for **LOGIC SIMULATOR** generated simultaneously with the **CRT** diagram being drawn . . . . $159.95 (A)

MANUAL AND DEMO DISK: Instruction Manual and demo disk illustrating capabilities of both program (s) . . . . $29.95 (A) (T)

ELECTRONIC SERIES VOL III & IV: Entire Series $259.95

CIRCUIT SIMULATOR: Tired of trial & error circuit design? Simulate & debug your designs before you build them! With **CIRCUIT SIMULATOR** you build a model of your circuit using **RESISTORS, CAPACITORS, INDUCTORS, TRANSISTORS, DIODES, VOLTAGE** and **CURRENT SOURCES** and simulate the waveform response to inputs such as **PULSES, SINUSOIDS, SAWTOOTHS,** etc. . .all fully programmable. The output is displayed as an **OSCILLOSCOPE-STYLE PLOT** of the selected waveforms (Apple only) or as a printed table of voltage vs time. Handles up to 200 notes and up to 20 sources. Requires 48 **RAM** . . . . $159.95 (A) (T)

CIRCUIT DESIGNER: Interactive **HI-RES** graphics program for designing electronic circuits. Draw directly on the screen up to 10 different component types, including those referenced above. Components interconnect list for **CIRCUIT SIMULATOR** generated automatically. Requires $159.95

MATHEMATICS SERIES: Entire Series $49.95

STATISTICAL ANALYSIS I: This menu driven program performs **LINEAR REGRESSION** analysis, determines the mean, standard deviation and plots the frequency distribution of user-supplied data sets. Printer, Disk, I/O routines $19.95

NUMERICAL ANALYSIS: HI-RES 2-Dimensional plot of any function. Automatic scaling. At your option, the program will plot the function, plot the **INTEGRAL,** plot the **DERIVATIVE,** determine the **ROOTS, MAXIMA, MINIMA, INTEGRAL VALUE** $19.95

MATRIX: A general purpose, menu driven program for determining the **INVERSE** and **DETERMINANT** of any matrix, as well as the **SOLUTION** to any set of **SIMULTANEOUS LINEAR EQUATIONS.** $19.95

3-D SURFACE PLOTTER: Explore the **ELEGANCE** and **BEAUTY** of **MATHEMATICS** by creating **HI-RES PLOTS** of 3-dimensional surfaces from any 3-variable equation. Disk save and recall routines for plots. Menu driven to vary surface parameters. Hidden line or transparent plotting $19.95

ACTION ADVENTURE GAMES: Entire Series $29.95 (A)

RED BARON: Can you outfly the **RED BARON?** This fast action game simulates a machine-gun **DOGFIGHT** between your **WORLD WAR I BI-PLANE** and the baron's. You can **LOOP, DIVE, BANK** or **CLIMB**-and so can the **BARON.** In **HI-RES** graphics plus sound. $14.95

BATTLE OF MIDWAY: You are in command of the **U.S.S. HORNETS' DIVE-BOMBER** squadron. Your targets are the Aircraft carriers, Akagi, Soryu and Kaga. You must fly your way through **ZEROS** and **AA FIRE** to make your **DIVE-BOMB** run. In **HI-RES** graphics plus sound. $14.95

SUB ATTACK: It's April 1943. The enemy convoy is headed for the **CONTROL SEA.** Your sub, the **MORAY,** has just sighted the **CARRIERS** and **BATTLESHIPS'** Easy pickings. But watch out for the **DESTROYERS** - they're fast and deadly. In **HI-RES** graphics plus sound $14.95

FREE CATALOG-All programs are supplied on disk and run on Apple II w/Disk & Applesoft **ROM** Card & **TRS-80** Level II and require 32K **RAM** unless otherwise noted. Detailed instructions included. Orders shipped within 5 days. Card users include card number. Add $1.50 postage and handling with each order. California residents add 6½% sales tax. Foreign orders add $5.00 postage and handling.

SPECTRUM SOFTWARE
142 Carlow, P.O. Box 2084
Sunnyvale, CA 94087

FOR PHONE ORDERS: (408) 738-4387
DEALER INQUIRIES INVITED.

VISA master charge

Listing 4 continued:

```
   if not(CD) then MM_SET_MODEM(chr(0))
   else MM_SET_MODEM(chr(M_OFFHOOK + M_ORIG + M_INIT
                          + M_XMTE + M_300BAUD));
   MM_DIALER := CD;
   MM_SETUP;
   end {MM_DIALER};

function MM_ANSWER;
{                                                   }
{ MM_ANSWER answers the telephone if ringing occurs }
{ during the wait interval and returns "true" if    }
{ a carrier is detected otherwise "false"           }
{                                                   }
   begin
{ Wait for Ring indication and then carrier }
   J := 20;
   CD := false;
   RI := false;
   repeat
      I := 0;
      repeat
        if not(MM_GET_MODEM(7)) then RI := true;
        I := I+1;
      until (I=500) or RI;
      if TIMING_ENABLED then J := J-1;
   until (J=0) or RI;
   if RI then
      begin
{ Answer the phone and wait for carrier }
      MM_SET_MODEM(chr(M_OFFHOOK + M_XMTE + M_300BAUD + M_INIT));
      I := ord(MM_GET_DATA); {Ensure valid CD bit}
      J := 15;
      repeat
```

Listing 4 continued on page 320

Circle 74 on inquiry card.

Listing 4 continued:

```
         WAIT(A_2_SEC_DELAY);
         CD := not(MM_GET_STATUS(2));
         if TIMING_ENABLED then J := J-1;
      until (J=0) or CD;
      end;
{ If carrier wasn't found then hangup the phone }
   if not(CD) then MM_SET_MODEM(chr(0));
   MM_ANSWER := CD;


   MM_SETUP;
   end {MM_ANSWER};

procedure MM_HANGUP;
{                                                  }
{ HANGUP hangs up the telephone and returns to     }
{ the caller.                                      }
{                                                  }
   begin
   MM_SET_MODEM(chr(0));
   end {HANGUP};

begin {Main Program just Initializes }
  MM_SETUP;
end {unit MICROMODEM}.
```

Listing 5: *Assembly-language routine for the 6502 microprocessor that determines if the next character to be received is waiting in the Micromodem, eliminating problems caused by attempts to retrieve a character before it is ready. The name MM_KEYPRESS is derived from its similarity to the APPLESTUFF "keypress" routine, which performs the same function for the Apple keyboard.*

```
ASMBLR:MMKEY.TEXT     (c) 1980 Scott G. Robinson     Sept. 14, 1980     Page 1
;MM_KEYPRESS support for MICROMODEM
--------------------------------------------------------------------------------

        .TITLE  "MM_KEYPRESS support for MICROMODEM"
;---------------------------------------------------
; MM_KEYPRESS returns a boolean value indicating
; whether a character is waiting in the micromodem
; and can be read with UNITREAD in PASCAL
;
; Author: Scott G. Robinson
;         120 Upland Rd.
;         Marlboro, MA 01752
;
; (c) 1980 by Scott G. Robinson
; All Commercial Rights Reserved
;---------------------------------------------------

RETURN  .EQU    0               ;Return Address
SLTX16  .EQU    020
MMSTAT  .EQU    0C0A6           ;Status Register

        .FUNC   MMKEYPRE
;
; function MM_KEYPRESS : boolean;
;
        PLA                     ;Store Return Address
        STA     RETURN
        PLA
        STA     RETURN+1
        PLA                     ;Discard Stack Bias
        PLA
        PLA
        PLA
```

Listing 5 continued on page 322

Listing 5 continued:

```
         LDA      MMSTAT                  ;See if character available
         AND      #01                     ;Bit 0 is Character Ready
         TAX                              ;Store temp
         LDA      #00
         PHA                              ;Put MSB of return
         TXA
         PHA                              ;Put LSB of return value
         LDA      RETURN+1                ;Put Return Address back on Stack
         PHA
         LDA      RETURN
         PHA
         RTS                              ;Exit Routine
;
         .END
```

Listing 6: *Sample utility program that gives the user menu-driven access to the Micromodem support procedure, MICROMODEM.*

```
MMUTIL1.TEXT          (c) 1980 Scott G. Robinson     Sept. 14, 1980
{Micromodem Utility Routine}
-----------------------------------------------------------------------

program MMUTIL;
uses APPLESTUFF,
(*$UMICROMODEM.CODE*)
     MICROMODEM;
{-------------------------------------------}
{ Micromodem Utility Routine                 }
{                                            }
{ Demonstrates the usage of the micromodem   }
{  support unit.                             }
{                                            }
{ Author: Scott G. Robinson                  }
{         120 Upland Rd.                     }
{         Marlboro, MA 01752                 }
{-------------------------------------------}

const
    KEYINP=2;
    MMINPUT=7;
    MMOUTPUT=8;

var
   ANYCHAR : char;
   DONE : boolean;
   NUMBER : string[32];
   RESULT : boolean;
   PCHAR : packed array[0..0] of char;

procedure PRINT_MENU;
begin
   page(output);
   writeln('D.C. Hayes Micromodem II Utility');
   writeln('');
   writeln('');
   writeln('Pick an option from the following list:');
   writeln('');
   writeln('      # --> Number to Dial = ',NUMBER);
   writeln('');
   writeln('      D --> Dial the number');
   writeln('      A --> Answer the phone');
   writeln('      H --> Hangup the phone');
   writeln('      T --> Go into Terminal mode');
   writeln('');
   writeln('Type <esc> to leave program');
end {PRINT_MENU};

begin
```

Listing 6 continued on page 324

Put Time and BSR/X-10 Control in Your APPLE II

THUNDERCLOCK PLUS™



The THUNDERCLOCK PLUS is two peripheral systems on one card for your APPLE II, II PLUS, or III. An accurate, reliable, real-time clock/calendar and an interface for the popular BSR X-10 Home Control System.

The THUNDERCLOCK clock/calendar makes accurate time and date available to your programs: month, date, day-of-week, hour, minute, and second, in any of four software selectable formats. On-board batteries keep your THUNDERCLOCK running when your APPLE II is turned off - for up to four years before battery replacement. On-card 1K firmware makes reading or setting the time easy from APPLESOFT or INTEGER BASIC, PASCAL, or assembly language programs. And it provides software selectable interrupts at any of three rates: 64, 256, or 2048 interrupts/second. All features are software selectable - no switches or jumpers!

THE PLUS

Add THUNDERWARE'S X-10 ULTRASONIC INTERFACE OPTION to your THUNDERCLOCK and your programs can send all 22 BSR X-10 commands so you can remotely control lights and appliances. Plus a powerful disk software package! The THUNDERWARE SCHEDULER software lets you create schedules to control lights, appliances, security systems, or almost any other electrical device. The software includes: SCUTIL - the SCHEDULER utility that lets you make or change a schedule, and SCHED - executes your schedules in real-time using the THUNDERCLOCK. SCHED runs in the 'background' so you can run other programs in the 'foreground'. Our PASCAL software lets you use all the THUNDERCLOCK'S features and sets the filer date whenever you boot. The THUNDERCLOCK PLUS is a SYSTEM for your APPLE II. Supported by intelligent, easy to use firmware, a powerful software package, and good documentation!



See your APPLE dealer.

Suggested retail prices:

THUNDERCLOCK PLUS $139
Clock/calendar card with batteries and user's manual

X-10 INTERFACE OPTION $49
BSR X-10 Ultrasonic interface, disk with SCHEDULER SOFTWARE & demos, and user's manual

PASCAL SOFTWARE $29
Disk with PASCAL interface for clock and X-10 interface, and user's guide

MANUALS ONLY, each $5

California residents add 6% sales tax

If your dealer doesn't carry the THUNDERCLOCK PLUS:

ORDER TOLL FREE (VISA/MC) CALL:
800-227-6204 Ext 307 (Outside California)
800-632-2131 Ext 307 (California Only)

OR WRITE TO:
THUNDERWARE INCORPORATED
P.O. Box 13322, Oakland, CA 94661

Let the THUNDERCLOCK PLUS time/date stamp your DOS files whenever you create or modify them with our DOS-DATER software.

The THUNDERCLOCK PLUS will work in any APPLE, including the APPLE III.

BSR X-10 is a trademark of BSR (USA) LTD.
APPLE II is a trademark of APPLE COMPUTER, INC

Listing 6 continued:

```
DONE := false;
NUMBER := '999-9999';
repeat
   RESULT := true;
   PRINT_MENU;
   read(keyboard,ANYCHAR);
   if ANYCHAR <> chr(27) then
      case ANYCHAR of
         '#','3':
             begin
                page(output);
                writeln('Enter Telephone Number to dial:');

                   readln(NUMBER);
                end;
            'A','a':
                begin
                page(output);
                writeln('Waiting for call...');
                RESULT := MM_ANSWER(true);
                end;
            'D','d':
                begin
                page(output);
                writeln('Dialing ',NUMBER);
                RESULT := MM_DIALER(NUMBER);
                end;
            'H','h': MM_HANGUP;
            'T','t':
                begin
                page(output);
                writeln('Terminal Mode - type ^P to exit');
                RESULT := false;
                repeat
                   if keypress then
                      begin
                      unitread(KEYINP,PCHAR[0],1,,1);
                      if PCHAR[0] = chr(16) then RESULT := true
                      else unitwrite(MMOUTPUT,PCHAR[0],1,,1);
                      end;
                   if MM_KEYPRESS then
                      begin
                      unitread(MMINPUT,PCHAR[0],1,,1);
                      write(PCHAR[0]);
                      end;
                until RESULT;
                end;
         end {case}
      else
         DONE := TRUE;
      if not(RESULT) then
         begin
         page(output);
         writeln('Operation Failed, type <space> to continue');
         repeat read(keyboard,ANYCHAR); until (ANYCHAR = ' ');
         end;
   until DONE;
end.
```

Text continued from page 310:

The remaining program listings contain comments that detail the full implementation of the unit. These listings contain characters that you are probably not used to seeing in Apple Pascal unless you have an external terminal. The "_" (underline) character breaks names to make them more readable. You can leave out the "_" everywhere it appears and the program will still work. The brace characters "{ }" replace the comment delimiters "(* *)", in most cases. Listing 4 is the completed Micromodem support unit. Listing 5 is the 6502 assembly-language MM_KEYPRESS routine used as part of the unit. Listing 6 is a sample utility program that uses the unit. ■

THE MAROT EXECUTIVE MENU

THE COMPUTER SOLUTION FOR NON-COMPUTER PEOPLE

Now Marot brings you another delicious first: a menu-driven information system so simple even a CEO can use it.

A single key-stroke takes you directly to the required application:

DATA BASE MANAGER (CONTROL™): a combined program generator that works with standard English query. That means it talks your language. So there's no need to learn a computer language or write a program to be a successful user.

WORD PROCESSOR (MAGIC WAND™): a powerful word processor that allows full screen creation and editing of files. It also produces true proportional spacing, microjustification and kerning. In addition, documentation can be fully examined at the CRT prior to printing.

ACCOUNTING: consists of several complete business packages either in standard ANSI '74 COBOL or OASIS™ BASIC, including accounts receivable and payable, general ledger, payroll, order entry and inventory. Financial modeling and job costing are also available.

MAILING LIST (POSTMAN™): delivers up to 65,000 entries in zip and name order and is completely interactive with MAGIC WAND.

SCHEDULER: maintains a complete office diary with ability to compare schedules.

Although the Marot Menu appears simplistic, it also incorporates OASIS with user logons, accounting histories and password protection. Languages available include JCL (EXECUTIVE), BASIC, PASCAL, COBOL and FORTRAN.

As a result, the Marot Executive Menu is a tasty pleasure for the higher-ups and the higher-techs.

A la carte extra

OPSCAN SERVICE™: available exclusively from Marot. Send us your well-printed or typed files. We'll read them directly into MAGIC WAND at a speed that would take 20 typists to match. The cost is less than conventional typing and the turn-around is never more than 5 days.

CONTROL and OASIS are trademarks of Phase One Systems Inc.
POSTMAN is a trademark of Marot Systems Inc.
OPSCAN SERVICE is a trademark of Marot Systems Inc.
MAGIC WAND is a trademark of Retail Sciences Inc.



MAROT SYSTEMS INC.
310 Madison Avenue, Suite 408, New York, N.Y. 10017
(212) 661-8550 TWX: 710-581-2477

I'd like to order more information on
☐ MAROT MENU ☐ OPSCAN SERVICES.
I am a ☐ computer consultant
☐ computer dealer ☐ computer user ☐ CEO

Name ____________________
Title ____________________
Address ____________________
City/State/Zip ____________________

Circle 219 on inquiry card.

Life After Death

Pat Macaluso
9 Church Ct
White Plains NY 10603

"All this and heaven too!"
—Mathew Henry's *Life of Philip Henry*

"And shall I couple Hell?"
—Shakespeare's *Hamlet*

In the conventional game of Life, death is final, and birth is the beginning. Cells simply vanish when they die, and they appear magically out of nowhere when births occur. The void on both ends saddened me. I could not accept Life without hope or a spiritual dimension. The result is Life After Death. After all, we create the microcosms known as cellular automata and make the rules known as state transitions. We can just as easily change the rules. If we want a cell to have an existence in the hereafter, then so be it.

In Life After Death, cells that die pass on to another state of existence; they enter a netherworld. Likewise, when a birth occurs, a cell from the other world descends to become the newly born cell, a gift from cell heaven or a reincarnation, if you will. More on this later.

The idea behind Life After Death is to explore Life systems with a view to generating interesting moving video displays or attractive printed patterns. This kind of study, however, poses several problems. One is the time and effort required to modify algorithms for new Life systems. A second problem is the slow execution of high-level interpretive languages. (Few of us have the time or inclination to tackle such studies in machine language or assembly language.) A third problem is the difficulty involved in analyzing results and manipulating output. This article illustrates one approach to simplifying these problems. It also suggests the many structures and rules that can be readily implemented.

A good starting point is offered by Jonathan Millen in "One-dimensional Life" (BYTE, December 1978, page 68). One-dimensional Life is easy to program in high-level languages. It also runs fast enough for study purposes.

A program to run this one-dimensional form of Life is shown in listing 1. It is written in extended BASIC for the Radio Shack TRS-80 Model I microcomputer. This version uses a wrap-around procedure so that the first cell, UN(1), is treated as being adjacent to the last cell UN(E), where E represents the number of elements in the cellular universe, or Life-line. The ASCII (American Standard Code for Information Interchange) codes 32 and 191 represent a blank and a fully white video character block on the TRS-80. To facilitate study, the program displays each line as it's generated. But, the entire screen can be changed by storing the lines and then displaying them after a time delay between displays.



Figure 1: *A parallel pattern in the hereafter, H-line, is formed by negating the current Life pattern, P-line, and then rotating it by a circular shift to the left.*

Adding a Hereafter

One way to add a hereafter is to specify a parallel one-dimensional universe of cells, or H-line (hereafter line). Once a pattern is formed in the real world, or P-line (present line), two events immediately take place. First, an H-line is formed as a negation of the P-line of zeros and ones, ie: each zero or off-cell in P is paralleled by an on-cell or a one in H, and vice versa. Second, the H-line drifts relative to the P-line by rotating one cell to the left. (These events are shown in figure 1.) The rules for Millen's one-dimensional Life are now applied to the P-line, but with a significant exception. An otherwise possible birth will not occur unless a parallel cell in the spirit world is on. Likewise, a moribund cell will not die unless the adjacent cell in the hereafter is vacant. Its time has not come. (This is illustrated in figure 2.)

Listing 1: *Radio Shack Level II BASIC program for one-dimensional Life using Millen's rules. The Life-line wraps around to form a logical circle composed of E elements. Lines are displayed successively as generated until the screen is full. The display then returns to the top of the screen and continues.*

```
100 '---1-D LIFE, MILLEN'S RULES +WRAPAROUND +11-LINE DISPLAY
110 CLEAR 128:DIM UN(64):G=0:C=0
115 INPUT "DISPLAY WIDTH (MAX 60)",E '---SHOULD BE>PATTERN SIZE
120 PRINT"ENTER PATTERN OF 1'S & 0'S --MAX ",:PRINTE:INPUT P$
125 IF E<LEN(P$) THEN E=LEN(P$)    '---CENTERING ROUTINE 125-150
130 K=INT((E-LEN(P$))/2)
140 FOR J=1 TO LEN(P$)
150 UN(K+J)=VAL(MID$(P$,J,1)):NEXT
152 CLS:PRINT@K+4,P$; :GOTO 310
155 U1=UN(1):U2=UN(2):T2=UN(E-1):T1=UN(E) '----ALGORITHM 155-260
170 I=1:G=G+1:C=C+1
180 L1=UN(I+1):L2=UN(I+2)
190 T0=UN(I):N=T2+T1+L1+L2
200 IF T0=0 THEN GOTO 220
210 IF NOT(N=2 OR N=4) THEN  UN(I)=0.GOTO 230: ELSE 230
220 IF N=2 OR N=3 THEN  UN(I)=1
230 T2=T1:T1=T0:I=I+1
240 IF I<E-1 GOTO 180
250 IF I=E-1 L1=UN(E):L2=U1:GOTO 190
260 IF I=E THEN L1=U1:L2=U2:GOTO 190    '----"THEN" IS A MUST!
310 L=15427+C*64:PRINT@0,G;     '---DISPLAY ROUTINE 310 TO 340
320 FOR J=1 TO E
330 IF UN(J)=1 POKE L+J,191:ELSE POKE L+J,32
340 NEXT:IF C>13 THEN C=-1:GOTO 155: ELSE 155 '---MAX C=13!!!
```

The rules for Life After Death can now be stated:

- Every cell in the hereafter is set opposite in state to its corresponding cell in the parallel current pattern immediately after it is established.
- The cells in the hereafter then drift (rotate) one position to the left. The cause of this drift is not known. Perhaps the drift is more apparent than real. While the world rushes on with its daily concerns of growth and survival, the occupants of the tenuous spirit world simply fade into memory.
- The cells of the pattern are scanned. A birth occurs if a cell is off and has 2 or 3 neighbors and the adjacent spirit cell is on. A neighborhood consists of 2 cells to the left and 2 cells to the right of the cell being scanned. The changes are deferred until the next step is complete.
- A death occurs if a cell in the pattern is on and has 0, 1, or 3 neighbors and the adjacent spirit world cell is off. Changes reflecting births and deaths are now made in the pattern-line. A new cycle of rules can now be applied.



Figure 2: *Without a spirit in the adjacent otherworld cell, an otherwise possible birth cannot occur. If the adjacent space in the hereafter is occupied, an otherwise moribund cell cannot die.*

To achieve the objective of easy exploration, Millen's one-dimensional Life (MIL) was implemented in APL, as shown in listing 2. This gives results identical to the results of the BASIC version in listing 1 except that the APL program is set up for printing. This particular version was run on an APL microcomputer, the MCM-70, of Micro Computer Systems. Readers who studied the article by Mark Niemiec "Life Algorithms" (BYTE, January 1979, page 90) will see that this is the same type of APL algorithm used for John Conway's two-dimensional Life, but much simpler in the one-dimensional system. [**Editor's note:** *John Conway is the English mathematician who invented the game of Life.*] The heart of the algorithm is in line 6 of listing 2. The extended pattern (universe) is rotated 2 and 1 positions to the left and 2 and 1 positions to the right. The 4 shifted patterns are then summed.

H & E COMPUTRONICS INC.

• EVERYTHING FOR YOUR TRS-80* • ATARI* • APPLE* • PET* •

*TRS-80 is a trademark of the Radio Shack Division of Tandy Corp. - *ATARI is a trademark of Atari Inc. - *Apple is a trademark of Apple Corp. - *Pet is a trademark of Commodore

NEW

★ All orders processed within 24-Hours
★ 30-Day money back guarantee on all Software

BUSINESS PAC 100

100 Ready-To-Run Business Programs

(ON CASSETTE OR DISKETTE).....Includes 110 Page Users Manual.....5 Cassettes (Or Diskettes)
Inventory Control.....Payroll.....Bookkeeping System.....Stock Calculations.....
Checkbook Maintenance.....Accounts Receivable.....Accounts Payable.....

BUSINESS 100 PROGRAM LIST

1	RULE78	Interest Apportionment by Rule of the 78's
2	ANNUI	Annuity computation program
3	DATE	Time between dates
4	DAYYEAR	Day of year a particular date falls on
5	LEASEINT	Interest rate on lease
6	BREAKEVN	Breakeven analysis
7	DEPRSL	Straightline depreciation
8	DEPRSY	Sum of the digits depreciation
9	DEPRDB	Declining balance depreciation
10	DEPRDDB	Double declining balance depreciation
11	TAXDEP	Cash flow vs. depreciation tables
12	CHECK2	Prints NEBS checks along with daily register
13	CHECKBK1	Checkbook maintenance program
14	MORTGAGE/A	Mortgage amortization table
15	MULTMON	Computes time needed for money to double, triple, etc.
16	SALVAGE	Determines salvage value of an investment
17	RRVARIN	Rate of return on investment with variable inflows
18	RRCONST	Rate of return on investment with constant inflows
19	EFFECT	Effective interest rate of a loan
20	FVAL	Future value of an investment (compound interest)
21	PVAL	Present value of a future amount
22	LOANPAY	Amount of payment on a loan
23	REGWITH	Equal withdrawals from investment to leave 0 over
24	SIMPDISK	Simple discount analysis
25	DATEVAL	Equivalent & nonequivalent dated values for oblig.
26	ANNUDEF	Present value of deferred annuities
27	MARKUP	% Markup analysis for items
28	SINKFUND	Sinking fund amortization program
29	BONDVAL	Value of a bond
30	DEPLETE	Depletion analysis
31	BLACKSH	Black Scholes options analysis
32	STOCVAL1	Expected return on stock via discounts dividends
33	WARVAL	Value of a warrant
34	BONDVAL2	Value of a bond
35	EPSEST	Estimate of future earnings per share for company
36	BETAALPH	Computes alpha and beta variables for stock
37	SHARPE1	Portfolio selection model-i.e. what stocks to hold
38	OPTWRITE	Option writing computations
39	RTVAL	Value of a right
40	EXPVAL	Expected value analysis
41	BAYES	Bayesian decisions
42	VALPRINF	Value of perfect information
43	VALADINF	Value of additional information
44	UTILITY	Derives utility function
45	SIMPLEX	Linear programming solution by simplex method
46	TRANS	Transportation method for linear programming
47	EOQ	Economic order quantity inventory model
48	QUEUE1	Single server queueing (waiting line) model
49	CVP	Cost-volume-profit analysis
50	CONDPROF	Conditional profit tables
51	OPTLOSS	Opportunity loss tables
52	FQUOQ	Fixed quantity economic order quantity model
	NAME	**DESCRIPTION**
53	FQEOWSH	As above but with shortages permitted
54	FQEOQPB	As above but with quantity price breaks
55	QUEUECB	Cost-benefit waiting line analysis
56	NCFANAL	Net cash-flow analysis for simple investment
57	PROFIND	Profitability index of a project
58	CAP1	Cap. Asset Pr. Model analysis of project
59	WACC	Weighted average cost of capital
60	COMPBAL	True rate on loan with compensating bal. required
61	DISCBAL	True rate on discounted loan
62	MERGANAL	Merger analysis computations
63	FINRAT	Financial ratios for a firm
64	NPV	Net present value of project
65	PRINDLAS	Laspeyres price index
66	PRINDPA	Paasche price index
67	SEASIND	Constructs seasonal quantity indices for company
68	TIMETR	Time series analysis linear trend
69	TIMEMOV	Time series analysis moving average trend
70	FUPRINF	Future price estimation with inflation
71	MAILPAC	Mailing list system
72	LETWRT	Letter writing system-links with MAILPAC
73	SORT3	Sorts list of names
74	LABEL1	Shipping label maker
75	LABEL2	Name label maker
76	BUSBUD	DOME business bookkeeping system
77	TIMECLCK	Computes weeks total hours from timeclock info.
78	ACCTPAY	In memory accounts payable system-storage permitted
79	INVOICE	Generate invoice on screen and print on printer
80	INVENT2	In memory inventory control system
81	TELDIR	Computerized telephone directory
82	TIMUSAN	Time use analysis
83	ASSIGN	Use of assignment algorithm for optimal job assign.
84	ACCTREC	In memory accounts receivable system-storage ok
85	TERMSPAY	Compares 3 methods of repayment of loans
86	PAYNET	Computes gross pay required for given net
87	SELLPR	Computes selling price for given after tax amount
88	ARBCOMP	Arbitrage computations
89	DEPRSF	Sinking fund depreciation
90	UPSZONE	Finds UPS zones from zip code
91	ENVELOPE	Types envelope including return address
92	AUTOEXP	Automobile expense analysis
93	INSFILE	Insurance policy file
94	PAYROLL2	In memory payroll system
95	DILANAL	Dilution analysis
96	LOANAFFD	Loan amount a borrower can afford
97	RENTPRCH	Purchase price for rental property
98	SALELEAS	Sale-leaseback analysis
99	RRCONVBD	Investor's rate of return on convertable bond
100	PORTVAL9	Stock market portfolio storage-valuation program

Circle 163 on inquiry card.

☐ **CASSETTE VERSION**	**$99.95**
☐ **DISKETTE VERSION**	**$99.95**
☐ **TRS-80* MODEL II VERSION**	**$149.95**

ADD $3.00 FOR SHIPPING IN UPS AREAS
ADD $4.00 FOR C.O.D. OR NON-UPS AREAS
ADD $5.00 OUTSIDE U.S.A, CANADA & MEXICO

H & E COMPUTRONICS INC.
MATHEMATICAL APPLICATIONS SERVICE™

50 N. PASCACK ROAD
SPRING VALLEY, NEW YORK 10977

NEW TOLL-FREE ORDER LINE
(OUTSIDE OF N.Y. STATE)
(800) 431-2818

24 HOUR ORDER LINE
(914) 425-1535

VISA · master charge

The next 3 lines apply the transition rules as a series of logical operations. I refer to this as the "shake and bake" algorithm.

The advantage of using APL becomes evident when we modify the program to achieve Life After Death, (LD1), as shown in listing 2. All we have to do is replace line 3, which is a do-nothing line in MIL, with a new line. This defines the hereafter, H, as the negation of the pattern, P, rotated 1 cell to the left. This is done with the built-in editor, which is a standard feature of APL. The new variable joins the logical operations in line 9. OLD represents survivors; NEW and H represent births; P and H represent those whose time has not yet come. Note how closely the coding follows the concept (negate, rotate). It's easy and fast. Another advantage is the ease of display manipulation.

Preliminary experiments with these two programs, MIL and LD1, reveal a weakness in Life After Death. While one-dimensional patterns usually settle down to oscillating forms, the LD1 forms become stationary objects with a tendency to drift to the right of the screen (see figure 3). Failure to generate interesting patterns by a simple extension of one-dimensional Life is another example of a long known fact—it is difficult to improve existing Life systems. This applies to Millen's simplified system as well as to Conway's two-dimensional Life. The remainder of this article explores ways out of this difficulty. Some of the suggestions may well apply to the standard game of Life.

Before we discuss the addition of a netherworld, it is worth noting that we are dealing with a generalization of the game of Life. We are adding parallel structures with their own transition rules and with rules for interaction between the structures. In the present case, we have two or three parallel, interacting, one-dimensional spaces. Theorists may be quick to point out that Life After Death is equivalent to a simple one-dimensional Life with more than two states for cells and with more complex transition rules. Thus, the states "on" and "off" are augmented by the states "off but candidate for on" and "on but candidate for off." There are practical advantages with the present approach—ease of handling and pattern-generation spinoffs. We can, for example, print only the hereafter or netherworld Life-lines (by replacing P in line 4 of LD1 [listing 2] with H, for example), or we can combine the different Life-lines in various ways for display effects. Note the simplicity of specifying a display. An array of characters is indexed by an array of integers with the result taking the shape of the indexing array.

The introduction of a netherworld, N, brings complications. To speed things along, we will use a cellular theology of heaven and hell. As creators of such a system, we now face difficult choices. Shall hell be the negation of heaven or the reversal? Shall it drift or rotate in the opposite direction and how far? There are more problems. Shall dead cells go to one place or the other or both if vacancies exist? Shall the spirits of the newborn come only from heaven, or shall the innocence of the newborn be corrupted from below? After some experimentation, LD3 and LD6 emerged as interesting for pattern-generation potential. They are shown in listing 2 and are compared with MIL and LD1 in the last two columns of figure 3.

LD3 leans toward a variety of oscillators and stationary forms, while LD6 leans more toward stationary forms with some tendency for wider growth. Both of these triple-line forms of Life allow birth if an adjacent cell is occupied in either heaven or hell. Both of them also require an opening in at least one of the parallel lines for an otherwise allowable death to occur. They differ in that hell for LD3 is a combined negation, reversal, and rotation of one cell to the right. LD6, on the other hand, sees the netherworld as a simple contrary rotation of the heavenly pattern 2 cells to the right. These modifications are shown in line 3 of LD3 and LD6 in listing 2. The birth and death consequences show up in line 9. To assist in the inter-

Text continued on page 332

Listing 2: *These APL programs for four different Life systems differ in lines 3 and 9 only. Program MIL gives the same results as the BASIC program in listing 1. LD1 adds a hereafter, H. LD3 adds a netherworld, N. LD6 does the same, but defines N differently (see text). The influence of the parallel N- and H-lines is determined in line 9 of each program.*

```
   DISPLAY 'MIL'
 0∇R←S MIL P
 1  →0×⍳2≠⍴,S←(1⍴S),(1↓S)⌈⍴P←,P
 2  R←0⍴P←(1↓S)⍴((⌈0.5×(1↓S)-⍴P)⍴G←0),P='1'
 3START:X←''
 4  ⎕←' ⎕'[P+1],'     ',⍕G
 5  →0×⍳(G←G+1)>¯1+1⍴S
 6  SUM←+/[1]2 1 ¯1 ¯2 ⌽(4,⍴P)⍴P
 7  OLD←(2=SUM×P)∨4=SUM×P
 8  NEW←(2=SUM×~P)∨3=SUM×~P
 9  P←OLD∨NEW
10  →START
  ∇

   DISPLAY 'LD1'
 0∇R←S LD1 P
 1  →0×⍳2≠⍴,S←(1⍴S),(1↓S)⌈⍴,P
 2  R←0⍴P←(1↓S)⍴((⌈0.5×(1↓S)-⍴P)⍴G←0),P='1'
 3START:H←1⌽~P
 4  ⎕←' ⎕'[P+1],'     ',⍕G
 5  →0×⍳(G←G+1)>¯1+1⍴S
 6  SUM←+/[1]2 1 ¯1 ¯2 ⌽(4,⍴P)⍴P
 7  OLD←(2=SUM×P)∨4=SUM×P
 8  NEW←(2=SUM×~P)∨3=SUM×~P
 9  P←(P∧H)∨(NEW∧H)∨OLD
10  →START
  ∇

   DISPLAY 'LD3'
 0∇R←S LD3 P
 1  →0×⍳2≠⍴,S←(1⍴S),(1↓S)⌈⍴P←,P
 2  R←0⍴P←(1↓S)⍴((⌈0.5×(1↓S)-⍴P)⍴G←0),P='1'
 3START:N←¯1⌽⌽~H←1⌽~P
 4  ⎕←' ⎕'[P+1],'     ',⍕G
 5  →0×⍳(G←G+1)>¯1+1⍴S
 6  SUM←+/[1]2 1 ¯1 ¯2 ⌽(4,⍴P)⍴P
 7  OLD←(2=SUM×P)∨4=SUM×P
 8  NEW←(2=SUM×~P)∨3=SUM×~P
 9  P←(P∧H∧N)∨(NEW∧H∨N)∨OLD
10  →START
  ∇

   DISPLAY 'LD6'
 0∇R←S LD6 P
 1  →0×⍳2≠⍴,S←(1⍴S),(1↓S)⌈⍴P←,P
 2  R←0⍴P←(1↓S)⍴((⌈0.5×(1↓S)-⍴P)⍴G←0),P='1'
 3START:N←¯2⌽H←1⌽~P
 4  ⎕←' ⎕'[P+1],'     ',⍕G
 5  →0×⍳(G←G+1)>¯1+1⍴S
 6  SUM←+/[1]2 1 ¯1 ¯2 ⌽(4,⍴P)⍴P
 7  OLD←(2=SUM×P)∨4=SUM×P
 8  NEW←(2=SUM×~P)∨3=SUM×~P
 9  P←(P∧H∧N)∨(NEW∧H∨N)∨OLD
10  →START
  ∇
```

Text continued from page 330:

pretation, the three phrases in line 9 of LD3, for example, can be read as:

- Cells whose time has not yet come (P, H, and N)
- Cells that are newborn (NEW, H, or N)
- Cells that survive (OLD)

The use of the reversal operation (backward order) in LD3 leads to an interesting property. The uniqueness of a pattern is determined not only by the sequence of on and off cells, but by its position with respect to the wrap-around point or "ends" of the Life-line. This is shown in figure 4 where the patterns 1011100, 0101110, and 0010111 are compared using LD3. Another point to note with circular or wrap-around Life is that the number of elements and their parity (odd or even) will modify the results when interacting patterns crowd the available space and approach the wrap-around point. Things get more interesting and complicated with larger patterns and Life-lines than are shown here. Many continue to evolve after a few dozen generations. These are left for the interested reader to explore. For those lacking access to APL, it will be necessary to modify the BASIC program accordingly. While not terribly difficult, it will take much more time and effort. Although APL has its problems, when it comes to speed of creating an application and maintaining (modifying) it, it has no peer among languages.

Now what about pattern generation? Many possibilities are open to us using what we have developed here. One scheme would be to fill the screen, then select a different pattern by program every time the scan starts at the top of the screen. Alternatively, a new pattern could be created by some random change in the pattern of the first video line. Likewise, the graphic characters can be changed on each new full screen cycle. Another variation would be to switch algorithms. Strong symmetries can be produced by running the reversed order line display on each half, quarter, and so on, of the screen. If



Figure 3: *Comparison of the four APL Life systems using four simple starting patterns. The Life-lines are 15 cells wide and were run for 14 generations.*



Figure 4: *The results for Life system LD3 are sensitive to the relative position of the starting pattern, in this case 10111, and the parity (odd or even) of the number of cells in the Life-line. This is a consequence of the reversal operation used in forming the H-line (see text); it's another simple way to generate display patterns.*

the routines are implemented in machine language, they will change much faster. Generally,this makes patterns more interesting. It would also allow lines to be traversed up and down at good speeds so that changing borders or rectangles might be designed. The key to pattern generation thru Life forms is that patterns are evolved not by programming their development but by changing the input data. This is easier than programming specific displays, and it may at times produce some spectacular surprises. The monotony or limited variation that is characteristic of programmed displays is easily avoided with the Life approach.

Many people say that the game of Life is addictive. One purpose of this article is to show how you can study Life without spending entire days in front of your computer. For example, I conducted trials of various triple-line Life systems while I went about other business by writing short supervisory programs (3 short APL lines) that could grind out sequences of pattern variations. I occasionally find it relaxing to experiment with Conway's Life. But I try to avoid the tube-trance syndrome by keeping a notebook on starting patterns and then placing a cardboard screen in front of the tube. On suitable occasions, I let myself peek. If a bare piece of cardboard is too stark for you, label it something like "Conway Cage" or "Anti-Medusa screen."

One final observation on the game of Life. We all have had the experience of demonstrating our home computer to non-computer-type guests who just stand by and yawn. I have found one sure-fire way to hold their interest: say nothing about Life, simply draw their initials or even their names on the screen. Then hit the start key. The reaction is always the same, a cry or a gasp as they see the familiar lines suddenly disintegrate or explode into strange patterns. Now as you explain what your computer does, they won't be bored. You'll have their attention —they've just seen your machine do something magical. ■

System Review

DOSPlus: Double-Density Operating System for the TRS-80

Yvon Kolya
POB 22
Peterborough NH 03458

Percom's Doubler, an add-on circuit board that allows your TRS-80 to store and retrieve data from the Radio Shack disk drives in double-density mode, has been on the market for almost a year now (see the review "Percom's Doubler" on page 344 in this issue of BYTE). The board comes with Percom's Double-DOS (disk operating system), an adaption of Radio Shack's TRS-DOS that lets you use the doubler board without buying a DOS from another source.

Double-DOS is simply Radio Shack's TRS-DOS with the BACKUP, FORMAT, and COPY commands altered to operate in double-density mode. The COPY command has been changed to let you use special syntax to specify when you are going to transfer files to and from single-density DOS disks. Thus, as soon as you have installed the board and turned on the system, you can immediately enter double-density mode.

The disadvantage of the DOS supplied by Percom is that you can only use double-density formatted disks; single-density disks cannot be mixed with double-density disks. You can transfer files to and from single-density disks, but you cannot read data files, read the directory, or use the disks in any other way while running Percom's double-density DOS.

There is, however, another double-density DOS on the market that can do this and more: DOSPlus is a complete rewrite of TRS-DOS. Available from Micro Systems Software of Hollywood, Florida, it is a double-density DOS that not only outperforms Percom's double-density DOS, but also outperforms most of the single-density DOSs. DOSPlus has all the features of TRS-DOS (and Percom's Double-DOS), so I won't detail the duplicate functions. Instead, I will focus on the additions to TRS-DOS by DOSPlus, beginning with the LIB (library) functions.

At a Glance

Name
DOSPlus Double Density

Type of package
Disk operating system

Publisher
Micro Systems Software, Inc
5846 Funston St
Hollywood FL 33023
(305) 983-3390

Price
$99.95

Medium
5-inch disk, TRS-DOS compatible

Documentation
45 pages, 8½ by 11 inches

Computer
TRS-80 Model I Level II with Expansion Interface, 5-inch disk drives, and Percom Double Density Board

Required Hardware
Percom Double Density Board (not supplied)

Audience
Programmers and owners of TRS-80 Model I Disk Systems with Percom's Double Density Board

DOSPlus Commands

The LIB command clearly shows the additions that have been made by DOSPlus (see table 1 for a comparison list of the library functions supplied by TRS-DOS and DOSPlus). There are also alterations in some of the commands that are common to both operating systems. I'll start with those and then deal with the new commands.

The first command usually given when a new disk is loaded is DIR (directory). With DOSPlus, instead of just getting the names of the entries in the disk's directory track, you get each file's protection attributes; logical record length, which is 256 for programs, 1 for ASCII (American Standard Code for Information Interchange) files, and anything in between for data files; the number of logical records used by the files; the number of sectors occupied by the files; the number of granules used by the files; the number of segments each file is broken into; and the position in the last sector of the end-of-file byte (see listing 1). At the bottom of the directory display is a final line that indicates the number of free (unoccupied) granules left on the disk, and what that equals in actual bytes.

Also, some changes have been made in the parameters allowed by DOSPlus. In TRS-DOS you can specify:

```
DIR :1 (S,I,A)
```

where S means display system files in addition to normal files, I means display invisible files in addition to normal files, and A means display the information on all the files.

In DOSPlus you can specify:

```
DIR :1 (S,I,D,P)
```

where S means display system files in addition to normal files; I means display invisible files in addition to normal files; D means display all those files in the directory that are currently considered *dead* files, in addition to the normal files (dead files are files that have been KILLed; they can be recovered if you haven't written a new file over the dead file); and P means send the directory display to the line printer. Typing in DIR alone under DOSPlus displays all visible files, statistics, and free disk space in granules and bytes.

The next major difference is in the FREE command. Rather than give the number of available free granules in the disk drives, DOSPlus gives an actual map of the disk drive specified, clearly labeling those granules used by the directory (a D is displayed), and by programs or data files (an X is displayed). Unused granules have only a period displayed (see listing 2).

Another improvement is in the COPY command. It is not necessary to repeat the name of a file to copy it. For example:

```
COPY MYFILE/CMD:0 :1
```

does the same thing as the TRS-DOS command:

```
COPY MYFILE/CMD:0 TO
MYFILE/CMD:1
```

TRS-DOS	DOSPlus
APPEND	APPEND
ATTRIB	ATTRIB
AUTO	AUTO
	BREAK
	BUILD
	CLEAR
CLOCK	CLOCK
	CONFIG
COPY	COPY
	CREATE
DATE	DATE
DEBUG	DEBUG
DEVICE	DEVICE
DIR	DIR
	DO
DUMP	DUMP
	FORCE
	FORMS
FREE	FREE
KILL	KILL
LIB	LIB
LIST	LIST
LOAD	LOAD
PRINT	(handled by LIST)
	PAUSE
PROT	PROT
RENAME	RENAME
	RS232
TIME	TIME
VERIFY	VERIFY

Table 1: *Comparison of functions provided by Radio Shack's TRS-DOS versus those provided by DOSPlus.*

OUR TIMING CONTROL UNIT HELPS YOUR COMPUTER KEEP SCORE OF TIME AND DATE.

Power-up or power-down, your computer always knows the time, *exactly*, with Digital Pathway's Timing Control Unit (TCU). Even during extended power interruptions. Rechargeable battery support makes our TCU immune from power failure of any kind. For as long as three months. And an on-board crystal-controlled oscillator ensures supreme accuracy.

No matter what model computer you have, you'll find our TCUs offer many features that make living with computer timeouts less complicated. And some models can even be set to initiate an interrupt at a chosen date and time. Or at specified intervals.

Find out how we can help make your time more productive. Call or write Digital Pathways today for more information at 1260 L'Avenida, Mountain View, CA 94043. Telephone (415) 969-7600. TWX: 910-379-5034.



*PDP-11 and LSI-11/2 are registered trademarks of Digital Equipment Corp. Others listed are trademarks, respectively, of Intel Corp., Motorola Inc., Hewlett-Packard, Lockheed Corp. and Computer Automation Inc.

*PDP-11	TCU-100	$495
	TCU-150	$460
*LSI-11/2	TCU-50D	$325
*Multi-Bus	TCU-410	$325
*EXORcisor	TCU-68	$325
*HP 2100	TCU-2100	$395
*Lockheed SUE	TCU-200	$550
*Naked Mini	TCU-310	$385
Any Model Computer (RS-232/20mA)	SLC-1	$640

DIGITAL PATHWAYS

NOW YOU'RE SAFE FROM COMPUTER TIMEOUTS EVEN AFTER THE POWER GOES.

Circle 122 on inquiry card.

Canada: (403) 286-2744 • England: 403 813 813
Germany: (089) 60 60 71-72 Telex: 5216290 isio d • Switzerland: 022/310587 Telex: 289191

Listing 1: *An example of the DOSPlus directory function.*

```
DIRECTORY DRIVE: 0      DOS 3.1S - 01/22/81 - 3.2
FILENAME        ATTRB   LRL   #LOG   #PHY   #GRN   #SEG    EOF
TBASIC   CMD    N*U6    256     16     16      4      1    120
DISKZAP  CMD    N*U6    256     11     11      3      1    166
COM64768 OBJ    N*X0    256      3      3      1      1      0
LISTER   CMD    N*X0    256     21     21      5      1      0
TRANSFER CMD    N*U6    256      4      4      1      1      4
CRUNCH   CMD    N*U6    256      3      3      1      1     65
CLRFILE  CMD    N*U6    256      2      2      1      1    153
DISKDUMP CMD    N*U6    256      4      4      1      1     84
SPOOL    CMD    N*U6    256      5      5      1      1     95
COPY1    CMD    N*U6    256      4      4      1      1    144
PURGE    CMD    N*U6    256      3      3      1      1     70
COMPARE         N*X0    256     12     12      3      2     36
RESTORE  CMD    N*U6    256      4      4      1      1     50
BASIC    CMD    N*X0    256     21     21      5      2     47
***      18 GRANS,      22 K ***
```

Listing 2: *An example of the DOSPlus FREE function.*

```
                   Free space map - Drive 0
00-06:    X X ! X X ! X . ! . . ! X X ! X X ! . .
07-13:    . . ! X X ! X X ! X X ! X . ! . . ! . .
14-20:    X X ! X X ! X X ! D D ! X X ! X X ! X X
21-27:    X X ! X X ! X X ! X X ! X X ! X X ! X X
28-34:    X X ! X X ! X X ! X X ! . . ! . . ! . .
```

There are other improvements but they are minor.

New Library Commands

BREAK lets you disable the break key to prevent people from using it to get into your programs.

BUILD lets you build a file of DOS commands that can be executed one right after the other. You can build a file that can go from a "boot-up" all the way to running a BASIC program (and setting the memory size to protect a machine-language program and any necessary disk buffers), without the operator having to do anything except press the Reset button.

CLEAR is a simple command that sets all memory locations above hexadecimal 7000 to 0.

CONFIG lets you tell DOSPlus of any special system or drive configurations. You can modify the number of tracks on a disk from 35 to 80, set the track-to-track stepping rate of the read/write head of the drive, use the high-speed or reverse-video modifications (if you have them), or specify if your drives are double sided. You can use this command, for example, to tell DOSPlus that you have an 80-track drive as drive 0, a 35-track drive as drive 1, and a double-sided 40-track drive as drives 2 and 3, as well as take advantage of the high-speed clock modification you've put into your computer. It will now "know" this each time you turn it on, giving you maximum effectiveness and efficiency.

CREATE lets you allocate space to a file before you actually put any information in it, thus eliminating the time required for updating the directory when you use the file. As well, this helps to prevent the file from being "chopped up" into many segments all over the disk. (Keeping the file together reduces drive-head seek time.)

DO tells DOSPlus to execute a file constructed by the BUILD command. It can be used in the AUTO command structure.

FORCE lets you route the I/O (input/output) between the different devices. You can force the computer to send all LPRINTs to the video instead of to the printer, for example. Or you can send the keyboard echo to the printer instead of to the video (handy when trying to do program documentation).

FORMS is, by far, one of the most



Hayden's APPLESOFT COMPILER means Speed for your Apple II™—

New! **APPLESOFT COMPILER** (Eiten) Hayden's Applesoft Compiler will convert standard Applesoft programs into 6502 machine binary files, which can be B-Run, from three to ten times faster. It compiles code at user-specified address. The seventeen phase compiler provides a map of the program structure at the end of compilation. ***#08809, Apple II Disk, $200***

DISK CERTIFIER AND COPIER (Jacc Inc.) A handy utility program that certifies the acceptability of blank diskettes and rejects those with flaws. It also includes a fast machine language disk copying program that will work on single and dual drive systems. ***07809, APPLE II Disk, $19.95***

LINE & VARIABLE CROSS REFERENCE GENERATOR (Johnson) Provides a cross-reference of line numbers and variable names. ***07301, PET tape, $16.95***

RENUMBER & APPEND: Utility Programs for the Apple (Gilder) Renumber your Applesoft program and append a second program to the one in memory. ***03804, Apple II tape, $14.95***

REVIVE (Gilder) When a program is accidentally erased, REVIVE searches through memory and finds the information that enables it to restore the pointers that have been changed. ***03604, Apple II tape, $19.95***

ORDER NOW!

Hayden Book Co., Inc.
50 Essex St. Rochelle Park, NJ 07662

Please send me the software checked on a 10-day FREE examination. At the end of that time, I will send payment, plus postage and handling, or return the software and owe nothing. On all prepaid orders, publisher pays postage and handling - same return guarantee. Residents of NJ and CA must add sales tax. Offer good in USA only. Prices subject to change without notice. Payment must accompany orders from PO Box numbers. Allow 4 to 6 weeks for delivery. Name of individual ordering must be filled in.

☐ 03504	☐ 04909	☐ 05208	☐ 08609
☐ 03604	☐ 05004	☐ 05409	☐ 08809
☐ 03804	☐ 05009	☐ 05509	☐ 09009
☐ 03904	☐ 05103	☐ 05713	☐ 09109
☐ 04609	☐ 05108	☐ 07301	☐ 09409
☐ 04804	☐ 05203	☐ 07809	☐ 09704

Name ____________________

Street ____________________

City/State/Zip ____________________

B 7/81-009

APPLESOFT UTILITY PROGRAMS (Gilder) Increase your BASIC programming speed and flexibility. Contains 9 useful subroutines: 1. REM Writer 2. PRINT Writer 3. POKE Writer 4. Hexadecimal/Decimal Converter 5. Line Counter 6. Renumber 7. Append 8. Byte Counter 9. Slow List/Stop List ***03504, Apple II tape, $29.95***

SLOW LIST/STOP LIST: Utility Programs for the Apple (Gilder) Start, stop, and control the speed of your program with Apple II's game paddles. ***03904, Apple II tape, $10.95***

PSEUDODISK (Neuschatz) This money-saving program simulates a disk memory system for Integer BASIC programs. It allows multiple programs in memory at the same time which can be run from a catalog. ***04804, APPLE II tape, $24.95***

6502 DISASSEMBLER (Stamm) Produce assembly language source files with labeled subroutines and references from programs already in memory. It is compatible with Hayden's ASSEMBLY LANGUAGE DEVELOPMENT SYSTEM. ***08609, APPLE II Disk, $39.95***

DISK CATALOGER (LeBar) Automatically maintains a cross-reference listing of all your programs, their location by disk number, their function and use. Catalogs, lists and sorts programs. ***05203, TRS-80 Level II tape, $16.95; 05208, TRS-80 Level II Disk, $21.95***

FINPLAN: A Financial Planning Program for Small Businesses (Montgomery) Allows you to enter data from a balance sheet into the program, to make assumptions about the future growth of business, and to have the computer project results for up to a five year period based on those assumptions. And if you change any data, the program revises all resulting data automatically. The disk version can be used only with TRSDOS version 2.3. ***05103, TRS-80 Level II tape, $69.95; 05108, TRS-80 Level II Disk Version, $74.95***

MAILING LIST (Tru-Data Software) Lists addresses, prints labels, allows for alterations and deletions, and has the capacity to make duplicate data file disks. Can only be used with version 1.5. ***05713, Heath Disk $49.95***

Apple is a trademark of Apple Computer Company, Inc., and is not affiliated with Hayden Book Company, Inc.

DATA MANAGER: A Data Base Management System and Mailing List (Lutus) Store information on a floppy disk, and retrieve it quickly and easily by specific names, or by category. ***04909, Apple II Disk Version, $49.95.***

PROGRAMMING IN APPLE™ INTEGER BASIC: Self-Teaching Software (Banks & Coan) Teach yourself Apple Integer BASIC and control your own progress at all times with this interactive programmed instruction format. ***05004, Apple II, tape, $29.95; 05009, Apple II Disk Version, $39.95***

APPLE™ ASSEMBLY LANGUAGE DEVELOPMENT SYSTEM: An Assembler/Editor/Formatter (Lutus) Write and modify your machine language programs quickly and easily. ***04609, Apple II Disk Version, $39.95.***

SUPER APPLE™ BASIC (Lutus) A structured BASIC that compiles into an optimized Applesoft or Integer BASIC program. ***05409, Apple II Disk, $39.95***

Super FORTH (Bugbee) This is a fast, high-level, expandable language that features integer and floating-point math, high-resolution graphics and string handling capability. ***05509, APPLE II Disk, $49.95***

NEW!

OP-AMP DESIGN (Gabrielson) Provides the necessary values for your design and will suggest appropriate op-amp types. Includes a choice of six op-amps, and the program will then determine if your selection of an op-amp will be acceptable within your chosen parameters. Can be updated to accommodate future op-amps. ***09704, Apple II tape, $16.95***

DOUBLE PRECISION FLOATING POINT FOR APPLESOFT (S-C Software) Extends the accuracy of the arithmetic available on the Apple from nine digits to a full 21-digit precision on all functions in Applesoft compatible format. ***09409, Apple II Disk, $49.95***

DATA-GRAPH (Boyd) Aids in the preparation of graphs and charts. Numeric data can be entered into Data-Graph and used to create colorful one-, two-, or four-quadrant graphs. ***09109, Apple II Disk, $49.95***

HISTO-GRAPH (Boyd) A calendar-based histogram or bar-graph production system. Allows the user to enter numeric data that relates to a date, and reproduces that data as a high-resolution histogram. ***09009, Apple II Disk, $29.95***

Available at your local computer store!

Hayden Book Company, Inc.
50 Essex Street, Rochelle Park, NJ 07662

requested features of a DOS. You can set the number of lines on each page (for printing on special forms such as invoices); the number of characters on each line (nice if you have a 132-column printer and only 80-column paper). You can direct all normal printer output to the RS232 serial port instead of to the printer port. (All the software that is needed to drive the serial I/O is built into DOSPlus.) DOSPlus even generates an automatic linefeed upon carriage return, for printers that don't have this feature.

PAUSE halts program execution (usually a file being executed by the DO command) so the user can perform a needed operation such as inserting a data disk. It can be executed from BASIC by using the CMD " " command.

RS232 automatically prints out the switch settings of the RS232 board.

DOSPlus Utilities

The BACKUP utility works essentially the same as the BACKUP supplied with TRS-DOS except it is possible to BACKUP a 35-track disk to a 40-, 77-, or 80-track (or any number in between) disk, without losing the additional tracks. This means that although you have purchased a 35-track DOS, you can convert it to a 40-track DOS simply by using FORMAT to make a 40-track disk, and then using BACKUP to move all of the system files, utility files, and any other files on your 35-track disk, to the 40-track disk. You can also reverse the procedure and BACKUP a 40-track disk to a 35-track disk. If you have used only 34 tracks of your 40-track disk, this will work without problems, but if you have used all 40 tracks of your 40-track disk, then you will lose those files on the last 5 tracks.

FORMAT is similar to the TRS-DOS; the difference is that DOSPlus asks you how many tracks you want to format onto the new disk. Any number from 35 to 80 is acceptable.

CLRFILE is an interesting utility that lets you set the contents of a disk file to all 0s, achieving the results of KILLing a file without altering the file's directory entry. The end result is

as if you used the CREATE command to preallocate space to a file.

COPY1 allows single-drive owners to copy a file from one disk to another without keeping a system disk in drive 0.

CRUNCH is a compression utility that removes unnecessary blanks and REM statements from a BASIC program. CRUNCH will ignore lines containing DATA statements to preserve the integrity of any string DATA. Unlike all the other compression utilities, this one is executed from DOS and reads the BASIC program file and writes it back to the disk under a new name. Thus, you have two files on the disk instead of one—your source file and your new file.

DISKDUMP is a machine-language program for displaying and modifying files on the disk.

DISKZAP is a powerful disk editor. It is similar in many ways to Apparat's Superzap. It lets you put all 0s in disk sectors, copy sectors, print them, verify them, format a disk, and display and modify sectors.

PURGE takes the drudgery out of removing files from your disk. When you type and enter PURGE, DOSPlus will list each file in the directory, one at a time, followed by a question mark. If you type Y, then that file will be deleted from the directory. If you just press ENTER, then nothing is done to that file and the next one is listed.

RESTORE is an emergency use utility. It recovers files that you've accidentally KILLed. It cannot recover files that have been overwritten by SAVEs or DUMPs that you've done since you KILLed the target file.

SPOOL is good for handling large amounts of printer output when you don't want to tie up the computer. This program sets up a buffer in memory (you set the size when you call up this utility) in which output to the printer is stored as it is generated. This buffer is dumped to the printer as fast as the printer can accept it, but if the program is generating data faster than this, the buffer holds the data until it can be printed. This allows more efficient use of the computer's time, since it no longer has to

stop and wait for the printer to catch up with it. In addition, if the buffer is likely to be overfilled itself, you can specify a disk file that will be used to store data.

TRANSFER moves all the user files on one drive to another in one command, instead of typing in COPY for each file.

DOSPlus BASIC

DOSPlus is sold with two different BASICs on the disk. Both are written in Z80 Assembly Language code, unlike Microsoft BASIC that is written in 8080 code. It has many advantages over the BASIC sold by Radio Shack (and Percom). You can:

- Load BASIC with no protected memory and no disk-file buffers: <BASIC>
- Go from BASIC to DOS, and then reenter BASIC without losing your program: <BASIC*>
- Load BASIC and automatically RUN a program: <BASIC filespec>
- Load BASIC and reserve disk-file buffers: <BASIC −F:2>
- Load BASIC and protect memory: <BASIC −M:64000>
- Do 3, 4, and 5 together: <BASIC filespec −F:3 −M:60000>

Any DOS command can be executed from BASIC by typing CMD"DOS command". (This works internally or externally to a program.) You can move a line from one place in a program to another without having to type it in again: DI xxxx,yyyy moves line xxxx to a new line numbered yyyy. You can duplicate a line: DU xxxx,yyyy puts a duplicate of line xxxx at a new line numbered yyyy. The RENUMBER command allows renumbering of all or part of any BASIC program.

You can add data directly to the end of a sequential file without having to read the entire file into memory first: OPEN"E",1,"filespec." Sector deblocking of file records is supported in random-access files: OPEN"R",1,"filespec",xx where xx is

any number between 1 and 256. Therefore, you can deal with any logical record length desired, regardless of the length of a physical disk sector.

The TAB function has been fixed so that you can LPRINTTAB(101) and have the line printer correctly tab to the 101st column of your paper. TRACE has been modified to control execution of a program by pressing <ENTER> each time you want the next program line to be executed. A variable and line number cross-reference utility has been added to BASIC. And a new command, CMD"M", is now available. CMD"M" will automatically give you a list of all of your program's variables *and their current values*. CMD"M" is a valid program-line command. It is easily the most powerful debugging tool a programmer could have.

Three main differences exist between DOSPlus BASIC and memory-saving DOSPlus TBASIC (Tiny BASIC): BASIC gives you 35,978 available memory locations; TBASIC gives you 40,205. TBASIC does not have expanded error messages (TBASIC says SN ERROR instead of SYNTAX ERROR). And TBASIC does not allow DOS commands from BASIC.

Overall, DOSPlus is a well written and executed DOS. It includes many features not found on other DOSs. It certainly outperforms Percom's Double-DOS. And even though you have to buy it as a separate unit from the Doubler board, it is worth the money, considering its power. ■

Update

Since this review was written, Micro Systems Software has released version 3.3 of DOSPlus which contains several new features as well as some changes to original functions. Version 3.3 is available in three formats: single-density Radio Shack TRS-80 Model I, double-density TRS-80 Model I with the Percom Doubler, and double-density TRS-80 Model III. Except for some minor aspects of the system conversion (ie: single-density to double-density conversion) utilities and storage capacity, these three versions of DOSPlus are identical from the user's point of view. In fact, DOSPlus-equipped Model IIIs and Model Is can read each other's double-density disks.

Several changes were made to the basic system configuration. The version 3.3 CONFIG utility no longer assigns a separate drive number to each side of a double-sided disk drive; it defines them as one drive with two sides, A and B. Thus, the user may have either four single-sided drives or three double-sided drives on a system (only three double-sided drives are supported because the select signal for the fourth drive is used as a side-select signal). Unlike version 3.1 DOSPlus, all disk drives on a given system are assigned the same number of tracks.

CONFIG also can access a mode where TRS-80 graphics characters may be directly transmitted to compatible printers such as the Epson MX-80 and the Okidata Microline-80.

Version 3.3 DOSPlus has an improved RS232 command that lets you alter as well as display the serial interface control parameters. You can specify the communications rate in bits per second, alter the format of a data word (number of stop bits, word length, and parity), and control the handshaking protocol for interfacing with virtually any RS232C-compatible device.

The CLEAR command has been modified so that it clears memory starting at location 5700 hexadecimal.

The MAP command shows the disk space allocated to each file on a disk, by track and sector.

In BASIC, a CMD"REF", <parameter> command will immediately print a cross-reference by line number of all variables, keywords, or targets of GOTOs and GOSUBs (with optional hard copy) of any BASIC program in memory. A "LOAD filename,V" or "RUN filename,V" command placed in a BASIC program will execute or load the next BASIC program specified without destroying the contents of the variables used by the previous program. You can now easily pass data and arrays from one BASIC program to the next without having to write to the disk. ...**KC**

Percom's Doubler

Mahlon G Kelly, 268 Turkey Ridge Rd
Charlottesville VA 22901

Did you ever wish that you had an 8-inch floppy-disk-drive system, 80-track drives, or even a hard disk for your (Radio Shack) TRS-80 Model I?

Granted, disks were a great improvement over cassette tape for storage of programs and data, but many of us quickly found that even disk storage was limiting. Consequently, we bought additional drives but *still* wanted more storage than was available on each drive. Few of us could afford to trade in our old drives on the new, larger units, and many experimenters read about double-density drives and sighed wishfully, "Why didn't Radio Shack make the Model I a double-density system?"

At a Glance

Name
Doubler

Function
Hardware add-on and associated software to implement double-density disk operation on a TRS-80 Model I

Manufacturer
Percom Data Co
211 North Kirby
Garland TX 75042
(214) 272-3421

Price
$219.95

Features
Allows operation with 35-, 40-, 77-, and 80-track 5¼-inch floppy-disk drives in single density (ten sectors per track) or double density (eighteen sectors per track), giving the user 180 K bytes of disk storage on a regular 40-track drive

Documentation
Detailed installation and software-patching instructions

Options
Patches for at least four different operating systems

Audience
TRS-80 owners seeking to increase the storage capacity of their regular 5¼-inch disks

A single-density drive expects that much of the data stored on the disk is in the form of null characters. With the older recording heads and disks this practice was necessary. Removal of the null characters can improve storage capacity by 80% (and effect an equivalent change in the data transfer rate). This is called double density, and, in theory, by changing the LSI (large-scale integration) disk-controller device and the DOS (disk operating system) software, it should work with the TRS-80.

More than two years ago, one of the main suppliers of floppy-disk drives, Vista, advertised (and even pictured) a unit that would allow double density with the TRS-80. I was among the first to place an order, and about six phone calls and a year later I learned that they had abandoned the project because of insurmountable software problems. They actually told me that it couldn't be done.

Ten months ago, Percom, another disk-drive supplier, advertised a similar system, called the Doubler. With a certain amount of skepticism I ordered one. After a month (with delivery promised in a week) and two lost purchase orders, the double-density system arrived. Is it reliable? Does it perform as promised? Is it compatible with other software? Is it easy to install? These and other questions occurred to me, and now that I've answered them, I'm convinced. Percom's conversion nearly doubles the capacity of most disk drives, and it's very easy to use.

Hardware and Operation

How does the Percom system work? The answer is simple: by putting 18, rather than 10 sectors on a disk track. With a 40-track drive and normal density, you have 400 sectors of storage. With Percom's Doubler system you have 40 times 18, or 720 sectors of data. During routine operation you only notice this change by the increased storage and speed. (The speed is greater by a factor of 1.8 because more data is read on each rotation of the disk.) If you have 35-, 40-, or 77-track drives, the track number

Quick, name the only working 5¼" Hard Disk Controller Cards You can order off-the-shelf!

The 5¼" Hard Disk Controller Packages from ACT.

Now you can pick up your phone and order the only working digital data separator based 5¼" controller cards for your Zenith/Heath, TRS-80, S-100, and Superbrain micro-computer systems.

And software too! Every disk controller package comes complete with CP/M 2.2 and all of the software required to install the hard disk on **your** system. And best of all, we include full source of every file supplied which was written by ACT. Packages for H89, TRS-80, and Superbrain are preconfigured for those systems. Just install the hardware and boot the system.

But beware, these controller packages are proving themselves to major U.S. and European OEM manufacturers as very efficient little jewels. Once you plug-in our 5¼" hard disk and controller cards, you may not recognize your computer. . .

5,000,000 super-fast bytes will transform your microcomputer into a high-throughput workhouse. Faster turn-around and greater efficiency are so obvious that it'll leave you wondering how you put up with the slower, less reliable 5¼" or 8" floppies.

The fact that our patent pending HOP Digital Data Separator gives our controller packages maintenance-free reliability should convince even the dyed-in-the-wool 5¼" or 8" floppy disk fanatics.

5¼" hard disks are the way of the future and ACT has an affordable, efficient 5¼" hard disk package you can order off-the-shelf. Just pick up your phone and call us.

High-performance meets low cost.

In terms of byte-per-dollar cost, 5¼" Winchester types are up to five times more affordable than 5¼" floppies. In terms of reliability, efficiency and sheer speed, the 5¼" hard disks blow everything else right out of the water.



ACT manufactures quality controller card packages with low-cost and high-performance in mind. Even the first ACT HOP controller card package we delivered to Western Europe is still running like a dream. So are our other deliveries.

So if you're looking for the way to affordably upgrade your own microcomputer system, or your whole company's microcomputer system, call the company that introduced high-performance to low-cost.

Plug-it-in; turn-it-on.

You can order our products in any configuration you desire. Order just the HOP Digital Data Separator, or just the controller card package.



Or, you can order fully assembled CRT terminals with an integrated 5¼" Winchester Hard Disk and controller card package. Should you want a 5¼" floppy back-up, you can order our dual 5¼" hard disk and floppy combination.

Whatever you order, remember that our units feature simple, standard plug-in compatibility with your Zenith/Heath, TRS-80,* S-100 or Superbrain* micro-computers. Just plug-it-in and turn-it-on.

Call ACT today for your 5¼" hard disk needs; we believe our products will impress you and your computer. Call (703) 471-9750.

$1,250.

(single quantity) for the complete ACT 5¼" Hard Disk Controller Card Package. Hard Disks, CRT Terminals, etc. are priced extra. Substantial OEM and dealer discounts are available.

act

American Computer and Telecommunications Corporation

11301 Sunset Hills Road
Reston Virginia 22090
(703) 471-9750

Circle 21 on inquiry card.

*TRS-80 is a trademark of RADIO SHACK, a division of Tandy Corporation
SUPERBRAIN is a trademark of INTERTEC DATA SYSTEMS

doesn't change—there is simply more data stored on each track. The change is made by the simple installation of a small printed-circuit board in the Expansion Interface, and use of one of the double-density operating systems provided by Percom (it provides five different operating systems, the standard being DBLDOS). I will describe these systems later in the article. (See also "DOSPlus: A Double-Density Operating System" on page 334 of this issue.)

Percom supplies almost no information on the hardware modification, although it gives very detailed (almost intimidating) directions for the simple installation. Installation consists of removing the large, conspicuous disk-controller integrated circuit from the interface, plugging it into the little board, and then plugging the board into the original disk-controller socket. There's no trace cutting or soldering. Percom's printed-circuit board has ten small integrated circuits, a few capacitors and resistors, a second disk controller, and a socket for the controller from your interface. I was amused that Percom has removed all of the numbers from the devices, yet an advertisement in a major magazine shows a picture of the board on which all of the numbers can be read. The new controller circuit is used for double-density operation, while the old one allows normal operation. The double-density operating system actually boots in single density, then actuates a software switch that changes between the controllers (the first track on the double-density disks is really single density).

An important point of the modification is that if you used your old single-density operating system, you would never know that the hardware modification had been made, except that operation would be more reliable. (For some time, Percom has sold a nice modification called the Data Separator that corrects a reputed design fault in the TRS-80. This board, installed in the same way as the Doubler, prevents read/write and format errors on the highly packed center tracks. The Doubler does the same thing.)

Software

Percom provides five different operating systems: OS-80D, a modification of its own BASIC-oriented operating system OS-80; DBLDOS, the system provided with the Doubler (which is a modification of TRSDOS 2.1 but with errors and key bounce corrected); and NEWDOS/80 or VTOS 4.0, for which it sells patch programs (called DoubleZaps) that convert the systems for double density. It also sells a "super" version of the NEWDOS/80 patch (DoubleZap 2) that sets individual drives to either single or double density. Thus, just as NEWDOS/80 lets you set up a mixture of 35-, 40-, and 77-track drives, this lets you mix single- and double-density units.

I haven't used the OS-80 or OS-80D, and I've only briefly used VTOS without Percom's modification, so I'll say nothing about those systems. Percom tells me that the operating systems are continuously upgraded and that revisions will be sent to users who have returned their warranty card. I did not, however, find much need for revision.

The logical place to begin discussing the software is with DBLDOS. DBLDOS is so similar to TRSDOS that the TRSDOS manual is used for DBLDOS (and you'll need it if you're buying drives for the first time). Percom's documentation of the differences is very complete, with more examples than most of us want to read. There are changes in the BACKUP, FORMAT, and COPY functions, in the invocation of BASIC, and in different track numbers and track seek times. (The useless DEVICE function is also eliminated.) The function changes are needed for double density; the others are logical, simple enhancements of TRSDOS.

To back up (save a copy) or format (initialize) a disk, DOUBLE must be entered first. DOUBLE FORMAT :1 (enter) starts the double-density formatting procedure. You are then asked for the disk name, the date, and the number of tracks on the disk. Nonstandard track numbers are supported, and the default value on the number of tracks is 40.

The command DOUBLE BACKUP :0 TO :1 does what you would expect: it produces a double-density backup of the disk in drive 0 by copying to drive 1, and with the same number of tracks. DOUBLE BACKUP :0 TO :1 T77, however, would format the disk in drive 1 at 77 tracks, and then back up the information from 0, regardless of the number of tracks on that drive. Thus, the 35-track disk that DBLDOS is supplied on can be

COMPUTER CENTER

31 East 31st Street • New York, N.Y. • (212) 889-8130
(between Madison & Park Avenues)

480 Lexington Avenue • New York, N.Y. • (212) 687-5090
(American Brands Bldg. between 46th & 47th St.)

presenting the LARGEST SELECTION OF SOFTWARE EVER ASSEMBLED...

for ATARI® • APPLE® • PET® • TRS-80® and other Microcomputers

at SUPER DISCOUNT PRICES!

ATARI
- ☐ ATARI 800 COMPUTER 775.00
- ☐ ATARI 400 COMPUTER 375.00
- ☐ SPACE INVADERS (AT) 17.95
- ☐ ASSEMBLER DEBUG (AT) 53.95
- ☐ BASKETBALL (AT) 35.95
- ☐ VIDEO EASEL-LIFE (AT) 35.95
- ☐ SUPER BREAKOUT (AT) 35.95
- ☐ MUSIC COMPOSER (AT) 53.95
- ☐ COMPUTER CHESS (AT) 35.95
- ☐ 3-D TIC TAC TOE (AT) 35.95
- ☐ STAR RAIDERS (AT) 35.95
- ☐ PADDLES (AT) 17.95
- ☐ JOYSTICKS (AT) 17.95

ADVENTURE INTERNATIONAL
- ☐ ADVENTURE #0 (T) 6.25
- ☐ ADVENTURE (1,2,3) [D] (AP,T) 35.95
- ☐ ADVENTURE (4,5,6) [D] (AP,T) 35.95
- ☐ ADVENTURE (7,8,9) [D] (AP,T) 35.95
- ☐ ADVENTURE (specify 1-10) (AP,T,AT) 13.55
- ☐ PROJECT OMEGA (T) 13.55
- ☐ PROJECT OMEGA (T) [D] 22.50
- ☐ PLANETOIDS [D] (AP) 17.95
- ☐ MEAN CHECKERS MACHINE (T) 17.95
- ☐ DR. CHIPS (T) 13.55
- ☐ KID-VENTURE 1 (AP,T) 17.95
- ☐ LUNAR LANDER (T) 13.55
- ☐ MOUNTAIN SHOOT (AT) 8.95
- ☐ SLAG (T) 13.55
- ☐ STAR TREK 3.5 (AT,T) 13.55
- ☐ STAR TREK 3.5 [D] (T) 17.95
- ☐ SUNDAY GOLF (AT) 8.95
- ☐ ZOSSED IN SPACE (T) 13.55
- ☐ SILVER FLASH (T) 13.55
- ☐ SILVER FLASH [D] (T) 17.95
- ☐ MISSILE ATTACK (T) 13.55
- ☐ STAR SCOUT (T) 13.55
- ☐ GALACTIC EMPIRE (AT) 13.45

AVALON HILL
- ☐ MIDWAY (P,T,AP) 13.50
- ☐ NUKE WAR (P,T,AP) 13.50
- ☐ PLANET MINERS (P,T,AP) 13.50
- ☐ CONVOY RAIDER (P,T,AP) 13.50
- ☐ B1 BOMBER (P,T,AP) 13.50
- ☐ LORDS OF KARMA (P,T,AP) 18.00
- ☐ CONFLICT 2500 (AP,AT,P,T) 13.50
- ☐ COMPUTER ACQUIRE (AP,P,T) 18.00

ACORN SOFTWARE
- ☐ ATERM (T) 17.95
- ☐ SYSTEM SAVERS (T) 13.55
- ☐ DISASSEMBLER (T) 13.55
- ☐ DISK/TAPE UTILITY (T) 17.95
- ☐ STAR TREK SIMULATION (T) 8.95
- ☐ GAMMON CHALLENGER (T) 13.55
- ☐ PIGSKIN (T) 13.55
- ☐ ULTRA TREK (T) 13.55
- ☐ SPACEWAR (T) 8.95
- ☐ WARP/LANDER (T) 8.95
- ☐ BASKETBALL [D] (T) 18.95
- ☐ BASKETBALL (T) 13.55
- ☐ DUEL-N-DROIDS [D] (T) 18.95
- ☐ DUEL-N-DROIDS (T) 13.55
- ☐ INVADERS FROM SPACE (T) 13.55
- ☐ INVADERS FROM SPACE [D] (T) 18.95
- ☐ PIGSKIN [D] (T) 18.95
- ☐ PINBALL (T) 13.55
- ☐ PINBALL [D] (T) 18.95
- ☐ SUPERSCRIPT [D] (T) 28.95
- ☐ EVEREST EXPLORER (T) 13.55
- ☐ EVEREST EXPLORER [D] (T) 18.95

AUTOMATED SIMULATION
- ☐ TUESDAY QUARTERBACK [D] (AP) 26.95
- ☐ STAR WARRIOR [C,D] (AP,T) 35.95
- ☐ THREE PACK [D] (AP,P,T) 45.00

AUTOMATED SIMULATION
- ☐ STARFLEET ORION [C,D] (AP,T) 24.95
- ☐ STARFLEET ORION [C] (P) 24.95
- ☐ INVASION ORION [C,D] (AP,T) 24.95
- ☐ INVASION ORION [C] (P) 24.95
- ☐ TEMPLE OF APSHAI [D] (AP,T) 35.95
- ☐ TEMPLE OF APSHAI [C] (P,T) 35.95
- ☐ DATESTONES OF RYN [D,C] (AP,T) 19.95
- ☐ DATESTONES OF RYN [C] (P,AP) 19.95
- ☐ MORLOC TOWER [C,D] (AP,T) 19.95
- ☐ MORLOC TOWER [C] (P,AP) 19.95
- ☐ RESCUE AT RIGEL [C,D] (AP,T) 26.95
- ☐ RESCUE AT RIGEL [C] (P) 26.95
- ☐ HELLFIRE WARRIOR [D] (AP,T) 35.95
- ☐ HELLFIRE WARRIOR [C] (P) 35.95

BIG FIVE SOFTWARE
- ☐ ATTACK FORCE (T) 14.30
- ☐ GALAXY INVASION (T) 14.30
- ☐ METEOR MISSION II (T) 14.30
- ☐ SUPER NOVA (T) 14.30
- ☐ COSMIC FIGHTER (T) 14.30

COMPUTER SIMULATIONS COMPANY
- ☐ BATTLE OF BULGE-BASTGONES (T) 17.95
- ☐ D-DAY INVASION OF FRANCE (T) 17.95
- ☐ DARK KINGDOM (T) 11.75
- ☐ DOG RACE, COLOR ONLY 5.95
- ☐ EMPIRE STRIKES BACK (T) 13.55
- ☐ MINI ARCADE, COLOR 13.55
- ☐ POLARIS, COLOR ONLY 5.95
- ☐ SHARK, COLOR ONLY 5.95
- ☐ SLOT MACHINE (T) 7.25
- ☐ BATTLE OF BULGE-ST. VITH (T) 13.55
- ☐ STAR CRUISERS (T) 13.55
- ☐ U-BOAT, COLOR ONLY 5.95
- ☐ ASTEROID PIRATES (T) 13.55

INSTANT SOFTWARE
- ☐ AIR FLIGHT SIMULATION (AP,T) 8.95
- ☐ BALL TURRET GUNNER (T) 8.95
- ☐ CHESSMATE-80 (T) 17.95
- ☐ COSMIC PATROL (T) 13.55
- ☐ DAREDEVIL (T) 8.95
- ☐ DISASSEMBLER (T) 8.95
- ☐ DISK EDITOR [D] (T) 36.55
- ☐ DLDIS [D] (T) 17.95
- ☐ FLIGHT PATH (T) 8.95
- ☐ IRV (T) 22.50
- ☐ JET FLIGHTER PILOT (T) 13.55
- ☐ NIGHT FLIGHT (T) 8.95
- ☐ OTHELLO (T) 8.95
- ☐ SANTA PARAVIA FIUMACCIO (AP,T,P) 8.95
- ☐ SKIRMISH-80 (T) 8.95
- ☐ TLDIS (T) 13.55
- ☐ WORDSLINGER (T) 26.00

PERSONAL SOFTWARE
- ☐ CCA MGMT-TRS-80 [D] (T) 65.00
- ☐ DESK TOP PLAN II [D] (AP) 175.00
- ☐ MONTY MONOPOLY [D] (AP) 31.55
- ☐ VISICALC [D] (AT,P,AP) 170.00
- ☐ ZORK (T) [D] 35.95

QUALITY SOFTWARE
- ☐ 3D TIC TAC TOE (T) 13.55
- ☐ 6502 DISASSEMBLER (AT) 10.55
- ☐ ATARI ASSEMBLER (AT) 22.50
- ☐ ASTEROIDS IN SPACE [D] (AP) 17.95
- ☐ BATTLESHIP COMMANDER (AP) 13.55
- ☐ BATTLESHIP COMMANDER [D] (AP) 17.95
- ☐ FASTGAMMON [D] (AP,T) 22.50
- ☐ FASTGAMMON (AP,T,AT) 17.95
- ☐ FRACAS ADVENTURE [D] (AP) 22.50
- ☐ QS LIGHT PEN (T) 17.95
- ☐ SKETCH 80 (T) 13.55
- ☐ FORTH (AT) [D] 72.00

STRATEGIC SIMULATIONS
- ☐ COMPUTER AMBUSH [D] (AP) 51.50
- ☐ COMPUTER BISMARCK [D] (AP,T) 51.50

STRATEGIC SIMULATIONS
- ☐ COMPUTER BISMARCK (T) 42.00
- ☐ COMPUTER CONFLICT [D] (AP) 35.00
- ☐ COMPUTER NAPOLEONICS [D] (AP) 51.50
- ☐ COMPUTER QUARTERBACK [D] (AP) 35.00
- ☐ COMPUTER AIR COMBAT [D] (AP) 51.50
- ☐ WARP FACTOR [D] (AP) 35.00
- ☐ CUTHROATS & CARTELS [D] (AP) 51.50
- ☐ OPERATION APOCALYPSE [D] (AP) 51.50
- ☐ TORPEDO FIRE [D] (AP) 51.50

SUB-LOGIC
- ☐ 3D GRAPHICS (AP) 40.00
- ☐ 3D GRAPHICS [D] (AP) 48.00
- ☐ A-2 FS1 FLIGHT SIMULATOR (AP) 22.00
- ☐ A-2 FS1 FLIGHT [D] (AP) 29.00
- ☐ T80-FS1 FLIGHT SIMULATOR (T) 22.00
- ☐ 3D GRAPHICS (T) 26.50

MICROSOFT SOFTWARE
- ☐ ADVENTURE [D] (AP,T) 25.50
- ☐ ASSEMBLY DEVELOPMENT [D] (T) 80.00
- ☐ BASIC COMPILER [D] (T) 175.00
- ☐ EDITOR/ASSEMBLER (T) 25.50
- ☐ FORTRAN COMPILER [D] (T) 80.00
- ☐ LEVEL III BASIC (T) 44.00
- ☐ MuMATH [D] (T) 64.00
- ☐ OLYMPIC DECATHALON [D] (T,AP) 20.00
- ☐ OLYMPIC DECATHALON (T) 20.00
- ☐ TYPING TUTOR (AP,T) 13.55
- ☐ TYPING TUTOR [D] (AP) 17.95
- ☐ Z-80 SOFTCARD [D] (AP) 280.00
- ☐ 16k RAM BOARD (AP) 165.00

ON LINE SYSTEMS
- ☐ HI RES ADVEN. #0 [D] (AP) 17.95
- ☐ HI RES ADVEN. #1 [D] (AP) 22.50
- ☐ HI RES ADVEN. #2 [D] (AP) 29.00
- ☐ HI-RES FOOTBALL [D] (AP) 36.00
- ☐ HI-RES CRIBBAGE [D] (AP) 22.50
- ☐ MISSILE DEFENSE [D] (AP) 26.95
- ☐ SUPERSCRIBE [D] (AP) 81.00

SIRIUS SOFTWARE
- ☐ STAR CRUSIER (AP) [D] 22.50
- ☐ BOTH BARRELS (AP) [D] 22.50
- ☐ CYBER STRIKE (AP) [D] 36.00
- ☐ PHANTOM FIVE (AP) [D] 26.95
- ☐ SPACE EGGS (AP) [D] 26.95

BRODERBUND SOFTWARE
- ☐ GALACTIC EMPIRE (AP) [D] 22.50
- ☐ GALACTIC TRADER (AP) [D] 22.50
- ☐ GALACTIC REVOLUTION (AP) [D] 22.50
- ☐ TAWALA'S REDOUBT (AP) [D] 26.95
- ☐ HYPER HEAD ON (AP) [D] 22.50
- ☐ GALAXY WARS (AP) [D] 22.50
- ☐ APPLE GALAXIAN (AP) [D] 22.50
- ☐ TANK COMMAND (AP) [D] 13.55
- ☐ GOLDEN MOUNTAIN (AP) [D] 17.95
- ☐ PUCKMAN [D] (AP) 22.50

BOTTOM SHELF
- ☐ ANALYSIS PAD [D] (T) 90.00
- ☐ CHECKBOOK III [D] (T) 44.50
- ☐ CHECK REGISTER [D] (T) 67.00
- ☐ LIBRARY 100 (T) 44.50
- ☐ HEAD CLEANER [D] (AP,T) 17.00

SYNERGISTIC SOFTWARE
- ☐ DUNGEON & WILDERNESS [D] (AP) 29.00
- ☐ DUNGEON [D] (AP) 15.75
- ☐ ODYSSEY [D] (AP) 27.00
- ☐ WILDERNESS [D] (AP) 18.00
- ☐ PROGRAM LINE EDITOR [D] (AP) 36.00
- ☐ THE LINGQUIST (AP) [D] 36.00

APPARAT
- ☐ NEWDOS 80 [D] (T) 125.00

ARTSCI
- ☐ MAGIC WINDOW [D] (AP) 89.95

If you don't see it listed, write... we probably have it in stock!

**Check program desired-
Complete ordering information
and mail entire ad.
Immediate Shipments from stock.**

Ship the above programs as checked to:

Mr./Mrs. ____________________

Address ____________________

City ____________________

State ______________ Zip ________

I have a ____________________
Name of Computer

with ____________________ K memory

Number of Programs Ordered .... ________

Amount of order .... ________

N.Y. residents add Sales Tax ...... ________

Add shipping anywhere in the U.S. **2.00**

Total amount enclosed .... ________

Charge my: ☐ Master Charge ☐ Visa

Signature ____________________

Card No. ____________ Expires ________

BYTE-JULY '81

Personal Checks please allow 3 weeks.

KEY:
- **AT**-Atari
- **AP**-Apple
- **P**-Pet
- **T**-TRS-80
- **C**-Cassette
- **D**-on Disc.
- If not marked-Cassette

Mail to:

DIGIBYTE SYSTEMS CORP.

31 East 31st Street, New York, N.Y. 10016
Phone: (212) 889-8975

ATARI is a trademark of ATARI INC.
APPLE is a trademark of APPLE COMPUTER, INC.
TRS-80 is a trademark of TANDY CORP
PET is a trademark of COMMODORE BUSINESS MACHINES

Prices subject to change without notice.

Circle 117 on inquiry card.

backed up with whatever track format is best for your system. Note that you can't back up a single-density disk to double density or vice versa: the drive that's incompatible with the operating system will simply spin until it realizes that something is wrong, then give you an error message. When making a backup from single to double density (or vice versa), files must be copied individually.

When converting from single to double density, the copy function is the most essential part of DBLDOS. It has been enhanced to operate on a single-drive system in a way that is similar to the old BACKUP function, and except for requiring a lot of disk "swapping" by hand, it works well. In the interest of simplicity, however, I'll describe the use of COPY with a multiple-drive system.

Entering a $ before the file name indicates that the file is on a single-density disk. Thus, COPY $GARBAGE:1 TO $GARBAGE:2 copies the file between two single-density disks. COPY $GARBAGE:1 TO GARBAGE:2 copies a file from the single-density disk on drive 1 to the double-density disk on drive 2; this is how you convert your old single-density files to double density. COPY GARBAGE:1 TO $GARBAGE:2 converts a double-density file in drive 1 to a single-density file in drive 2. Of course the disks must be formatted in single or double density, as appropriate.

If you're going to copy from double to single density on a virgin disk, you must format the disk using an old single-density operating system. If no $'s are specified, then the system assumes you're making a double to double copy. If you're operating completely in double-density mode, the COPY function is the same as for single density.

The BASIC-invocation procedure has been changed to conform with the NEWDOS format; no questions are asked after BASIC is loaded. You can specify the memory size and number of files when you call up BASIC. Thus, BASIC 64000 5 RUN"GARBAGE/BAS" will load BASIC, specify a memory size of 64000 bytes, ask for five files, and run a program named GARBAGE/BAS. The defaults are the same as before, and this usually saves hitting ENTER twice. More importantly, I suspect it saves memory so that the DBLDOS system will fit in the same space as TRSDOS. But whatever the reason, it is an improvement.

The final enhancement in DBLDOS is really only an implementation of modifications that have been available in the TRS-80 for some time. This feature allows you to speed up the disk drives. The system disk includes a program called PATCH/BAS that can be merged with the other programs provided, to give a variety of track-seek speeds. When the program is run, it modifies the operating system to perform at the faster speeds. If your drives allow a seek time of less than 40 ms (and most do) the patch is very worthwhile.

Are there any software incompatibilities with the DBLDOS operating system? The answer is, any machine-language program that does its own reads and writes from disk must be considered suspect. Z80ZAP/CMD,

ALPHA BYTE DOES IT AGAIN...

Call us for our never undersold price.

ALPHA BYTE STORES

(213) 883-8594

Circle 16 on inquiry card.

5115 Douglas Fir Road • Suite B • Calabasas, CA 91302

DIRCHECK/CMD, and the machine-language version of SuperZap will not work (although the BASIC version will), and RSM2D will not work with disk commands. Patches (using PATCH/BAS) for Electric Pencil, SUPERSCRIPT, the MISOSYS DISK*MOD EDTASM, and the Microsoft editor are provided. Microsoft compiled BASIC works, except for a minor and apparently unimportant change in the use of the Break key. Microsoft FORTRAN-80 is compatible. I'm sure that there are other programs that don't work, but they must be few in number since they would have to have their own disk I/O (input/output) routines, and not many do. All of my own utilities (and I have many) work well.

Problems

Are there any disadvantages to DBLDOS and the Doubler? Yes. The disadvantages become apparent if you have to convert many disks to double density, if you want to use double- and single-density disks on different drives at the same time, or if you want to use cheap disks and cheap drives. Every file must be individually copied from single to double density, and if you have several hundred files it is a very tedious task. Percom should have provided a single-to-double-density backup facility to remedy the problem.

Similarly annoying is the fact that neither the FREE nor DIR command will work on a single-density disk with DBLDOS installed. Thus, when you copy files from single to double you must have another list of file names that were produced using a single-density operating system. Suppose you have a three-drive system and a single-density disk installed in drive 2. If you type FREE, the system will "hang up" while drive 2 makes ten passes, then gives you a meaningless error message. Suppose that, while in DOS, you type GRIBBLE by mistake: the machine will search drives 0 and 1 and then hang up on drive 2 while it is trying to find this absurd, nonexistent file. The delays are irritating, and Percom's advertising doesn't alert you to the problem. Worse, the way I read the advertising suggested that single-density disks could be directly accessed from DBLDOS, and a conversation with a sales engineer left me with the same misconception. If you rely on DBLDOS you should have only double-density disks in the drives unless you are converting from one density to the other.

Percom's answer to this problem was that there is not enough memory to allow mixed-disk (double and single density) operation, although such a system could have been programmed. I can't believe that the system couldn't have been designed so that it would at least recognize a single-density disk and immediately respond with an error message. Also, DIR and FREE utilities (perhaps $DIR and $FREE) that work with single-density disks would have made things much easier. Both programs should have loaded into the same space.

Percom's documentation warns against using disks that are not rated for 40-track and double-density use. If you try to format a bad disk several errors will occur, and if

more than five errors occur the system will refuse to format the disk. I use the cheapest disks available, and some are more than two years old. I found only two out of ten disks that could not take double density, and they only failed on the oldest and most battered of my three drives. I called Percom, and an engineer said they were having a problem discovering which disks worked best with which disk drives (including their own). When I told him I was using MPI (Micro-Peripherals Inc) drives, his response was, "Oh, that explains it—they've been checking their drives for double density for more than a year...."

Not all drives are created equal.

Many of the drives that are rated for double density perform well only with disks that are certified for double-density use. I was lucky. If you're not sure whether or not your drives will work with the commonly available disk media, be prepared to pay for double-density-rated disks, or to replace your drives. (Percom warns that early Shugart Associates drives, as sold by Radio Shack, may not work with double density, although several of my friends use them successfully.)

More on Software

Can these problems be overcome if you use other operating systems? NEWDOS/80 works the same in double density as in single, except that the enhancements for file copying are the same as those used in DBLDOS. And the problems are there as well. All of the utilities that come with NEWDOS/80 also work, except for SuperZap, which is a real loss. The DoubleZap 2 for NEWDOS/80 overcomes all of my previous complaints. If you have a multiple-drive system, any of the drives will automatically operate as single or double density as soon as the command ADR (automatic density recognition) is given after power-up. The status of the drives can be found and changed with the command DSET. Thus DSET may respond with: 0=A/D, 1=A/S, 2=S, indicating that drive 0 is in automatic mode with double density assumed for the first try, 1 is automatic but in single, and 2 is set in single. DSET 2=D would change drive 2 to fixed double, while DSET 2=A/D would make it automatic. The only time I use DSET is to format a disk in single density or to find the setting of the drives.

There are some other changes in DoubleZap 2, and most relate to the allocation of disk space. The operating system now works with "logical track numbers," each composed of ten physical sectors. Since there are eighteen sectors on a track, the physical track and logical track numbers are different. This has few repercussions except when you are copying. A disk copy is done by logical tracks, so you see 70 tracks copied on a 40-track drive. SuperZap (the machine-language version now works) also looks at logical tracks unless the DFS (display files sector) option is used. This use of logical tracks means that when a disk is copied it must already be formatted, and the copy must be done with the NFMT (no format) option. Otherwise, the copy would try to use the old for-

mat routine (which is still there and can still be used for single-density formatting).

Copying from single to double density must be done using the CBF (copy by file) specification, since the track numbers are different. Double-density formatting is done with the DBLFMT command, which works in the same way as the old FORMAT. A final difference is that when a system disk is copied, the single-density track 0 must be written by a separate routine loaded by the command FIXBOOT. A complete copy sequence for a system disk would look like the following:

```
DBLFMT :1 NAME 12/12/80
COPY :0 TO :1 12/12/80 NFMT
FIXBOOT 1
```

All of the other features of NEWDOS/80 seem to work well, and with double, single, and mixed density. This includes DIRCHECK, FREE, DIR, and every command I tried. In my estimation, the DoubleZap 2 modification of NEWDOS/80 is almost essential for serious use of the modified system.

Are there any remaining problems? Very few. I had some trouble installing DoubleZap, but that was my own fault. Installation is complex, but it is very well described. It does require that all zaps (software patches) through 31 be applied to the old system, and I made a mistake in zap 31 that took me some time to locate. (Presumably, the mistake would have found me sooner or later.) The double-density system is not compatible with some of the more recent NEWDOS/80 zaps, but Percom has provided modified zaps.

A real problem lies in the use of DBLFMT. I found that it would not work on virtually any of my disks; it told me there were verification errors on the upper tracks. Upon inquiry, Jim Stutsman of Software Etc, who wrote the system, sent me a zap that solved the problem. Apparently the verify uses a worst-case test, and a less stringent test (as used in DLBDOS) passes many more disks. He did warn me to use the modification at my own risk, since bad disks might be formatted.

What about service for any problems that might arise? Although I had problems when I bought the unit, I later found that a knowledgeable sales engineer was always available when I called. I have had no hardware problems, and the three sets of initials on the board that I received showed that it had been very well checked. Percom's literature describes one of the best service arrangements I have seen, and its reputation for service on disk drives is very good. All of my encounters with the manufacturer have been pleasant, and the response has always been helpful and refreshingly forthright.

Overall

Should you buy the Doubler system? If you want more disk space, and particularly more room on each disk, then this seems a practical choice. If you are satisfied with your present system, then it's a gimmick, and unless you like gimmicks you don't need it. If you have 77-track drives, the Doubler will give you more space than you would have with installation of 8-inch drives. If you have 40-track drives, for $200 you can have almost as much space as you would with a 77-track unit. If you have a single 35- or 40-track drive, it might be cheaper to sell your drive and buy a 77-track system.

The Doubler seems to be most useful to a multiple-drive user who must store large amounts of data or many programs; that is, the same person who might consider buying 8-inch drives. In this case, the "super" NEWDOS/80 operating system is almost essential. Most users who need additional drive space will have many files to copy, and the ability of DoubleZap 2 to allow copying of whole disks really improves speed. Of course, the ability to mix double- and single-density disks is also nice.

In summary, I like the Doubler; it's the greatest improvement to my system since I installed disks. It is well designed and reliable, the manufacturer is helpful, the software support is outstanding, and the flexibility of having five operating systems available is great. There's room for improvement in the procedure for converting from single to double density with the operating system provided, but I'm sure that will come. The TRS-80 has had a reputation for being a toy, but with the right enhancements it is a professional machine. The Doubler is one such enhancement. ■

FIRST WE REDUCED THE PRICE . . . NOW, WE HAVE INCREASED THE PERFORMANCE

TRS-80® MOD III

FIRST . . . We lowered the prices of the Model III from $2499* to

$1899

*We have taken the basic 16K Model III computer, expanded the memory to 48K and added our ultra-reliable MTI Dual Disk Drive system. System is fully compatible with Radio Shack DOS and peripherals.

MOD III PLUS - PROFESSIONAL SYSTEM

Now we have enhanced the basic system to increase the processing speed and increase the display capability from 64 x 16 characters to 80 x 24 characters. This allows complete word processing capability on the MOD III. Speed-up, the basic processing speed has been upgraded by adding a Z-80B processor. Programs run many times faster compatibly without the use of special software. **$2799**

MOD III/80

Upgraded MOD III, two disk system. Now you can get 80 track Disk Drives allowing 350K bytes per drive or 700K bytes per disk drive. An Outstanding Value. .... AS LOW AS **$2249**

MTI has a complete assortment of COMPUTER KITS - & Accessories

MTI DISK DRIVES for MOD III

Internal Kits - 40 TK.		External Add-on Kits - 40 TK.			
Disk Drive 1	$649	Disk Drive 3	$379	Model III DOS & Manual	$21.95
Disk Drive 2	$279	Disk Drive 4	$359	16K RAM Kit	$59
				RS-232 Serial Interface	$95

Ask About Our Extended Warrantee Plan

MICROCOMPUTER TECHNOLOGY, INC.

3304 W. MACARTHUR, SANTA ANA, CA 92704
★ PHONE (714) 979-9923 ★ TELEX #678401TAB IRIN

*Uses MTI Memory, Disk Drives & Components

®TRS-80™ IS A REGISTERED TRADEMARK OF TANDY CORPORATION

MasterCard VISA

ALL PRICES CASH DISCOUNTED
FREIGHT FOB FACTORY
ASK FOR FREE CATALOG

Circle 244 on inquiry card.

Videx Keyboard and Display Enhancer

Mark Pelczarski, 1206 Kings Cir, West Chicago IL 60185

If you plan to use your Apple II computer for word processing and are looking for a lowercase adapter, the Videx Keyboard and Display Enhancer may be your answer. Several adapters allowing an Apple to display lowercase letters on the screen are available. But a problem occurring with most Apple word-processing systems, or any software using uppercase and lowercase, is that the Apple keyboard does not recognize most shifted keys. It will, for instance, identify I and shift-I as the same character, even if you wanted one of them to be lowercase. The most popular adaptation has been to use the ESC (Escape) key as a pseudoshift. When ESC is pressed, a character is actually sent to the computer. Therefore, most text editors have required any character you want capitalized to be preceded by an Escape character. If you wanted the word HUMBUG in all capitals, you'd have to type ESC, H, ESC, U, ESC, M, ESC, B, ESC, U, ESC, G. This tedious process is necessary with most other lowercase adapters because they modify only the display, not the input from the keyboard.

The Videx Keyboard and Display Enhancer modifies both the display and the keyboard input. It uses a jumper to the keyboard ROM (read-only memory) to allow acceptance of standard shift-key operations, and it displays uppercase and lowercase letters on the screen. With this device, you can use an Apple as you would a typewriter. In addition, the Enhancer allows you to change RESET to work only when the CTRL (Control) key is pressed, a useful safety feature for people with early-production Apples. It also allows you to remap character sets by modifying the 2716 EPROM (erasable programmable ROM) included on the board.

At a Glance

Name
Videx Keyboard and Display Enhancer

Use
Provides the Apple II with a full ASCII keyboard and 96 ASCII display characters

Manufacturer
Videx Inc
897 NW Grant Ave
Corvallis OR 97330
(503) 758-0521

Price
$129

Dimensions
6¼- by 5½-inch card, fits on motherboard under the keyboard

Features
Uppercase/lowercase display, 96 ASCII display characters, all 128 ASCII codes available from keyboard, shift keys operate as a normal typewriter, Reset disable, user-definable character sets by changing EPROM

Hardware needed
Apple II or Apple II Plus, compatible with most other peripherals and word-processing software available

Manual
84 pages, 6 by 8½ inches

Software
Modifications to existing software, where necessary, are well documented in manual

Comments
Of interest to those seeking uppercase/lowercase display and standard keyboard operation, including shift key for uppercase; of particular use to anyone using an Apple for word processing

The Hardware

The Keyboard Enhancer comes on a 6¼- by 5½-inch card that fits onto the Apple motherboard beneath the keyboard. It replaces the character-generator chip, and two other chips are moved from the motherboard to the Enhancer board. Also, a jumper wire is attached to the keyboard circuit on the underside of the keyboard. Installation takes about an hour, since the Apple housing must be disassembled to reach the required circuits. The manual gives detailed and easy-to-follow instructions for installation, with many photographs. It can be accomplished easily by a novice.

The 2716 EPROM contains two character maps and a character set. The maps determine which character is displayed when a certain keystroke is received. The character set includes all 96 ASCII display characters. All 128 ASCII codes are accessible from the keyboard. Any character or mapping may be changed by reprogramming the EPROM.


CREATE !

There are two versions of the Enhancer card: one for Revision 0 thru 6 Apples, and one for Revision 7 and later. The Revision 0 thru 6 card has a set of four DIP (dual-inline pin) switches. These switches control the mode of operation the Apple assumes when turned on. In the alpha-lock mode, the Apple operates as it would without the Keyboard Enhancer until you press SHIFT-RESET. This puts you in the alpha-unlock mode, giving you uppercase and lowercase. A Reset operation returns you to the default mode. The DIP switches may be set so the modes are reversed and alpha-unlock is the default. The switches may also be set so the RESET key itself does nothing; CTRL-RESET accomplishes the Reset operation. The fourth switch selects between the two alternate character maps.

The Revision 7 version contains an additional set of four switches. One setting of these switches selects whether a set of flashing characters will be numerals and special characters or lowercase letters. The other setting for these switches changes inverse characters to flashing characters, or vice versa.

Compatibility

The de facto standard for lowercase adapters has been the one produced by Dan Paymar. The Videx board works with any software compatible with the Paymar adapter. The manual also contains simple modifications allowing Apple Writer, a word-processing program from Apple Computer Inc, to work with the Enhancer. Also in the manual are patches allowing Pascal and either Applesoft floating-point BASIC or Integer BASIC to use the lowercase capabilities. The manual details modifications for any Apple configuration, describing each option available.

The Keyboard Enhancer works with any peripheral card compatible with the Paymar adapter, including the Videx Videoterm 80-column board, the Microsoft SoftCard (except that the SoftCard changes all display output to capitals, though some 80-column boards correct this), and the Hayes Microcomputer Products Micromodem II. A single-byte adjustment to the Micromodem software is also given in the manual.

Conclusions

When I opened the Enhancer package, I was quite skeptical. There were prominent disclaimers saying Videx would not be liable for damage done to any hardware as a direct or indirect result of installing its product. "The entire risk as to its quality and performance is with the buyer." That sounded ominous! After finally getting the nerve to risk the health and well-being of my Apple, I pulled it apart and installed the Enhancer. From step one of the installment, I was extremely impressed with the documentation. The simple instructions answered every question I had. Buyers are not left scrambling for back issues of magazines or newsletters to find fixes for software. The price is $129, twice that of other lowercase display adapters, but if you do much word processing, it's worthwhile. ■

"WITH THE UCSD p-SYSTEM,™ WE CAN WRITE ONE APPLICATION THAT GOES FROM APPLE TO ZENITH."

HARRY BLAKESLEE, President, Denver Software



UCSD p-System and UCSD Pascal are trademarks of the Regents of the University of California.

Our business is bigger and better than ever.

A lot of the credit for that goes to the UCSD p-System software from SofTech Microsystems. It's given us ten times the market we used to have.

We can write a single, sophisticated applications program with the UCSD p-System—like our financial management package—and it just keeps on running. On Apple, Commodore, Ohio Scientific, Texas Instruments, Zenith, and more. That's the real beauty of the UCSD p-System. Any program you write for one microcomputer runs on others, both today and tomorrow. You protect your software investment, without restricting your hardware options.

And with the UCSD p-System, you can use the language of your choice—UCSD Pascal,™ FORTRAN-77, BASIC, or assembly language. All are backed by SofTech Microsystems, a leading system software company who's been around for over a decade, who knows how to develop professional quality software, and who's committed to delivering it.

Get a head start on tomorrow. With the microcomputer software that goes from "A" to "Z." Distribution licensing and single copies available. Write or call for details, so you can start going places, too.

SOFTECH
MICROSYSTEMS
A SUBSIDIARY OF SOFTECH

For the software that's going places.

9494 Black Mountain Road, San Diego, CA 92126. (714) 578-6105
TWX: 910-335-1594

Circle 358 on inquiry card.

Animation in Computer-Assisted Instruction

The Replication of DNA

Dr Richard R Eckert
Colegio de Ciencias
Universidad Catolica de Puerto Rico
Ponce PR 00731

CAI, or computer-assisted instruction, programs have achieved a high level of effectiveness as surrogate teachers. These programs present the student with written material on a video display and invite a response to written questions—a valuable approach, as the computer can be programmed to answer according to the individual response, and either reinforce correct answers or aid in the discovery of errors (see figure 1). Unfortunately, the effectiveness of this traditional use of CAI programs is limited by the student's interest in the material and his ability to read it. In many cases, a student does not learn effectively from the written word—whether it appears in a book or on a video screen.

An Example of a Lesson

This article will present a CAI lesson module that uses animated graphics and sound, in addition to the written word, to introduce material to a student. The module is not truly interactive, since my purpose is to demonstrate the use of animation and sound in computer-assisted instruction, but it would be a straightforward procedure to make it interactive. The program is written for the Radio Shack TRS-80 in Level II BASIC, but it can be adapted to other personal computers.

The subject of the module is the replication of a DNA (deoxyribonucleic acid) molecule, which, since it concerns the transmission of hereditary information, is one of the most important topics in any biology course.



Figure 1: *The common CAI program follows this general flowchart. The instruction is repetitive, and since only simple text is displayed, no real advantage is gained through the use of a video display.*

The Audio Program

The program in listing 1 uses the BASIC instructions SET and RESET to control the TRS-80 video graphic display and present diagrams that represent the structure of the DNA molecule. (The POKE instruction can be used on other systems.) These diagrams move on the screen, in demonstration of how a DNA molecule replicates itself in the nucleus of a living cell, while an audio text, recorded on cassette tape and controlled by the program, explains the figures and the written information on the video screen. The key BASIC instruction is the Level II output instruction OUT *port, value*. On the TRS-80, output port 255 controls the cassette recorder: a value of 5 in the OUT instruction turns the recorder on, and a value of 16 turns it off.

The instructor prepares both the visual display and the accompanying audio material on a cassette tape. The most laborious aspect of the preparation concerns the coordination of the display with its accompanying sound. Once the instructor has recorded the audio information in proper sequence, he must determine its duration so that the program can delay the visual display and coordinate it with

Education Forum

Listing 1: *This program, designed for use with the CAI lesson module and written in Level II BASIC for the Radio Shack TRS-80, presents an animated visual display of DNA replication.*

The subroutine beginning at line 890 fixes the location of a nucleotide on the screen, with its base facing downward. The subroutine beginning at line 760 places a nucleotide on the screen with its base facing upward, and moves it vertically. The values of Q and Z determine which nucleotide is to be displayed (for thymine, Q=1 and Z=1; for adenine, Q=2 and Z=1; for cytosine, Q=1 and Z=2; and for guanine, Q=2 and Z=2). The subroutines beginning at lines 580 and 670 present an entire segment of a DNA molecule, and call the subroutines at lines 890 and 760 as needed.

```
1 REM  "THE REPLICATION OF DNA--A TRS-80 COMPUTER ASSISTED INSTRUCTION MODULE"
2 REM  AUTHOR:  RICHARD R. ECKERT
3 REM  BOX 145, STATION 6, PONCE, PUERTO RICO.
4 REM  IN ORDER TO COORDINATE PROPERLY WITH THE AUDIO TEXT I HAVE ON TAPE,
5 REM  ALL <REM> STATEMENTS SHOULD BE REMOVED FROM THE PROGRAM.
9 REM  A, B, C, D, E DETERMINE THE POSITION ON THE SCREEN OF THE VARIOUS FIGURES
10 A=16:B=41:C=24:D=35:E=63
20 CLS
30 PRINT"THIS IS A COMPUTER ASSISTED INSTRUCTION MODULE."
40 PRINT"GET THE TAPE RECORDER READY."
50 INPUT"WHEN YOU'RE ALL SET HIT <ENTER>";XX
60 CLS
70 PRINT@394,"R E P L I C A T I O N   O F   D N A"
79 REM  SET DELAY TIME FOR UPCOMING AUDIO MATERIAL; SUBROUTINE CONTROLS RECORDER
.
80 TM=17.2:GOSUB950
90 CLS
100 Y=A
109 REM  DRAW UPPER HALF OF DNA MOLECULE
110 GOSUB580
120 Y1=C:S=C
129 REM  DRAW LOWER HALF OF DNA MOLECULE
130 GOSUB670
140 TM=7.4:GOSUB950
150 CLS
160 Y=A
170 GOSUB580
180 PRINT@277," T      C      A      G";
190 TM=23.5:GOSUB950
200 CLS
209 REM  PREPARE TO DRAW NUCLEOTIDE WITH THYMINE POINTING DOWNWARD
210 Q=1:Z=1:X=B:Y=A
219 REM  DRAW IT
220 GOSUB890
230 PRINT@396,"THYMINE";
240 TM=11.2:GOSUB950
248 REM  PREPARE TO DRAW NUCLEOTIDE WITH ADENINE POINTING UPWARD
249 REM  SINCE S=Y1, IT WILL NOT MOVE
250 Q=2:S=D:Y1=D
259 REM  DRAW IT
260 GOSUB760
270 PRINT@716,"ADENINE";
280 TM=18.0:GOSUB950
289 REM  PREPARE TO DRAW CITOSINE
290 Q=1:Z=2:Y=A:X=E
299 REM  DRAW IT
300 GOSUB890
310 PRINT@422,"CITOSINE";
320 TM=8.7:GOSUB950
329 REM  PREPARE TO DRAW GUANINE (STATIONARY)
330 Q=2:Y1=D:S=D
340 GOSUB760
349 REM  DRAW IT
350 PRINT@742,"GUANINE";
360 TM=10.0:GOSUB950
370 CLS
380 PRINT@466,"G E N E T I C   C O D E";
390 TM=24.5:GOSUB950
400 CLS
410 Y=A
419 REM  LINES 420-460 DRAW DNA MOLECULE COMPLETELY LABELED
420 GOSUB580
430 Y1=C:S=C
440 GOSUB670
450 PRINT@277," T      C      A      G";
460 PRINT@597," A      G      T      C";
470 TM=17.0:GOSUB950
479 REM  LINES 480-490 ELIMINATE ONE-HALF OF THE MOLECULE
480 FORX=41TO63:RESET(X,20):NEXT
490 FORY=21TO29:FORX=41TO84:RESET(X,Y):NEXT:NEXT
500 TM=16.0:GOSUB950
510 PRINT@790,"A      G      T      C";
519 REM  PREPARE FOR REPLICATION;  SINCE S<Y1, NUCLEOTIDES WILL MOVE
520 Y1=D:S=C
529 REM  PLACE MOVING NUCLEOTIDES ON SCREEN TO DEMONSTRATE REPLICATION
530 GOSUB670
540 PRINT@597," A      G      T      C";
550 PRINT@790,"REPLICATION COMPLETE";
560 TM=24.8:GOSUB950
570 END
579 REM  SUBROUTINE 580-660 DRAWS THE UPPER HALF OF THE DNA MOLECULE
580 FORN=1TO2
```

Listing 1 continued on page 362

NEW! ANOTHER APPLE* GIFT FROM PROMETHEUS



The IPP Guardian

Always awake. . .even when your Apple sleeps. . .

NOW. . .there is an Intelligent Peripheral Processor with "always on" background scheduling and BSR control . . .even when your Apple is turned off!

Only the IPP-Guardian can make your Apple into a turn-key BSR control and scheduling system *that requires no Apple overhead.* The unique "Apple Juice Switch" provides true "wake-up" operation. Your Apple is turned ON and OFF either by internal scheduling or unscheduled external events. This enables your system to perform a wide variety of control functions – energy management, alarm systems, environmental monitoring, communication control, etc. – without requiring any of your Apple's processing power.

The heart of the IPP-Guardian Board is an independent CMOS intelligent processor with up to 2K of user programmable RAM and a real-time clock/calendar with 1-millisecond resolution. They operate in background without any Apple overhead. Long-life battery back-up provides independence from AC power. 20 general purpose I/O lines are available for external interface.

Operational expansion can provide additional capability for expanded parallel I/O, serial I/O, and future expansion. Software options include general purpose or BSR scheduling, multitasking, and monitor routines.

There's a great deal more to the IPP-Guardian. Call **Prometheus** or see your local dealer for additional information about the IPP-1 and a demonstration.

MEMORY EXPANSION MODULE-1. The preferred 16K RAM Expansion Module for Apple II. *Compare these features:* • RAM data out is buffered into bus. • User selectable reset function. • Terminated data and control inputs. • Low noise array layout. • Extra decoupling capacitors for higher noise immunity. • 24-hour dynamic burn-in (minimum) • Total compatibility with all Apple and Microsoft Softcard software. • 1-year parts and labor warranty.

Order PP-1, Still only $149.50

DUAL SERIAL CARD-1. All functions of two independent serial cards on one board.

Order PP-DSC-1 @ $189.00

PASCAL MT+ MEM-1. A modular native Z-80 code Pascal compiler and a MEM-1 (detailed above).

Order PP-PMT-1 @ $229.00



MONEY BACK GUARANTEE: All Prometheus boards are completely tested and burned-in prior to shipment. One-year warranty covers parts and labor. Order now without risk. Boards may be returned, in good condition (after up to 10 days of trial), for a full and prompt cash refund. California: add 6% tax; BART Counties, 6½%. *Quantity discounts available.*

Dealer inquiries invited.

PROMETHEUS

PROMETHEUS PRODUCTS INCORPORATED

4509 Thompson Ct. • Fremont, CA 94538 • (415) 791-0266

*Registered Trade Mark: Apple Computers, Inc.

Listing 1 continued:

```
590 X=30+N*11:Q=1:Z=N
600 GOSUB890
610 NEXT
620 FORN=1TO2
630 X=52+N*11:Q=2:Z=N
640 GOSUB890
650 NEXT
660 RETURN
669 REM  SUBROUTINE 670-750 DRAWS THE LOWER HALF OF THE DNA MOLECULE
670 FORN=1TO2
680 X=30+N*11:Q=2:Z=N
690 GOSUB760
700 NEXT
710 FORN=1TO2
720 X=52+N*11:Q=1:Z=N
730 GOSUB760
740 NEXT
750 RETURN
756 REM  SUBROUTINE 760-880 DRAWS ONE NUCLEOTIDE FACING UPWARD.
757 REM  THE NUCLEOTIDE DRAWN DEPENDS ON THE VALUES OF Q & Z.
758 REM  IF S=Y1, THE NUCLEOTIDE REMAINS STATIONARY; IF NOT IT MOVES
759 AND EVENTUALLY MATES WITH ITS PARTNER ON THE UPPER HALF OF THE CHAIN.
760 FORY=Y1TOSSTEP-1
770 FORI=XTOX+10:SET(I,Y):NEXT
780 FORJ=1TOQ:SET(X+5,Y-J):NEXT
790 FORI=X+3TOX+7:SET(I,Y-Q-1):NEXT
800 IFZ=1THENFORI=X+4TOX+6STEP2:SET(I,Y-Q-2):NEXT
810 IFZ=2THENFORI=X+3TOX+7STEP2:SET(I,Y-Q-2):NEXT
820 FORK=1TO10:NEXT
830 IFY=STHENRETURN
840 IFQ=1ANDY=S+1THEN860
850 FORI=X+3TOX+7:RESET(I,Y-5):NEXT
860 FORI=X+3TOX+7:FORJ=Y-1TOY-4STEP-1:RESET(I,J):NEXT:NEXT
870 FORI=XTOX+10:RESET(I,Y):NEXT
880 NEXT
888 REM  SUBROUTINE 890-940 DRAWS ONE NUCLEOTIDE FACING DOWNWARD.
889 REM  THE NUCLEOTIDE DRAWN DEPENDS ON THE VALUES OF Q & Z.
890 FORI=XTOX+10:SET(I,Y):NEXT
900 FORJ=1TOQ:SET(X+5,Y+J):NEXT
910 FORI=X+3TOX+7:SET(I,Y+Q+1):NEXT
920 IFZ=1THENFORI=Y+4TOX+6STEP2:SET(I,Y+Q+2):NEXT
930 IFZ=2THENFORI=X+3TOX+7STEP2:SET(I,Y+Q+2):NEXT
940 RETURN
948 REM  SUBROUTINE 950-1000 TURNS ON THE CASSETTE RECORDER, DELAYS
949 REM  ACCORDING TO THE VALUE OF TM, AND THEN TURNS OFF THE RECORDER.
950 OUT255,5
960 TM=TM*485
970 FORIM=0TOTM:NEXT
980 TM=0
990 OUT255,16
1000 RETURN
```

the audio material. In the program of listing 1, the subroutine beginning at line 950 turns on the recorder, line 960 converts the duration of the audio material (expressed in seconds and stored in the variable TM) to the appropriate terminal value of a FOR-NEXT delay loop (lines 960 and 970), and line 990 turns the recorder off.

Video Animation

The program listing contains many comments, but an explanation of some of the graphics may also be helpful. The subroutines beginning at lines 890 and 760 do most of the work. The former fixes the location of a nucleotide (one of the basic structural units of DNA) on the screen, with its base facing downward. The latter subroutine places a nucleotide with its base facing upward, and moves it vertically, as needed. In each case the values of two variables, Q and Z, determine which nucleotide will be displayed.

At those moments when the entire DNA molecular segment is to be presented, the subroutines at lines 580 and 670 come into play. These subroutines call one nucleotide-locating subroutine for each nucleotide on the molecule. (This makes it easy to expand the program to show DNA segments that are longer than the four-unit chain presented here.)

A Sample Lesson

Before a lesson begins, the material is recorded on tape, and the cassette is placed in the recorder. (The connecting cable from the computer must be removed from the earphone jack on the recorder for the speaker to be activated.) The recorder must be set in the play mode before the program is started.

When the program begins to execute, the first in a series of graphic displays appears on the video screen, and the cassette recorder matches its information to the appearance of the images. Some of the more interesting graphic displays are shown in the ac-

FMS-80
Organizes Your Organization
FMS-80, a data base management system, offers the user a quick and easy way to organize and efficiently manipulate data so sound decisions can be made on facts displayed.
FMS-80*** is the most powerful stand alone DBM program available to the microcomputer industry.
Completely menu driven and written in assembly language, it offers these features:
• User definable File Definitions Screen Displays Reports (with math and field break analysis) Selection Criteria (on any or all fields) Menus (that applications programs can be selected from)
• Instantaneous data query on indexed records.
• Mathematical manipulation of numeric data fields using the report generator or the programming language EFM (Extended File Maintenance)
• Easy to use video "how to" training tapes are available.
• Manipulation of up to 19 different data files (using EFM) at one time and displaying this information on the screen, generating reports, generating other data files or on-line updating of input files that already exist
• FMS-80 is able to call other programs like subroutines in EFM
• FMS-80 is able to read data files that other programs have generated
• No restrictions to record size other than available RAM memory space
• Operates under CP/M,* MP/M* or CDOS**
FMS-80 allows the flexibility to quickly create programs that allow data to be entered in a form that a secretary recognizes and generates reports that the manager requires.
If you're continuously asked to do applications programs and don't have time to do it in BASIC, consider FMS-80. For additional information contact
Systems Plus, 3975 East Bayshore, Palo Alto, CA 94303. Phone 415/969/7047
THIS GUN FOR HIRE
FMS 80 File Management System
Systems Plus
***TM of DJR Associates
**TM of Cromemco, Sunnyvale, CA
*TM of Digital Research, Pacific Grove, CA

companying photos, but many of the displays are animated so it is impossible to convey the true image.

Audio Transcript

DNA is a molecule found in the nuclei of all living cells. In this lesson we'll examine the role it plays in the process of cell division. The DNA molecule is a double chain of nucleotides; let's look at a section of this molecule. (Display in photo 1a appears.)

Here we see part of the double chain. Now let's split it down the middle to examine its structure. (Photo 1b.)

We see the chain split down the middle. Each section of the chain consists of a nucleotide, and each nucleo-

(1a)



(1b)



Photo 1a and 1b: *The initial displays help to orient the introductory information that is played on the computer-controlled cassette recorder.*

(2a)



(2b)



(2c)



(2d)



Photos 2a thru 2d: *Series of displays that shows the possible variations in any nucleotide. Each nucleotide section may have a base with a unique combination of two or three bonding sites, and several possible lengths.*

The Text Solution for APPLE II®

Now APPLE II® Owners Can Solve Text Problems With VIDEOTERM 80 Column by 24 Line Video Display Utilizing 7 X 9 Dot Character Matrix

Perhaps the most annoying shortcoming of the Apple II® is its limitation of displaying only 40 columns by 24 lines of text, all in uppercase. At last, Apple II® owners have a reliable, trouble-free answer to their text display problem. VIDEOTERM generates a full 80 columns by 24 lines of text, in upper and lower case. Twice the number of characters as the standard Apple II® display. And by utilizing a 7 by 9 character matrix, lower case letters have true descenders. But this is only the start.

VIDEOTERM, MANUAL, SWITCHPLATE



7X12 MATRIX
18X80 OPTIONAL

7X9 MATRIX
24X80 STANDARD

VIDEOTERM

BASICs VIDEOTERM lists BASIC programs, both Integer and Applesoft, using the entire 80 columns. Without splitting keywords. Full editing capabilities are offered using the ESCape key sequences for cursor movement. With provision for stop/start text scrolling utilizing the standard Control-S entry. And simultaneous on-screen display of text being printed.

Pascal Installation of VIDEOTERM in slot 3 provides Pascal immediate control of the display since Pascal recognizes the board as a standard video display terminal and treats it as such. No changes are needed to Pascal's MISC.INFO or GOTOXY files, although customization directions are provided. All cursor control characters are identical to standard Pascal defaults.

Other Boards The new Microsoft Softcard* is supported. So is the popular D. C. Hayes Micromodem II*, utilizing customized PROM firmware available from VIDEX. The powerful EasyWriter* Professional Word Processing System and other word processors are now compatible with VIDEOTERM. Or use the Mountain Hardware ROMWriter* (or other PROM programmer) to generate your own custom character sets. Naturally, VIDEOTERM conforms to all Apple OEM guidelines, assurance that you will have no conflicts with current or future Apple II* expansion boards.

Advanced Hardware Design VIDEOTERM's on-board asynchronous crystal clock ensures flicker-free character display. Only the size of the Pascal Language card, VIDEOTERM utilizes CMOS and low power consumption ICs, ensuring cool, reliable operation. All ICs are fully socketed for easy maintenance. Add to that 2K of on-board RAM, 50 or 60 Hz operation, and provision of power and input connectors for a light pen. Problems are designed out, not in.

Available Options The entire display may be altered to inverse video, displaying black characters on a white field. PROMs containing alternate character sets and graphic symbols are available from Videx. A switchplate option allows you to use the same video monitor for either the VIDEOTERM or the standard Apple II* display, instantly changing displays by flipping a single toggle switch. The switchplate assembly inserts into one of the rear cut-outs in the Apple II* case so that the toggle switch is readily accessible. And the Videx KEYBOARD ENHANCER can be installed, allowing upper and lower case character entry directly from your Apple II* keyboard.

Firmware 1K of on-board ROM firmware controls all operation of the VIDEOTERM. No machine language patches are needed for normal VIDEOTERM use.

Firmware Version 2.0

Characters	7 x 9 matrix	Display	24 x 80 (full descenders)
Options	7 x 12 matrix option; Alternate user definable character set option; Inverse video option.		18 x 80 (7 x 12 matrix with full descenders)

Want to know more? Contact your local Apple dealer today for a demonstration. VIDEOTERM is available through your local dealer or direct from Videx in Corvallis, Oregon. Or send for the VIDEOTERM Owners Reference Manual and deduct the amount if you decide to purchase. Upgrade your Apple II* to full terminal capabilities for half the cost of a terminal. VIDEOTERM. At last.

Apple II* is a trademark of Apple Computer Inc.
ROMWriter* is a trademark of Mountain Hardware Inc.
Micromodem II* is a trademark of D. C. Hayes Associates Inc.
Softcard* is a trademark of Microsoft
EasyWriter* is a trademark of Information Unlimited Software Inc.

PRICE:
- VIDEOTERM includes manual $345
- SWITCHPLATE .... $ 19
- MANUAL refund with purchase .... $ 19
- 7 x 12 CHARACTER SET .... $ 39
- MICROMODEM FIRMWARE ...... $ 25

APPLE II® OWNERS!

introducing the
KEYBOARD & DISPLAY ENHANCER

- *PUT THE SHIFT AND SHIFT LOCK BACK WHERE IT BELONGS*
- *SEE REAL UPPER AND lower CASE ON THE SCREEN*
- *ACCESS ALL YOUR KEYBOARD ASCII CHARACTERS*

Videx has the perfect companion for your word processor software: the **KEYBOARD AND DISPLAY ENHANCER**. Install the enhancer in your APPLE II and be typing in lower case just like a typewriter. If you want an upper case character, use the SHIFT key or the CTRL key for shift lock. Not only that, but you see upper and lower case on the screen as you type. Perfectly compatible with Apple Writer and other word processors like, for example, Super-Text.

If you want to program in BASIC, just put it back into the alpha lock mode; and you have the original keyboard back with a few improvements. Now you can enter those elusive 9 characters directly from the keyboard, or require the Control key to be pressed with the RESET to prevent accidental resets.

KEYBOARD AND DISPLAY ENHANCER is recommended for use with all revisions of the APPLE II. It includes 6 ICs, and EPROM and dip-switches mounted on a PC board, and a jumper cable. Easy installation, meaning no soldering or cutting traces. Alternate default modes are dip-switch selectable. You can even remap the keyboard, selecting an alternate character set, for custom applications.



PRICE • **KDE-700 (REV. 7 or greater) .... $129.**
• **KDE-000 (REV. 6 or less) .... $129.**

Apple II* is a trademark of Apple Computer, Inc.

Videx INC.

VIDEX
897 N.W. Grant Avenue
Corvallis, Oregon 97330
Phone (503) 758-0521

Circle 417 on inquiry card.

(3a)



(3b)



(3c)



(3d)



(3e)



(3f)



(3g)



Photos 3a thru 3g: *Animated sequence that demonstrates the passing of genetic information from parent cell to offspring cells. The DNA chain splits, the missing portion of each half is replaced when free nucleotides bond in place, and the new DNA chains take their positions as the cell splits.*

tide has a different base. Let's take a look at each one.

Now we see a nucleotide with the base thymine hanging downward. (Photo 2a.) Observe that there are two places where bonding can occur. Let's look at another nucleotide.

In this example, the base is adenine, and it is facing upward. (Photo 2b.) Notice that the base is larger than thymine and that it also has two places for bonding. Therefore, if nucleotides with thymine and adenine should meet, they can form a chemical bond and unite.

Another nucleotide uses the base citosine. (Photo 2c.) As we see, it is small and has three bonding sites.

The fourth nucleotide has the base guanine. (Photo 2d.) Its large size and the presence of three bonding sites allow it to unite with citosine.

Hereditary information is determined by the order of the nucleotides along the DNA molecule. This is known as the genetic code. (Photo 3a.) One DNA molecule may have more than 1000 nucleotides along the chain, so the number of possible combinations is enormous. This is the property that allows such variety among life forms.

We will now explore the question of how genetic information is passed from mother to daughter cells. The first action in the replication process is the splitting of the DNA molecule. Here we see part of a DNA molecule. (Photo 3b.)

Here we see one-half of the split molecule. Free nucleotides begin to bond to each half of the molecule. Observe that the bonding occurs only when adenine pairs with thymine, or when citosine pairs with guanine. (Photos 3c, 3d, 3e, and 3f.)

The replication has finished, and a new DNA molecule, identical to the original, has been formed from each half of the double chain. (Photo 3g.) We have seen how the molecule DNA, found in all living cells, replicates itself and passes the genetic information to new cells. ■

Acknowledgments

I wish to thank Ramon Rivera for his technical suggestions regarding this project.

Catch Bytes with a Comparator

Doug MacDonald, Suite 2, 533 Harbinger St
Victoria BC, V8V 4H9, Canada

Anyone who has tried to track down glitches and bugs on a data bus has probably looked with envy at advertisements for those multi-thousand-dollar logic analyzers. If those Cadillac devices are out of your price range, you might like to try the Byte Catcher. This device has quickly become an invaluable addition to my test bench.

Very often your goal is to catch a malfunctioning microprocessor at a particular portion of a program: the occurrence of one instruction, or a port output. Often you simply want to know if a program reached a certain stage. Unfortunately, the days of the front panel with that row of blinking address lights and a single-step switch are gone. Did a certain memory select signal come up when it was supposed to? Is that PROM (programmable read-only memory) putting out correct data?

The Byte Catcher can answer most of these questions. It is based on Advanced Micro Devices' 25LS2521, an 8-bit Equal-to Comparator. This 20-pin TTL (transistor-transistor logic) integrated circuit puts out a logic-low signal whenever the eight *A* inputs are equal to the eight *B* inputs. By switch selecting the *A* inputs you can catch that elusive byte on the fly whenever it occurs. The match can be as short as about 10 ns, which is fast enough for most microcomputer circuits.

A separate enabling line on the chip allows you a ninth input, which is usually used as a data strobe. You can use any number of the eight inputs. I often set the Byte Catcher to watch a single line. On the other hand, ganging two of these devices together allows you to monitor all sixteen address lines.

With the addition of a few gates for polarity selection, a DIP (dual-inline package) switch, a 555 timer, and two LEDs (light-emitting diodes), you end up with a fairly powerful multibit logic probe.

The components fit nicely on a breadboard strip, or you can mount the circuit in a box. Since the entire circuit pulls a maximum of only 65 milliamps (with both LEDs on), you can usually take your power off the circuit under test.

Figure 1 shows the Byte Catcher's design. The 8-bit "word" for comparison is preset on the switch SW1. I used an 8-line mini-DIP type, but there are various other types — a thumbwheel hexadecimal switch might be nice for a box-mounted version. The set data is negative logic (that is, a closed switch for a logic zero) because TTL is

Technical Forum is a feature intended as an interactive dialog on the technology of personal computing. The subject matter is open-ended, and the intent is to foster discussion and communication among readers of BYTE. We ask that all correspondents supply their full names and addresses to be printed with their commentaries. We also ask that correspondents supply their telephone numbers, which will not be printed.

When Steinway builds a concert grand, they don't compromise on quality.

Neither do we.

The low price is deceiving. Synertek Systems Corporation allows no compromise in the versatility, reliability, and quality of the KTM-3.

This complete, low-cost terminal offers no-frills, solid performance. With its power supply and connecting cables, the KTM-3 requires only a CRT monitor or television screen to provide a functioning system for data entry and display.

The KTM-3 incorporates all the latest features of standard terminals such as:

- Choice of character screen size:
  - 24×80 characters in the KTM-3/80
  - 24×40 characters in the KTM-3
- 110 to 19.2K baud
- 7×9 character matrix in an 8×10 field
- "CAPS LOCK" key
- 128 ASCII characters with descenders
- Full and half duplex with modem control
- Built-in power supply and cables included
- Scrolling and full cursor control
- Display of framing and parity errors
- Auto key-repeat
- Debug mode (Display of control characters)
- Built-in diagnostics
- 50/60 Hz operation with 220 volt version available

STARTING AT **$389**,
OUR PRICE WILL BE MUSIC TO YOUR EARS.

Synertek Systems Corporation
150 S. Wolfe Road Sunnyvale, CA 94086
Telephone: (408) 988-5689
TWX: 910-338-0135

Dealer inquiries invited.

easier to pull low than high. The 4.7 K pull-up resistors (R5 to R12) are not really necessary, but are good insurance against noise.

The *B* inputs come from the device under test. You can fit them onto the board any way you choose, but my experience is that care here saves a lot of cursing later. I bought some Tektronix test clips which attach onto an integrated circuit pin and stay there, as well as some flexible test leads from AP Products (who also make breadboard strips). I brought all inputs to a 16-pin DIP header which plugs into the breadboard.

The optional input trigger (pin 1 of IC2) is handy for creating a "window"; the device will only signal a match when the input trigger is active. For example, you might want to search the data bus for a particular byte, but only when some specific device-select signal is active. SW2 allows either an active high or active low trigger. With the exclusive OR gate (IC2), the rule is to set the switch for the same polarity as your desired trigger: to ground for active low, to VCC for active high. If the trigger is not used, leave the switch on VCC, since an open TTL input pulls itself high; or better, tie the trigger high.

The remainder of the circuit gives you a visible clue of what is going on in the test. More often than not, I take the comparator's output (pin 19 of IC1) and use it as a scope trigger or send it back into the test circuit to generate an interrupt or some other function.

For poking around in a circuit, however, it is handy to use LEDs. The RC (resistor-capacitor) network (R1 and C1) provides a fast trigger pulse for the 555; if the data matches and stays matched for longer than the timer's duty cycle, it stays latched on and you don't know what's happening. R2 and C2 provide the 555 (rigged as a monostable multivibrator) with an on-time of about a half second; you can change this value to suit your taste. Or, you can substitute a beeper for the LED.

The LED (D1) will light for any data match down to about 10 ns. I use the cross-coupled NAND gate set-reset latch to "remember" a data match, in case I have my head buried in a circuit when it occurs. D2 will light and stay lit when a match occurs. SW3 resets the latch and turns the LED off again. This feature can be eliminated if desired.

You can add any bells and whistles which occur to you. For example, to gang two of the comparators together, you would tie the enable out (pin 19) of the first to the trigger input (pin 1) of the second and use the second enable out as your signal. Tying these two directly to the address bus gives you a switch-selectable, memory-mapped device-select strobe.

Another possibility is to use a pre-settable binary or decade counter (such as a 74LS161) to keep track of how many "hits" occur, or as a trigger input divider (flag a data match on the third...or fifth...or tenth..occurrence of a certain signal). Further gating of the inputs from the device under test could be added for various boolean functions. Or the output (pin 19 of IC1) could be tied back into the polarity selector on the exclusive-OR gate for further decoding. The possibilities are almost endless; I have found I can usually rig up whatever logic I need quickly, with the Byte Catcher as my basic test instrument. ■



Figure 1: *Schematic diagram of the Byte Catcher Logic Analyzer. The 25LS2521 integrated circuit is an 8-bit Equal-to Comparator made by Advanced Micro Devices which outputs logic low whenever the eight* A *inputs are equal to the eight* B *inputs. Parts placement is not critical. See the text for a number of possible variations and modifications to this circuit.*

Circle 373 on inquiry card.

Event Queue

July 1981

July-September
Short Courses from the Continuing Education Institute (CEI), various sites throughout the US. Three- and four-day courses on data-base systems, applied microprocessor systems, microprocessor interfacing, digital filtering, and applied time-series analysis, are being offered by CEI. Fees range from $595 to $795. Contact the Continuing Education Institute, 10889 Wilshire Blvd, Suite 1030, Los Angeles CA 90024, (213) 824-9545.

July 9-10
Software Engineering, Denver CO. Tailored for systems analysts, designers, programmers, and managers, this seminar examines the latest developments in software engineering. For more information, contact Battelle, Seminar and Studies Program, 4000 NE 41st St, POB C-5395, Seattle WA 98105, (206) 525-3130.

July 13-15
The Automated Office, Chicago IL. Sessions will describe an automated office and how it functions. Word and data processing, electronic-communication, and computerized records-management approaches to implementing office automation will be covered. This conference is designed for executives and professionals. Contact Department K-Automated Off, NIMR Seminars, POB 3727, Santa Monica CA 90403, (213) 450-0500.

July 13-17
The Eighth International Colloquium on Automata, Languages, and Processing (ICALP 81), Palm Beach Hotel, Acre (Akko), Israel. Among the seminar topics to be covered at this conference are factoring algorithms, data-flow analysis, linear-decision trees, and countable nondeterminism. For more information, contact Dr Oded Kariv, ICALP 81, Computer Science Department, The Technion, Haifa, Israel.

July 13-24
Computer Camp East, various sites throughout New England. The camp is open to children aged 10 to 17. Contact Professor Howard A Peelle, Instructional Applications of Computers, School of Education, University of Massachusetts, Amherst MA 01002, (413) 545-0496.

July 15-17
Summer Computer Simulation Conference, Washington DC. This conference will present over forty sessions on topics of computer-simulation technology and applications. Contact William E Buchanan, Applied Physics Laboratory, Johns Hopkins Rd, Laurel MD 20810, (301) 953-7100.

S-100 SERIAL PORT CARD



- with 4 ports
- all handshaking lines provided
- easy to interface

$269.

UNTIE YOUR COMPUTER!

"FAST SPOOLER"

With the "Fast Spooler," your computer can be used for other functions while your printer is in use. Large blocks of data are transmitted to the "Fast Spooler" board which acts independently to supply data to your printer. A real computer timesaver!

- Z-80 CPU
- two serial ports
- 3 parallel imput/output ports
- 64K buffer memory
- 2K ROM
- on board power supply
- includes cabinet

$695.



DOUBLE SIDED QUME DRIVE DATATRAK 8

$540.

Regularly $808.

6809E CPU CARD FOR *APPLE II™

- includes editor and assembler
- inialization subroutines are included on disk
- board is slot independent
- jumpers for 6809E interrupts
- full handshaking between 6809E and 6502

$379.



*Apple II is a registered trademark of Apple Computer, Inc.

CALIFORNIA COMPUTER SYSTEMS

Order Number	Our Price
2032A 32K Static MEM-450NS	$560.00
2032B 32K Static MEM-300NS	640.00
2032C 32K Static MEM-200NS	649.00
2065C 64K Dynamic MEM-200NS	569.00
2116A 16K Static MEM-450NS	257.00
2118B 16K Static MEM-300NS	261.00
2116C 16K Static MEM-200NS	290.00
2116X 16K BD only	67.00
2200A Mainframe 110/60	386.00
2422A Floppy Controller	320.00
2710A 4-Port Serial I/O	279.00
2718A Serial/Parallel I/O	290.00
2720A 4-Port Parallel I/O	200.00
2810A Z-80 CPU BD	235.00

APPLE BDS:

Order Number	Our Price
7114A 12K Rom/Prom Bd.	$ 63.00
7424A Calendar Clock Bd.	103.00
7440A Programmable Timer	90.00
7470A A/D Converter	97.00
7490A GPIB IEEE 488	230.00
7710A Serial Asynch Bd.	127.00
7712A Serial Synch Bd.	152.00
7720A Parallel Interface Bd.	99.00
7720B Centronic Parallel Interface	99.00
7811B Arithmetic Processor with Diskette	329.00
7811C Arithmetic Processor with Rom	329.00

RECTIFIERS (1A)

		100+
1N4001	12/1.00	.07
1N4002	12/1.00	.07
1N4003	12/1.00	.07
1N4004	12/1.00	.07
1N4005	10/1.00	.08
1N4006	10/1.00	.08
1N4007	10/1.00	.08

ZENER DIODES

½ WT

Part#	Price
1N5231B	.20
1N5239B	.20
1N5242B	.20
1N5245B	.20
1N5248B	.20
1N5250B	.20
1N5252B	.20
1N5255B	.20

1 WT

Part#	Price
1N4733A	.30
1N4739A	.30
1N4742A	.30
1N4744A	.30
1N4746A	.30
1N4747A	.30
1N4749A	.30

CRYSTALS

(Part# includes frequency in MHZ)

Part#	Price
SY1	5.75
SY1.8432	5.75
SY2	5.75
SY2.4576	5.75
SY3.579	5.75
SY4	4.50
SY5.068	4.50
SY6	4.50
SY6.144	4.50
SY8	4.50
SY10	4.50
SY12	4.50
SY14.31818	4.50
SY15	4.50
SY18	4.50
SY18.432	4.50

SOLID DIPPED TANTALUM CAPACITORS 20%

Value	Volts	1+	25+	100+
.1mf	35v	.35	.30	.26
.15mf	35v	.35	.30	.26
.22mf	25v	.35	.30	.26
.33mf	35v	.35	.30	.26
.47mf	35v	.35	.30	.26
.68mf	35v	.35	.30	.26
1mf	35v	.35	.30	.26
1.5mf	35v	.45	.39	.33
2.2mf	35v	.45	.39	.33
3.3mf	35v	.50	.42	.36
4.7mf	25v	.50	.42	.36
4.7mf	35v	.65	.56	.44
6.8mf	35v	.65	.56	.44
10mf	25v	.85	.72	.61
10mf	35v	1.19	1.00	.84
15mf	25v	1.30	1.09	.92
22mf	25v	1.30	1.09	.92
33mf	25v	1.35	1.12	.95
47mf	25v	1.55	1.29	1.05
100mf	6v	2.95	2.48	2.08

SOCKETS

LOW-PROFILE SOLDER TIN

Part#	1+	25+	100+
S8LT	.15	.11	.08
S14LT	.18	.16	.14
S16LT	.21	.18	.16
S18LT	.26	22	18
S20LT	.31	.26	.20
S22LT	.33	.28	.22
S24LT	.35	.29	.24
S28LT	.41	.34	.28
S40LT	.53	.47	.40

WIRE-WRAP SOLDER TIN

Part#	1+	25+	100+
S8WT	.37	.33	.30
S14WT	.48	43	.39
S16WT	.53	.48	.43
S18WT	.61	.55	50
S20WT	.85	.77	.69
S22WT	.89	.80	.72
S24WT	.96	.86	.77
S28WT	1.22	1.11	.99
S40WT	1.75	1.57	1.40

WIRE-WRAP GOLD

Part#	1+	25+	100+
S8WG	54	.49	.44
S14WG	.77	.69	.62
S16WG	.83	.75	.68
S18WG	1.00	.90	.81
S20WG	1.24	1.11	.99
S22WG	1.35	1.22	1.10
S24WG	1.40	1.26	1.13
S28WG	1.78	1.60	1.44
S40WG	2.25	2.03	1.83

VOLTAGE REGULATORS

Part#	Case	Price
78L05	TO92	.45
78L12	TO92	.45
78L15	TO92	.45
79L05	TO92	.65
79L12	TO92	.65
79L15	TO92	.65
7805P	TO220	1.20
7812P	TO220	1.20
7815P	TO220	1.20
7905P	TO220	1.25
7912P	TO220	1.25
7915P	TO220	1.25
7605K	TO3	1.50
7812K	TO3	1.50
7815K	TO3	1.50
7905K	TO3	1.60
7912K	TO3	1.60
7915K	TO3	1.60
309H	TO39	.95
309K	TO3	1.25
317P	TO220	1.95
317K	TO3	2.95
323K	TO3	5.50
337P	TO220	2.40
337K	TO3	3.80
350K	TO3	5.75

CERAMIC DISC CAPACITORS 50V

Value	1+	25+	100+
4.7pf	.07	.06	.04
10pf	.07	.06	.04
22pf	.07	.06	.04
33pf	.07	.06	.04
39pf	.07	.06	.04
47pf	.07	.06	.04
68pf	.07	.06	.04
100pf	.07	.06	.04
150pf	.07	.06	.04
220pf	.07	.06	.04
270pf	.07	.06	.04
330pf	.07	.06	.04
470pf	.07	.06	.04
.001mf	.07	.06	.04
.0022mf	.07	.06	.04
.0033mf	.07	.06	.04
.0047mf	.07	.06	.04
.01mf	.07	.06	.04
.022mf	.10	.08	.06
.033mf	.10	.08	.06
.047mf	.11	.09	.07
.1mf	.14	.12	.10

DIODES

Switching

1N914	12/$1.00
1N4148	12/$1.00

TRANSISTORS

2N2219A	$ .35
2N2222A	.25
2N2905A	.30
2N2907A	.25
2N2369A	.25
2N3904	.20
2N3906	.20
PN2222A	.19
PN2907A	.19

¼ WT & ½ WT CARBON FILM 5% RESISTORS

10	100	1K	10K	100K	1M
11	110	1.1K	11K	110K	1.1M
12	120	1.2K	12K	120K	1.2M
13	130	1.3K	13K	130K	1.3M
15	150	1.5K	15K	150K	1.5M
16	160	1.6K	16K	160K	1.6M
18	180	1.8K	18K	180K	1.8M
20	200	2K	20K	200K	2M
22	220	2.2K	22K	220K	2.2M
24	240	2.4K	24K	240K	2.4M
27	270	2.7K	27K	270K	2.7M
30	300	3K	30K	300K	3M
33	330	3.3K	33K	330K	3.3M
36	360	3.6K	36K	360K	3.6M
39	390	3.9K	39K	390K	3.9M
43	430	4.3K	43K	430K	4.3M
47	470	4.7K	47K	470K	4.7M
51	510	5.1K	51K	510K	5.1M
56	560	5.6K	56K	560K	5.6M
62	620	6.2K	62K	620K	
68	680	6.8K	68K	680K	
75	750	7.5K	75K	750K	
82	820	8.2K	82K	820K	
91	910	9.1K	91K	910K	

MINIMUM ORDER PER TYPE:
5 pcs—any qty 5 pack @ $.25

MINIMUM ORDER PER TYPE:
100 pcs

Price Per 100 Pk:

QTY	¼ WT	½ WT
100 up	$1.70	$1.80
1,000 up	1.50	1.60
5,000 up	1.30	1.40
10,000 up	1.10	1.20

74 LS

Part #	Price
74LS00	.32
74LS01	.32
74LS02	.32
74LS03	.32
74LS04	.32
74LS05	.32
74LS08	.32
74LS09	.35
74LS10	.38
74LS11	.38
74LS12	.39
74LS13	.32
74LS14	.65
74LS15	.35
74LS20	.32
74LS21	.36
74LS22	.36
74LS26	.35
74LS27	.39
74LS28	.37
74LS30	.36
74LS32	.40
74LS37	.38
74LS38	.39
74LS40	.36
74LS42	.95
74LS47	1.15
74LS48	1.15
74LS51	.32
74LS54	.38
74LS55	.34
74LS73	.49
74LS74	.49
74LS75	.63
74LS76	.55
74LS83	.95
74LS85	1.25
74LS86	.55
74LS90	.79
74LS92	.75
74LS93	.75
74LS95	.99
74LS107	.50
74LS109	.50
74LS112	.52
74LS113	.52
74LS114	.52
74LS123	1.05
74LS125	.70
74LS126	.70
74LS132	.95
74LS136	.53
74LS138	.85
74LS139	.85
74LS148	1.75
74LS151	.79
74LS152	.79
74LS153	.79
74LS154	2.05
74LS157	1.15
74LS158	1.15
74LS160	.85
74LS161	.85
74LS162	.85
74LS163	.95
74LS164	1.10
74LS165	1.10
74LS166	2.55
74LS170	1.90
74LS173	1.35
74LS174	1.25
74LS175	.95
74LS181	2.35
74LS190	1.15
74LS191	1.15
74LS192	1.15
74LS193	1.15
74LS194	1.15
74LS195	1.15
74LS196	.99
74LS197	.99
74LS221	.95
74LS240	1.05
74LS241	1.05
74LS242	1.45
74LS243	1.45
74LS244	1.05
74LS245	2.15
74LS251	1.29
74LS253	.99
74LS255	.99
74LS257	1.15
74LS258	1.15
74LS260	.95
74LS261	2.49
74LS266	.65
74LS273	1.65
74LS283	1.05
74LS365	.85
74LS366	.85
74LS367	.85
74LS368	.85
74LS373	1.65
74LS374	1.45
74LS375	.99
74LS377	1.15
74LS386	.59
74LS390	1.75
74LS393	1.75
81LS95	1.35
81LS96	1.35
81LS97	1.35
81LS98	1.35

Southern Semiconductor carries complete lines of California Computer Systems, GC Electronics, Vector Electronics and Circuit Assembly Corp. We stock what we sell. Write or call today for catalog.

- Minimum order: $10.00
- Ga. residents add 3% sales tax
- Dealer, OEM and institutional inquiries invited
- Prices good in U.S.A. only
- Master card and Visa welcome

master charge THE INTERBANK CARD · VISA®

Southern Semiconductor, Inc. ™
6030 Unity Drive, Suite J, Norcross, Georgia 30071, (404) 449-6666

Circle 363 on inquiry card.

July 20
Passive-Solar Architecture and Computers, Berkeley CA. CALPAS3 is a computer program to model the thermal performance of residential buildings. It is explained in this class for architects, engineers, and energy consultants. Contact Sara Bennett, Berkeley Solar Group, 3140 Grove St, Berkeley CA 94703, (415) 843-7600.

July 20-21
Software Engineering, Seattle WA. For details, see July 9-10.

July 22-24
Diagnostic Software: Planning and Design, the Registry Hotel, Bloomington MN. This is a seminar for design, test, and diagnostic engineers and managers. Design examples, lectures, informal sessions, and individual and group diagnostic-programming sessions are part of the course. Tuition is $495. Contact Professor Donald D French, Institute for Advanced Professional Studies, One Gateway Center, Newton MA 02158, (617) 964-1412.

July 27-August 10
Computer Camp East, various sites throughout New England. For details, see July 13-24.

July 29-31
The 1981 Microcomputer Show, Wembley Conference Centre, London, England. Seminars on microcomputer applications in business, production, and education will be presented. Topics for conference sessions include hardware availability, software packages and development, automatic test equipment, robotics and process control. Exhibits from major European and American manufacturers will also be featured. Contact TMAC, 680 Beach

St, Suite 428, San Francisco CA 94109, (800) 227-3477; in California (415) 474-3000.

August 1981

August 3-7
Workshops in Digital Sound Synthesis and Processing, Digital Music Systems Inc, Boston MA. These workshops will provide a hands-on introduction for electronic-music composers and performers, recording engineers, psychoacoustic researchers, and others who work in the digital-audio field. The topics to be covered are fundamentals of digital audio, unit generators, automated synthesis and processing, nonlinear techniques, digital delay, filtering and reverberation, digital-audio hardware, and future trends. The fee is $300. Contact Digital Music Systems Inc, POB 1632, Boston MA 02110, (617) 542-3042.

August 10-14
Reliability and Life Testing, University of California, Los Angeles, Los Angeles CA. Engineers and scientists involved with the reliability, design, product assurance, quality, and safety aspects of components, equipment, and systems are invited to attend this course. The fee is $775. Contact the Short Course Program Office, 6266 Boelter Hall, UCLA Extension, Los Angeles CA 90024, (213) 825-1047.

August 10-21
Computer Camp East, various sites throughout New England. For details, see July 13-24.

August 10-14
Workshops in Digital Sound Synthesis and Processing, Digital Music Systems Inc, Boston MA. For details, see August 3-7.

August 17-21
Workshops in Digital Sound Synthesis and Processing, Digital Music Systems Inc, Boston MA. For details, see August 3-7.

August 24-27
Software Design, Reliability, and Testing, Sheraton Motor Inn, Lexington MA. This four-day seminar for engineers, programmers, and technical managers examines concepts and techniques for developing and testing reliable, cost-effective software. The conference also addresses management concerns and recommended policies. Tuition is $600, which includes course notes, luncheon, refreshments, and an evening reception. Contact Professor Donald D French, Institute for Advanced Professional Studies, One Gateway Center, Newton MA 02158, (617) 964-1412.

August 24-28
The Seventh International Joint Conference on Artificial Intelligence, University of British Columbia, Vancouver British Columbia, Canada. This conference examines computer applications of medical diagnosis, computer-aided design, robotics, programmable automation, speech understanding, vision, and other artificial-intelligence-related topics. A tutorial program and artificial-intelligence exhibits are to be presented. For more information, contact Louis G Robinson, American Association for Artificial Intelligence, Stanford University, POB 3036, Stanford CA 94305, (415) 495-8825.

August 25-28
Vector and Parallel Processors in Computational Science, Chester, England. The conference will concentrate on hardware, software, algorithms, applications, and case studies concerning vec-

tor and parallel processors. For information, contact Mrs S A Lowndes, Science Research Council, Daresbury Laboratory, Daresbury, Warrington, WA4 4AD, England.

August 26-29

The Fifth Annual National Small Computer Show, New York Coliseum, New York NY. Daily lectures and a five-hour executives-only seminar will be featured. The executive seminar is designed for upper-level managers who need an introduction to the understanding, acquisition, and use of computers in business. The registration fee for the show is $10 per day. The seminar for executives is $200, which includes all materials and show registration. For information, contact the National Small Computer Show, 110 Charlotte Pl, Englewood Cliffs NJ 07632, (201) 569-8542.

August 28-30

Personal-Computer Arts Festival '81 (PCAF '81), Philadelphia Civic Center, Philadelphia PA. PCAF '81 will include technical sessions, demonstrations, and exhibits. Also featured is the annual computer-music concert and computer-graphics film and video show. PCAF '81 is being held in conjunction with the Personal Computing Show '81. For complete details, contact PCAF '81, POB 1954, Philadelphia PA 19105.

September 1981

September-December

Four Seminars from Management Information Corporation (MIC), various sites throughout the US. These seminars are designed for businesspeople who need an introduction to system selection and use. For a complete



schedule of seminars, fees, and locations, contact Carrol Bell, c/o MIC, 140 Barclay Ctr, Cherry Hill NJ 08034, (609) 428-1020.

September 1-3

Computerized Office Equipment Expo (COEE), Civic Center, Atlanta GA. COEE provides a forum where the owners and executives of small and large businesses can learn about office automation. Office equipment for word processing, record storage and retrieval, and micrographics will be exhibited. Contact Cahners Exposition Group, 222 W Adams St, Chicago IL 60606, (312) 263-4866.

September 9-11

Eurographics '81, Technical University, Darmstadt, West Germany. Almost seventy exhibitors are expected to attend this computer graphics show. Detailed information can be obtained from Diebold Deutschland GmbH, Attn: Dr H J Grobe, Feuerbachstrasse 8, D-6000 Frankfurt/Main, West Germany.

September 10-13

Mid-West Computer Show, McCormick Place, Chicago IL. This show features office systems, data- and word-processing equipment, telecommunications equipment, microcomputers, computer graphics, peripherals, and other related supplies. For information, contact the National Computer Shows, 824 Boylston St, Chestnut Hill MA 02167, (617) 739-2000.

September 14-17

Productivity—An Urgent Priority, Capital Hilton Hotel, Washington DC. This conference is intended to provide a focus on productivity throughout the computer industry. General inquiries for program information should be addressed to Compcon

Fall '81, POB 639, Silver Spring MD 20901, (301) 589-3386.

September 15-17

WESCON/81, Brooks Hall, Municipal Auditorium, and Hilton Hotel, San Francisco CA. Sessions on communications, components and devices, computer and microprocessor hardware and software, office automation, and memory systems will be presented. Computer equipment and related products exhibits will be featured. Contact Electronic Conventions Inc, Suite 410, 999 N Sepulveda Blvd, El Segundo CA 90245, (213) 772-2965.

September 16-18

Diagnostic Software: Planning and Design, Boston MA. For details, see July 22-24.

September 16-18

The Engineer as a Communicator, Crystal City Marriott, Arlington VA. This conference will feature discussions on communications technology, information gathering, storage, and retrieval, using computers in technical communications, and other related topics. Contact Dr Daniel Rosich, School of Business Administration, University of Connecticut, Stamford CT 06903, (203) 322-1673.

September 24-25

Microprocessors: Hardware, Software, and Applications, Worcester Polytechnic Institute, Worcester MA. Among the courses to be offered are hardware and software basics, selection and evaluation of microprocessors, memory and input/output systems, multiprocessor systems, real-time system design, and circuit testing and debugging. For more information, contact Ginny Bazarian, c/o Office of Continuing Education, Worcester

Polytechnic Institute, Worcester MA 01609, (617) 753-1411, ext 517.

September 24-27
Mid-Atlantic Computer Show, Washington Armory, Washington DC. For details, see September 10-13.

September 30-October 2
Data and Telecommunications Expo '81, Rhein-Main-Halle, Wiesbaden, West Germany. This exhibition and conference will cover all areas of technology in data handling and distribution and telecommunications. Power supplies, processors, software, terminals, cables, test equipment, and modems are some of the items that will be exhibited. Contact Kiver Communications S A, UK Branch Office, Millbank House, 171/185 Ewell Rd, Surbiton, Surrey, KT6 6AX, England. ■

BYTE's Bits

Engineering Design Data on Tap

How do scientists, engineers, and technicians resolve conflicts in research materials? Many find help at Purdue University's Center for Information and Numerical Data Analysis and Synthesis (CINDAS). CINDAS evaluates and resolves conflicts in published information and concludes what should be transmitted as valid. The service cuts through the inconsistencies found in research materials, especially in heat, electrical, electronic, magnetic, and optical studies.

When a conflict is deemed resolved, the information is entered into the CINDAS data banks, which now have more than 180,000 indexed and coded entries. Each year

CINDAS adds more than 10,000 new citations from well over 8500 unclassified sources.

The service also has property-measurement laboratories offering analytical services and technical assistance. In addition, retrospective searches, document reproduction service, and data publications can be obtained.

For inquiry services, contact CINDAS, Purdue University, 2595 Yeager Rd, West Lafayette IN 47906, (800) 428-7675; in Indiana (317) 463-1581.

Call for Papers

"Reliability in Electrical and Electronic Components and Systems" is the theme for the Fifth European Conference on Electrotechnics. The conference will be held at the Technical University of Denmark June 14 through the 18, 1982.

The program committee is soliciting papers on reliability theory, management and economic issues, human and legal aspects, energy processing, and communication data and signal processing. Three copies of a one- or two-page summary in English (the conference language) should be submitted by September 1, 1981. The papers will be accepted on the basis of the summaries. Authors transfer their copyright to the conference after submission of the article.

The conference program will be designed for electrical and electronic engineers, marketing experts, and those concerned with research and development, manufacturing, and applications of electrical and electronic systems. Contact DIEU, Danish Engineers' Post Graduate Institute, The Technical University of Denmark, Bldg 208, DK-2800 Lyngby, Denmark.■

Clubs and Newsletters

Software Maintenance Techniques

The first issue of *Software Maintenance Techniques*, a new quarterly newsletter devoted to maintaining programs and systems, is available free upon request. The publication acts as a focal point for the collection and distribution of knowledge about maintenance.

Each issue presents topics applicable to all levels of data processing and to all data-processing systems. *Software Maintenance Techniques* has articles on the latest modification tools and approaches.

Reader contributions are invited. Subscriptions are $20 per year. Contact EduCo Corporation, 6777 Wadsworth, Suite 102, Arvada CO 80003, (303) 424-4425.

Club Apple de Quebec

Club Apple de Québec meets every Monday at 7 PM. The club's principal interest is languages, but it will review everything from hardware to games. Fees are $5 per month (Canadian funds).

For complete details, contact Octavio Prieto-Cox, Club Apple de Québec, 1575 De Niverville, #4, P Q, G1J 4Z7, Canada, (418) 663-3241; or Societé d'Informatique Amateur du Québec, c/o Club Apple de Québec, POB 9242, Ste-Foy, P Q, G1V 4B1, Canada.

Flint 6500 Users Group

The Flint 6500 Users Group can be contacted at POB 4310, Flint MI 48504; or by calling R Riley (313) 695-1117, weekdays from 7 to 8 PM.

Computer Club in Delaware

DUMPS (Delaware Users of Micro-Processor Systems) is a group of enthusiasts in northern Delaware. DUMPS has a program exchange and supports different microcomputers. Contact John T Lund, 901 Centre Rd, Westover Hills, Wilmington DE 19807, (302) 655-1854.

Apple Group for Teachers

The Apple for the Teacher group promotes the educational uses of Apple computers. Its primary interests are in computer-aided instruction, special education, and funding sources for educational uses of the Apple. A journal, *Apple Educators Newsletter*, is published.

For additional information, contact Ted Perry, 5848 Riddio St, Citrus Heights CA 95610, (916) 961-7776.

Educational Electronics

Educational Electronics is a new monthly newsletter with information on advances in technology for educational purposes. It focuses on the development of computer hardware and software for instructional and administrative purposes. Also included is material on information-retrieval systems, voice synthesis, speech control, audio-visual equipment, and materials for training the handicapped.

Educational Electronics keeps track of research and development programs within the manufacturing community. Information about grants, legislation, and government trends affecting educational technology and reviews of new products are featured. Subscriptions are $60 per year.

For more information, contact Educational Electronics Inc, 1 Lincoln Plz, New York NY 10023, (212) 877-8539.

Earn Money with Your Hobby

The *Micro Moonlighter* newsletter is a publication for those wishing to use their microcomputer for part- or full-time business ventures. Marketing methods, advertising hints, contracts, and industry trends are covered regularly. The newsletter is aimed at advanced computer users.

Charter subscriptions are $25 per year in the US, $29 in Canada, and $35 elsewhere. Contact J Norman Goode, 2115 Bernard Ave, Nashville TN 37212.

TRS-80 Group In West LA

The TRS-80 Users Group of West Los Angeles, California, has been organized. An exchange of public-domain software and discussions of hardware and software topics are planned. Contact the group at POB 85, Culver City CA 90230, (213) 836-4103.

Attention ZX80 and MicroAce Fans

The ZX80 and the Micro-Ace computers deserve a user group. If you're interested in exchanging or publishing newsletters about these computers and if you would like to help form a users group for that purpose, contact Conan La Motte, 712 Pidgeon St, San Diego CA 92114.

Wanted: SD Systems Z80 Starter Kit Users

The SD Systems Z80 Starter Kit is a single-board computer that longs for a central information clear-

inghouse. If you'd like to exchange information, write an article, or devise tutorials, contact Cary N Davids, 6000 Puffer Rd, Downers Grove IL 60516.

TUG Calls

The Technico Users Group (TUG) is interested in hearing from anyone who has a Technico computer or any computer based on the Texas Instruments 990 or TMS 9900's architecture. TUG publishes a newsletter and is looking for articles on software, hardware, novel applications, other items of interest, and ads for software and hardware. Currently, there are no dues.

Contact Penn S Avera, Quantum Data Systems Inc, 259 S Farragut Ter, Philadelphia PA 19139, (215) 747-8341.■

BYTE's Bits

Microcomputers In Public Service

Suncoast Micro-Systems (SMS) is developing and placing microcomputers within community-based, public service and charitable organizations. SMS, a nonprofit corporation, seeks contact and collaboration with other groups involved in similar activities in communities around the country. Information on software and hardware materials available or being developed is sought.

Contact SMS at 1870 Sailfish Rd, St Petersburg FL 33707, (813) 347-6733.■

Software Received

Apple

App-L-ISP, a version of the LISP programming language for the Apple II. Floppy disk, $124.95. DataSoft Inc, 19519 Business Center Dr, Northridge CA 91324.

The Asteriod Field, graphics arcade game for the Apple II. Floppy disk, $24.95. Cavalier Computer, POB 2032, Del Mar CA 92014.

Baker's Trilogy, three arcade-type games for the Apple II. Floppy disk, $29.95. Softape, 10432 Burbank Blvd, North Hollywood CA 91601.

Graphtrix, a text and high-resolution graphics-printing program for the Apple II. Floppy disk, $55. Data Transforms Inc, 906 E Fifth Ave, Denver CO 80218.

Job Costing II, a project-management program for the Apple II. Floppy disk, $160. Garbo, 1205 W Riverside Dr, Carlsbad NM 88220.

Personal Check Manager, a checkbook utility program for the Apple II. Floppy disk, $30. D R Poling, 6929 La Cienega Blvd, Los Angeles CA 90045.

Star Warrior, a graphics action game for the Apple II. Floppy disk, $29.95. Automated Simulations Inc, POB 4247, Mountain View CA 94040.

Super FORTH, a version of the FORTH programming language for the Apple II. Floppy disk, $49.95. Hayden Book Company Inc, 50 Essex St, Rochelle Park NJ 07662.

CP/M

Eliza, the original Rogerian therapist simulation program for CP/M computers. Floppy disk, $24.95. The Artificial Intelligence Research Group, 921 N La Jolla Ave, Los Angeles CA 90046.

RAID, an assembly-language debugging utility for CP/M computers. Floppy disk, $250. Southern Computer Systems, POB 3373A, Birmingham AL 35255.

Radio Shack

BasicPro, BASIC programming utility for the TRS-80 Model I. Cassette, $24.95. Softworx, Inc, POB 9080, Seattle WA 98109.

CIE Head Azimuth Alignment Tape, a program-recorder head-alignment utility for the TRS-80 Model I. Cassette, $3.95. Computer Information Exchange, POB 159, San Luis Rey CA 92068.

Devil's Island, an adventure program for the TRS-80 Model I. Cassette, $14.95. Computhings, 708 Broadway, Chelsea MA 02150.

GAPP, a cassette-based file-card program for the TRS-80 Model I or III. Cassette, $9.50. Robert G Gallie, 4726 W 13th St, Cicero IL 60650.

Menu Master, a formatted video input and output utility for the TRS-80 Model I or III. Floppy disk, $24.95. AHEA, 545 Macenta Ln, Diamond Bar CA 91765.

Star Warrior, a graphics-action game for the TRS-80. Cassette, $29.95. Automated Simulation (see above).

Texas Instruments

The Cube, Rubik's Cube simulation program for the TI 99/4. Cassette, $14.95. Linear Aesthetic Systems, POB 23, West Cornwall CT 06796.

The Shrink, an artificial-intelligence simulation program for the TI 99/4. Cassette, $15. Tinnware, 30 S First Ave, Suite 171, Arcadia CA 91006. ■

This is a list of software packages that have been received by BYTE Publications during the past month. The list is correct to the best of our knowledge, but it is not meant to be a full description of the product or the forms in which the product is available. In particular, some packages may be sold for several machines or in both cassette and floppy-disk format; the product listed here is the version received by BYTE Publications.

This is an all-inclusive list that makes no comment on the quality or usefulness of the software listed. We regret that we cannot review every software package we receive. Instead, this list is meant to be a monthly acknowledgment of these packages and the companies that sent them. All software received is considered to be on loan to BYTE and is returned to the manufacturer after a set period of time. Companies sending software packages should be sure to include the list price of the packages and (where appropriate) the alternate forms in which they are available.

BYTE's Bits

Calling All TRS-80 Model II Users

A group of enthusiasts invites all TRS-80 Model II users to participate in a project to document user-developed SVCs (supervisor calls) for TRSDOS 2.0 and to establish a BASIC memory map for those users that want to use the PEEK and POKE modifications available from several sources. The project seeks to act as a clearinghouse for all TRSDOS 2.0 SVCs and BASIC memory-map information. The accumulated data will be published and distributed to all participants.

Here are the guidelines:

All submissions must include name, address, and telephone number. Submitted material must not be restricted from being published. When submitting information, send a listing in 80-column format, with as many remarks as possible. The purpose of the SVC must be explained. If the purpose of the SVC is not apparent, a listing using the SVC should be given. Any variables passed must be identified, and their handling into and out of the SVC must be explained. Indicate if the SVC is not original and give the source if possible. Any memory-map information submitted with doubts about its location must be indicated. If the location must work with others, document the use.

The group would appreciate the SVCs being sent on floppy disk, which will be returned after transfer. The group reserves the right to select or reject any submissions and to merge or condense the submission with another. Those submissions printed will be credited to the persons or companies that submitted them.

The group is also interested in any Model II "tricks" or subtle programming ideas. Send submissions to Pete Charlton, 491 Elbow Ct, Weatherford TX 76086.

Camp Instructors Needed

Computer Camp East is looking for instructors for its July 27 to August 7 and August 10 to August 21 sessions. The sessions are held in different parts of New England. The camp directors are looking for individuals to teach 10- to 17-year-olds APL, BASIC, Pascal, and Logo, and to supervise the use of Apple II, PET, Atari 800, and TI 99/4 microcomputers.

Contact Professor Howard A Peelle, Instructional Applications of Computers, School of Education, University of Massachusetts, Amherst MA 01002, (413) 545-0496. ■

Circle 58 on Inquiry card.

SURPLUS BUYS of the YEAR!!

The Most Sought After. Most Desireable

DIABLO 10 MEG DISK DRIVES

Model 44B

- 5 Mb Fixed. 5 Mb Removable
- 115 VAC 60 Hz
- Takes 5440 Disk
- Industry Std. Drive
- Daisy chain up to 4
- I/O Data included

- Built-in power supplies
- 200 tracks / inch
- 256 Bytes per sector
- 24 sectors / track
- 19.583 sectors / platter

Special Offer!!!

REFURBISHED & FULLY OPERATIONAL!

Only **$2200.00** each. Includes 2 FREE DISK CARTRIDGES

MODEL 44A DISK DRIVE 10 Mb. earlier design, same I/O. Used, whole, untested. Includes schematics & data .... **$1200ea.**

MODEL 43 5 MEG DISK DRIVE 100 TPI, good cond., used, whole, untested. With data and schematics .... **$795 ea.**

MODEL 429 POWER SUPPLY ±24VDC @ 6 amps, 5V @ 6 amps. Required for both the 44A and 43 drives (above) .... **$75.00 ea.**

OTHER BARGAINS

***SELECTRIC-II Typewriter/Printer**

With stepper-driven platen & carrier. Exciting possibilities. Removed from sophisticated word processors. Solenoids (standard selectric corresp. code) self contained. Mostly whole; "as-is", with schematics and data. ..... **Only $399.00 ea.**

RO*SELECTRIC-II Printer

"Receive-only" (no keyboard). Features X&Y steppers plus all solenoids & standard IBM Selectric-II printer mechanism. Takes Tech-III ribbon cartridges. Less case and platen, mostly whole, "as-is". Schematics included.

.... **Only $129.00 ea.**

Disk Drives: Add $30 for Hdlg. & Pkg., Pay Shipping on Delivery
Selectric Printers: Add $20 for Hdlg. & Pkg., Pay Shipping on Delivery
**Reg. Trade-Mark of IBM Corp.*

CFR Associates, Inc.

MAIL ORDERS: Box 144, Newton, N.H. 03858

PHONE ORDERS: 617/372-8536 (Sorry, No Collect Calls) MasterCharge & VISA Welcome

WAREHOUSE: 18 Granite Street, Haverhill, Mass. 01830

Electronic Engineers

Immediate openings for development engineers in fast moving field of traffic control products and transportation systems.

BS or MS Degree in Electrical Engineering and experience in micro-processor and micro-computer software and hardware development required. Knowledge of traffic control devices and system design beneficial.

Please call (612) 733-1358 or send your resume in confidence to Jim Egan.

Staffing & Employee Resources/3M
224-1W 3M Center
St. Paul, Minnesota 55144

We Are An Equal Opportunity Employer M/F/H/V

3M

Circle 410 on inquiry card.

Circle 134 on inquiry card.



E.R. Hardin's

MILITARY MADNESS

for Apple, Atari and TRS-80

TOMCAT vs. MIG

Blue skies and 40,000 feet over the Rhine Valley, when a MIG-25 suddenly blips onto your radar screen.
Your F-14 Tomcat has a brace of rockets and avionics to help survive the antics of Ivan.
Are you brave enough to climb into the cockpit and take your chances against a Russian pilot?

cassette $19.95

GUNSHIP

Dateline; Vietnam. Tet offensive of 1968. Battle ground troops with mini-guns and rockets. Crash and burn if you're clumsy.

cassette $19.95

GREEN BERET

Run a mission behind the lines, in North Vietnam. Blow up bridges, kidnap politicos, raid prison camps. You are the team commander.

cassette $19.95

511 Iowa Ave.
Iowa City, IA 52240

Call 1-800-227-1617, operator 364
(in California 800-772-3545, operator 364)

VISA
MASTERCHARGE

Computer-Aided Drafting with Apple Pascal

Dan Sokol
285 Pacific Ave
Brookdale CA 95007

Electronic hardware design, like any creative endeavor, has its high points and its low points. A personal low point has always been the time it takes to draw usable schematics. The problem is compounded when you consider that after the schematic is drawn and the hardware prototyped, the schematic must be modified (in any number of colors) as the circuit is debugged. Then, of course, the circuit has to be redrawn. And usually by me.

At a trade show a few years ago, I saw a high-quality graphics terminal that was used with a light pen to draw schematic diagrams. A menu of devices was available from the keyboard, and the light pen was used to place the selected device on the screen. Fantastic! . . . and only $150,000.

Technology marches on. Some time ago, Apple Computer announced a new product—a Graphics Tablet. My Apple already had Pascal and an M & R Enterprises Sup'r'terminal board, so I only needed the Graphics Tablet (and some software) to build a computer-aided drafting system (see photo 1).

I began the project with a great deal of enthusiasm. Being fairly proficient with Pascal, I did not anticipate any major problems. It was only after I read the fourth page of the Graphics Tablet operation manual that I began to realize I might have bitten off more than I could compile. It read, ". . . the Graphics Tablet software will not operate . . . in an Apple Pascal environment." I immediately called the Apple Software Hotline (408-996-9868).

Fortunately, the people at Apple were very helpful. They explained that the reason the tablet would not interface to Pascal was that the Pascal BIOS (basic input/output subsystem) did not recognize its existence. They sent me a copy of the BIOS initialization routines, from which I was able to write an assembly-language linkage routine to read data from the pad and transfer it back to Pascal. (Not one to dwell on failures, suffice it to say that it took me three weeks of experimentation to reach that point.)

The program that accomplished this feat was called PAD.ASSY.TEXT (see listing 1). It contained two procedures, one for setting the default parameters, and the other for reading the pad, flashing the cursor, and scaling the results. Both procedures worked in essentially the same manner. First, I accessed hexadecimal location CFFF to disable any active read-only memories in the C800 thru CFFF range (one is found on the Sup'r'terminal board). Then the slot number that contained the Graphics Tablet interface card was stored at hexadecimal location 7F8 and in the 6502 microprocessor's X-register (a small piece of information missing from the Graphics Tablet manual).



Photo 1: *The author's computer-aided drafting system for the Apple II computer. Addition of a Graphics Tablet, a Sup'r'terminal 80-column display board, and some software can take the drudgery out of designing electronic circuits.*

The first address of the slot where the interface card was located was accessed (with a load or store instruction) to enable the read-only memory. (In my case, this was slot number five.) Now the subroutines in the read-only memory were available to the processor. After I called the routines that I needed, I turned off the read-only memories at hexadecimal C800 and executed a return. Pascal's BIOS took care of turning the Sup'r'terminal read-only memory back on.

After reading the tablet and flashing the cursor, the x and y coordinates were stored at decimal locations 645 thru 648. Pascal recovered this data using the PEEK intrinsic that I added to my library (see "Notes on Absolute Location Interfaces to Apple Pascal," September 1980 BYTE, page 324). After compiling the main program the Pascal linker linked the program to PAD.ASSY.CODE.

As soon as I could read data from the tablet, I began to work on the program, which I had named LOGIC-

Circle 345 on inquiry card.

IEEE-488 TO TRS-80* INTERFACE

Everything needed to add *powerful* BASIC GPIB-488 controller capability to TRS-80 Model 1 or 3, Level 2 or DOS with a minimum of 16K.

MODEL 488-80B
For Model 1 Operation

MODEL 488-80C
For Model 3 Operation

Price of Model 488-80B or 488-80C $245.
+ shipping, insurance & tax

WHEN ORDERING SPECIFY DISK OR TAPE

SCIENTIFIC ENGINEERING LABORATORIES
11 Neil Drive • Old Bethpage, NY 11804
Telephone: (516) 694-3205

**Trademark of Tandy Corp.*
There is no affiliation between Scientific Engineering Laboratories and Tandy Corp. or Radio Shack.

Circle 99 on inquiry card.

consumer computers

master charge · VISA · AMERICAN EXPRESS

WE WILL TRY TO BEAT ANY ADVERTISED PRICE

CALL US AND ASK ABOUT OUR WEEKLY SPECIALS!

SEE OUR AD ON PAGES 130-131

APPLE II PLUS
48K FOR $1189
16K FOR $1049
DISK II
with DOS 3.3 and controller card
$529

ORDER TOLL-FREE **1-800-854-6654**
California (and outside continental U.S.) **714-698-8088**

Olympic Sales Company

SERVING YOU SINCE 1947

Main Showroom & Offices:
216 South Oxford Avenue
Los Angeles, CA 90004

WE HONOR
VISA and MASTERCHARGE

YOUR BANK VISA · master charge

TELEX: 67 34 77
ORDER DESKS open 7 Days a Week!
7:00 AM to 7:00 PM Mon thru Sat
Sunday Noon to 5:00 PM
Order Desks: (213) 739-1130

TOLL-FREE (outside Calif.)	TOLL-FREE (within Calif.)
800-421-8045	**800-252-2153**

Write & request our FAMOUS Catalog!
Hundreds & hundreds of products-from many manufacturers-such as SONY, CASIO, VICTOR, CODE-A-PHONE, MATTEL, SHARP, CANON, and on and on. . .too many to list here!

All goods subject to availability; this ad supersedes all previous ads; we are not responsible for typographical errors; we will meet or beat any advertised prices if the competition has the goods on hand.
Minimum shipping and handling $4.95.
All orders subject to verification and acceptance.

HEWLETT PACKARD

	Retail	Your Cost
HP-85 Microcomputer	3250.00	2495.00
HP-83 Microcomputer	2250.00	1795.00
16K Exp-Memory Module	295.00	259.95
Graphics Plotter 7225	2450.00	2089.95
Personality Mod. for 7225	750.00	679.95
2631B Impact prnter/hvy dty	3950.00	3295.00
Option 020 for 2631B	150.00	129.95
8 Disk Drives to choose from		
82902S	1300.00	1149.95
9895A 8" Dual Drive	6850.00	5595.00
Graphics Tablet 9111A	2050.00	1699.95
HP-41CV New 2.2K bytes mem	325.00	259.95
HP-41C Calculator	250.00	188.95
Card Reader for 41CV/C	215.00	168.95
Printer for 41CV/C	385.00	284.95
Optical Wand for 41CV/C	125.00	97.95
System One (41CV & Card Rdr)	495.00	394.95
System Two (41CV/Cd Rdr/Prtr)	840.00	669.95
Quad Ram equals 4 Mem. Mods	95.00	84.95
Memory Modules for 41C		26.95
HP-97 Progrmble Printer	750.00	579.95
HP-67 Progrmble Calculator	375.00	297.95
HP-34C Progrmble Scientific	150.00	117.95
HP-38C Progrmble Bus. R/E	150.00	119.95
HP-32E Adv. Scientific	55.00	48.95
HP-37E Business Mgmt.	75.00	58.95

We carry a large inventory of Libraries, accessories and supplies.

Texas Instruments

TI-99/4 Home Computer	950.00	449.95

★ FREE $100.00 worth of software/goods from Texas Instruments with purchase of TI-99/4. Offer ends June 30, 1981.

10" Color Monitor for 99/4	650.00	319.95
32K Exp. Mem. Module	399.95	314.95
Extended Basic, a MUST for 32K Module	100.00	75.00
Speech Synthesizer	150.00	129.95
Disk Memory Drive	500.00	397.95
RF Modulator	69.50	49.50
Telephone Coupler (Modem)	225.00	189.95
Printer (solid state)	400.00	319.95
TI-59 Progrmble Calculator	295.00	199.95
TI-58C Progrmble Calculator	130.00	93.95
PC-100C Prntr/Plotr for 59/58	225.00	149.95

	Retail	Your Cost
TI-57 Scientific Calculator	99.95	39.95
MBA Finance & Business	70.00	51.95
TI Investmt Analyst	65.00	46.95
TI-55 Slide Rule	40.00	32.95
TI-Progrmr Hexidecml/Octal	65.00	48.50

We carry a large inventory of software, accessories and supplies.

apple computer

We are an AUTHORIZED SERVICING APPLE DEALER

the best price in America!

16K--32K–48K–96K–128K

Drive with controller DOS 3.3 and others. . .
80 column cards
Dow Jones & Quote Reporter
DC Hayes Micromodem II
and others. . .
Graphics Tablet
Pascal and Fortran Languages
VisiCalc and more and more



APPLE III 96K and 128K "CALL US"
Ask for Package One to Three Special Prices!

OHIO SCIENTIFIC

Professional Computers	Retail	Your Cost
C8PDF–48K	3295.00	2995.00

• Dual 8" Drives • 64 col x 32 line/color
• .7 MIPS –*FAST!* • Many more stndard features
Fortran & Pascal available

Many other OSI products available –at discounted prices, of course!

ATARI® PERSONAL COMPUTER

800 16K bytes of RAM	1080.00	759.95
410 Program Recorder	90.00	79.95
810 Disk Drive	600.00	469.95
825 Printer (80 col Centronic 737)	999.95	779.95
820 Printer (40 col impact)	450.00	359.95
830 Acoustic Modem	200.00	159.95
850 Interface Module	220.00	179.95
Atari VisiCalc	200.00	169.95

Large inventory of software and accessories.

PRINTERS

• DIABLO (Letter Quality)		
630 R102 bi-directnal/tractors	2965.00	2699.00
1640K109 keyboard, tractors	3072.00	2899.95
630 RO Receive only	2710.00	2499.95
1650K136 keyboard/tractors	3220.00	2999.95
• CENTRONICS dot matrix		
700-9 Parallel, heavy duty	1460.00	1199.95
704-9 Serial, heavy duty	1795.00	1599.95
737-1 Parallel	995.00	799.95
737-3 Serial	1045.00	899.95
704-11 Parallel	1870.00	1695.00
P-1 Electrostatic	495.00	189.95
• PAPER TIGER		
445G with Graphics	795.00	695.00
460G with Graphics	1394.00	1195.00
560G New full size	1695.00	1399.00
• EPSON		
MX 80 Impact	645.00	499.95
MX 70 Impact	500.00	399.95
NEW! From TI–Series 10 Personal Information Terminal	995.00	795.00

- Internal direct-connect modem
- 5½" dia. non-glare screen
- 40 col. by 24 lines-up to 960 characters displayed
- EIA RS-232-C interface
- Aux. port for optional hard copy print applications

WE ALSO HAVE . . .

• NOVATION Modems	Retail	Your Cost
CAT	199.95	159.95
D-CAT	199.95	159.95
APPLE-CAT Direct connect	349.95	314.95
• SANYO Monitors		
High Resolution, Number 1 seller!		
13" Color (new) high quality	550.00	399.95
12" Green Phosphorous	360.00	239.95
12" Black and White	340.00	219.95
15" Black and White	370.00	239.95
9" B/W the best seller!	235.00	149.95

• HAZELTINE Video Display Terminals
• SHUGART Disk Drives
• DEC VT100 & VT103

Call us for your DISCOUNTED price TODAY!

Circle 285 on inquiry card.

Listing 1: *Assembly-language routine that reads data from the Graphics Tablet for use in Pascal.*

```
ØØØØ|                        ; assembly language linkage
ØØØØ|                        ; to APPLE GRAPHICS TABLET
ØØØØ|                        ;
ØØØØ|                        ; 28 Mar 8Ø - Dan Sokol
ØØØØ|                        ;
ØØØØ|                        ; procedure SETUPAD; external;
ØØØØ|                        ; procedure READPAD; external;
ØØØØ|
ØØØØ| CFFF                   CFFF     .EQU    ØCFFF      ; TURN OFF ALL ROMS
ØØØØ| Ø7F8                   MSLOT    .EQU    7F8        ; ACTIVE SLOT = Cn
ØØØØ| C5ØØ                   PADAT    .EQU    ØC5ØØ      ; SLOT ADDR FOR PAD
ØØØØ| CEF9                   MREAD    .EQU    ØCEF9      ; READ THE PAD
ØØØØ| C8FØ                   CURSOUT  .EQU    ØC8FØ      ; XOR CURSOR AND SCALE PAD OUTPUTS
ØØØØ| CCA1                   QWAIT    .EQU    ØCCA1      ; MIDEAST COUNTRY WITH MUCH OIL
ØØØØ| CE9Ø                   DEFAULT  .EQU    ØCE9Ø      ; SETUP PAD
ØØØØ| CEEA                   DEF4     .EQU    ØCEEA      ; SETUP PAGE AND MPAGE FOR SCREEN 1
ØØØØ| ØØ8Ø                   DELAY    .EQU    8Ø         ; DELAY FOR QWAIT (CURSOR ON)
ØØØØ|
ØØØØ|                                 .PROC SETUPAD,Ø;
ØØØØ|
ØØØØ| AD FFCF                DFLT     LDA     CFFF       ; ALL ROMS OFF
ØØØ3| A9 C5                           LDA     #ØC5
ØØØ5| AA                              TAX
ØØØ6| 8D F8Ø7                         STA     MSLOT
ØØØ9| AD ØØC5                         LDA     PADAT
ØØØC| AD ØØC5                         LDA     PADAT      ; TURN PAD ON
ØØØF| 2Ø 9ØCE                         JSR     DEFAULT
ØØ12| A9 2Ø                           LDA     #2Ø
ØØ14| A8                              TAY
ØØ15| 2Ø EACE                         JSR     DEF4       ; SET SCREEN 1 & STREAM ON
ØØ18| AD FFCF                         LDA     CFFF
ØØ1B| A9 C3                           LDA     #ØC3
ØØ1D| 8D F8Ø7                         STA     MSLOT
ØØ2Ø| AA                              TAX                ; RESET SUP'RTERM
ØØ21| 6Ø                              RTS
ØØ22|
ØØØØ|                                 .PROC READPAD,Ø;
ØØØØ|
ØØØØ| AD FFCF                READIT   LDA     CFFF       ; ALL ROMS OFF
ØØØ3| A9 C5                           LDA     #ØC5
ØØØ5| AA                              TAX
ØØØ6| 8D F8Ø7                         STA     MSLOT
ØØØ9| AD ØØC5                         LDA     PADAT
ØØØC| AD ØØC5                         LDA     PADAT      ; PAD ON
ØØØF| 2Ø F9CE                         JSR     MREAD      ; READ PAD
ØØ12| 2Ø FØC8                         JSR     CURSOUT    ; FLASH CURSOR & SCALE X & Y
ØØ15| A9 8Ø                           LDA     #DELAY
ØØ17| 2Ø A1CC                         JSR     QWAIT
ØØ1A| 2Ø FØC8                         JSR     CURSOUT
ØØ1D| AD FFCF                         LDA     CFFF
ØØ2Ø| A9 C3                           LDA     #ØC3
ØØ22| 8D F8Ø7                         STA     MSLOT      ; RESET SUP'RTERM
ØØ25| AA                              TAX
ØØ26| 6Ø                              RTS
ØØ27|                         ;
ØØ27|                         ; ON EXIT >>> PEN UP/DOWN      -      64Ø (decimal)
ØØ27|                         ;             SCALED X (HIGH BYTE)  - 646
ØØ27|                         ;             SCALED X (LOW BYTE )  - 645
ØØ27|                         ;             SCALED Y (HIGH BYTE)  - 648
ØØ27|                         ;             SCALED Y (LOW BYTE )  - 647

Assembly complete:        62 lines
     Ø   Errors flagged on this Assembly
```

DESIGN. At first, I had intended to include the initialization of the logic symbols in the program, but the program got very large, very fast. I then decided to create a file with the logic symbols in it (I needed the practice). I used the example on one of the disks supplied with the Apple's language card (APPLE3, the butterflies program) as a basis for converting groups of strings into boolean arrays. The program LOGIC.SYMB.TEXT (see listing 2) was the result.

As you can see from the listing, each named shape is a square array of pixels (picture elements), 16 elements on a side. Some of the larger devices (eg: JK flip-flop, MSI) are made up of two shapes, end to end. There are ten initialization procedures (INIT1 thru INIT10): Pascal, it seems, has a limit to the number of (code) words in a procedure. When executed, the program creates two files called LOGIC. CHARSET and USER.CHARSET. The files must exist on the prefix disk prior to running LOGICDESIGN. The source file (LOGIC.SYMB.TEXT) and the code file (LOGIC.SYM.CODE) used to create the character-set files

Circle 202 on inquiry card.

Circle 275 on inquiry card.

Circle 27 on inquiry card.

should be saved elsewhere, as they occupy too much room on the disk and are not needed once the character sets have been created.

The program LOGICDESIGN (see listing 3, on page 415) performs an initialization of the tablet and then, waiting for input from the tablet, loops in the procedure MYPLOT. The bottom three rows of the tablet are used as a menu (see figure 1) for selecting the device to be plotted or the function to be executed.

The command menu, from the lower leftmost corner of the tablet to the lower right-hand corner (ie: the bottom row), is decoded as follows:

CLEAR SCREEN: clears the graphics screen
CLEAR BLOCK: clears a section of the screen
CLEAR LOCK: clears the horizontal and vertical locks
HORIZ LOCK: sets the horizontal lock
VERT LOCK: sets the vertical lock
LIST ITEMS: lists the device names on the text screen
LOAD: loads an image file to the HIRES screen
SAVE: saves the HIRES screen to an image file
EXIT: leaves the program (does a SAVE first)
PRINT SCREEN: transfers the HIRES screen to the printer
ERASE BORDER: removes the border from the HIRES screen
DRAW BORDER: draws a border around the HIRES screen
LABEL: writes characters on the HIRES screen
DRAW LINES: draws horizontal or vertical lines only
EAT RIGHT: deletes lines going to the right
EAT LEFT: deletes lines going to the left
EAT UP: deletes lines going upwards
EAT DOWN: deletes lines going downward
SET USER: allows the user to create a new device
TOGGLE DEBUG FLAG: sets/clears debug flag

The next two rows up from the bottom of the tablet are used to select devices for plotting (see figure 1). Representations of the devices that can be plotted are shown in the boxes in these two rows. When the program is running, the user simply selects the device he wants to plot or the command he wants to perform from the tablet's menu. The Sup'r'terminal screen displays the active mode and other useful information (see photos 2a and 2b).

I wrote the program LOGICDESIGN a little at a time and added new functions as I debugged the old ones. Such is the beauty of Pascal. Two procedures do most of the work: the first, MYPLOT, is inside a never-ending loop in the main program (the variable HELLFREEZESOVER does not ever become true). MYPLOT calls MENU if the pen is pushed down outside of the tablet area that is mapped on the Apple's HIRES (high-resolution) screen (ie: if VALIDXY is false). If the pen is pushed down within the screen area, the active device is plotted (if you're in the plotting mode).

When you enter MYPLOT, it checks to see if the pen is down over the CLEAR pad in the upper left-hand corner of the tablet: this executes a special function. It exclusive-OR's the last device plotted, thus making it disappear from the screen. The variable D is used to determine which device to plot. If D is 0, then nothing is plotted. The procedure MENU selects the device that will be plotted or calls a sequence of procedures to effect a specific function. MENU begins by setting D to 0. It then divides X and Y by a value that neatly generates integers concurrent with the boundaries of the boxes on the tablet. (The actual value of the divisor may be different on another tablet.) A set of nested

(2a)



(2b)



Photo 2: *Component types available for drafting. All figures shown are created by the program in listing 2.*



Figure 1: *Graphics Tablet menu. The bottom row is dedicated to plotting functions, while the second and third rows from the bottom contain component types to be plotted.*

Circle 402 on inquiry card.

TERMINALS FROM TRANSNET

PURCHASE PLAN • 12-24 MONTH FULL OWNERSHIP PLAN • 36 MONTH LEASE PLAN

	DESCRIPTION	PURCHASE PRICE	PER MONTH 12 MOS.	24 MOS.	36 MOS.
DEC	LA36DECwriter II	$1,095	$105	$ 58	$ 40
	LA34 DECwriter IV	995	95	53	36
	LA34 DECwriter IV Forms Ctrl.	1,095	105	58	40
	LA120 DECwriter III KSR	2,295	220	122	83
	LA120 DECwriter III RO	2,095	200	112	75
	VT100 CRT DECscope	1,595	153	85	58
	VT132 CRT DECscope	1,995	190	106	72
TEXAS INSTRUMENTS	TI745 Portable Terminal	1,595	153	85	58
	TI765 Bubble Memory Terminal	2,595	249	138	93
	TI Insight 10 Terminal	945	90	53	34
	TI785 Portable KSR, 120 CPS	2,395	230	128	86
	TI787 Portable KSR, 120 CPS	2,845	273	152	102
	TI810 RO Printer	1,895	182	102	69
	TI820 KSR Printer	2,195	211	117	80
DATAMEDIA	DT80/1 CRT Terminal	1,695	162	90	61
	DT80/5 APL CRT	2,095	200	112	75
	DT80/5L APL 15" CRT	2,295	220	122	83
LEAR SIEGLER	ADM3A CRT Terminal	875	84	47	32
	ADM31CRT Terminal	1,450	139	78	53
	ADM42 CRT Terminal	2,195	211	117	79
HAZELTINE	1420 CRT Terminal	945	91	51	34
	1500 CRT Terminal	1,095	105	58	40
	1552 CRT Terminal	1,295	125	70	48
TELEVIDEO	920 CRT Terminal	895	86	48	32
	950 CRT Terminal	1,075	103	57	39
NEC SPINWRITER	Letter Quality, 55/15 RO	2,895	278	154	104
	Letter Quality, 55/25 KSR	3,295	316	175	119
QUME	Letter Quality KSR, 55 CPS	3,395	326	181	123
	Letter Quality RO, 55 CPS	2,895	278	154	104
HEWLETT PACKARD	2621A CRT Terminal	1,595	153	85	58
	2621P CRT Terminal	2,750	263	154	99
CENTRONICS	730 Desk Top Printer	715	69	39	26
	737 W/P Desk Top Printer	895	86	48	32

FULL OWNERSHIP AFTER 12 OR 24 MONTHS • 10% PURCHASE OPTION AFTER 36 MONTHS

MICROCOMPUTERS—APPLE, COMMODORE, HP85, DEC LSI

ACCESSORIES AND PERIPHERAL EQUIPMENT

ACOUSTIC COUPLERS • MODEMS • THERMAL PAPER • RIBBONS • INTERFACE MODULES • FLOPPY DISK UNITS

TRANSNET CORPORATION
1945 ROUTE 22 • UNION, N.J. 07083 • (201) 688-7800
TWX 710-985-5485

Circle 221 on inquiry card.

Unlock the ENGINEERING POWER of the Microcomputer

Engineering Software for TRS-80 Mods I, II & III



- Air Cond. Com. Cooling/Heating Load
- Residential Cooling/Heating Load
- Structural Space Frame Analysis
- Fire Sprinkler System Design
- Lighting Design
- Air Duct Design
- Accounting
- Surveying
- Word Processing for Spec Writing
- Hydraulic Pipe Design
- Hardy Cross Water Analysis
- Electrical Fault Current
- Life Cycle Cost Analysis

WE HAVE SOLAR PROGRAMS

Selected programs also available for other microcomputers.

PLEASE TELL ME MORE ABOUT YOUR ENGINEERING PROGRAMS.

Name__________

Company__________ Phone__________

Address__________ B-7

City__________ State______ Zip__________

I am interested in __________

MC↑2 PROGRAMS™

McClintock Corp.
P.O. Box 430980
Miami, FL 33143
(305) 666-1300

RACET SORTS — RACET UTILITIES — RACET computes — RACET SORTS — RACET UTILITIES — RACET computes — RACET SORTS — RACET UTILITIES — RACET computes —

HARD DISK MULTIPLEXOR WITH 10 MEG HARD DISK FOR THE TRS-80* Mod II

NOW YOU CAN HAVE THAT LARGE COMMON DATA BASE!!

- Allows up to 4 Mod II's to connect to a single controller — up to 4 hard disk drives per controller. Users may access the same file simultaneously (first-come first-served).
- Uses Cameo controller and standard 10-megabyte cartridge (hard) disk drives along with RACET Hard/Soft Disk System (HSD) software.
- Access times 3 to 8 times faster than floppy. Mixed floppy/hard disk operation supported
- Compatible with your existing TRSDOS programs! All BASIC statements are identical.
- A single file may be as large as one disk. Alternate mode allows 24-million byte record range. Directory expandable to handle thousands of files.
- Includes special utilities — backup and copies, HPURGE for multiple deletions, HDCS directory catalog system, and Hard Disk Superzap. FORMAT utility includes options for specifying sectors/gran, platters/drive, logical disk size, etc.

HARD DISK DRIVE & CONTROLLER $5995 **RACET HSD Software $400**
Call for multiuser pricing. Dealers call for OEM pricing.

INFINITE BASIC (Mod I & III Tape or Disk) **Mod I $50.00, Mod III $60.00**
Extends Level II BASIC with complete MATRIX functions and 50 more string functions. Includes RACET machine language sorts! Sort 1000 elements in 9 seconds!! Select only functions you want to optimize memory usage.

INFINITE BUSINESS (Requires Infinite BASIC) **Mod I & III $30.00**
Complete printer pagination controls — auto headers, footers, page numbers. Packed decimal arithmetic — 127 digit accuracy +, −, *, /. Binary search of sorted and unsorted arrays. Hash codes.

BASIC CROSS REFERENCE UTILITY (Mod II 64K) **$50.00**
SEEK and FIND functions for Variables, Line Numbers, Strings, Keywords. 'All' options available for line numbers and variables. Load from BASIC — Call with 'CTRL'R. Output to screen or printer!

DSM **Mod I $75.00, Mod II $150.00, Mod III $90.00**
Disk Sort/Merge for RANDOM files. All machine language stand-alone package for sorting speed. Establish sort specification in simple BASIC command File. Execute from DOS. Only operator action to sort is to change diskettes when requested! Handles multiple diskette files! Super fast sort times — improved disk I/O times make this the fastest Disk Sort/Merge available on your TRS.
(Mod I Min 32K 2-drive system. Mod II 64K 1-drive. Mod III 32K 1-drive)

★★NEW★★ DISCAT (32K 1-drive Min) **Mod I, III $50.00**
This comprehensive Diskette Cataloguing/Indexing utility allows the user to keep track of thousands of programs in a categorized library. Machine language program works with all TRSDOS and NEWDOS versions. Files include program names and extensions, program length, diskette numbers, front and back, and diskette free space.

★★NEW★★
KFS-80 (1-drive 32K Min — Mod II 64K) **Mod I, III $100.00; Mod II $175.00**
The keyed file system provides keyed and sequential access to multiple files. Provides the programmer with a powerful disk handling facility for development of data base applications. Binary tree index system provides rapid access to file records.

★★NEW★★
MAILLIST (1-drive 32K Min - Mod II 64K) **Mod I, III $75.00; Mod II $150.00**
This ISAM-based maillist minimizes disk access times. Four keys — no separate sorting. Supports 9-digit zip code and 3-digit state code. Up to 30 attributes. Mask and query selection. Record access times under 4 seconds!!

★★NEW★★ LPSPOOL (32K 1-drive Min) **Mod I $75.00**
LPSPOOL — Add multi-tasking to permit concurrent printing while running your application program. The spooler and despooler obtain print jobs from queues maintained by the system as print files are generated. LPSPOOL supports both parallel and serial printers.

UTILITY PACKAGE (Mod II 64K) **$150.00**
Important enhancements to the Mod II. The file recovery capabilities alone will pay for the package in even one application! Fully documented in 124 page manual! XHIT, XGAT, XCOPY and SUPERZAP are used to reconstruct or recover date from bad diskettes! XCOPY provides multi-file copies, 'Wild-card' mask select, absolute sector mode and other features SUPERZAP allows examine/change any sector on diskette include track-0, and absolute disk backup/copy with I/O recovery. DCS builds consolidated directories from multiple diskettes into a single display or listing sorted by disk name or file name plus more. Change Disk ID with DISKID. XCREATE preallocates files and sets 'LOF' to end to speed disk accesses. DEBUGII adds single step, trace, subroutine calling, program looping, dynamic disassembly and more!!

DEVELOPMENT PACKAGE (Mod II 64K) **$125.00**
Includes RACET machine language SUPERZAP, Apparat Disassembler, and Model II interface to the Microsoft 'Editor Assembler Plus' software package including uploading services and patches for Disk I/O.

CHECK, VISA, M/C, C.O.D., PURCHASE ORDER
TELEPHONE ORDERS ACCEPTED (714) 637-5016
*TRS-80 IS A REGISTERED TRADEMARK OF TANDY CORPORATION

RACET COMPUTES
1330 N. Glassel, Suite 'M'
Orange, CA 92665

RACET SORTS — RACET UTILITIES — RACET computes — RACET SORTS — RACET UTILITIES — RACET computes — RACET SORTS — RACET UTILITIES — RACET computes —

Circle 333 on inquiry card.

CASE statements determines the function that is to be performed.

The procedures SAVESCREEN and LOADSCREEN can (with one or two minor alterations) be found in the Pascal Reference Manual in section 2.2.6.2 (untyped files). These procedures are used to save (or load) the Apple's HIRES display to (or from) a disk file. The disk files are sixteen blocks long (8 K bytes). HIRES image files are appended with .SCRN for the purpose of directory identification. I have considered compressing the data in order to save disk space, but unfortunately I haven't found a method that guarantees this result. I have tried various approaches, including counting the number of similar dots in succession. This works, but if there are more than 4 K changes (on-to-off, off-to-on) then the disk file exceeds sixteen blocks. (I'd be glad to hear any innovative ideas in this area.)

The procedures CONVERTFROM and CONVERTO are used to convert small integer values (between 0 and 16) to and from the boolean array USER3. The values that are stored are the plot offsets used by the "drawblock" statement in MYPLOT. The offset aligns the cursor with a specific point in the plot array. CONVERTO is called by SETUSR. SETUSR allows you to define two devices that are then saved on disk in the file USER.CHARSET, along with the offset information.

GETXY reads the tablet. When this routine is called, it loops around the external procedure READPAD until the pen is pushed down. It then sets the condition of VALIDXY and fixes the Y value. (The tablet's 0,0 is at the top left, Pascal's is the bottom left.)

The final routine that I will mention is PRINTOUT. PRINTOUT is decidedly implementation-dependent. My printer is a HyType I (old, slow, and occasionally reliable) with a serial interface, and it has a limited graphics capability. This limitation is primarily one of time: at 300 bps (bits per second) it takes about 1½ hours to print the screen; to generate a dot, I print "dot-space-space", and "space-space" for no dot. (See figure 2.) In order to increase the speed of this process, I look ahead at the beginning of each line, and stop after the last dot in the line. (I also try to avoid printing pictures with borders.)

The sequence of screens in photo 3 labeled "CMOS frequency doubler" gives you some idea of the ease of designing with this system. It took about 1½ minutes to reach the stage shown in photo 3. I then changed the



Figure 2: *Sample hard copy produced by HyType I with serial interface.*

(3a)



(3b)



(3c)



(3d)



(3e)



Photo 3: *Sequence of displays in an actual design project. Diagrams 3a thru 3c were created in less than two minutes, and the circuit was slightly changed in photo 3d. The finished product is shown in photo 3e.*

Photo 4: *Definition of nonstandard devices. Each component is composed of a 16 by 16 pixel array; two menu items allow users to draw their own components on the video screen.*

(4a)



(4b)



inverter to a NAND gate (used as an inverter) to minimize package count.

The tablet's command *set user* allows you to define two devices of your own choosing. These are plotted as USER1 and USER2. When the command is called, the text screen displays a blank 16 by 16 array (see photo 4). The array is filled by typing a space for a space and any alphanumeric character for a dot. The backspace key moves the cursor back, and the escape key aborts the command. After the last position in the array has been filled, the system asks for the coordinates of the cursor. This is the position that the cursor will be in when the array is plotted.

This program has all of the appearances of one that will grow forever. I already have several ideas for additions, and have had abundant input from friends. And although I have managed to resist the urge to modify long enough to write this article, now that it's done....Did I hear someone say, "Boolean equations as input, schematics as output"?■

Listing 2: *Apple Pascal program INITLOGIC for creating the components displayed on the video monitor.*

```
 1    1:D    1 (*$L PRINTER:*)
 1    1:D    1 (*$I PART1.SYMB.TEXT*)
 1    1:D    1 (*****************************************************************
 1    1:D    1 *                                                               *
 1    1:D    1 *        This program creates the file 'LOGIC.CHARSET'          *
 1    1:D    1 *        which is used by LOGICDESIGN. Each character           *
 1    1:D    1 *        is a 16 by 16 array (of boolean .. i.e. true           *
 1    1:D    1 *        or false .. 1 or 0).                                   *
 1    1:D    1 *                                                               *
 1    1:D    1 *        Dan Sokol - 2 Apr 80                                   *
 1    1:D    1 *                                                               *
 1    1:D    1 *****************************************************************)
 1    1:D    1 Program INITLOGIC;
```

Listing 2 continued on page 398

Circle 72 on inquiry card.

computer case company

comp case

• RS204

• AP101	Apple II with Single Disk Drive	$109
• AP102	Apple II with Double Disk Drives	119
• AP103	Apple II, 9 inch Monitor & Double Drives	129
• AP104	Apple ///, two additional Drives & Silentype	139
• AP105	12 inch monitor plus accessories	99
• RS201	TRS-80 Model I, Expansion Unit & Drives	109
• RS202	TRS-80 Monitor or TV set	84
• RS204	TRS-80 Model III	129
• RS205	Radio Shack Color Computer	89
• P401	Paper Tiger 440/445/460	99
• P402	Centronics 730/737 - Line Printer II/IV	89
• P403	Epson MX70 or MX80	89
• CC90	Matching Attaché Case	75

computer case company

5650 INDIAN MOUND CT. COLUMBUS, OHIO 43213 (614) 868-9464

MasterCard VISA

Circle 150 on inquiry card.

A is for Apple.



--And the first thing you should know about Apple is Farnsworth Computer Center for sales, service, instruction, easy access, --and one of the finest showrooms you will find.

Featuring now--
Apple II Plus w/48K
Disk Drive w/3.3
System Price $1795
List $2175

HP-41C
Reg. $250 Now $185

apple computer
Authorized Dealer

FARNSWORTH COMPUTER CENTER

1891 N. Farnsworth Ave. (at the E-W Tollway)
Aurora. Il. 60505 Ph. (312)851-3888
Weekdays 10-8; Sat. 10-5

ADD DISK DRIVES TO YOUR MODEL III AND MODEL I

VERBATIM • APPLE • TI • ANADEX

CENTRONICS • NEC • OKIDATA • EPSON

$599

(includes Disk Drive)

Fully compatible with Radio Shack's operating system TRSDOS.

- One, two, three, four drive configurations.
- 134K to over 1 Meg of storage
- 40 track and 80 track available
- 90 day warranty, 100% parts and labor
- Extended warranty available

Complete upgrade includes one mini-disk drive, power supply, controller, and mounting hardware. IMMEDIATE DELIVERY.

	OUR PRICE	RADIO SHACK	SAVINGS
Complete one drive kit	$599.	$849.	29%
Additional internal drive	265.	399.	34%
External drive	299.	499.	32%
80 track drives (inc. patch) add	195. ea.	N/A	
16K memory (required to use drives)	49.	119.	59%
Model III 32K w/VR Data two drive assembly	1812.	2380.	24%
RS232 Adapter Board	75.	99.	25%

WE DISCOUNT RADIO SHACK & OTHER COMPUTER PRODUCTS

To order call toll free (800) 345-8102, or (215) 461-5300 in PA.

$299*

We've broken through the three hundred dollar barrier.

- Fully compatible with TRSDOS™
- Fully compatible with RS Drives
- Easy plug-in installation
- Rigid extender board
- 90 day warranty — 100% parts and labor
- Extended warranty available — $45/year
- Choice of Tandon or MPI drives
- * Includes power supply, enclosure, single sided — 40tk drive and **EXTENDER BOARD**

1 sided 80 tk - $419   2 sided 40tk - $419
2 sided 80tk - $549

MONTHLY SPECIALS

Centronics 739	$750.00
Microline 80	$425.00
Lexicon Modem	$135.00

PRICES SUBJECT TO CHANGE WITHOUT NOTICE

PUBLISHED PRICE REFLECTS CASH DISCOUNT

VR Data, a manufacturer of innovative computer products, is known worldwide for quality, dependability and prompt, personal service since 1972.

VR Data corp

VISA master charge

VR Data Corporation • 777 Henderson Boulevard • Folcroft, PA 19032

Circle 421 on inquiry card.

Listing 2 continued:

```
 1    1:D    3
 1    1:D    3 type SHAPE = packed array [0..15,0..15] of boolean;
 1    1:D    3
 1    1:D    3 var INVERTER,NAND,NOR,ORGATE,ANDGATE,DTOP,DBOT,JKTOP,JKBOT,BUFFER,GND,PLUS5,
 1    1:D    3     MSITOP,MSIBOT,INV,INTHING,OUT,DOT,CAP,RESISTOR,XOR,XNOR,HCAP,DIODE,SW,BAT,
 1    1:D    3     MINIDIP,HDIODE,OPAMP,NPN,PNP,MINIDIP,HMSIL,HMSIR,XTAL,WIPER,ZENER,
 1    1:D    3     LCOIL,RCOIL,VRESIST,USER1,USER2,USER3 : SHAPE;
 1    1:D  691
 1    1:D  691     USERFILE,SHAPEFILE : file of SHAPE;
 1    1:D 1323
 1    1:D 1323     I,J,ROW : integer;
 1    1:D 1326
 1    1:D 1326     BIT : boolean;
 1    1:D 1327
 1    1:D 1327
 1    1:D 1327
 1    1:D 1327 (***************  MAKESHAPES  ***********************************
 1    1:D 1327 *                                                                *
 1    1:D 1327 *       Converts strings to boolean arrays.                      *
 1    1:D 1327 *       This procedure is borrowed from GRAFDEMO.TEXT            *
 1    1:D 1327 *       on APPLE3:                                               *
 1    1:D 1327 *                                                                *
 1    1:D 1327 *       Called from : INIT1 thru INIT10.                         *
 1    1:D 1327 *                                                                *
 1    1:D 1327 ****************************************************************)
 1    2:D    1 procedure MAKESHAPES(var BITMAP:shape;ST:string);
 1    2:0    0         begin
 1    2:1    0          for J:=1 to length(ST) do
 1    2:2   23           begin
 1    2:3   23             BIT:=(ST[J]<>' ');
 1    2:3   35             BITMAP[ROW,J-1]:=BIT;
 1    2:2   59           end;
 1    2:1   69          ROW:=ROW-1;
 1    2:0   77        end;
 1    2:0   92
 1    2:0   92 (*$P*)
 1    2:0   92 (***************  SAVESHAPES  ***********************************
 1    2:0   92 *                                                                *
 1    2:0   92 *       Saves the ARRAYS in a disk file.                         *
 1    2:0   92 *                                                                *
 1    2:0   92 *       Called from : Main program loop.                         *
 1    2:0   92 *                                                                *
 1    2:0   92 ****************************************************************)
 1    3:D    1 procedure SAVESHAPES;
 1    3:0    0         begin
 1    3:1    0           rewrite(SHAPEFILE,'LOGIC.CHARSET');
 1    3:1   26           SHAPEFILE^:=INVERTER; put(SHAPEFILE);
 1    3:1   42           SHAPEFILE^:=NAND; put(SHAPEFILE);
 1    3:1   58           SHAPEFILE^:=NOR; put(SHAPEFILE);
 1    3:1   74           SHAPEFILE^:=ORGATE; put(SHAPEFILE);
 1    3:1   90           SHAPEFILE^:=ANDGATE; put(SHAPEFILE);
 1    3:1  106           SHAPEFILE^:=DTOP; put(SHAPEFILE);
 1    3:1  122           SHAPEFILE^:=DBOT; put(SHAPEFILE);
 1    3:1  138           SHAPEFILE^:=JKTOP; put(SHAPEFILE);
 1    3:1  154           SHAPEFILE^:=JKBOT; put(SHAPEFILE);
 1    3:1  170           SHAPEFILE^:=BUFFER; put(SHAPEFILE);
 1    3:1  186           SHAPEFILE^:=GND; put(SHAPEFILE);
 1    3:1  202           SHAPEFILE^:=PLUS5; put(SHAPEFILE);
 1    3:1  218           SHAPEFILE^:=MSITOP; put(SHAPEFILE);
 1    3:1  234           SHAPEFILE^:=MSIBOT; put(SHAPEFILE);
 1    3:1  250           SHAPEFILE^:=INV; put(SHAPEFILE);
 1    3:1  266           SHAPEFILE^:=INTHING; put(SHAPEFILE);
 1    3:1  282           SHAPEFILE^:=OUT; put(SHAPEFILE);
 1    3:1  298           SHAPEFILE^:=DOT; put(SHAPEFILE);
 1    3:1  314           SHAPEFILE^:=CAP; put(SHAPEFILE);
 1    3:1  330           SHAPEFILE^:=RESISTOR; put(SHAPEFILE);
 1    3:1  346           SHAPEFILE^:=XOR; put(SHAPEFILE);
 1    3:1  362           SHAPEFILE^:=XNOR; put(SHAPEFILE);
 1    3:1  378           SHAPEFILE^:=HCAP; put(SHAPEFILE);
 1    3:1  394           SHAPEFILE^:=DIODE; put(SHAPEFILE);
 1    3:1  410           SHAPEFILE^:=HDIODE; put(SHAPEFILE);
 1    3:1  426           SHAPEFILE^:=OPAMP; put(SHAPEFILE);
 1    3:1  442           SHAPEFILE^:=NPN; put(SHAPEFILE);
 1    3:1  458           SHAPEFILE^:=PNP; put(SHAPEFILE);
 1    3:1  474           SHAPEFILE^:=BAT; put(SHAPEFILE);
 1    3:1  490           SHAPEFILE^:=SW; put(SHAPEFILE);
 1    3:1  506           SHAPEFILE^:=MINIDIP; put(SHAPEFILE);
 1    3:1  522           SHAPEFILE^:=HMSIL; put(SHAPEFILE);
 1    3:1  538           SHAPEFILE^:=HMSIR; put(SHAPEFILE);
 1    3:1  554           SHAPEFILE^:=XTAL; put(SHAPEFILE);
```

Listing 2 continued on page 400

Circle 116 on inquiry card.

To further improve service to our customers we have installed a toll-free WATS line in our Peterborough, New Hampshire office. If you would like to order a subscription to BYTE, or if you have a question related to a BYTE subscription, you are invited to call* (800)258-5485 between 8:00 AM and 4:30 PM Eastern Time. (Friday 8 AM - Noon). *Calls from continental U.S. only.

BYTE's Toll-free Subscriber W.A.T.S. Line

(800) 258-5485

We thank you and look forward to serving you.

9178

MAPS®
Multi-Application Processing System



THREE COMPUTERS IN ONE!

THE DIGIAC MAPS® CT-80 SYSTEM

Multi-User, Multi-Tasking, Cost Effective.

• **3 business systems can run concurrently - that's 3 times the overall system productivity!** • Time share word processing, accounting, order processing, inventory, forms processing, billing & more! • 3 workstations can share data base - preparations can be done by several operators concurrently! • All workstations can share common peripherals. • Uses DIGIAC MAPS-80 operating system. (Digital Research MP/M) • High level language processors including Fortran - Basic - Pascal - Cobol. • Complete Turn-key system for ease of operation & learning!

DIGIAC® CORPORATION

For Additional Information Contact:
MAPS, Commercial Products Division of:
DIGIAC CORPORATION
175 Engineers Road, Smithtown, N.Y. 11787
Phone: (516) 273-8600

MP/M is a trademark of Digital Research Corp.

Introducing... The all NEW Printer from DigiTec®

6400 SERIES features:
Low Cost – $299 in 100 Quantities
Expanded Warranty – 1 Full Year
Compact Size – 7.38"W x 3.08"H x 6.12"D. WT 3-1/2 LBS

- Selectable serial RS-232-C/20 mA current loop or 8-bit parallel interface
- Selectable baud rates 110, 300, 600 or 1200
- Parallel-data rates in excess of 2000 characters per second
- 21 characters per line (optional 32 characters)
- 36 character input buffer
- Electrosensitive or thermal printing
- 5 x 7 Dot Matrix, 64 character ASCII Code
- Boldface characters for emphasis



$299
in 100 quantities
$399 list

Circle 411 for demonstration only
Circle 439 for more information

DigiTec. UNITED SYSTEMS CORPORATION
918 Woodley Road, Dayton, Ohio 45403
(513) 254-6251, TWX (810) 459-1728

Listing 2 continued:

```
1   3:1   570           SHAPEFILE^:=WIPER; put(SHAPEFILE);
1   3:1   585           SHAPEFILE^:=ZENER; put(SHAPEFILE);
1   3:1   600           SHAPEFILE^:=LCOIL; put(SHAPEFILE);
1   3:1   615           SHAPEFILE^:=RCOIL; put(SHAPEFILE);
1   3:1   630           SHAPEFILE^:=VRESIST; put(SHAPEFILE);
1   3:1   645           close(SHAPEFILE,lock);            (* create dummy userfile *)
1   3:1   654           rewrite(USERFILE,'USER.CHARSET');
1   3:1   679           USERFILE^:=USER1; put(USERFILE);
1   3:1   694           USERFILE^:=USER2; put(USERFILE);
1   3:1   709           USERFILE^:=USER3; put(USERFILE);
1   3:1   724           close(USERFILE,lock);
1   3:0   733         end;
1   3:0   746 (*$P*)
1   3:0   746 (***************  INIT1  ****************************************
1   3:0   746 *                                                               *
1   3:0   746 *       Creates arrays from strings.                            *
1   3:0   746 *                                                               *
1   3:0   746 *       Called from : Main program loop.                        *
1   3:0   746 *                                                               *
1   3:0   746 ***************************************************************)
1   4:D     1 procedure INIT1;
1   4:0     0           begin
1   4:1     0             write('.');
1   4:1    10             ROW:=15;
1   4:1    14             MAKESHAPES(INV,' XX             ');
1   4:1    38             MAKESHAPES(INV,'X  X            ');
1   4:1    62             MAKESHAPES(INV,'X  X            ');
1   4:1    86             MAKESHAPES(INV,' XX             ');
1   4:1   110             for I:=1 to 12 do
1   4:2   124             MAKESHAPES(INV,'                ');
1   4:1   158             ROW:=15;
1   4:1   162             MAKESHAPES(INVERTER,'X               ');
1   4:1   186             MAKESHAPES(INVERTER,'XX              ');
1   4:1   210             MAKESHAPES(INVERTER,'X X             ');
1   4:1   234             MAKESHAPES(INVERTER,'X  X            ');
1   4:1   258             MAKESHAPES(INVERTER,'X    X XX       ');
1   4:1   282             MAKESHAPES(INVERTER,'X     X  X      ');
1   4:1   306             MAKESHAPES(INVERTER,'X    X XX       ');
```

Listing 2 continued on page 402

Circle 165 on inquiry card.

HappyHands

Offers Discounts on All

TRS-80™ COMPUTERS

Call Collect For Prices
And Shipping Schedules
505-257-7865
or write
HAPPY HANDS
P.O. DRAWER I
RUIDOSO, NEW MEXICO
88345

We Have What You Are Looking For

- ☐ PROMPT SHIPPING
- ☐ AVAILABLE SERVICE CONTRACTS
- ☐ DISCOUNTED PRICES COMPARABLE TO ANY OTHERS
- ☐ NO TAX ON OUT OF STATE SHIPMENTS

Circle 263 on inquiry card.

BUY COMPUTERS BY MAIL ORDER AND SAVE 16%

APPLE HARDWARE

48K	$1,199.00
Disk with Controller	$ 540.00
Disk	$ 440.00
Pascal	$ 445.00
Graphics Tablet	$ 655.00
Versawriter Digitizer System	$ 215.00

ATARI 800 16K $ 775.00

PRINTERS

TI Basic Serial	$1,495.00
Epson MX-80	CALL
Centronics 737 Parallel	$ 719.00
IDS 560	$1,395.00

TERMINALS

Zenith Z-19	$ 789.00
Soroc IQ120	$ 729.00
Televideo 950	$ 989.00
Televideo 920C	$ 759.00
Televideo 912C	$ 729.00
ADDS Viewpoint	$ 589.00

SOFTWARE

Superbrain Double Density 64K	$2,650.00
Quad Density 64K	$2,977.00

NORTHSTAR

Horizon-2-64 QD $3,350.00

VERBATIM & MEMOREX

5¼" $ 27.50

MONITORS

Leedex 12" B&W	$ 138.00
12" GP	$ 152.00

Send certified check (regular checks require 2 weeks to clear) or charge to VISA or Master Charge. Customer pays shipping.

MIRO COMPUTERS, INC.

27 Long Meadow Place South Setauket, L.I., N.Y. 11720
(516) 423-7955 CALL MON.-SAT., 10AM-6PM



VIP's Call A.E.I.

VIP's customarily need top quality and service within stringent budgetary limits. Naturally, they call A.E.I.

...For software, firmware, or hardware; For custom systems assistance, connectors, interface boards and service; For peripherals, including printers, CR 's, disc drives, or modems; For as little as one part such as a cable or connector, or as much as an entire national computer complex for a multi-branch company.

Item: A.E.I. tests virtually every* item sold, before shipping.

Item: A.E.I. initializes every piece of software, and makes a copy. If you have a problem, A.E.I. can check to locate the problem by using the in-house duplicate, saving you time.

Item: A.E.I. has in-house expertise on every item offered.

Item: A.E.I. prices are competitive with the lowest, no-service, no in-house expertise dealer.

40% OF ALL A.E.I. SALES ARE TO PUBLIC AND SEMI-PUBLIC INSTITUTIONS.

A partial list** of A.E.I. customers who purchased during the last quarter of 1980 includes: University of Nebraska, University of Virginia, U.S. Dept. of Interior, University of Kentucky, University of California, Massachusetts Institute of Technology, U.S. Air Force, Naval Air Development Center, Brown University, University of Oregon, University of Utah, Ohio State University, University of Southern California, California State Dept. of Water Resources, University of Michigan, and Princeton University.

In the private sector, an equal number of major national organizations purchased during the same period.

You can call A.E.I. too!

*With our normal fast shipping, we have time to test; expedited shipment may preclude testing.

**A.E.I. does not wish to imply that any of these fine organizations endorse A.E.I., merely that A.E.I. is proud to have them as customers.

Automated Equipment, Inc.
18430 Ward Street, Fountain Valley, California 92708 (714) 964-7514 (Outside of California (800) 854-7635)

Communication Arts, Huntington Beach, Ca.

Circle 39 on inquiry card.

```
1  4:1    330              MAKESHAPES(INVERTER,'X  X            ');
1  4:1    354              MAKESHAPES(INVERTER,'X X             ');
1  4:1    378              MAKESHAPES(INVERTER,'XX              ');
1  4:1    402              MAKESHAPES(INVERTER,'X               ');
1  4:1    426              for I:=1 to 5 do
1  4:2    440              MAKESHAPES(INVERTER,'                ');
1  4:1    474              ROW:=15;
1  4:1    478              MAKESHAPES(ORGATE,'XXXX            ');
1  4:1    502              MAKESHAPES(ORGATE,' X  XX          ');
1  4:1    526              MAKESHAPES(ORGATE,'  X   XX        ');
1  4:1    550              MAKESHAPES(ORGATE,'   X    X       ');
1  4:1    574              MAKESHAPES(ORGATE,'   X     X      ');
1  4:1    598              MAKESHAPES(ORGATE,'   X     X      ');
1  4:1    622              MAKESHAPES(ORGATE,'   X     X      ');
1  4:1    646              MAKESHAPES(ORGATE,'   X    X       ');
1  4:1    670              MAKESHAPES(ORGATE,'  X   XX        ');
1  4:1    694              MAKESHAPES(ORGATE,' X  XX          ');
1  4:1    718              MAKESHAPES(ORGATE,'XXXX            ');
1  4:1    742              for I:=1 to 5 do
1  4:2    756              MAKESHAPES(ORGATE,'                ');
1  4:1    790              ROW:=15;
1  4:1    794              MAKESHAPES(NOR,'XXXX            ');
1  4:1    818              MAKESHAPES(NOR,' X  XX          ');
1  4:1    842              MAKESHAPES(NOR,'  X   XX        ');
1  4:1    866              MAKESHAPES(NOR,'   X    X       ');
1  4:1    890              MAKESHAPES(NOR,'   X      XX    ');
1  4:1    914              MAKESHAPES(NOR,'   X     X  X   ');
1  4:1    938              MAKESHAPES(NOR,'   X      XX    ');
1  4:1    962              MAKESHAPES(NOR,'   X    X       ');
1  4:1    986              MAKESHAPES(NOR,'  X   XX        ');
1  4:1   1010              MAKESHAPES(NOR,' X  XX          ');
1  4:1   1034              MAKESHAPES(NOR,'XXXX            ');
1  4:1   1058              for I:=1 to 5 do
1  4:2   1072              MAKESHAPES(NOR,'                ');
1  4:0   1106            end;
1  4:0   1126  (*$P*)
1  4:0   1126  (***************  INIT2  ****************************************
1  4:0   1126  *                                                               *
1  4:0   1126  *       Creates arrays from strings.                            *
1  4:0   1126  *                                                               *
1  4:0   1126  *       Called from : Main program loop.                        *
1  4:0   1126  *                                                               *
1  4:0   1126  ***************************************************************)
1  5:D      1  procedure INIT2;
1  5:0      0            begin
1  5:1      0              write('.');
1  5:1     10              ROW:=15;
1  5:1     14              MAKESHAPES(XOR,'X  XXXX         ');
1  5:1     38              MAKESHAPES(XOR,' X  X  XX       ');
1  5:1     62              MAKESHAPES(XOR,'  X  X   XX     ');
1  5:1     86              MAKESHAPES(XOR,'   X  X    X    ');
1  5:1    110              MAKESHAPES(XOR,'   X  X     X   ');
1  5:1    134              MAKESHAPES(XOR,'   X  X     X   ');
1  5:1    158              MAKESHAPES(XOR,'   X  X     X   ');
1  5:1    182              MAKESHAPES(XOR,'   X  X    X    ');
1  5:1    206              MAKESHAPES(XOR,'  X  X   XX     ');
1  5:1    230              MAKESHAPES(XOR,' X  X  XX       ');
1  5:1    254              MAKESHAPES(XOR,'X  XXXX         ');
1  5:1    278              for I:=1 to 5 do
1  5:2    292              MAKESHAPES(XOR,'                ');
1  5:1    326              ROW:=15;
1  5:1    330              MAKESHAPES(XNOR,'X  XXXX         ');
1  5:1    354              MAKESHAPES(XNOR,' X  X  XX       ');
1  5:1    378              MAKESHAPES(XNOR,'  X  X   XX     ');
1  5:1    402              MAKESHAPES(XNOR,'   X  X    X    ');
1  5:1    426              MAKESHAPES(XNOR,'   X  X      XX ');
1  5:1    450              MAKESHAPES(XNOR,'   X  X     X  X');
1  5:1    474              MAKESHAPES(XNOR,'   X  X      XX ');
1  5:1    498              MAKESHAPES(XNOR,'   X  X    X    ');
1  5:1    522              MAKESHAPES(XNOR,'  X  X   XX     ');
1  5:1    546              MAKESHAPES(XNOR,' X  X  XX       ');
1  5:1    570              MAKESHAPES(XNOR,'X  XXXX         ');
1  5:1    594              for I:=1 to 5 do
1  5:2    608              MAKESHAPES(XNOR,'                ');
1  5:1    642              ROW:=15;
1  5:1    646              MAKESHAPES(NAND,'XXXX            ');
1  5:1    670              MAKESHAPES(NAND,'X   XX          ');
1  5:1    694              MAKESHAPES(NAND,'X     XX        ');
1  5:1    718              MAKESHAPES(NAND,'X       X       ');
1  5:1    742              MAKESHAPES(NAND,'X         XX    ');
1  5:1    766              MAKESHAPES(NAND,'X        X  X   ');
1  5:1    790              MAKESHAPES(NAND,'X         XX    ');
1  5:1    814              MAKESHAPES(NAND,'X       X       ');
1  5:1    838              MAKESHAPES(NAND,'X     XX        ');
1  5:1    862              MAKESHAPES(NAND,'X   XX          ');
```

Listing 2 continued on page 404

Circle 181 on inquiry card.

LOWEST PRICES 16K S100 STATIC RAM

RAM 16 $179.

BY COMPUTER SYSTEM RESOURCES



- Expandable to ½ million byte system.
- 4 MHZ operation with no wait states
- Addressable in 4K steps
- 1K segment disable for ROMs, etc.
- Exclusive memory protect feature

1 YEAR FACTORY WARRANTY
SATISFACTION GUARANTEED OR MONEYREFUNDED

RAM 65 $189.

BY COMPUTER SYSTEM RESOURCES



- Expandable to 16 million byte system
- I/O port bank select
- Ideal for multi-user systems
- 4 MHZ operation with no wait states
- Plus all of the RAM 16 features

7131 OWENSMOUTH AVE. / #21D
CANOGA PARK, CALIFORNIA 91303
213 / **883-3244**

INNOVATIVE PRODUCTS

Circle 344 on inquiry card.

CATCH THE S-100 INC. BUS!



Spectacular Savings — July only.

Deduct an extra 5% from our already low prices for all prepaid orders.

We will be closed from July 25th until August 10, 1981.

Watch our August ad for a special announcement.

Subject to Available Quantities • Prices Quoted Include Cash Discounts.
Shipping & Insurance Extra.

We carry all major lines such as
S.D. Systems, Cromemco, Ithaca Intersystems, North Star, Sanyo, ECT, TEI, Godbout, Thinker Toys, SSM, Tarbell, Tecmar, Central Data, Micropro Int'l, Scion, CCS, Shugart.

S-100, inc.
7 White Place, Clark, N.J. 07066
201-382-1318
Hours: Mon. - Fri. — 10 a.m. to 6 p.m.

MULTI-USER MULTI-SYSTEM



A PROFESSIONAL MICROCOMPUTER

All the features, power, and capacity your professional system will require.

- Hard and flexible disks and streamer tape.
- **EXO/NET** multi-user, multi-system network.
- CP/M,® MP/M® operating systems.
- Simultaneous high speed and letter quality printing.

® CP/M and MP/M are registered trademarks of Digital Research, Inc.

EXO ™ EXO SYSTEMS CORPORATION

Circle 148 on inquiry card

1089 AIRPORT ROAD, MINDEN, NEVADA 89423 –(702) 782-8166
TELEX: 18149 WEST LSA "ATT: EXO"

Circle 148 on Inquiry card.

TRS-80®

DISCOUNT PRICING

Call Us

For Discount Prices on All Radio Shack Hardware and Software



MODEL II 26-4002 **$3,439.00**

MODEL III 26-1063 **$2,220.00**

PHONE (209) 526-1475

We Pay Freight

No Taxes on Out of State Shipments

Franchise Store 7079

Circle 334 on inquiry card.

Radio Shack
221 McHenry Ave.
Modesto, Calif. 95354

Listing 2 continued:

```
1    5:1   886          MAKESHAPES(NAND,'XXXX               ');
1    5:1   910          for I:=1 to 5 do
1    5:2   924          MAKESHAPES(NAND,'                   ');
1    5:0   958        end;
1    5:0   976
1    5:0   976 (*$P*)
1    5:0   976 (***************  INIT3  *****************************************
1    5:0   976 *                                                               *
1    5:0   976 *       Creates arrays from strings.                            *
1    5:0   976 *                                                               *
1    5:0   976 *       Called from : Main program loop.                        *
1    5:0   976 *                                                               *
1    5:0   976 ****************************************************************)
1    6:D     1 procedure INIT3;
1    6:0     0          begin
1    6:1     0            write('.');
1    6:1    10            ROW:=15;
1    6:1    14            MAKESHAPES(ANDGATE,'XXXX           ');
1    6:1    38            MAKESHAPES(ANDGATE,'X  XX          ');
1    6:1    62            MAKESHAPES(ANDGATE,'X    XX        ');
1    6:1    86            MAKESHAPES(ANDGATE,'X      X       ');
1    6:1   110            MAKESHAPES(ANDGATE,'X       X      ');
1    6:1   134            MAKESHAPES(ANDGATE,'X       X      ');
1    6:1   158            MAKESHAPES(ANDGATE,'X       X      ');
1    6:1   182            MAKESHAPES(ANDGATE,'X      X       ');
1    6:1   206            MAKESHAPES(ANDGATE,'X    XX        ');
1    6:1   230            MAKESHAPES(ANDGATE,'X  XX          ');
1    6:1   254            MAKESHAPES(ANDGATE,'XXXX           ');
1    6:1   278            for I:=1 to 5 do
1    6:2   292            MAKESHAPES(ANDGATE,'               ');
1    6:1   326            ROW:=15;
1    6:1   330            MAKESHAPES(BUFFER,'X              ');
1    6:1   354            MAKESHAPES(BUFFER,'XX             ');
1    6:1   378            MAKESHAPES(BUFFER,'X X            ');
1    6:1   402            MAKESHAPES(BUFFER,'X  X           ');
1    6:1   426            MAKESHAPES(BUFFER,'X   X          ');
1    6:1   450            MAKESHAPES(BUFFER,'X    X         ');
1    6:1   474            MAKESHAPES(BUFFER,'X     XXXXX    ');
1    6:1   498            MAKESHAPES(BUFFER,'X    X         ');
1    6:1   522            MAKESHAPES(BUFFER,'X   X          ');
1    6:1   546            MAKESHAPES(BUFFER,'X  XX          ');
1    6:1   570            MAKESHAPES(BUFFER,'X X X          ');
1    6:1   594            MAKESHAPES(BUFFER,'XX  X          ');
1    6:1   618            MAKESHAPES(BUFFER,'X   X          ');
1    6:1   642            MAKESHAPES(BUFFER,'    X          ');
1    6:1   666            MAKESHAPES(BUFFER,'               ');
1    6:1   690            MAKESHAPES(BUFFER,'               ');
1    6:1   714            ROW:=15;
1    6:1   718            MAKESHAPES(RESISTOR,' X   X   X     ');
1    6:1   742            MAKESHAPES(RESISTOR,'XX X X X X X XXX');
1    6:1   766            MAKESHAPES(RESISTOR,'   X   X   X   ');
1    6:1   790            for I:=1 to 13 do
1    6:2   804            MAKESHAPES(RESISTOR,'               ');
1    6:1   838            ROW:=15;
1    6:1   842            for I:=1 to 5 do
1    6:2   856            MAKESHAPES(GND,'   X           ');
1    6:1   890            MAKESHAPES(GND,'XXXXXXX        ');
1    6:1   914            MAKESHAPES(GND,'               ');
1    6:1   938            MAKESHAPES(GND,' XXXXX         ');
1    6:1   962            MAKESHAPES(GND,'               ');
1    6:1   986            MAKESHAPES(GND,'  XXX          ');
1    6:1  1010            for I:=1 to 6 do
1    6:2  1024            MAKESHAPES(GND,'               ');
1    6:0  1058          end;
1    6:0  1078 (*$P*)
1    6:0  1078 (***************  INIT4  *****************************************
1    6:0  1078 *                                                               *
1    6:0  1078 *       Creates arrays from strings.                            *
1    6:0  1078 *                                                               *
1    6:0  1078 *       Called from : Main program loop.                        *
1    6:0  1078 *                                                               *
1    6:0  1078 ****************************************************************)
1    7:D     1 procedure INIT4;
1    7:0     0          begin
1    7:1     0            write('.');
1    7:1    10            ROW:=15;
1    7:1    14            MAKESHAPES(PLUS5,' XXX      XXX  ');
1    7:1    38            MAKESHAPES(PLUS5,'XXXXX  X  X    ');
1    7:1    62            MAKESHAPES(PLUS5,'XXXXX XXX XXX  ');
1    7:1    86            MAKESHAPES(PLUS5,' XXX   X    X  ');
1    7:1   110            MAKESHAPES(PLUS5,'  X       XXX  ');
1    7:1   134            for I:=1 to 5 do
1    7:2   148            MAKESHAPES(PLUS5,'  X            ');
1    7:1   182            for I:=1 to 6 do
1    7:2   196            MAKESHAPES(PLUS5,'               ');
```

Listing 2 continued on page 406

Listing 2 continued:

```
1    7:1    230              ROW:=15;
1    7:1    234              for I:=1 to 4 do
1    7:2    248              MAKESHAPES(CAP,'   X            ');
1    7:1    282              MAKESHAPES(CAP,'XXXXXXX         ');
1    7:1    306              MAKESHAPES(CAP,'                ');
1    7:1    330              MAKESHAPES(CAP,'                ');
1    7:1    354              MAKESHAPES(CAP,'XXXXXXX         ');
1    7:1    378              for I:=1 to 4 do
1    7:2    392              MAKESHAPES(CAP,'   X            ');
1    7:1    426              for I:=1 to 4 do
1    7:2    440              MAKESHAPES(CAP,'                ');
1    7:1    474              ROW:=15;
1    7:1    478              MAKESHAPES(DOT,' XX             ');
1    7:1    502              MAKESHAPES(DOT,'XXXX            ');
1    7:1    526              MAKESHAPES(DOT,'XXXX            ');
1    7:1    550              MAKESHAPES(DOT,' XX             ');
1    7:1    574              for I:=1 to 12 do
1    7:2    588              MAKESHAPES(DOT,'                ');
1    7:1    622              ROW:=15;
1    7:1    626              MAKESHAPES(INTHING,'X               ');
1    7:1    650              MAKESHAPES(INTHING,' X              ');
1    7:1    674              MAKESHAPES(INTHING,'  X             ');
1    7:1    698              MAKESHAPES(INTHING,'   XXXX         ');
1    7:1    722              MAKESHAPES(INTHING,'  X             ');
1    7:1    746              MAKESHAPES(INTHING,' X              ');
1    7:1    770              MAKESHAPES(INTHING,'X               ');
1    7:1    794              for I:=1 to 9 do
1    7:2    808              MAKESHAPES(INTHING,'                ');
1    7:0    842            end;
1    7:0    868 (*$P*)
1    7:0    868 (***************  INIT5  ****************************************
1    7:0    868 *                                                                *
1    7:0    868 *       Creates arrays from strings.                             *
1    7:0    868 *                                                                *
1    7:0    868 *       Called from : Main program loop.                         *
1    7:0    868 *                                                                *
1    7:0    868 *****************************************************************)
1    8:D      1 procedure INIT5;
1    8:0      0            begin
1    8:1      0              write('.');
1    8:1     10              ROW:=15;
1    8:1     14              MAKESHAPES(OUT,'  X             ');
1    8:1     38              MAKESHAPES(OUT,'   X            ');
1    8:1     62              MAKESHAPES(OUT,'    X           ');
1    8:1     86              MAKESHAPES(OUT,'XXXXXX          ');
1    8:1    110              MAKESHAPES(OUT,'    X           ');
1    8:1    134              MAKESHAPES(OUT,'   X            ');
1    8:1    158              MAKESHAPES(OUT,'  X             ');
1    8:1    182              for I:=1 to 9 do
1    8:2    196              MAKESHAPES(OUT,'                ');
1    8:1    230              ROW:=15;
1    8:1    234              MAKESHAPES(MSITOP,'XXXXXXXXXXXXXXXX');
1    8:1    258              for I:=1 to 15 do
1    8:2    272              MAKESHAPES(MSITOP,'X              X');
1    8:1    306              ROW:=15;
1    8:1    310              for I:=1 to 15 do
1    8:2    324              MAKESHAPES(MSIBOT,'X              X');
1    8:1    358              MAKESHAPES(MSIBOT,'XXXXXXXXXXXXXXXX');
1    8:1    382              ROW:=15;
1    8:1    386              MAKESHAPES(JKTOP,'         XX     ');
1    8:1    410              MAKESHAPES(JKTOP,'        X  X    ');
1    8:1    434              MAKESHAPES(JKTOP,'         XX     ');
1    8:1    458              MAKESHAPES(JKTOP,'    XXXXXXXXXXXX');
1    8:1    482              MAKESHAPES(JKTOP,'    X          X');
1    8:1    506              MAKESHAPES(JKTOP,'    X          X');
1    8:1    530              MAKESHAPES(JKTOP,'    X      XX  X');
1    8:1    554              MAKESHAPES(JKTOP,'    X  X  X  X X');
1    8:1    578              MAKESHAPES(JKTOP,'XXXXX  X  X  X X');
1    8:1    602              MAKESHAPES(JKTOP,'    XX X  X XX X');
1    8:1    626              MAKESHAPES(JKTOP,'    X X    XXX X');
1    8:1    650              for I:=1 to 3 do
1    8:2    664              MAKESHAPES(JKTOP,'    X          X');
1    8:1    698              MAKESHAPES(JKTOP,' XX X          X');
1    8:1    722              MAKESHAPES(JKTOP,'X  XX          X');
1    8:1    746              ROW:=15;
1    8:1    750              MAKESHAPES(JKBOT,'X  XX          X');
1    8:1    774              MAKESHAPES(JKBOT,' XX X          X');
1    8:1    798              MAKESHAPES(JKBOT,'    X          X');
1    8:1    822              MAKESHAPES(JKBOT,'    X     XXXX X');
1    8:1    846              MAKESHAPES(JKBOT,'    X          X');
1    8:1    870              MAKESHAPES(JKBOT,'    X      XX  X');
1    8:1    894              MAKESHAPES(JKBOT,'    X X X X  X X');
1    8:1    918              MAKESHAPES(JKBOT,'XXXXX XX  X  X X');
1    8:1    942              MAKESHAPES(JKBOT,'    X X X X XX X');
```

Listing 2 continued on page 408

Listing 2 continued:

```
1     8:1    966              MAKESHAPES(JKBOT,'     X X   X XXX  X');
1     8:1    990              MAKESHAPES(JKBOT,'     X            X');
1     8:1   1014              MAKESHAPES(JKBOT,'     X            X');
1     8:1   1038              MAKESHAPES(JKBOT,'     XXXXXXXXXXXX');
1     8:1   1062              MAKESHAPES(JKBOT,'          XX       ');
1     8:1   1086              MAKESHAPES(JKBOT,'         X  X      ');
1     8:1   1110              MAKESHAPES(JKBOT,'          XX       ');
1     8:0   1134            end;
1     8:0   1154 (*$I PART1.SYMB.TEXT*)
1     8:0   1154 (*$I PART2.SYMB.TEXT*)
1     8:0   1154 (*$P*)
1     8:0   1154 (****************   INIT6   ********************************
1     8:0   1154 *                                                          *
1     8:0   1154 *       Creates arrays from strings.                       *
1     8:0   1154 *                                                          *
1     8:0   1154 *       Called from : Main program.                        *
1     8:0   1154 *                                                          *
1     8:0   1154 **********************************************************)
1     9:D      1 procedure INIT6;
1     9:0      0            begin
1     9:1      0              write('.');
1     9:1     10              ROW:=15;
1     9:1     14              MAKESHAPES(DTOP,'         XX      ');
1     9:1     38              MAKESHAPES(DTOP,'        X  X     ');
1     9:1     62              MAKESHAPES(DTOP,'         XX      ');
1     9:1     86              MAKESHAPES(DTOP,'  XXXXXXXXXXXXXX');
1     9:1    110              for I:=1 to 3 do
1     9:2    124              MAKESHAPES(DTOP,'  X             X');
1     9:1    158              MAKESHAPES(DTOP,'  X          XX  X');
1     9:1    182              MAKESHAPES(DTOP,'  X         X  X X');
1     9:1    206              MAKESHAPES(DTOP,'  X XX      X  X X');
1     9:1    230              MAKESHAPES(DTOP,'  X X X     X XX X');
1     9:1    254              MAKESHAPES(DTOP,'XXX X X      XXX X');
1     9:1    278              MAKESHAPES(DTOP,'  X X X          X');
1     9:1    302              MAKESHAPES(DTOP,'  X XX           X');
1     9:1    326              for I:=1 to 2 do
1     9:2    340              MAKESHAPES(DTOP,'  X              X');
1     9:1    374              ROW:=15;
1     9:1    378              MAKESHAPES(DBOT,'  X              X');
1     9:1    402              MAKESHAPES(DBOT,'  X   XX         X');
1     9:1    426              MAKESHAPES(DBOT,'XXX X            X');
```

Listing 2 continued on page 410

Circle 44 on inquiry card.

ATARI®

COMPLETE LINE OF ATARI PRODUCTS AT SUPER LOW PRICES!

Atari 400 with 16K $399	Atari 822 Thermal Printer $360
Atrai 410 Cassette $69	Atari 810 Disk Drive $460
Atari 815 Dual Disk Drive $1200	Atari 16K RAM Module $90
Atari 8K RAM Module $50	Microsoft Basic $72
Star Raiders $32	Basketball $24
Video Easel $24	Tic Tac Toe $24

SPECIAL SUMMER OFFERS THROUGH AUGUST

Atari 800 with 32K $810	Atari 820 Printer $299
Atari 800 with 40K $860	Atari 825 Printer $650

THIRD PARTY HARDWARE AND SOFTWARE

Ramcram 32K RAM Modules .. $199	Visicalc $160
Kurta Graphics Tablet $560	Epson MX80 Printer $520

LJK Letter Perfect Word Processor $120

20% OFF ON AXLON 256K MEMORY SYSTEM

PLUS

Software by POI, THESIS and CRYSTAL - ALL at similar discounts

PLUS

Z19 Terminals $800
Novation DCAT Modems $169
Intertec Super Brain 64K $2810

NEC Spinwriters, Diablo Printers, Complete lines of Centronics Printers and Commodore Equipment. All at reduced prices.

The Bit Bucket
168 NORTH BEACON STREET
P.O. BOX 365
NEWTON HIGHLANDS, MA 02161
617-783-3144

Circle 381 on inquiry card.

NEW TARBELL S-100 CPU/IO BOARD



- Z-80™ will run at 2 or 4 Mhz
- 2 RS-232 Serial I/O ports
- Powerful Memory Management
- Programmable Timer
- Full masked priority interrupts
- Has everything needed for MP/M™
- 6 month full warranty

Z-80 is a trademark of Zilog Inc.
MP/M is a trademark of Digital Research

Tarbell Electronics

950 Dovlen Place, Suite B
Carson, CA 90746
Phone (213) 538-4251

ECT™

Building Blocks for Microcomputer Systems, Dedicated Controllers and Test Equipment.

R²I/O S-100 ROM, RAM & I/O BOARD



ECT's R²I/O is an S-100 Bus I/O Board with 3 Serial I/O Ports (UART's), 1 Parallel I/O Port, 4 Status Ports, 2K of ROM with the 8080 Apple Monitor Program and 2K of Static RAM.

$295.00

RM-10 S-100 RACK MOUNT CARD CAGE



ECT's RM-10 is a rack mount 10 slot Card Cage with Power Supply, consisting of an ECT-100 rack mount Card Cage (19"W x 12.25"H x 8"D), the MB-10 Mother Board (with ground plane and termination) all 10 connectors and guides and the PS-15A Power Supply (15A @ 8V, 1.5A @ ± 16V).

$295.00

Specializing in Quality Microcomputer Hardware
Industrial • Educational • Small Business • Personal
Card Cages, Power Supplies, Mainframes, CPU's, Memory, I/O, OEM Variations

ECT™ ELECTRONIC CONTROL TECHNOLOGY (201) 686-8080
763 Ramsey Ave., Hillside, NJ 07205

Circle 138 on inquiry card.

Listing 2 continued:

```
1     9:1    450                MAKESHAPES(DBOT,'  X X     XXXX X');
1     9:1    474                MAKESHAPES(DBOT,'  X  XX        X');
1     9:1    498                MAKESHAPES(DBOT,'  X        XX  X');
1     9:1    522                MAKESHAPES(DBOT,'  X       X  X X');
1     9:1    546                MAKESHAPES(DBOT,'  X       X  X X');
1     9:1    570                MAKESHAPES(DBOT,'  X       X XX X');
1     9:1    594                MAKESHAPES(DBOT,'  X        XXX X');
1     9:1    618                for I:=1 to 2 do
1     9:2    632                MAKESHAPES(DBOT,'  X            X');
1     9:1    666                MAKESHAPES(DBOT,'  XXXXXXXXXXXXXX');
1     9:1    690                MAKESHAPES(DBOT,'         XX     ');
1     9:1    714                MAKESHAPES(DBOT,'        X  X    ');
1     9:1    738                MAKESHAPES(DBOT,'         XX     ');
1     9:0    762              end;
1     9:0    780
1     9:0    780 (*$P*)
1     9:0    780 (***************  INIT7  ********************************
1     9:0    780 *                                                        *
1     9:0    780 *       Creates arrays from strings.                     *
1     9:0    780 *                                                        *
1     9:0    780 *       Called from : Main program.                      *
1     9:0    780 *                                                        *
1     9:0    780 **********************************************************)
1    10:D      1 procedure INIT7;
1    10:0      0         begin
1    10:1      0         write('.');
1    10:1     10         ROW:=15;
1    10:1     14         for I:=1 to 3 do
1    10:2     28         MAKESHAPES(HCAP,'    X  X        ');
1    10:1     62         MAKESHAPES(HCAP,'XXXXX  XXXXX    ');
1    10:1     86         for I:=1 to 3 do
1    10:2    100         MAKESHAPES(HCAP,'    X  X        ');
1    10:1    134         for I:=1 to 9 do
1    10:2    148         MAKESHAPES(HCAP,'                ');
1    10:1    182         ROW:=15;
1    10:1    186         for I:=1 to 4 do
1    10:2    200         MAKESHAPES(DIODE,'   X            ');
1    10:1    234         MAKESHAPES(DIODE,'XXXXXXX         ');
1    10:1    258         MAKESHAPES(DIODE,'   X            ');
1    10:1    282         MAKESHAPES(DIODE,'  XXX           ');
1    10:1    306         MAKESHAPES(DIODE,' XXXXX          ');
1    10:1    330         MAKESHAPES(DIODE,'XXXXXXX         ');
1    10:1    354         for I:=1 to 3 do
1    10:2    368         MAKESHAPES(DIODE,'   X            ');
1    10:1    402         for I:=1 to 4 do
1    10:2    416         MAKESHAPES(DIODE,'                ');
1    10:1    450         ROW:=15;
1    10:1    454         MAKESHAPES(HDIODE,'   X   X        ');
1    10:1    478         MAKESHAPES(HDIODE,'   XX  X        ');
1    10:1    502         MAKESHAPES(HDIODE,'   XXX X        ');
1    10:1    526         MAKESHAPES(HDIODE,'XXXXXXXXXXXX    ');
1    10:1    550         MAKESHAPES(HDIODE,'   XXX X        ');
1    10:1    574         MAKESHAPES(HDIODE,'   XX  X        ');
1    10:1    598         MAKESHAPES(HDIODE,'   X   X        ');
1    10:1    622         for I:=1 to 9 do
1    10:2    636         MAKESHAPES(HDIODE,'                ');
1    10:1    670         ROW:=15;
1    10:1    674         MAKESHAPES(OPAMP,'   XXXX         ');
1    10:1    698         MAKESHAPES(OPAMP,'   X   X        ');
1    10:1    722         MAKESHAPES(OPAMP,'   X    X       ');
1    10:1    746         MAKESHAPES(OPAMP,'   X  X  X      ');
1    10:1    770         MAKESHAPES(OPAMP,'XXXX XXX  X     ');
1    10:1    794         MAKESHAPES(OPAMP,'   X  X    X    ');
1    10:1    818         MAKESHAPES(OPAMP,'   X        X   ');
1    10:1    842         MAKESHAPES(OPAMP,'   X         XXX');
1    10:1    866         MAKESHAPES(OPAMP,'   X        X   ');
1    10:1    890         MAKESHAPES(OPAMP,'   X       X    ');
1    10:1    914         MAKESHAPES(OPAMP,'XXXX XXX  X     ');
1    10:1    938         MAKESHAPES(OPAMP,'   X     X      ');
1    10:1    962         MAKESHAPES(OPAMP,'   X    X       ');
1    10:1    986         MAKESHAPES(OPAMP,'   X   X        ');
1    10:1   1010         MAKESHAPES(OPAMP,'   XXXX         ');
1    10:1   1034         MAKESHAPES(OPAMP,'                ');
1    10:0   1058       end;
1    10:0   1084
1    10:0   1084 (*$P*)
1    10:0   1084 (***************  INIT8  ********************************
1    10:0   1084 *                                                        *
1    10:0   1084 *       Creates arrays from strings.                     *
1    10:0   1084 *                                                        *
1    10:0   1084 *       Called from : Main program.                      *
1    10:0   1084 *                                                        *
1    10:0   1084 **********************************************************)
1    11:D      1 procedure INIT8;
1    11:0      0        begin
```

Listing 2 continued on page 412

ROBOTS

The Future Arrives



Intelligent machines are rapidly appearing in homes, automobiles, offices and factories. Affordable cameras, speech synthesizers, and even robot arms are now on the market. Such advances are giving microcomputers the power to see, hear, grasp objects, and to move around the room. Where can you learn about this technology? In **Robotics Age Magazine,** the journal of intelligent machines. **Robotics Age** reports the experience of hobbyists building their own robots, the latest products from industry, and the most powerful techniques from research labs. The face of the world is changing. Join us as we enter the Robotics Age.

YES! I want to stay up-to-date on this fascinating new technology!

Name ______ Title ______

Company ______ Address ______

City State/Providence/Country ______ Postal Code ______

	United States	Canada Mexico*	Foreign Rates*
☐ 1 year (6 issues)	$15	$17	$19
☐ 2 years (12 issues)	$28	$32	$36
☐ 3 years (18 issues)	$39	$45	$51

*US Funds on US Bank

☐ Bill VISA ☐ MasterCard ☐ Bill me (N. America only)

Card No. ______ Exp. ______

Signature ______

Send to: ROBOTICS AGE, PO Box 512, Tujunga, CA 91042

P&T CP/M®2 Supports Hard Disk Storage for the TRS-80 Model II

P&T CP/M 2 now supports two popular hard disk subsystems for the Mod II; thus you can combine all the features of the best CP/M for the Mod II with the speed and capacity of the hard disk drives.

Cameo Electronics

- uses mature cartridge disk technology for maximum reliability
- supports up to 4 drives
- removable cartridges make backup and data transfer fast and easy

Corvus System

- support for 10 and 20 Mbyte drives
- special mirror utility allows backup by logical drive
- supports up to 4 drives

Price: $250 (FOB Goleta) for P&T CP/M 2-hard disk version (CA residents add 6% sales tax)

PICKLES & TROUT
P. O. BOX 1206, GOLETA, CA 93116, (805) 685-4641

CP/M is a registered trademark of Digital Research. TRS-80 is a trademark of Tandy Corp.

BYTE BACK ISSUES FOR SALE

The following issues are available:
1976: July
1977: April thru December except October
1978: February thru December except November
1979: January thru December except March
1980: January, March thru August, and December
1981: February to current issue

Cover price for each issue through August 1977 is $1.75 Domestic; $2.75 Canada and Mexico; $3.75 Foreign. September 1977 through October 1979 issues are $2.50 Domestic; $3.50 Canada and Mexico; $4.50 Foreign. November 1979 to current is $3.00 Domestic; $4.00 Canada and Mexico; $5.00 Foreign.

Send requests with payment to:

BYTE Magazine
70 Main St, Peterborough NH 03458
Attn: Back Issues

Please allow 4 weeks for domestic delivery and 8 weeks for foreign delivery.

* Payments from foreign countries must be made in US funds payable at a US bank.

A LOGIC ANALYZER FOR $395?

YES!

OWL

LA 1600-A
High Speed
16 Channels

Interfaces to dual channel scope or Apple computer.

- 10 MHZ capture rate
- Gold plated connectors and clips
- Stores 16 words of 16 bits
- Crystal controlled internal clock
- 1, 0, X compare word bit selection
- Time domain display
- Data domain display*
- Hex display*
- Internal and external trigger modes

*Options with use of Apple computer

Comes complete with interconnecting cables; logic probe clips, diskette for Apple computer, and operating instructions.

— Send for FREE brochure —

Osborne Wilson Ltd.
508 Waterberry Drive
Pleasant Hill, California 94523
(415) 932-5489

Listing 2 continued:

```
1    11:1     0          write('.');
1    11:1    10          ROW:=15;
1    11:1    14          for I:=1 to 3 do
1    11:2    28          MAKESHAPES(NPN,'       X        ');
1    11:1    62          MAKESHAPES(NPN,'  X   X         ');
1    11:1    86          MAKESHAPES(NPN,'  X  X          ');
1    11:1   110          MAKESHAPES(NPN,'  X X           ');
1    11:1   134          MAKESHAPES(NPN,'  XX            ');
1    11:1   158          MAKESHAPES(NPN,'XXX             ');
1    11:1   182          MAKESHAPES(NPN,'  XX            ');
1    11:1   206          MAKESHAPES(NPN,'  X XXX         ');
1    11:1   230          MAKESHAPES(NPN,'  X XX          ');
1    11:1   254          MAKESHAPES(NPN,'  X X X         ');
1    11:1   278          for I:=1 to 4 do
1    11:2   292          MAKESHAPES(NPN,'      X         ');
1    11:1   326          ROW:=15;
1    11:1   330          for I:=1 to 3 do
1    11:2   344          MAKESHAPES(PNP,'       X        ');
1    11:1   378          MAKESHAPES(PNP,'  X   X         ');
1    11:1   402          MAKESHAPES(PNP,'  X  X          ');
1    11:1   426          MAKESHAPES(PNP,'  X X           ');
1    11:1   450          MAKESHAPES(PNP,'  XX            ');
1    11:1   474          MAKESHAPES(PNP,'XXX             ');
1    11:1   498          MAKESHAPES(PNP,'  XX            ');
1    11:1   522          MAKESHAPES(PNP,'  X X X         ');
1    11:1   546          MAKESHAPES(PNP,'  X XX          ');
1    11:1   570          MAKESHAPES(PNP,'  X XXX         ');
1    11:1   594          for I:=1 to 4 do
1    11:2   608          MAKESHAPES(PNP,'      X         ');
1    11:1   642          ROW:=15;
1    11:1   646          MAKESHAPES(BAT,'   X   X        ');
1    11:1   670          MAKESHAPES(BAT,'   X   X   XXX  ');
1    11:1   694          MAKESHAPES(BAT,'   X X X X      ');
1    11:1   718          MAKESHAPES(BAT,'XXXX X X XXXXXXX');
1    11:1   742          MAKESHAPES(BAT,'   X X X X      ');
1    11:1   766          MAKESHAPES(BAT,'   X   X        ');
1    11:1   790          MAKESHAPES(BAT,'   X   X        ');
1    11:1   814          for I:= 1 to 9 do
1    11:2   828          MAKESHAPES(BAT,'                ');
1    11:1   862          ROW:=15;
1    11:1   866          MAKESHAPES(SW,'         X      ');
1    11:1   890          MAKESHAPES(SW,'        X       ');
1    11:1   914          MAKESHAPES(SW,'       X        ');
1    11:1   938          MAKESHAPES(SW,' XX   X      XX ');
1    11:1   962          MAKESHAPES(SW,'XXXXXX    XXXXXX');
1    11:1   986          MAKESHAPES(SW,' XX          XX ');
1    11:1  1010          for I:=1 to 10 do
1    11:2  1024          MAKESHAPES(SW,'                ');
1    11:0  1058        end;
1    11:0  1082
1    11:0  1082 (*$P*)
1    11:0  1082 (***************  INIT9  *********************************
1    11:0  1082 *                                                         *
1    11:0  1082 *       Creates arrays from strings.                      *
1    11:0  1082 *                                                         *
1    11:0  1082 *       Called from : Main program.                       *
1    11:0  1082 *                                                         *
1    11:0  1082 ***********************************************************)
1    12:D     1 procedure INIT9;
1    12:0     0        begin
1    12:1     0          write('.');
1    12:1    10          ROW:=15;
1    12:1    14          MAKESHAPES(MINIDIP,'XXXXXXXXXXXXXXXX');
1    12:1    38          for I:=1 to 14 do
1    12:2    52          MAKESHAPES(MINIDIP,'X              X');
1    12:1    86          MAKESHAPES(MINIDIP,'XXXXXXXXXXXXXXXX');
1    12:1   110          ROW:=15;
1    12:1   114          MAKESHAPES(HMSIL,'XXXXXXXXXXXXXXXX');
1    12:1   138          for I:=1 to 14 do
1    12:2   152          MAKESHAPES(HMSIL,'X               ');
1    12:1   186          MAKESHAPES(HMSIL,'XXXXXXXXXXXXXXXX');
1    12:1   210          ROW:=15;
1    12:1   214          MAKESHAPES(HMSIR,'XXXXXXXXXXXXXXXX');
1    12:1   238          for I:=1 to 14 do
1    12:2   252          MAKESHAPES(HMSIR,'               X');
1    12:1   286          MAKESHAPES(HMSIR,'XXXXXXXXXXXXXXXX');
1    12:1   310          ROW:=15;
1    12:1   314          MAKESHAPES(XTAL,'    X     X     ');
1    12:1   338          MAKESHAPES(XTAL,'    X XXX X     ');
1    12:1   362          MAKESHAPES(XTAL,'    X XXX X     ');
1    12:1   386          MAKESHAPES(XTAL,'XXXXX XXX XXXXXX');
1    12:1   410          MAKESHAPES(XTAL,'    X XXX X     ');
1    12:1   434          MAKESHAPES(XTAL,'    X XXX X     ');
```

Listing 2 continued on page 414

Listing 2 continued:

```
 1  12:1   458         MAKESHAPES(XTAL,'    X     X     ');
 1  12:1   482         for I:=1 to 9 do
 1  12:2   496         MAKESHAPES(XTAL,'                ');
 1  12:1   530         ROW:=15;
 1  12:1   534         MAKESHAPES(WIPER,' X             ');
 1  12:1   557         MAKESHAPES(WIPER,' XXX           ');
 1  12:1   580         MAKESHAPES(WIPER,'XXXXX          ');
 1  12:1   603         for I:=1 to 4 do
 1  12:2   617         MAKESHAPES(WIPER,' X             ');
 1  12:1   650         for I:=1 to 9 do
 1  12:2   664         MAKESHAPES(WIPER,'               ');
 1  12:1   697         ROW:=15;
 1  12:1   701         MAKESHAPES(ZENER,'     X          ');
 1  12:1   724         MAKESHAPES(ZENER,'     X          ');
 1  12:1   747         MAKESHAPES(ZENER,'     X   X      ');
 1  12:1   770         MAKESHAPES(ZENER,'     X  X       ');
 1  12:1   793         MAKESHAPES(ZENER,'   XXXXX        ');
 1  12:1   816         MAKESHAPES(ZENER,'  X  X          ');
 1  12:1   839         MAKESHAPES(ZENER,' X  XXX         ');
 1  12:1   862         MAKESHAPES(ZENER,'   XXXXX        ');
 1  12:1   885         MAKESHAPES(ZENER,'  XXXXXXX       ');
 1  12:1   908         for I:=1 to 4 do
 1  12:2   922         MAKESHAPES(ZENER,'     X          ');
 1  12:1   955         for I:=1 to 3 do
 1  12:2   969         MAKESHAPES(ZENER,'                ');
 1  12:0  1002       end;
 1  12:0  1030 (*$P*)
 1  12:0  1030 (***************  INIT10  ******************************
 1  12:0  1030 *                                                      *
 1  12:0  1030 *       Creates arrays from strings.                   *
 1  12:0  1030 *                                                      *
 1  12:0  1030 *       Called from : Main program.                    *
 1  12:0  1030 *                                                      *
 1  12:0  1030 ********************************************************)
 1  13:D     1 procedure INIT10;
 1  13:0     0       begin
 1  13:1     0         for I:=1 to 4 do begin
 1  13:3    14           ROW:=16-(4*I);
 1  13:3    24           MAKESHAPES(LCOIL,'X X X           '); end;
 1  13:1    57         for I:=1 to 8 do begin
 1  13:3    71           ROW:=16-(2*I)+1;
 1  13:3    83           MAKESHAPES(LCOIL,'X X  XXX        '); end;
 1  13:1   116         for I:=1 to 4 do begin
 1  13:3   130           ROW:=16-(4*I)+2;
 1  13:3   142           MAKESHAPES(LCOIL,'X X X   X       '); end;
 1  13:1   175         for I:=1 to 4 do begin
 1  13:3   189           ROW:=16-(4*I);
 1  13:3   199           MAKESHAPES(RCOIL,'    X           '); end;
 1  13:1   232         for I:=1 to 8 do begin
 1  13:3   246           ROW:=16-(2*I)+1;
 1  13:3   258           MAKESHAPES(RCOIL,' XXX            '); end;
 1  13:1   291         for I:=1 to 4 do begin
 1  13:3   305           ROW:=16-(4*I)+2;
 1  13:3   317           MAKESHAPES(RCOIL,'X   X           '); end;
 1  13:1   350         ROW:=15;
 1  13:1   354         for I:=1 to 16 do
 1  13:2   368           MAKESHAPES(USER1,'                ');
 1  13:1   401         ROW:=15;
 1  13:1   405         for I:=1 to 16 do
 1  13:2   419           MAKESHAPES(USER2,'                ');
 1  13:1   452         ROW:=15;
 1  13:1   456         for I:=1 to 16 do
 1  13:2   470           MAKESHAPES(USER3,'                ');
 1  13:1   503         ROW:=15;
 1  13:1   507         MAKESHAPES(VRESIST,' X              ');
 1  13:1   530         MAKESHAPES(VRESIST,' X              ');
 1  13:1   553         MAKESHAPES(VRESIST,'X               ');
 1  13:1   576         MAKESHAPES(VRESIST,' X              ');
 1  13:1   599         MAKESHAPES(VRESIST,'  X             ');
 1  13:1   622         MAKESHAPES(VRESIST,' X              ');
 1  13:1   645         MAKESHAPES(VRESIST,'X               ');
 1  13:1   668         MAKESHAPES(VRESIST,' X              ');
 1  13:1   691         MAKESHAPES(VRESIST,'  X             ');
 1  13:1   714         MAKESHAPES(VRESIST,' X              ');
 1  13:1   737         MAKESHAPES(VRESIST,'X               ');
 1  13:1   760         MAKESHAPES(VRESIST,' X              ');
 1  13:1   783         MAKESHAPES(VRESIST,'  X             ');
 1  13:1   806         MAKESHAPES(VRESIST,' X              ');
 1  13:1   829         MAKESHAPES(VRESIST,' X              ');
 1  13:1   852         MAKESHAPES(VRESIST,' X              ');
 1  13:0   875       end;
 1  13:0   906
 1  13:0   906 (*$P*)
```

```
    1   13:0   906 (*****************************************************
    1   13:0   906 *                                                   *
    1   13:0   906 *       MAIN PROGRAM STARTS HERE ....               *
    1   13:0   906 *                                                   *
    1   13:0   906 *****************************************************)
    1    1:0     0 begin
    1    1:1     0      write('initializing array');
    1    1:1    52      INIT1;
    1    1:1    54      INIT2;
    1    1:1    56      INIT3;
    1    1:1    58      INIT4;
    1    1:1    60      INIT5;
    1    1:1    62      INIT6;
    1    1:1    64      INIT7;
    1    1:1    66      INIT8;
    1    1:1    68      INIT9;
    1    1:1    70      INIT10;
    1    1:1    72      writeln; writeln('Writing "LOGIC.CHARSET" to disc');
    1    1:1   131      SAVESHAPES;
    1    1:0   133 end.
```

Listing 3: *Apple Pascal program LOGICDESIGN accepts plotting inputs from the Graphics Tablet.*

```
   1    1:D     1 (*$L PRINTER:*) (* last update - 25 Apr 80 *)
   1    1:D     1 (*$I PART1.TEXT*)
   1    1:D     1 (* PART1 OF LOGICDESIGN *)
   1    1:D     1 program LOGICDESIGN;
   1    1:D     3 (**********************************************
   1    1:D     3 *                                             *
   1    1:D     3 * This program draws logic diagrams on the hires *
   1    1:D     3 * screen. It uses the Graphics Tablet for most  *
   1    1:D     3 * input.                                        *
   1    1:D     3 *                                               *
   1    1:D     3 * It expects (and requires) the Graphics Tablet *
   1    1:D     3 * card to be in slot #5, and a Sup'r'terminal   *
   1    1:D     3 * board in slot #3.                             *
   1    1:D     3 *                                               *
   1    1:D     3 *          Dan Sokol - 28 Mar 80                *
   1    1:D     3 *              rev B   12 Apr 80                *
   1    1:D     3 *                                               *
   1    1:D     3 ***********************************************)
  26    1:D     3
  26    1:D     3
  26    2:D     1 PROCEDURE POKE(VAR ADDR,DATA:INTEGER);
  26    3:D     3 FUNCTION PEEK(VAR ADDR:INTEGER):INTEGER;
  26    3:D     4
  22    1:D     4 {$  }
  22    1:D     3
  22    1:D     3
  22    2:D     3     FUNCTION PADDLE(SELECT: INTEGER): INTEGER;
  22    3:D     3     FUNCTION BUTTON(SELECT: INTEGER): BOOLEAN;
  22    4:D     1     PROCEDURE TTLOUT(SELECT: INTEGER; DATA: BOOLEAN);
  22    5:D     3     FUNCTION KEYPRESS: BOOLEAN;
  22    6:D     3     FUNCTION RANDOM: INTEGER;
  22    7:D     1     PROCEDURE RANDOMIZE;
  22    8:D     1     PROCEDURE NOTE(PITCH,DURATION: INTEGER);
  22    8:D     3
  22    1:D     3   IMPLEMENTATION
  22    1:D     1
  20    1:D     1
  20    1:D     3     TYPE
  20    1:D     1       SCREENCOLOR=(none,white,black,reverse,radar,
  20    1:D     1                    black1,green,violet,white1,black2,orange,blue,white2);
  20    1:D     1
  20    2:D     1     PROCEDURE INITTURTLE;
  20    3:D     1     PROCEDURE TURN(ANGLE: INTEGER);
  20    4:D     1     PROCEDURE TURNTO(ANGLE: INTEGER);
  20    5:D     1     PROCEDURE MOVE(DIST: INTEGER);
  20    6:D     1     PROCEDURE MOVETO(X,Y: INTEGER);
  20    7:D     1     PROCEDURE PENCOLOR(PENMODE: SCREENCOLOR);
  20    8:D     1     PROCEDURE TEXTMODE;
  20    9:D     1     PROCEDURE GRAFMODE;
  20   10:D     1     PROCEDURE FILLSCREEN(FILLCOLOR: SCREENCOLOR);
  20   11:D     1     PROCEDURE VIEWPORT(LEFT,RIGHT,BOTTOM,TOP: INTEGER);
  20   12:D     3     FUNCTION  TURTLEX: INTEGER;
  20   13:D     3     FUNCTION  TURTLEY: INTEGER;
  20   14:D     3     FUNCTION  TURTLEANG: INTEGER;
  20   15:D     3     FUNCTION  SCREENBIT(X,Y: INTEGER): BOOLEAN;
  20   16:D     1     PROCEDURE DRAWBLOCK(VAR SOURCE; ROWSIZE,XSKIP,YSKIP,WIDTH,HEIGHT,
  20   16:D     2                         XSCREEN,YSCREEN,MODE: INTEGER);
  20   17:D     1     PROCEDURE WCHAR(CH: CHAR);
  20   18:D     1     PROCEDURE WSTRING(S: STRING);
  20   19:D     1     PROCEDURE CHARTYPE(MODE: INTEGER);
```

Listing 3 continued on page 416

Listing 3 continued:

```
20    19:D     2
 1     1:D     2  uses peekpoke,applestu,turtlegr;
 1     1:D     3  (*$P*)
 1     1:D     3  (*********************************************************
 1     1:D     3  *                                                       *
 1     1:D     3  *           GLOBAL VARIABLE DECLARATIONS                *
 1     1:D     3  *                                                       *
 1     1:D     3  *********************************************************)
 1     1:D     3
 1     1:D     3  type SHAPE = packed array [0..15,0..15] of boolean;
 1     1:D     3
 1     1:D     3  (*********************************************************
 1     1:D     3  *                                                       *
 1     1:D     3  *           INTEGER VARIABLES                           *
 1     1:D     3  *                                                       *
 1     1:D     3  *********************************************************)
 1     1:D     3  var
 1     1:D     3
 1     1:D     3      PITCH,                          (* frequency for audio feedback *)
 1     1:D     3      DURATION,                       (* length of audio feedback     *)
 1     1:D     3      PEN,                            (* pen switch (up or down)      *)
 1     1:D     3      X,Y,                            (* pen position on pad          *)
 1     1:D     3      D,                              (* Device being plotted         *)
 1     1:D     3      I,J,K,                          (* various loop counters        *)
 1     1:D     3      USR1X,USR1Y,USR2X,USR2Y,        (* position pointer for user1&2 *)
 1     1:D     3      LASTD,LASTX,LASTY,              (* last D,X, & Y for deleting   *)
 1     1:D     3      DMODE                           (* mode used for plotting       *)
 1     1:D     3                                      : integer;
 1     1:D    20
 1     1:D    20
 1     1:D    20  (*********************************************************
 1     1:D    20  *                                                       *
 1     1:D    20  *           PLOTTED SHAPE NAMES                         *
 1     1:D    20  *                                                       *
 1     1:D    20  *********************************************************)
 1     1:D    20
 1     1:D    20      INVERTER,NAND,NOR,ORGATE,ANDGATE,DTOP,DBOT,JKTOP,JKBOT,BUFFER,GND,PLUS5,
 1     1:D    20      MSITOP,MSIBOT,INV,INTHING,OUT,DOT,CAP,RESISTOR,XOR,XNOR,HCAP,DIODE,SW,BAT,
 1     1:D    20      MINIDIP,HDIODE,OPAMP,NPN,PNP,MINDIP,HMSIL,HMSIR,XTAL,WIPER,ZENER,
 1     1:D    20      LCOIL,RCOIL,VRESIST,USER1,USER2,USER3 : SHAPE;
```

```
1      1:D     708
1      1:D     708
1      1:D     708 (*********************************************************
1      1:D     708 *                                                       *
1      1:D     708 *           DISK FILES                                  *
1      1:D     708 *                                                       *
1      1:D     708 *********************************************************)
1      1:D     708
1      1:D     708      SHAPEFILE,                   (* plotted devices are here *)
1      1:D     708      USERFILE                     (* The screen image file *)
1      1:D     768                                   : file of SHAPE;
1      1:D    1340 (*$P*)
1      1:D    1340 (*********************************************************
1      1:D    1340 *                                                       *
1      1:D    1340 *           BOOLEANS                                    *
1      1:D    1340 *                                                       *
1      1:D    1340 *********************************************************)
1      1:D    1340
1      1:D    1340      BIT,                         (* flags 'delete lastx' mode *)
1      1:D    1340      USR,                         (* Used in SETUSR could be local *)
1      1:D    1340      SAFETY,                      (* checks for SAVE on exit *)
1      1:D    1340      FLAG,                        (* debug - display X&Y on screen *)
1      1:D    1340      VALIDXY,                     (* true if X&Y are on screen *)
1      1:D    1340      HELLFREEZESOVER,             (* never true - for infinite repeats *)
1      1:D    1340      LOCKX,LOCKY                  (* locks X&Y axis *)
1      1:D    1340                                   : boolean;
1      1:D    1348
1      1:D    1348
1      1:D    1348 (*********************************************************
1      1:D    1348 *                                                       *
1      1:D    1348 *           STRINGS and THINGS                          *
1      1:D    1348 *                                                       *
1      1:D    1348 *********************************************************)
1      1:D    1348
1      1:D    1348      FILENAME,                    (* for LOAD and SAVE names *)
1      1:D    1348      IDENT                        (* for names of plotted devices *)
1      1:D    1348                                   : string;
1      1:D    1430      CH                           (* for inputs and control *)
```

Listing 3 continued on page 418

Listing 3 continued:

```
1    1:D  1430                                            : char;
1    1:D  1431
1    1:D  1431 (*$P*)
1    1:D  1431 (***************  SAVESCREEN  ***************************
1    1:D  1431 *                                                        *
1    1:D  1431 *   Copies HIRES screen 1 into a file named by the       *
1    1:D  1431 *   user (FILENAME).                                     *
1    1:D  1431 *                                                        *
1    1:D  1431 *   Called by : MENU,EXIT                                *
1    1:D  1431 *                                                        *
1    1:D  1431 *********************************************************)
1    1:D  1431 (*$I-*)
1    2:D     1 procedure SAVESCREEN;
1    2:D     1         var BLOCKNUMBER,SCREEN : integer;
1    2:D     3             IMAGE : file;
1    2:D    43             BUFFER : packed array[0..511] of char;
1    2:D   299             BADIO : boolean;
1    2:0     0         begin
1    2:1     0           write(chr(12)); write('Save with what name ?'); readln(FILENAME);
1    2:1    67           if length(FILENAME) = 0 then exit(SAVESCREEN);
1    2:1    80           SCREEN:=8192; BLOCKNUMBER:=0; BADIO:=false;
1    2:1    92           if length(FILENAME) > 10 then
1    2:2   101             begin writeln; writeln('File name is too long !!!',chr(7));
1    2:3   156               SAFETY:=false; exit(SAVESCREEN);
1    2:2   164             end else FILENAME:=concat(FILENAME,'.SCRN');
1    2:1   203           rewrite(IMAGE,FILENAME);
1    2:1   213           while ((IORESULT=0) and (NOT BADIO) and (BLOCKNUMBER<>16)) do
1    2:2   228             begin
1    2:3   228              for I:=0 to 511 do
1    2:4   244               begin J:=peek(SCREEN); BUFFER[I]:=chr(J); SCREEN:=SCREEN+1; end;
1    2:3   275              K:=blockwrite(IMAGE,BUFFER,1,BLOCKNUMBER);
1    2:3   290              BLOCKNUMBER:=BLOCKNUMBER+1;
1    2:2   295             end;
1    2:1   297            close(IMAGE , lock);
1    2:1   303            SAFETY:=true;
1    2:0   307          end;
1    2:0   330 (*$P*)
1    2:0   330 (***************  LOADSCREEN  ***************************
1    2:0   330 *                                                        *
1    2:0   330 *   Copies file named by the user into HIRES screen 1.  *
1    2:0   330 *                                                        *
1    2:0   330 *   Called by : MENU                                     *
1    2:0   330 *                                                        *
1    2:0   330 *********************************************************)
1    3:D     1 procedure LOADSCREEN;
1    3:D     1         var BLOCKNUMBER,SCREEN : integer;
1    3:D     3             IMAGE : file;
1    3:D    43             BUFFER : packed array[0..511] of char;
1    3:D   299             BADIO : boolean;
1    3:0     0         begin
1    3:1     0           write(chr(12)); write('Load what file name ?'); readln(FILENAME);
1    3:1    67           if length(FILENAME) = 0 then exit(LOADSCREEN);
1    3:1    80           SCREEN:=8192; BLOCKNUMBER:=0; BADIO:=false;
1    3:1    92           if length(FILENAME) > 10 then
1    3:2   101             begin writeln; writeln('File name is too long !!!',chr(7));
1    3:3   156                 exit(LOADSCREEN);
1    3:2   160             end else FILENAME:=concat(FILENAME,'.SCRN');
1    3:1   199           reset(IMAGE,FILENAME);
1    3:1   209           while ((IORESULT=0) and (NOT eof(IMAGE)) and (BLOCKNUMBER<>16)) do
1    3:2   228             begin
1    3:3   228              K:=blockread(IMAGE,BUFFER,1,BLOCKNUMBER);
1    3:3   243              for I:=0 to 511 do
1    3:4   259                begin J:=ord(BUFFER[I]); poke(SCREEN,J); SCREEN:=SCREEN+1; end;
1    3:3   289              BLOCKNUMBER:=BLOCKNUMBER+1;
1    3:2   294             end;
1    3:1   296            close(IMAGE);
1    3:0   302          end;
1    3:0   324 (*$I+*)
1    3:0   324
1    3:0   324 (*$I PART1.TEXT*)
1    3:0   324 (*$I PART2.TEXT*)
1    3:0   324 (*$P*)    (* Part2 of LOGICDESIGN *)
1    3:0   324 (***************  CLEARTTY  ******************************
1    3:0   324 *                                                        *
1    3:0   324 *    Clears Text screen & homes cursor.                  *
1    3:0   324 *                                                        *
1    3:0   324 *    Called from : Just about everywhere....             *
1    3:0   324 *                                                        *
1    3:0   324 *********************************************************)
1    4:D     1 procedure CLEARTTY;
1    4:0     0         begin
```

```
 1   4:1    0          write(chr(12));
 1   4:0   10        end;
 1   4:0   22
 1   4:0   22 (***************  BEEP  *********************************
 1   4:0   22 *                                                       *
 1   4:0   22 *    Audio feedback                                     *
 1   4:0   22 *                                                       *
 1   4:0   22 *    Called from : Just about everywhere....            *
 1   4:0   22 *                                                       *
 1   4:0   22 ********************************************************)
 1   5:D    1 procedure BEEP;
 1   5:0    0         begin note(PITCH,DURATION); end;
 1   5:0   20
 1   5:0   20 (***************  KEY  **********************************
 1   5:0   20 *                                                       *
 1   5:0   20 *    Replaces applestuff KEYPRESS function which        *
 1   5:0   20 *    doesn't work if there is a card in slot #3.        *
 1   5:0   20 *                                                       *
 1   5:0   20 *    Called from : GETXY                                *
 1   5:0   20 *                                                       *
 1   5:0   20 ********************************************************)
 1   6:D    3 function KEY : boolean;
 1   6:D    3         var CLEAR,KEYBOARD,TEMP : integer;
 1   6:0    0         begin
 1   6:1    0           CLEAR:=-16368; KEYBOARD:=-16384; TEMP:=peek(KEYBOARD);
 1   6:1   21           if TEMP > 128 then
 1   6:2   28           begin KEY:=true; poke(CLEAR,TEMP); end
 1   6:1   38           else KEY:=false;
 1   6:0   43         end;
 1   6:0   56
 1   6:0   56 (***************  CONVERTFROM  *************************
 1   6:0   56 *                                                       *
 1   6:0   56 *    Converts the boolean information in the shape      *
 1   6:0   56 *    USER3 to the integer values used by MYPLOT as      *
 1   6:0   56 *    the X & Y offset information.                      *
 1   6:0   56 *                                                       *
 1   6:0   56 *    Called from : GETSHAPES                            *
 1   6:0   56 *                                                       *
 1   6:0   56 ********************************************************)
 1   6:0   56 (*$R-*)
 1   7:D    1 procedure CONVERTFROM;
 1   7:0    0         begin
 1   7:1    0           K:=0; I:=0; USR1X:=0;
 1   7:1    9           while USER3[I,K] and (K<15) do begin K:=K+1; USR1X:=USR1X+1; end;
 1   7:1   37           I:=1; K:=0; USR1Y:=0;
 1   7:1   46           while USER3[I,K] and (K<15) do begin K:=K+1; USR1Y:=USR1Y+1; end;
 1   7:1   74           I:=2; K:=0; USR2X:=0;
 1   7:1   83           while USER3[I,K] and (K<15) do begin K:=K+1; USR2X:=USR2X+1; end;
 1   7:1  111           I:=3; K:=0; USR2Y:=0;
 1   7:1  120           while USER3[I,K] and (K<15) do begin K:=K+1; USR2Y:=USR2Y+1; end;
 1   7:0  148         end;
 1   7:0  168 (*$R+*)
 1   7:0  168 (*$P*)
 1   7:0  168 (***************  GETSHAPES  ****************************
 1   7:0  168 *                                                       *
 1   7:0  168 *       Loads the shapes from the file 'LOGIC.CHARSET'  *
 1   7:0  168 *                                                       *
 1   7:0  168 *       Called from : Main program loop.                *
 1   7:0  168 *                                                       *
 1   7:0  168 ********************************************************)
 1   8:D    1 procedure GETSHAPES;
 1   8:0    0         begin
 1   8:1    0           reset(SHAPEFILE,'LOGIC.CHARSET');
 1   8:1   26           INVERTER:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1   42           NAND:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1   58           NOR:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1   74           ORGATE:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1   90           ANDGATE:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  106           DTOP:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  122           DBOT:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  138           JKTOP:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  154           JKBOT:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  170           BUFFER:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  186           GND:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  202           PLUS5:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  218           MSITOP:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  234           MSIBOT:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  250           INV:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  266           INTHING:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  282           OUT:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  298           DOT:=SHAPEFILE^; get(SHAPEFILE);
 1   8:1  314           CAP:=SHAPEFILE^; get(SHAPEFILE);
```

Listing 3 continued on page 420

Listing 3 continued:

```
1     8:1    330            RESISTOR:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    346            XOR:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    362            XNOR:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    378            HCAP:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    394            DIODE:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    410            HDIODE:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    426            OPAMP:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    442            NPN:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    458            PNP:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    474            BAT:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    490            SW:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    506            MINIDIP:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    522            HMSIL:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    538            HMSIR:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    554            XTAL:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    570            WIPER:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    586            ZENER:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    601            LCOIL:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    616            RCOIL:=SHAPEFILE^; get(SHAPEFILE);
1     8:1    631            VRESIST:=SHAPEFILE^;
1     8:1    638            close(SHAPEFILE);
1     8:1    647            reset(USERFILE,'USER.CHARSET');
1     8:1    672            USER1:=USERFILE^; get(USERFILE);
1     8:1    687            USER2:=USERFILE^; get(USERFILE);
1     8:1    702            USER3:=USERFILE^; get(USERFILE);
1     8:1    717            close(USERFILE);
1     8:1    726            CONVERTFROM;
1     8:0    728          end;
1     8:0    740
1     8:0    740
1     8:0    740 (*$I PART2.TEXT*)
1     8:0    740 (*$I PART3.TEXT*)
1     8:0    740 (*$P*)  (* Part3 of LOGICDESIGN *)
1     8:0    740
1     8:0    740 (***************  SETUPAD & READPAD  ********************
1     8:0    740 *                                                        *
1     8:0    740 *       Assembly language procedures to setup and        *
1     8:0    740 *       read the graphics tablet.                        *
1     8:0    740 *                                                        *
1     8:0    740 *       Called by : GETXY and Main program               *
1     8:0    740 *                                                        *
1     8:0    740 *********************************************************)
1     9:D      1 procedure SETUPAD; external;
1     9:D      1
1    10:D      1 procedure READPAD; external;
1    10:D      1
1    10:D      1 (***************  CONVERTO  ****************************
1    10:D      1 *                                                        *
1    10:D      1 *       Converts the integer values set by the user      *
1    10:D      1 *       as the X & Y offsets for USER1 & 2 to boolean    *
1    10:D      1 *       values and saves them in USER3.                  *
1    10:D      1 *                                                        *
1    10:D      1 *       Called by : SETUSR                               *
1    10:D      1 *                                                        *
1    10:D      1 *********************************************************)
1    11:D      1 procedure CONVERTO;
1    11:D      1         var X1,X2,Y1,Y2 : integer;
1    11:0      0         begin
1    11:1      0           for I:=0 to 15 do for K:=0 to 15 do USER3[I,K]:=false;
1    11:1     53           I:=0; X1:=USR1X;
1    11:1     59           while X1 >=0 do begin
1    11:3     64              USER3[I,X1]:=true; X1:=X1-1; end;
1    11:1     88           I:=1; Y1:=USR1Y;
1    11:1     94           while Y1 >=0 do begin
1    11:3     99              USER3[I,Y1]:=true; Y1:=Y1-1; end;
1    11:1    123           I:=2; X2:=USR2X;
1    11:1    129           while X2 >=0 do begin
1    11:3    134              USER3[I,X2]:=true; X2:=X2-1; end;
1    11:1    158           I:=3; Y2:=USR2Y;
1    11:1    164           while Y2 >=0 do begin
1    11:3    169              USER3[I,Y2]:=true; Y2:=Y2-1; end;
1    11:0    193         end;
1    11:0    218
1    11:0    218 (*$P*)
1    11:0    218 (***************  SETUSR  ******************************
1    11:0    218 *                                                        *
1    11:0    218 *       Builds the shapes USER1 and USER2 and saves      *
1    11:0    218 *       them in the file 'USER.CHARSET'.                 *
1    11:0    218 *                                                        *
1    11:0    218 *       Called by : MENU                                 *
1    11:0    218 *                                                        *
```

```
1   11:0   218 ***********************************************************)
1   12:D     1 procedure SETUSR;
1   12:0     0    begin
1   12:1     0      CLEARTTY; writeln('Build your own device....');
1   12:1    47      write('Which one (1 or 2)'); read(CH);
1   12:1    88      if (CH='1') or (CH='2') then begin
1   12:3   101        CLEARTTY; for I:=0 to 15 do begin
1   12:5   114                    gotoxy((I+3),0); write(chr(I+65)); end;
1   12:3   140         for I:=1 to 16 do begin gotoxy(0,I); write(chr(I+64)); end;
1   12:3   175         if (CH='1') then USR:=true else USR:=false;
1   12:3   192         for I:=0 to 15 do
1   12:4   203          for K:=15 downto 0 do
1   12:5   214            begin gotoxy((15-K+3),(I+1)); read(CH);
1   12:6   236               BIT:=true;
1   12:6   240                case ord(CH) of
1   12:6   245                27: exit(SETUSR); (* ESC *)
1   12:6   251                32: BIT:=false;    (* SPACE *)
1   12:6   257                 8: begin if K<13 then K:=K+2 else
1   12:9   269                    begin K:=1; if I<>0 then I:=I-1; end;
1   12:8   282                    BIT:=false; end; (* BACK-SPACE *)
1   12:6   288                end; (* end of case *)
1   12:6   346               if USR then USER1[15-I,15-K]:=BIT else USER2[15-I,15-K]:=BIT;
1   12:5   399             end;
1   12:3   413      writeln; writeln; writeln('Select <draw from> point (X,Y) >> ');
1   12:3   483      read(CH); I:=(ord(CH)-65); read(CH); J:=(ord(CH)-65);
1   12:3   519                    if J>15 then J:=15; if I>15 then I:=15;
1   12:3   535                    if J<0 then J:=0; if I<0 then I:=0;
1   12:3   551                    if USR then begin USR1X:=I; USR1Y:=15-J; end
1   12:3   564                            else begin USR2X:=I; USR2Y:=15-J; end;
1   12:3   574      writeln; write('Saving user device on disk');
1   12:3   620      rewrite(USERFILE,'USER.CHARSET');
1   12:3   645      USERFILE^:=USER1; put(USERFILE);
1   12:3   660      USERFILE^:=USER2; put(USERFILE);
1   12:3   675      CONVERTO;
1   12:3   677      USERFILE^:=USER3; put(USERFILE);
1   12:3   692      close(USERFILE , lock);
1   12:2   701      end;
1   12:0   701    end;
1   12:0   728 (*$P*)
1   12:0   728 (***************  EXT  **********************************
1   12:0   728 *                                                         *
1   12:0   728 *       The only legitimate exit from LOGICDESIGN         *
1   12:0   728 *                                                         *
1   12:0   728 *       Called by : MENU                                  *
1   12:0   728 *                                                         *
1   12:0   728 ***********************************************************)
1   13:D     1 procedure EXT;
1   13:0     0         begin
1   13:1     0           SAFETY:=true;
1   13:1     4           CLEARTTY;
1   13:1     6           write('Do you want to save the screen ?'); read(CH); writeln;
1   13:1    69           if (CH='y') or (CH='Y') then SAVESCREEN;
1   13:1    84           if SAFETY then exit(program);
1   13:1    93           if not SAFETY then begin writeln; writeln;
1   13:3   115             write('The screen was NOT saved. Do you want to exit anyway ?');
1   13:3   181             read(CH); if (CH='Y') or (CH='y') then exit(program); end;
1   13:0   209         end;
1   13:0   222
1   13:0   222 (**********************************************************
1   13:0   222 *                                                         *
1   13:0   222 *       Sound-off when ready to go...                     *
1   13:0   222 *                                                         *
1   13:0   222 *       Called by : BORDER,Main.                          *
1   13:0   222 *                                                         *
1   13:0   222 ***********************************************************)
1   14:D     1 procedure BEEPREADY;
1   14:0     0         begin
1   14:1     0           PITCH:=24; DURATION:=15; BEEP;
1   14:0     8         end;
1   14:0    20
1   14:0    20 (*$I PART3.TEXT*)
1   14:0    20 (*$I PART4.TEXT*)
1   14:0    20 (*$P*)  (* Part4 of LOGICDESIGN *)
1   14:0    20
1   14:0    20 (***************  GETXY  *********************************
1   14:0    20 *                                                         *
1   14:0    20 *       Read tablet and get the X & Y coordinates.        *
1   14:0    20 *       Determine if X & Y are on screen (VALIDXY).       *
1   14:0    20 *                                                         *
1   14:0    20 *       Called by : MENU,DRAWLINE,EATLINE,SETLOCK,        *
1   14:0    20 *                   WRITEONSCREEN,CLEARBLOCK,Main         *
1   14:0    20 *
```

Listing 3 continued on page 422

Listing 3 continued:

```
1   14:0    20 ********************************************************)
1   15:D     1 procedure GETXY;
1   15:D     1         var B1,B6,B7,B8,
1   15:D     1             B9 : integer;
1   15:0     0         begin
1   15:1     0           B1:=640; B9:=648;
1   15:1    10           B6:=645; B7:=646; B8:=647;
1   15:1    25           repeat READPAD;
1   15:2    27             PEN:=peek(B1);
1   15:2    36             X:=256*(peek(B7))+peek(B6);
1   15:2    57             Y:=256*(peek(B9))+peek(B8);
1   15:2    78             if FLAG then begin              (* for debugging - displays *)
1   15:4    83               gotoxy(0,23);                 (* X & Y on screen          *)
1   15:4    88               write('X = ',X,'  Y = ',Y,'      ');
1   15:3   159             end;
1   15:2   159             if KEY then                     (* exit on keypress *)
1   15:3   165              begin
1   15:4   165                VALIDXY:=false;
1   15:4   169                X:=-100; Y:=-100;
1   15:4   177                exit(GETXY);
1   15:3   181              end;
1   15:1   181           until PEN=2;                      (* pen just went down *)
1   15:1   187           if (X>=0)
1   15:1   190              and (X<280)
1   15:1   195              and (Y>=0)
1   15:1   199              and (Y<192)
1   15:1   205              then VALIDXY:=true
1   15:1   208              else VALIDXY:=false;
1   15:1   218           if VALIDXY then Y:=191-Y;         (* Y axis inverted in Pascal *)
1   15:0   230         end;
1   15:0   244
1   15:0   244 (*$P*)
1   15:0   244 (***************  PRINTYPE  *****************************
1   15:0   244 *                                                       *
1   15:0   244 *       Prints out the name of the device that will     *
1   15:0   244 *       be plotted. Determined by the value of D.       *
1   15:0   244 *                                                       *
1   15:0   244 *       Called by : LISTALL,GETYPE                      *
1   15:0   244 *                                                       :
1   15:0   244 ********************************************************)
1   16:D     1 procedure PRINTYPE;
1   16:0     0         begin
1   16:1     0             case D of
1   16:1     3             0:IDENT:='** INVALID **   ';
1   16:1    29             1:IDENT:='tri-state buffer';
1   16:1    55             2:IDENT:='output arrow    ';
1   16:1    81             3:IDENT:='input arrow     ';
1   16:1   107             4:IDENT:='D flip-flop     ';
1   16:1   133             5:IDENT:='JK flip-flop    ';
1   16:1   159             6:IDENT:='MSI box (vert)  ';
1   16:1   185             7:IDENT:='connection dot  ';
1   16:1   211             8:IDENT:='resistor (horiz)';
1   16:1   237             9:IDENT:='capacitor (vert)';
1   16:1   263             10:IDENT:='gnd             ';
1   16:1   289             11:IDENT:='plus 5          ';
1   16:1   315             12:IDENT:='exclusive-nor   ';
1   16:1   341             13:IDENT:='exclusive-or    ';
1   16:1   367             14:IDENT:='nor gate        ';
1   16:1   393             15:IDENT:='or gate         ';
1   16:1   419             16:IDENT:='nand gate       ';
1   16:1   445             17:IDENT:='and gate        ';
1   16:1   471             18:IDENT:='invert symbol   ';
1   16:1   497             19:IDENT:='inverter        ';
1   16:1   523             20:IDENT:='zener diode     ';
1   16:1   549             21:IDENT:='vertical arrow  ';
1   16:1   575             22:IDENT:='crystal         ';
1   16:1   601             23:IDENT:='minidip         ';
1   16:1   627             24:IDENT:='switch          ';
1   16:1   653             25:IDENT:='battery         ';
1   16:1   679             27:IDENT:='pnp transistor  ';
1   16:1   705             26:IDENT:='npn transistor  ';
1   16:1   731             28:IDENT:='op amp          ';
1   16:1   757             29:IDENT:='diode (horiz)   ';
1   16:1   783             30:IDENT:='diode (vert)    ';
1   16:1   809             31:IDENT:='cap(horiz)      ';
1   16:1   835             32:IDENT:='MSI box (horiz) ';
1   16:1   861             34:IDENT:='coil (left side)';
1   16:1   887             33:IDENT:='transformer     ';
1   16:1   913             35:IDENT:='resistor (vert) ';
1   16:1   939             36:IDENT:='user1           ';
1   16:1   965             37:IDENT:='user2           ';
```

```
1   16:1   991             end;
1   16:1  1074             write(IDENT);
1   16:0  1086          end;
1   16:0  1102
1   16:0  1102 (*$I PART4.TEXT*)
1   16:0  1102 (*$I PART5.TEXT*)
1   16:0  1102 (*$P*)  (* Part5 of LOGICDESIGN *)
1   16:0  1102
1   16:0  1102 (***************  LISTALL  *****************************
1   16:0  1102 *                                                       *
1   16:0  1102 *       List all the names of all the devices that      *
1   16:0  1102 *       can be plotted on the text screen.              *
1   16:0  1102 *                                                       *
1   16:0  1102 *       Called by : MENU                                *
1   16:0  1102 *                                                       *
1   16:0  1102 *********************************************************)
1   17:D     1 procedure LISTALL;
1   17:0     0         begin
1   17:1     0           CLEARTTY;
1   17:1     2           for I:=1 to 18 do begin
1   17:3    13           write(I,' - '); D:=I; PRINTYPE;
1   17:3    43           write(chr(9),' ',chr(9),I+18,' - ');
1   17:3   100           D:=I+18; PRINTYPE;
1   17:3   107           writeln;
1   17:2   115           end;
1   17:0   122         end;
1   17:0   136
1   17:0   136 (***************  BORDER  ******************************
1   17:0   136 *                                                       *
1   17:0   136 *       Draws or Erases the border around the HIRES     *
1   17:0   136 *       screen.                                         *
1   17:0   136 *                                                       *
1   17:0   136 *       Called by : MENU                                *
1   17:0   136 *                                                       *
1   17:0   136 *********************************************************)
1   18:D     1 procedure BORDER;
1   18:0     0         begin
1   18:1     0           CLEARTTY;  X:=0; Y:=0; pencolor(none); moveto(X,Y);
1   18:1    17           if CH='F' then pencolor(black) else pencolor(white);
1   18:1    34           X:=279; moveto(X,Y); Y:=191; moveto(X,Y);
1   18:1    54           X:=0; moveto(X,Y); Y:=0; moveto(X,Y);
1   18:1    70           BEEPREADY;
1   18:0    72         end;
1   18:0    84
1   18:0    84 (***** FORWARD REFRENCES *****)
1   18:0    84
1   19:D     1 procedure LISTMODE; forward;
1   19:D     1
1   20:D     1 procedure MENU; forward;
1   20:D     1
1   21:D     1 procedure CANCEL; forward;
1   21:D     1
1   21:D     1 (*$P*)
1   21:D     1 (***************  GETYPE  ******************************
1   21:D     1 *                                                       *
1   21:D     1 *       Sets up text display to show what is being      *
1   21:D     1 *       plotted and the status of the X & Y locks.      *
1   21:D     1 *                                                       *
1   21:D     1 *       Called by : MENU                                *
1   21:D     1 *                                                       *
1   21:D     1 *********************************************************)
1   22:D     1 procedure GETYPE;
1   22:0     0         begin
1   22:1     0           CLEARTTY; gotoxy(0,19);
1   22:1     7           write('Device type >> '); PRINTYPE; CH:='P'; LISTMODE;
1   22:0    42         end;
1   22:0    54
1   22:0    54 (***************  TESTLAST  ****************************
1   22:0    54 *                                                       *
1   22:0    54 *       Sets up conditions for deleting the last        *
1   22:0    54 *       device plotted. (Activated by the CLEAR         *
1   22:0    54 *       pad in the upper left corner of the tablet).    *
1   22:0    54 *                                                       *
1   22:0    54 *       Called by : MYPLOT                              *
1   22:0    54 *                                                       *
1   22:0    54 *********************************************************)
1   23:D     1 procedure TESTLAST;
1   23:0     0         begin
1   23:1     0           if (X>-45) and (X<-30) and (Y>-65) and (Y<-50) then begin
1   23:3    21             BIT:=false; X:=LASTX; Y:=LASTY; DMODE:=6; D:=LASTD; VALIDXY:=true;
1   23:2    41           end;
1   23:0    41          end;
```

Listing 3 continued on page 424

Listing 3 continued:

```
1   23:0    54
1   23:0    54
1   23:0    54 (*$P*)
1   23:0    54 (***************  MYPLOT  ******************************
1   23:0    54 *                                                       *
1   23:0    54 *        Plots a device if X & Y are valid,             *
1   23:0    54 *        calls MENU if not.                             *
1   23:0    54 *                                                       *
1   23:0    54 *        Called by : Main program loop.                 *
1   23:0    54 *                                                       *
1   23:0    54 *********************************************************)
1   24:D     1 procedure MYPLOT;
1   24:0     0       begin
1   24:1     0         pencolor(white); TESTLAST;
1   24:1     6         if not VALIDXY then MENU;
1   24:1    14         if D=0 then exit(MYPLOT);
1   24:1    23         if BIT then begin if LOCKY then X:=LASTX; if LOCKX then Y:=LASTY; end;
1   24:1    44         if VALIDXY then case D of
1   24:2    52           1:drawblock(BUFFER,2,0,0,16,16,X,Y-9,DMODE);
1   24:2    70           2:drawblock(OUT,2,0,0,16,16,X,Y-12,DMODE);
1   24:2    88           3:drawblock(INTHING,2,0,0,16,16,X,Y-12,DMODE);
1   24:2   106           4:begin drawblock(DTOP,2,0,0,16,16,X,Y,DMODE);
1   24:4   120                   drawblock(DBOT,2,0,0,16,16,X,Y-16,DMODE); end;
1   24:2   138           5:begin drawblock(JKTOP,2,0,0,16,16,X,Y,DMODE);
1   24:4   152                   drawblock(JKBOT,2,0,0,16,16,X,Y-16,DMODE); end;
1   24:2   170           6:begin drawblock(MSITOP,2,0,0,16,16,X,Y,DMODE);
1   24:4   184                   drawblock(MSIBOT,2,0,0,16,16,X,Y-16,DMODE); end;
1   24:2   202           7:drawblock(DOT,2,0,0,16,16,X-2,Y-13,DMODE);
1   24:2   222           8:drawblock(RESISTOR,2,0,0,16,16,X,Y-14,DMODE);
1   24:2   240           9:drawblock(CAP,2,0,0,16,16,X-3,Y-16,DMODE);
1   24:2   260           10:drawblock(GND,2,0,0,16,16,X-3,Y-16,DMODE);
1   24:2   280           11:drawblock(PLUS5,2,0,0,16,16,X-2,Y-5,DMODE);
1   24:2   300           12:drawblock(XNOR,2,0,0,16,16,X,Y-10,DMODE);
1   24:2   318           13:drawblock(XOR,2,0,0,16,16,X,Y-10,DMODE);
1   24:2   336           14:drawblock(NOR,2,0,0,16,16,X,Y-10,DMODE);
1   24:2   354           15:drawblock(ORGATE,2,0,0,16,16,X,Y-10,DMODE);
1   24:2   372           16:drawblock(NAND,2,0,0,16,16,X,Y-10,DMODE);
1   24:2   390           17:drawblock(ANDGATE,2,0,0,16,16,X,Y-10,DMODE);
1   24:2   408           18:drawblock(INV,2,0,0,16,16,X,Y-14,DMODE);
1   24:2   426           19:drawblock(INVERTER,2,0,0,16,16,X,Y-10,DMODE);
1   24:2   444           20:drawblock(ZENER,2,0,0,16,16,X-4,Y-16,DMODE);
1   24:2   463           21:drawblock(WIPER,2,0,0,16,16,X-1,Y-16,DMODE);
1   24:2   483           22:drawblock(XTAL,2,0,0,16,16,X,Y-11,DMODE);
1   24:2   501           23:drawblock(MINIDIP,2,0,0,16,16,X,Y-8,DMODE);
1   24:2   519           24:drawblock(SW,2,0,0,16,16,X,Y-11,DMODE);
1   24:2   537           25:drawblock(BAT,2,0,0,16,16,X,Y-12,DMODE);
1   24:2   555           26:drawblock(PNP,2,0,0,16,16,X,Y-8,DMODE);
1   24:2   573           27:drawblock(NPN,2,0,0,16,16,X,Y-8,DMODE);
1   24:2   591           28:drawblock(OPAMP,2,0,0,16,16,X-2,Y-8,DMODE);
1   24:2   611           29:drawblock(HDIODE,2,0,0,16,16,X,Y-12,DMODE);
1   24:2   629           30:drawblock(DIODE,2,0,0,16,16,X-3,Y-16,DMODE);
1   24:2   649           31:drawblock(HCAP,2,0,0,16,16,X,Y-12,DMODE);
1   24:2   667           32:begin drawblock(HMSIL,2,0,0,16,16,X-16,Y-7,DMODE);
1   24:4   685                    drawblock(HMSIR,2,0,0,16,16,X,Y-7,DMODE); end;
1   24:2   703           33:begin drawblock(RCOIL,2,0,0,16,16,X-3,Y-16,DMODE);
1   24:4   720                    drawblock(LCOIL,2,0,0,16,16,X+3,Y-16,DMODE); end;
1   24:2   739           34:drawblock(RCOIL,2,0,0,16,16,X-3,Y-16,DMODE);
1   24:2   758           35:drawblock(VRESIST,2,0,0,16,16,X-1,Y-16,DMODE);
1   24:2   777           36:drawblock(USER1,2,0,0,16,16,X-USR1X,Y-USR1Y,DMODE);
1   24:2   796           37:drawblock(USER2,2,0,0,16,16,X-USR2X,Y-USR2Y,DMODE);
1   24:2   815           end; (* OF CASE STMNT *)
1   24:1   896           PITCH:=D+5; DURATION:=5; BEEP; DMODE:=14;
1   24:1   909           if VALIDXY then begin LASTX:=X; LASTY:=Y; LASTD:=D; end;
1   24:1   923           if not BIT then begin BIT:=true; D:=0; CANCEL; end;
1   24:0   938         end;
1   24:0   956 (*$I PART5.TEXT*)
1   24:0   956 (*$I PART6.TEXT*)
1   24:0   956 (*$P*)  (* Part6 of LOGICDESIGN *)
1   24:0   956
1   24:0   956 (***************  DRAWLINE  *****************************
1   24:0   956 *                                                       *
1   24:0   956 *        Draws horizontal or vertical lines only.       *
1   24:0   956 *        Exits on not VALIDXY (or keypress).            *
1   24:0   956 *                                                       *
1   24:0   956 *        Called by : MENU                               *
1   24:0   956 *                                                       *
1   24:0   956 *********************************************************)
1   25:D     1 procedure DRAWLINE;
1   25:D     1         var OLDX,OLDY : integer;
1   25:0     0         begin
```

```
1   25:1     0           GETXY; BEEP; pencolor(none);
1   25:1     8           moveto(X,Y); pencolor(white);
1   25:1    17           while VALIDXY do begin
1   25:3    22             OLDX:=X; OLDY:=Y; GETXY; BEEP;
1   25:3    32             if abs(OLDX-X) > abs(OLDY-Y) then Y:=OLDY else X:=OLDX;
1   25:3    51             if VALIDXY then moveto(X,Y);
1   25:2    61           end;
1   25:0    63         end;
1   25:0    78
1   25:0    78 (***************  EATLINE  *****************************
1   25:0    78 *                                                       *
1   25:0    78 *       Deletes lines in any one direction until        *
1   25:0    78 *       it runs out of line.                            *
1   25:0    78 *                                                       *
1   25:0    78 *       Called by : MENU                                *
1   25:0    78 *                                                       *
1   25:0    78 *********************************************************)
1   26:D     1 procedure EATLINE;
1   26:0     0         begin
1   26:1     0           repeat GETXY; until ((screenbit(x,y)) or (not VALIDXY));
1   26:1    16           if screenbit(X,Y) then
1   26:2    25            begin
1   26:3    25              PITCH:=5; DURATION:=12; BEEP;
1   26:3    33              pencolor(none); moveto(X,Y);
1   26:3    42              pencolor(black);
1   26:3    46              while screenbit(X,Y) do
1   26:4    55              begin
1   26:5    55                moveto(X,Y);
1   26:5    60                case CH of
1   26:5    65                'H': X:=X+1;            (* to the right *)
1   26:5    72                'I': X:=X-1;            (* to the left  *)
1   26:5    79                'J': Y:=Y+1;            (* going up     *)
1   26:5    86                'K': Y:=Y-1;            (* and down     *)
1   26:5    93                end;
1   26:4   108              end;
1   26:2   110            end;
1   26:0   110          end;
1   26:0   126
```

Listing 3 continued on page 426

Listing 3 continued:

```
1   26:0   126 (*$P*)
1   26:0   126 (****************  LISTMODE  ******************************
1   26:0   126 *                                                          *
1   26:0   126 *       More info for the text screen.                     *
1   26:0   126 *                                                          *
1   26:0   126 *       Called by : MENU,GETYPE,Main                       *
1   26:0   126 *                                                          *
1   26:0   126 ***********************************************************)
1   19:D     1 procedure LISTMODE;
1   19:0     0      begin
1   19:1     0        gotoxy(0,15); write('Mode = ');
1   19:1    24        case CH of
1   19:1    29        'A': write('Clear an area on screen - contact any 2 diagonal corners');
1   19:1    99        'G': write('Draw lines');
1   19:1   123        'H': write('Delete lines - to the right');
1   19:1   164        'I': write('Delete lines - to the left');
1   19:1   204        'J': write('Delete lines - going up');
1   19:1   241        'K': write('Delete lines - going down');
1   19:1   280        'P': begin  write('Plot devices'); gotoxy(17,5);
1   19:3   309          if LOCKY then write('<<< HORIZONTAL AXIS IS LOCKED AT ',LASTY,' >>>');
1   19:3   385          if LOCKX then write('<<< VERTICAL AXIS IS LOCKED AT ',LASTX,' >>>');
1   19:3   459          if (not LOCKX) and (not LOCKY) then write
1   19:4   470          ('                                              '); end;
1   19:1   524        'B','C','D': write('Setup lock');
1   19:1   548        'E': write('Transfering screen to printer - cancel with any key');
1   19:1   613        'Z': write(' ?????????? ');
1   19:1   639        end;
1   19:1   698        gotoxy(17,5);
1   19:1   703         if (not LOCKX) and (not LOCKY) then write
1   19:2   714        ('                                        ');
1   19:0   758      end;
1   19:0   774
1   19:0   774 (***************  SETLOCK  ********************************
1   19:0   774 *                                                          *
1   19:0   774 *       Sets up (or clears) the horizontal and             *
1   19:0   774 *       vertical locks for neat plotting.                  *
1   19:0   774 *                                                          *
1   19:0   774 *       Called by : MENU                                   *
1   19:0   774 *                                                          *
1   19:0   774 ***********************************************************)
1   27:D     1 procedure SETLOCK;
1   27:0     0        begin
1   27:1     0          case CH of
1   27:1     5          'C': begin writeln; writeln; write('Use pen to select row.');
1   27:3    55                     repeat GETXY; until VALIDXY; LASTX:=X; LASTY:=Y;
1   27:3    68                     LOCKX:=true; LOCKY:=false; end;
1   27:1    78          'D': begin writeln; writeln; write('Use pen to select column.');
1   27:3   131                     repeat GETXY; until VALIDXY; LASTX:=X; LASTY:=Y;
1   27:3   144                     LOCKX:=false; LOCKY:=true; end;
1   27:1   154          'B': begin LOCKX:=false; LOCKY:=false; end;
1   27:1   164          end;
1   27:0   178        end;
1   27:0   196
1   27:0   196 (*$I PART6.TEXT*)
1   27:0   196 (*$I PART7.TEXT*)
1   27:0   196 (*$P*)  (* Part7 of LOGICDESIGN *)
1   27:0   196
1   27:0   196 (***************  WRITEONSCREEN  ************************
1   27:0   196 *                                                          *
1   27:0   196 *       Overlays strings on HIRES screen 1.                *
1   27:0   196 *       Labels can be horiz or vertical.                   *
1   27:0   196 *                                                          *
1   27:0   196 *       Called by : MENU                                   *
1   27:0   196 *                                                          *
1   27:0   196 ***********************************************************)
1   28:D     1 procedure WRITEONSCREEN;
1   28:D     1        var ST : string;
1   28:D    42            C1 : char;
1   28:0     0        begin
1   28:1     0          CLEARTTY; write('H(orizontal or V(ertical labels?'); read(CH);
1   28:1    57          writeln; writeln; write('Enter label -> ');
1   28:1   100          readln(ST); GETXY;
1   28:1   121          chartype(6);
1   28:1   125          pencolor(none);
1   28:1   129          while VALIDXY do begin
1   28:3   134            case CH of
1   28:3   139            'h','H': begin moveto(X,Y); wstring(ST);  end;
1   28:3   151            'v','V': begin for I:=1 to length(st) do
1   28:6   166                     begin moveto(X,Y); C1:=ST[I]; wchar(C1); Y:=Y-9;  end;
1   28:4   195                     end;
1   28:3   197            end;
```

```
  1   28:3   298           GETXY;
  1   28:2   300           end; (* of while loop *)
  1   28:Ø   302         end;
  1   28:Ø   322
  1   28:Ø   322 (***************  CLEARBLOCK  ***************************
  1   28:Ø   322 *                                                       *
  1   28:Ø   322 *       Deletes a portion of the screen delimited       *
  1   28:Ø   322 *       by any two diagonal corners.                    *
  1   28:Ø   322 *                                                       *
  1   28:Ø   322 *       Called by : MENU                                *
  1   28:Ø   322 *                                                       *
  1   28:Ø   322 *********************************************************)
  1   29:D     1 procedure CLEARBLOCK;
  1   29:D     1         var X1,Y1,X2,Y2 : integer;
  1   29:Ø     Ø         begin
  1   29:1     Ø            GETXY; BEEP; X1:=X; Y1:=Y; if not VALIDXY then exit(CLEARBLOCK);
  1   29:1    2Ø            GETXY; BEEP; X2:=X; Y2:=Y; if not VALIDXY then exit(CLEARBLOCK);
  1   29:1    4Ø            pencolor(none);
  1   29:1    44            if X < X1 then begin X2:=X1; X1:=X; end;
  1   29:1    55            if Y < Y1 then begin Y2:=Y1; Y1:=Y; end;
  1   29:1    66            for I:=X1 to X2 do begin
  1   29:3    77              moveto(I,Y1); pencolor(black);
  1   29:3    86              moveto(I,Y2); end;
  1   29:Ø    98           end;
  1   29:Ø   112
  1   29:Ø   112 (*$P*)
  1   29:Ø   112 (***************  PRINTOUT  *****************************
  1   29:Ø   112 *                                                      *
  1   29:Ø   112 *       Transfers HIRES screen 1 to the printer.       *
  1   29:Ø   112 *       (In this case a Hytype I with limited          *
  1   29:Ø   112 *       graphics capability.) There are a number of    *
  1   29:Ø   112 *       local procedures which can be changed as       *
  1   29:Ø   112 *       required for other printers.                   *
  1   29:Ø   112 *                                                      *
  1   29:Ø   112 *       Called by : MENU                               *
  1   29:Ø   112 *                                                      *
  1   29:Ø   112 *********************************************************)
  1   30:D     1 procedure PRINTOUT;
  1   30:D     1         const  XMAX=279; YMAX=191;
  1   30:D     1                CR=13; LF=1Ø; ACK=6; BELL=7;
  1   30:D     1
  1   30:D     1         (***** LOCAL PROCEDURES *****)
  1   30:D     1
  1   31:D     1         procedure PRINT(X:char);          (* sends 1 character to printer *)
  1   31:Ø     Ø           begin
  1   31:1     Ø             unitwrite(6,X,1,,1);
  1   31:Ø     9           end;
  1   31:Ø    22
  1   32:D     1         procedure CRLF;                   (* in graphics mode does a CR and *)
  1   32:Ø     Ø           begin                           (* small LF .. 1/48th inch ..     *)
  1   32:1     Ø             PRINT(chr(CR)); PRINT(chr(LF));
  1   32:Ø     6           end;
  1   32:Ø    18
  1   33:D     1         procedure SETPRINTER;             (* BELL sets Text mode, ACK sets *)
  1   33:Ø     Ø           begin                           (* Graphics mode on printer.     *)
  1   33:1     Ø             PRINT(chr(BELL)); PRINT(chr(ACK));
  1   33:Ø     6           end;
  1   33:Ø    18
  1   34:D     1          procedure CLEARPRINTER;
  1   34:Ø     Ø            begin
  1   34:1     Ø            PRINT(chr(BELL)); CRLF;
  1   34:Ø     5            end;
  1   34:Ø    18
  1   35:D     3          function LASTTRUE(J:integer) : integer;       (* Finds the location *)
  1   35:Ø     Ø            begin                                     (* of the last dot in *)
  1   35:1     Ø             K:=XMAX;                                 (* in the line. Saves *)
  1   35:1     5              repeat K:=K-1                           (* time at 3ØØ baud   *)
  1   35:1     6              until ((screenbit(K,YMAX-J)) or (K=Ø));
  1   35:1    27             LASTTRUE:=K;
  1   35:Ø    3Ø            end;
  1   35:Ø    44
  1   35:Ø    44 (*$P*)
  1   36:D     1          procedure PRINTIT;               (* does the real work *)
  1   36:Ø     Ø            begin
  1   36:1     Ø              if KEY then I:=Ø; (* clears keyboard strobe *)
  1   36:1     9              pencolor(none);
  1   36:1    13               for J:=Ø to YMAX do
  1   36:2    26                begin
  1   36:3    26                  for I:=Ø to LASTTRUE(J) do
  1   36:4    41                   begin
  1   36:5    41                     pencolor(none); moveto(I-1,YMAX-J);
```

Listing 3 continued on page 428

```
1   36:5    56                  if screenbit(I,YMAX-J) then PRINT('.');
1   36:5    72                  PRINT(' '); PRINT(' ');
1   36:5    78                  pencolor(reverse); moveto(I,YMAX-J);
1   36:4    91                end;
1   36:3    98               CRLF; moveto(I-1,YMAX-J); pencolor(none);
1   36:3   115               if KEY then exit(PRINTIT);
1   36:2   125             end;
1   36:0   132         end;
1   36:0   148
1   30:0     0   begin                    (* procedure PRINTOUT *)
1   30:1     0     write(chr(25));
1   30:1    10     write('Print the screen (takes a while) - Type "Y" to start.');
1   30:1    75     read(CH); writeln; if (CH='Y') or (CH='y') then
1   30:2   107            begin
1   30:3   107              SETPRINTER;
1   30:3   109              PRINTIT;
1   30:3   111              CLEARPRINTER;
1   30:3   113              CRLF;
1   30:2   115            end;
1   30:0   115   end;
1   30:0   128
1   30:0   128 (*$P*)
1   30:0   128 (***************  CLEARSCREEN  **************************
1   30:0   128 *                                                        *
1   30:0   128 *       Clears Hires screen 1.                           *
1   30:0   128 *                                                        *
1   30:0   128 *       Called by : MENU                                 *
1   30:0   128 *                                                        *
1   30:0   128 *********************************************************)
1   37:D     1 procedure CLEARSCREEN;
1   37:0     0         begin
1   37:1     0           CLEARTTY; write('CLEAR THE SCREEN - Are you sure? (Y/N)');
1   37:1    52           read(CH); if (CH='Y') or (CH='y') then initturtle;
1   37:0    79         end;
1   37:0    92
1   37:0    92 (***************  CANCEL  *******************************
1   37:0    92 *                                                        *
1   37:0    92 *       Fixes Text screen on leaving any command.        *
1   37:0    92 *                                                        *
1   37:0    92 *       Called by : MENU,MYPLOT,Main                     *
1   37:0    92 *                                                        *
1   37:0    92 *********************************************************)
1   21:D     1 procedure CANCEL;
1   21:0     0         begin
1   21:1     0            CLEARTTY; gotoxy(27,12); write('*** NO MODE ACTIVE ***');
1   21:1    41            PITCH:=6; DURATION:=3; BEEP; PITCH:=4; DURATION:=6; BEEP;
1   21:1    57            D:=0; CH:='Z';
1   21:0    64         end;
1   21:0    76
1   21:0    76 (***************  ACCEPT  *******************************
1   21:0    76 *                                                        *
1   21:0    76 *       Beeps when a MENU command is acceptable.         *
1   21:0    76 *                                                        *
1   21:0    76 *       Called by : MENU                                 *
1   21:0    76 *                                                        *
1   21:0    76 *********************************************************)
1   38:D     1 procedure ACCEPT;
1   38:0     0         begin
1   38:1     0           PITCH:=(X div 16) + 5; DURATION:=7; BEEP;
1   38:0    12         end;
1   38:0    24
1   38:0    24
1   38:0    24 (*$I PART7.TEXT*)
1   38:0    24 (*$I PART8.TEXT*)
1   38:0    24 (*$P*)  (* Part8 of LOGICDESIGN *)
1   38:0    24
1   38:0    24 (***************  MENU  *********************************
1   38:0    24 *                                                        *
1   38:0    24 *       Main mode selection happens here.                *
1   38:0    24 *                                                        *
1   38:0    24 *       Called by : MYPLOT                               *
1   38:0    24 *                                                        *
1   38:0    24 *********************************************************)
1   20:D     1 procedure MENU;
1   20:D     1         var XPOS, YPOS : integer;
1   20:0     0         begin
1   20:1     0          D:=0;
1   20:1     3          XPOS:=trunc((X+65) / 16.0);     (* actual value of the divisor *)
1   20:1    18          YPOS:=trunc((Y-224) / 16.0);    (* may vary from Tablet to Tablet *)
```

```
 1   20:1    36          case YPOS of
 1   20:1    39          3: case XPOS of             (* Bottom row, left to right *)
 1   20:2    42               0: begin CLEARSCREEN; CANCEL; end;
 1   20:2    48               1: begin CH:='A'; CLEARTTY; LISTMODE;
 1   20:4    56                      ACCEPT; CLEARBLOCK; CANCEL; end;
 1   20:2    64               2: begin CH:='B'; CLEARTTY; LISTMODE;
 1   20:4    72                      ACCEPT; SETLOCK; CANCEL; end;
 1   20:2    80               3: begin CH:='D'; CLEARTTY; LISTMODE;
 1   20:4    88                      ACCEPT; SETLOCK; CANCEL; end;
 1   20:2    96               4: begin CH:='C'; CLEARTTY; LISTMODE;
 1   20:4   104                      ACCEPT; SETLOCK; CANCEL; end;
 1   20:2   112               5: begin LISTALL; end;
 1   20:2   116               6: begin ACCEPT; LOADSCREEN; CANCEL; end;
 1   20:2   124               7: begin ACCEPT; SAVESCREEN; CANCEL; end;
 1   20:2   132               8: EXT;
 1   20:2   136               9: begin CH:='E'; CLEARTTY; LISTMODE;
 1   20:4   144                      ACCEPT; PRINTOUT; CANCEL; end;
 1   20:2   152               10: begin CH:='F'; BORDER; CANCEL; end;
 1   20:2   162               11: begin CH:='L'; BORDER; CANCEL; end;
 1   20:2   172               12: begin ACCEPT; WRITEONSCREEN; CANCEL; exit(MYPLOT); end;
 1   20:2   184               13,14: begin CH:='G'; CLEARTTY; LISTMODE;
 1   20:4   192                    ACCEPT; DRAWLINE; CANCEL; end;
 1   20:2   200               15: begin CH:='H'; CLEARTTY; LISTMODE;
 1   20:4   208                       ACCEPT; EATLINE; CANCEL; end;
 1   20:2   216               16: begin CH:='I'; CLEARTTY; LISTMODE;
 1   20:4   224                       ACCEPT; EATLINE; CANCEL; end;
 1   20:2   232               17: begin CH:='J'; CLEARTTY; LISTMODE;
 1   20:4   240                       ACCEPT; EATLINE; CANCEL; end;
 1   20:2   248               18: begin CH:='K'; CLEARTTY; LISTMODE;
 1   20:4   256                       ACCEPT; EATLINE; CANCEL; end;
 1   20:2   264               19,20 : begin ACCEPT; SETUSR; CANCEL; exit(MYPLOT); end;
 1   20:2   276               21: FLAG:=not FLAG;
 1   20:2   285             end; (* of YPOS=3 *)
 1   20:1   338          2: begin D:=XPOS+1; if D>19 then D:=0; GETYPE; end;
 1   20:1   355          1: begin D:=XPOS+20; if D>37 then D:=0; GETYPE; end;
 1   20:1   372        end; (* of YPOS case stmt *)
 1   20:0   386      end;
 1   20:0   404
 1   20:0   404 (*$P*)
 1   20:0   404 (****************  MAIN PROGRAM LOOP  ********************
 1   20:0   404 *                                                        *
 1   20:0   404 *       Calls the initialization routines, loads         *
 1   20:0   404 *       shapes, loops in MYPLOT till the EXIT            *
 1   20:0   404 *       routine is called.                               *
 1   20:0   404 *                                                        *
 1   20:0   404 **********************************************************)
 1    1:0     0 begin
 1    1:0     0  (* initialize booleans *)
 1    1:1     0  SAFETY:=true;
 1    1:1    26  HELLFREEZESOVER:=false;
 1    1:1    30  FLAG:=false;
 1    1:1    34  LOCKX:=false;
 1    1:1    38  LOCKY:=false;
 1    1:1    42
 1    1:1    42  (* initialize ploting mode *)
 1    1:1    42  LASTD:=100; DMODE:=14;
 1    1:1    48  write('loading "LOGIC.CHARSET"'); GETSHAPES; writeln; BEEPREADY;
 1    1:1    95
 1    1:1    95  (* setup pad and screen *)
 1    1:1    95  SETUPAD;
 1    1:1    97  INITTURTLE;
 1    1:1   100
 1    1:1   100  (* setup text screen *)
 1    1:1   100  CANCEL; LISTMODE;
 1    1:1   104
 1    1:1   104  (* lets doit *)
 1    1:1   104  repeat
 1    1:2   104    GETXY; MYPLOT;
 1    1:1   108  until HELLFREEZESOVER;
 1    1:0   113 end.
```

ADVENTURE GAME
BY TOM SLOAN
I CAN REALLY GET INTO THIS ADVENTURE GAME.
COMMAND RUN ADVENTURE GAME
LET'S SEE NOW. I HAVE TO FIND THE BURIED TREASURE. I'M ON THE LEDGE OF THE 'TYPE MISMATCH MOUNTAIN'...
...THERE'S A TUNNEL NEARBY
I'LL GO IN.
INPUT
IT'S DARK IN HERE... I KNOW!, I'LL "LIGHT CANDLE"!
THERE... THATS BETTER
HELLO
AHH!
OH MAN! WHAT DO I DO NOW
LONGJOHN OVERFLOW APPEARS AND BLOCKS YOUR EXIT.
PIECES OF EIGHT BITS
OH LOOK!
SWISH
RUM
POLYMORPHIC WANNA CRACKER
HERE YOU GO.
YO HO HO
RUM
THAT GIVES HIM A HOBBY.
GEE. HERE'S THE RECTIFIER BRIDGE.
OH NO! A DIVIDE BY ZERO TROLL!
AHHHH
I MUST BE IN THE VALLEY OF THE DROPPED BITS.
CRASH
WHAT LUCK! I FOUND THE TREASURE
NOW I BETTER GET BACK BEFORE THESE SPECIAL CHARACTERS GET ME.
THERE ARE SOME OLD RUINS AHEAD
E PLURIBUS BAD PARAMETERS
OH-OH! THE SYNTAX MONSTER
AHH!
WOW! WHAT A WILD SITUATION TO BE IN.
SYNTAX MONSPER GRABS YOU
BUT THE ONLY TROUBLE IS THAT THE GAME IS NOT VERY REALISTIC.
TOM SLOAN

It's not hard . . .



to win with fast, reliable, mass storage

- The Cameo cartridge disk subsystem provides 40 to 100 times the storage capacity of floppy disks. Data transfer rates and reliability are correspondingly faster.
- Our cartridge feature lets you . . . COPY . . . BACK UP . . . EXTEND . . . or REMOVE your data base easily by just removing the disk pack as you now remove your floppy.
- The densely packed cartridges, although storing five million characters each, are byte-for-byte less expensive than floppy diskettes!
- Available on most 8-bit microprocessors (Apple, Heath, S-100, TRS-80 and others*) with most major operating systems (CPM, APPLE DOS, TRS DOS, OASIS, PASCAL, MPM, SCREEN EDIT and others*).

• CALL OR WRITE FOR MORE INFORMATION •

CAMEO ELECTRONICS INC.

1626 CLEMENTINE • ANAHEIM, CA 92802 • (714) 535-1682

*REGISTERED TRADE MARKS

Circle 54 on inquiry card.

Circle 225 on inquiry card.

What's New?

PERIPHERALS

Serial-Interface Board for Multibus

The Multibus Octal Serial Interface Board allows up to eight RS-232C interfaces to be hooked to any Multibus system. Each interface has a data-rate generator that enables users to set each USART (universal synchronous/asynchronous receiver/transmitter) at a different speed. The board allows 16-bit addressing and interrupt capabilities. Available data rates range from 50 to 19,200.

The Multibus Octal Serial Interface Board costs $435. For more information, contact Central Data Corporation, 713 Edgebrook Dr, Champaign IL 61820, (217) 359-8010.

Circle 500 on inquiry card.

Paper-Tape Reader for Hobbyists

The Model 605 paper-tape reader reads at 150 cps (characters per second), has a parallel TTL (transistor-transistor logic) output, and is bidirectional. It stops on character and has automatic taut-tape sensing. The reader has 5 V DC and 24 V DC output power available and an optional internal clock.

The 605 costs $495. It is available from Addmaster Corporation, 416 Junipero Serra Dr, San Gabriel CA 91776, (213) 285-1121.

Circle 501 on inquiry card.

Portable RS-232C Memory System

The MTL 900 is a portable cassette system for remote data gathering, memory downloading, and remote program updating. The unit uses a Braemar digital-cassette read/write unit with RS-232C interfacing. The necessary cable and connector assembly is included. Each miniature cassette holds up to 86 K bytes at 800 bits per inch. The MTL 900 has a data-transfer rate of 2400 bps (bits per second). Power is normally supplied from the host equipment, but internal AC or battery power supplies are available as options. The MTL 900 is priced at $425.

For additional information, contact Braemar Computer Devices Inc, 11950 12th Ave S, Burnsville MN 55337, (612) 890-5135.

Circle 502 on inquiry card.

Graphics Printer

The Model 84G graphics printer features a 7 by 7 or 14 by 7 dot matrix, six different character sizes, 100 cps (characters per second) bidirectional print speed, and selectable tractor or friction paper feed. It has variable line density and continuous form-length controls. Its high-resolution graphics capability can provide plotting, printing, videographics hard copy, and special-effect symbols. The printer has a 96-character ASCII set, upper- and lowercase printing, an 800-character buffer, a 100% duty cycle, and 40 to 132 characters per line. Operator controls include power, select/deselect, line-feed, top-of-form, self-test, and variable vertical-tab setting.

The 84G is $795. For more information, contact DIP Inc, 745 Atlantic Ave, Boston MA 02111, (617) 482-4214.

Circle 503 on inquiry card.

Thin, 58-Key Sealed Keyboard

The Model MK 058-001 keyboard meets the ergonometric (safety) standards now required by many European countries. The keyboard profile is approximately 0.4 inch. Key spacing, operating force, and row-offset of the MK 058-001 are that of a conventional typewriter. Normal specifications include 15 million mean characters between failure, 0.06-inch travel, 2.8-ounce force, 2 ms bounce, and 2-ohm contact resistance. The keys are sealed and provide tactile feel.

For information, contact Advanced Input Devices, POB 1818, Coeur d'Alene ID 83814, (208) 773-3586.

Circle 504 on inquiry card.

Where Do New Products Items Come From?

The information printed in the new products pages of BYTE is obtained from "new product" or "press release" copy sent by the promoters of new products. If in our judgment the information might be of interest to the personal computing experimenters and homebrewers who read BYTE, we print it in some form. We openly solicit releases and photos from manufacturers and suppliers to this marketplace. The information is printed more or less as a first-in first-out queue, subject to occasional priority modifications. While we would not knowingly print untrue or inaccurate data, or data from unreliable companies, our capacity to evaluate the products and companies appearing in the "What's New?" feature is necessarily limited. We therefore cannot be responsible for product quality or company performance.



Speech-Synthesizer Module

The Series III Speech Module can accommodate standard and custom vocabularies up to a total of 256 utterances. It consists of TSI's (Telesensory Systems Inc's) speech synthesizer, vocabulary memory, an on-board speech filter, and an audio amplifier. It is TTL- (transistor-transistor logic) compatible and uses a single +5 V supply. The memory can be a combination of one or two 16, 32, or 64 K ROMs (read-only memories) or PROMs (programmable ROMs), providing up to 128 K bits. With the Series III, about 100 seconds of speech can be stored in ROM. For complete details, contact Telesensory Systems Inc, 3408 Hillview Ave, POB 10099, Palo Alto CA 94304, (415) 493-2626.

Circle 575 on inquiry card.

Lowercase Conversion Kit for TRS-80 and Centronics Printers

The Conversion Kit I for the TRS-80 and the Centronics 779 printer allows the option of lowercase. This is a full 96-character ASCII (American Standard Code for Information Interchange) uppercase and lowercase set with the option of changing slash zero to a standard zero. The kit does not require etch cuts or soldering. Installation can be done with a screwdriver. No program modification or additional interfacing is required. The kit can be removed in a matter of seconds should any warranty repairs on the printer be required. The price is $125. For details, contact Service Technologies, 32 Nightingale Rd, Nashua NH 03062, (603) 883-5369.

Circle 505 on inquiry card.

Boost TRS-80 5-Inch Floppy-Disk Storage to 354 K Bytes

Using the Doubler, TRS-80 Model I users can store up to 354 K bytes of data on a 5-inch disk. The Doubler adapter plugs into the controller device socket of the TRS-80 Expansion Interface. The device reads, writes, and formats either single- or double-density floppy disks. The price for the Doubler, DBLDOS operating system, and a utility for converting TRSDOS, Percom OS-80, and other single-density files and programs into double-density format is $219.95. For additional information, contact Percom Data Company, 211 N Kirby, Garland TX 75042, (800) 527-1592.

Circle 506 on inquiry card.

8-Inch Floppy Disks for North Star

John D Owens Associates Inc has an 8-inch floppy-disk subsystem for North Star microcomputer users. The 8-inch drives allow transfers to and from standard North Star 5-inch drives. This software/hardware package is designed to operate in single or double density on 8-inch floppy disks.

The subsystem's hardware includes a Tarbell double-density controller and dual Shugart 800R drives in a cabinet with power supply, fan, and all cables. The software interface, DMA-DOS, is a single-user CP/M-compatible 8080/Z80 disk operating system that maintains control of the microcomputer systems' resources. Features of DMA-DOS include user-protect passwords; file-write protection and invisibility to the directory; storage for up to six files for printing; batched console processing; user-oriented prompting and error messages; support for disk files of up to 4.2 megabytes; and 20 basic system commands. The subsystem is available from John D Owens Associates Inc, 12 Schubert St, Staten Island NY 10305, (212) 448-6283, for $1910. The software can be purchased separately without the Tarbell interface for $150, or with the interface for $200.

Circle 508 on inquiry card.

Hand-Held Terminal with an LCD

The TransTerm 1 uses a 64-character, 5 by 7 dot-matrix LCD (liquid-crystal display) organized in two 32-character lines with an underscore cursor. The character set is standard 96-character ASCII. The keyboard contains fifty-three membrane keys. The unit communicates in full-duplex RS-232C serial asynchronous ASCII, with 20 mA current loop or RS-422 available as options. Switch-selectable data rates of 300 to 9600 bps (bits per second) are included. A teletypewriter-compatible mode, block-send mode, or polled multidropping operation are included. The unit measures 29.7 by 17.5 by 4.4 cm (11 7/10 by 6 9/10 by 1 3/4 inches). It consumes 10 W of power.

The TransTerm 1 is available for $449 from Computerwise Inc, 4006 E 137th Ter, Grandview MO 64030, (816) 765-3330.

Circle 507 on inquiry card.

What's New?

PERIPHERALS



TRS-80 Data Separator

Parasitic Engineering's 5-inch floppy-disk-drive data separator eliminates most disk errors, including CRC, track locked out, and disk I/O error. The separator uses a phase-locked-loop circuit for error tracking. It plugs inside the TRS-80 Model I Expansion Interface. The data separator is compatible with all TRS-80 software and includes the FD1771 disk controller. The 5-inch-drive unit is upward compatible with 8-inch drives.

The data separator costs $250. Contact Parasitic Engineering Inc, 1101 Ninth Ave, Oakland CA 94606, (415) 839-2636.

Circle 512 on inquiry card.

Interface for IBM Electronic Typewriters

The Mediamix ETI² connects IBM Model 50, 60, and 75 electronic typewriters to any computer with a Centronics-type parallel port. The device includes a Z80 microprocessor and 2 K bytes of programmable memory. It features user-definable codes and characters for any word-processing program and the ability to use all the functions of the IBM typewriters with most programs.

For more information, contact Mediamix, POB 67B57, Los Angeles CA 90067, (213) 475-9949.

Circle 513 on inquiry card.



Color-Matrix Printer from Britain

The Integrex CX80 is a new color-matrix printer that doesn't require special-absorbency paper. The machine can print text, graphs, histograms, and video-display images in seven colors without restrictions on mixing characters, dot-addressed areas, and color changes on the same line. Stripes from a three-color ribbon are selected to produce the required colors.

The unit is dot-addressable in all seven colors, and a character-set ROM (read-only memory) contains 96 ASCII (American Standard Code for Information Interchange) and 64 graphics characters. The seven-wire head produces 5 by 7 and 6 by 7 formats. The print width is 80 columns, resolution is 60 dots per inch, and print speed is 125 cps (characters per second) in a primary color. There are 15 user-programmable characters. All characters can be printed in double-length and reverse. Buffer length is two lines. Paper movement is programmable.

The printer comes with a Centronics-compatible interface; RS-232C and IEEE-488 interfaces are optional. The Integrex CX80 costs approximately $2000. For details, contact Integrex Ltd, Portwood Industrial Estate, Church Gresley, Burton-on-Trent, Staffs, DE11 9PT, England. In North America, contact Integrex Inc, 233 N Juniper St, Philadelphia PA 19107, (215) 627-0966.

Circle 514 on inquiry card.

Serial Interface for the Epson MX-80

The Epax is a buffered serial interface with selectable data rates for the Epson MX-80 printer. Epax is a single board that installs inside the printer and provides 1000 characters of buffer storage. Transmission restraints can operate in one of two ways: XON-XOFF signaling or Centronics-compatible handshaking. Buffer-control characters are user-selectable.

The Epax is $175 from Vardon & Associates Inc, 1401 Walnut Hill Ln, Irving TX 75062, (800) 527-7700; in Texas (214) 659-3800.

Circle 515 on inquiry card.

MISCELLANEOUS

50 W, Triple-Output Power Supplies

The Series 3050 power supplies feature two models, the 3050-1A and the 3050-2A. The Model 3050-1A has +5 V DC at 6 A and ±12 V DC at 1 A, and the Model 3050-2A has +5 V DC at 6 A and ±15 V DC at 1 A. Basic specifications include 80% efficiency; 90 to 130 V AC input; 20 kHz clock oscillator; ±0.1% line regulation; ±0.1% load regulation; 50 mV peak-to-peak output noise; 300 μs response time; and 1500 V AC input/output isolation. The units weigh 18 ounces. Output current limit and soft start are standard on both models. No external heat sink is required.

The price for Models 3050-1A and 3050-2A is $95 each. Contact Power General, 152 Will Dr, Canton MA 02021, (617) 828-6216. Circle 509 on inquiry card.



TRS-80 Model I Development System

The Developmate 81 upgrades the TRS-80 Model I into a full development system. Priced at $329, the Developmate 81 adds Z80 in-circuit emulation and EPROM (erasable programmable read-only memory) and EEPROM (electrically erasable programmable read-only memory) capabilities. The device plugs into the expansion connector and includes the PROM programmer and the emulator. The unit can handle 2758, 2508, 2716, 2516, 2532, 2816, and 48016 devices. Software for programming and verification is included.

When the target-system hardware and software works under emulation, the program is copied into PROM by the built-in PROM programmer. During emulation development, DMA (direct memory access) is not supported, nor are the HALT, NMI, RFSH, and M_1 signals. Clock speed during emulation is 1.8 MHz. Address mapping is not provided in the emulator, so target-system address assignments must be made to avoid conflict with addresses used by the TRS-80. Any of the 251 unassigned I/O (input/output) ports can be used in the target system. A program can be tested at one address space and run at another without reassembly.

Developmate 81 comes with a power supply, emulation cable, TRS-80 cable, and a universal personality module. The TRS-80 Expansion Interface is not required. For more information, contact Orion Instruments, 172 Otis Ave, Woodside CA 94062, (415) 851-1172.

Circle 510 on inquiry card.

Programmable Character Generator

The Model 801 character generator is a test instrument that aids in the design and production of raster-scan video displays. The unit is microprocessor-controlled and has an internal frequency synthesizer that provides video dot rates up to 65 MHz. Video-sync timing is user-programmable. The unit has a complete set of 5 by 7 and 7 by 9 characters and can display up to 256 characters per row with 128 rows. A built-in battery-backup memory system allows storage of five complete display formats. The unit automatically calculates and displays the vertical, horizontal, and video rates as a result of entered display parameters. It costs $1995. Contact Quantum Data Inc, 455 E Kehoe Blvd, Carol Stream IL 60187, (312) 668-3301.

Circle 511 on inquiry card.

What's New?

SYSTEMS

Multiuser, Multiprocessor Microcomputer



The Model 6500 is an S-100 bus, CP/M-compatible system expandable from one to sixty-four users. The motherboard can accommodate up to twelve users, and additional enclosures allowing up to eighteen users each can be added. Each unit contains two microprocessors, 64 K bytes of programmable memory, and serial and parallel I/O (input/output).

OSM's CP/M-compatible Multi-User System Executive operating system is written in Z80 code and features automatic print spooling, user selection of a local or a master system printer, file-sharing interlock, and a password/security system. Directories are provided for user- and common-file areas. Logon/off time is automatically stored.

Options include two 8-inch double-density double-sided floppy-disk drives and 29- to 96-megabyte hard-disk subsystems. System prices start at $5715. For more information, contact OSM Computer Corporation, 2364 Walsh Ave, Santa Clara CA 95051, (408) 496-6910.

Circle 516 on inquiry card.



64 K Bytes Standard with SuperBrain

SuperBrain, an S-100 microcomputer, is now marketed with 64 K bytes of programmable memory instead of 32 K. The retail price of the unit is $3495. SuperBrain features dual 5-inch floppy-disk drives capable of storing 350 K bytes, Digital Research's CP/M operating system, a 12-inch video monitor, and two Z80A microprocessors. For more information, contact Intertec Data Systems, 2300 Broad River Rd, Columbia SC 29210, (803) 798-9100.

Circle 517 on inquiry card.



6802 Single-Board Microcomputer

The CompTrol-1 Model SBC681 features a 6802 microprocessor and up to 8 K bytes of ROM or EPROM (read-only memory or erasable programmable ROM). Programmable-memory expansion sockets are provided for a 1 K-byte expansion beyond the 128 bytes inside the 6802. The board is provided with a 6821 PIA (peripheral interface adapter) and/or a 6522 VIA (versatile interface adapter). The VIA contains an 8-bit shift register, two programmable 16-bit timers, and two parallel ports. Jumper options select processor-interrupt connections and ROM size.

The board operates at 1 MHz from a single 5 V supply, or with a power-supply option, from an unregulated 8 V supply. Mounting options are provided. For more information on this $139.42 microcomputer board, contact Industrial Micro-Systems Inc, POB 306, Plantsville CT 06479, (203) 628-4844.

Circle 518 on inquiry card.

What's New?

SOFTWARE

Mate Solves Chess Problems on the Apple

Mate is a chess-problem-solving program that quickly determines whether or not mating is possible within the remaining number of moves, and it can solve mate in n moves, helpmate in n moves, and self-mate in n moves. Mate supports all four promotions, en passant, and castling. Abbreviations for the pieces are in FIDE (World Chess Federation) standard and the board layout uses European notation, but users can define their own abbreviations. Mate consists of instructions to use the program, examples of use, assembly-language code, chess-specific information tables, and a 6 K-byte data area.

Mate requires an Apple II or Apple II Plus with 48 K bytes of programmable memory and one floppy-disk drive. It is available for $60 from Mika Korhonen, Neitsytpolku 6 A 8, SF-00140 Helsinki 14, Finland. Circle 519 on inquiry card.

Lucidata Pascal for Heath Systems

Version 2.8 of Lucidata Pascal, for Heath systems operating under HDOS, is compatible with all HDOS files and devices. Pascal source programs compile into p-code for execution. Features include random and sequential disk-file access, integer and nine-digit floating-point arithmetic, virtual memory operation, and an assembly-language interface. Supplied on a 5-inch floppy disk, the system includes fourteen demonstration programs and a manual. The compiler can run in a 24 K-byte HDOS system, but 40 K bytes are recommended. It is available for $95 from Polybytes, 325 19th St SE, Cedar Rapids IA 52403.

Circle 520 on inquiry card.

Data-Base System for CP/M Systems

IDM-C1 is a data-base-management system that includes an initialization program, a data-base-manipulation program, and a report writer and generator. Features include up to forty fields, search commands, statistics, reuse of deleted records for key access, error trapping, and more. It requires a dual-disk system with 60 K bytes of programmable memory and CP/M. IDM-C1 costs $159 from Micro Architect Inc, 96 Dothan St, Arlington MA 02174, (617) 643-4713.

Circle 521 on inquiry card.

Data-Base System for Commodore Computers

Jinsam 8.0 for the Commodore 8000 series and Jinsam 4.0 for the Commodore 4000 series computers are data-base-management systems that use relative files, hold approximately 1900 records per data base, allow different data bases on each data disk, and impose no limit on record lengths or number of fields. The programs include the data-base core, label and report writers that allow sorting of three fields at one time, Wordpro interface for form-letter generation, mathematical and statistical interfaces, four-level password system, auto-time-out feature, auto-dating of all printouts, two recovery systems, and a rotating backup system. Utilities that upgrade data files to new Jinsam systems, change the current data-base form, and generate new data bases from an existing system are included. Jinsam 8.0 controls screen format and displays the maximum defined field lengths. For more information, contact Jini Micro-Systems Inc, POB 274, Riverdale NY 10463.

Circle 522 on inquiry card.

6809 Cross Assembler

XASM6809 is a 6809 cross assembler written in FORTRAN IV and designed for industrial and scientific applications. The assembler includes free-format input, statement labels up to eight characters long, and compatibility with all the instructions and addressing modes of the target microprocessor. Assembler directives are mostly identical to those found in the original manufacturer's assembler products. Output of complete assembly listings, including object code, source lines, addresses, and the number of machine cycles required for each instruction, is provided. Error messages are inserted into the assembled listings. The assembler comes in a punched-card-deck package for $75 and on magnetic tape for $100. Contact Intelligent Devices of Minnesota, POB 14538, Minneapolis MN 55414, (612) 427-0787.

Circle 523 on inquiry card.

Form-Letter Module from Muse

The Form-Letter Module features automatic repetitive printing of letters from mailing-list records using the Muse Address Book software, individual printing of letters without permanent mailing-list storage, insertion of mailing-list information anywhere in a letter, on-screen prompts, and commands that allow changing the contents of individual letters dependent on the recipient.

The program runs on the Apple II or Apple II Plus with 48 K bytes of memory and a disk drive. It retails for $100. Contact Muse Software, 330 N Charles St, Baltimore MD 21201, (301) 659-7212.

Circle 524 on inquiry card.

What's New?

SOFTWARE

Financial Planning Software for CP/M Systems

FPL (Financial Planning Language) can perform profit and loss forecasts, commercial-loan evaluations, pro forma statements, product-line planning, budget planning and consolidation, product evaluation, cash-flow management, real-estate acquisition and development analysis, acquisition or merger analysis, and computations for marketing plans and performance, material and labor requirements, and capital-investment analysis. Users can customize worksheets with FPL. Special report functions allow combination, extraction, and comparison of separate sets of data.

FPL operates on any 8080- or Z80-based microcomputer with 60 K bytes of programmable memory, CP/M, and Microsoft BASIC, version 5.X. The program costs $695, and documentation alone is $30. Contact Lifeboat Associates, 1651 Third Ave, New York NY 10028, (212) 860-0300.

Circle 525 on inquiry card.

Smart Programs for the TRS-80 Model III

SmartIII is a smart-terminal program for the TRS-80 Model III. It permits transfer of BASIC programs and source-code files between a remote computer and the local cassette or disk-storage device. The FILE program permits generation and storage of text, then transmission by SmartIII, for those who do not have word processors. AUTOBUF opens and closes the data-storage buffer automatically when up- or downloading. SmartIII recognizes the automatic buffer-open and -close codes transmitted by another Smart-series (ie: Model I or II) program. With SmartIII, the video-display line length can be formatted. Half- or full-duplex operation is software-selectable. The program will automatically send messages to bulletin boards and can be used with any RS-232C-compatible modem.

SmartIII is priced at $99.50 from The MicroPeripheral Corporation, 2643 151st Pl NE, Redmond WA 98052, (206) 881-7544.

Circle 526 on inquiry card.

Graphic Writer Program

The Graphic Writer program allows Apple users to get hard copy of the Gothic, Blippo Black, Roman, Outline, and other character sets available in Apple's Applesoft Tool Kit. This software can be used in conjunction with the Applewriter word-processing program. Graphic Writer can also be used as a stand-alone product for use with PRINT statements within a user's program.

Graphic Writer is available for Silentype and Paper Tiger Model 440G, 445G, or 460G printers. It requires a 48 K-byte Apple II or Apple II Plus, DOS 3.3, the Applesoft Tool Kit, Apple parallel or Centronics interface card, and a printer. It is available from Computer Station Inc, 12 Crossroads Plz, Granite City IL 62040, (618) 452-1860. The suggested retail price is $34.95.

Circle 527 on inquiry card.

PET Programs for Young Students

Menu-driven addition and subtraction programs, suitable for grades 1 through 6, provide twenty-four levels of difficulty for addition and twelve levels of difficulty for subtraction. Immediate feedback is given, with graphics reinforcing correct responses. The letters and numbers program uses large characters created with PET graphics. Options include matching of one or more items, completing sequences, and filling in missing items.

The match-game program is useful for memory building and for putting lesson reviews into a game format. The game can be played with exact matches or paired matches (eg: synonyms or translations). Users can enter their own items or can choose from options including shape matching, math problems and answers, and synonyms. One to four players can participate, and single players can play against the computer. These programs are available for $20 on cassette. They will run on any PET with at least 8 K bytes of memory and versions 1.0, 2.0, or 4.0 of ROM (read-only memory). For information, contact Teaching Tools, POB 12679, Research Triangle Park NC 27709, (919) 851-2374.

Circle 528 on Inquiry card.

A Gem of a Program

Amethyst combines Mince, a full-screen editor; Scribble, a text formatter; the BDS C compiler; the Mince command-set source code; and a user-support program. Mince is written in C, so it is possible to personalize or extend the editor. Amethyst can be used as an editor/compiler combination for program development. A user's manual and a book describing theory of operation are included. The program requires a 48 K-byte CP/M system and a video terminal with cursor positioning. Amethyst is $350. Mince and Scribble are $125 each, or $175 for both. Contact Mark of the Unicorn, POB 423, Arlington MA 02174, (617) 489-1387.

Circle 529 on inquiry card.

What's New?

PUBLICATIONS

Personal Computer Letter

The Carl Helmers Personal Computer Letter is a monthly analysis of issues, trends, and current events that affect the small-computer industry. A major topic affecting the design, marketing, and support of small-computer hardware and software is discussed in each letter. Some of the forthcoming topics include studies on computer options for small colleges, mass-storage technology, configurable software, standards, color graphics, the importance of smooth power supplies, object-oriented languages, artificial intelligence, local communications networks, high-level languages, and interactive operating systems.

Another feature of the newsletter is a free personal-computer industry telephone conference call held once a month. With up to twenty people on a conference line, Mr Helmers moderates discussions and answers questions from subscribers about issues concerning popular microcomputers and the industry.

A charter subscription to the newsletter is $200. For more information, contact North American Technology Inc, Strand Bldg, Suite 23, 174 Concord St, Peterborough NH 03458, (603) 924-6048.

Circle 530 on inquiry card.

Books from Addison-Wesley

Books on languages, hardware fundamentals, programming, and computer science are featured in the "Books About Computers" catalog from Addison-Wesley Inc, Reading MA 01867, (617) 944-3700.

Circle 531 on inquiry card.



Program Listing Catalog

Personal Computer Applications Software Compendium will contain program descriptions and information on how and where to buy programs written for many different microcomputers. For additional information on how you can be a contributor and place a listing in this book, contact El Dorado Publishing Company, POB 446, Los Alamitos CA 90720.

Circle 532 on inquiry card.

CMOS Databook

CMOS/MOS Integrated Circuits is a 688-page book on CMOS (complementary metal-oxide semiconductor) and MOS devices. The book includes technical data, application notes, product-classification and function-selection charts, package information, functional diagrams, operating and handling considerations, and ratings and characteristics for all standard digital integrated circuits in RCA's CMOS CD4000 product line. The book costs $7. Request CMOS/MOS Integrated Circuits, volume number SSD-250B, from RCA Solid State Division, RT 202, POB 3200, Somerville NJ 08876.

Circle 533 on inquiry card.

Keyboard Catalog

A catalog of standard keyboards is available from George Risk Industries. Bulletin KB-20 includes data on the company's Model 753, 756, and 771 keyboards, plus models ranging from 10 to 98 keys. Featured are the Process Control Keyboard for industrial-control-system applications, user-programmable ASCII (American Standard Code for Information Interchange) keyboards, and keyboard enclosures and accessories. Off-the-shelf models include units for hobby and educational use and keyboards suitable for a variety of prototype, limited production, and specialized applications. Versions for heavy-duty industrial and military applications are also offered.

Your free copy can be obtained from George Risk Industries Inc, GRI Plz, Kimball NE 69145, (800) 445-5218; in Nebraska (308) 235-4645.

Circle 534 on inquiry card.

Guide to Optical Cable

In its Guide to Optical Cable, Probe Research describes and compares the optical-communications cable being sold in the data and telephone/CATV applications market. Tables compare operating and mechanical specifications of the cables, including type of fiber used, cabling loss, application, cable construction, tensile strength, bandwidth, and more. The report also describes this rapidly changing market, including regulatory implications and the type of purchasing being done. The Probe Guide to Optical Cable is available for $50 from Probe Research Inc, POB 251, Millburn NJ 07041, (212) 732-5415.

Circle 535 on inquiry card.

What's New?

PUBLICATIONS

Shirt-Pocket Guide to the 6502

The 6502 Instruction Handbook is a handy shirt-pocket-sized guide to the 6502 microprocessor. It contains a synopsis of each instruction available for the 6502, with mnemonic and machine codes in hexadecimal format provided for each addressing mode. Appendices list the instruction set alphabetically by assembler mnemonics and numerically by machine code. A hexadecimal-to-decimal conversion chart is provided. A circuit pinout diagram, basic timing information, and diagrams of the architecture are also included.

The 6502 Instruction Handbook is available for $4.95 plus $0.50 postage from Scelbi Publications, 20 Hurlbut St, Elmwood CT 06110. Circle 536 on inquiry card.

Computer Equipment on CIA's List

CIA is a publication for advertising new and used computers, software, and related products. Display ad rates range from $35 to $175. The subscriber rate for classified ads is $0.10 per word, and the nonsubscriber rate is $0.30 per word.

For more information on deadlines and subscription prices, contact Computer Instant Ads Association, 277 E 6100 South, Salt Lake City UT 84107, (800) 453-6464; in Utah (801) 268-3000. Circle 537 on inquiry card.

Power Supply Catalog

Power General, makers of power supplies, has published a catalog describing its products. For a copy, contact Power General, 152 Will Dr, Canton MA 02021, (617) 828-6216.

Circle 538 on inquiry card.

Challenge Computer Supplies Catalog

Challenge Computer Supplies has published its Spring/Summer 1981 Catalog. The company sells computer furniture, magnetic media, computer-paper forms, and related items. For a copy, contact Challenge Computer Supplies Inc, POB 3269, 727 Middlefield Rd, Redwood City CA 94064, (415) 365-8105.

Circle 539 on inquiry card.

Ampex Offers a Magazine

Databits is a quarterly magazine designed to keep Ampex customers informed of developments in the Ampex Memory Products Division. The magazine reviews new Ampex computer-product developments, discusses applications of existing products, lists trade shows, and provides technical discussions of various aspects of computer technology. Interested readers can obtain a free copy of Databits by writing Ampex Corporation, Memory Products Division, Attn: Marketing Communications M-15, 200 N Nash St, El Segundo CA 90245.

Circle 540 on inquiry card.

Furniture Catalog

A color catalog from Structural Concepts Corporation describes furniture for office and personal computers. Both stock and custom units are available. Pre-wired and dedicated electrical circuits are available in some of the furniture. A variety of options and accessories, including pass-throughs and shared terminal turntables, are featured. Contact Structural Concepts Corporation, 17237 Van Wagoner Rd, Spring Lake MI 49456, (800) 253-5102; in Michigan (616) 846-3300.

Circle 541 on inquiry card.

Catalog Lists TI 99/4 Hardware and Software

TI Source is a catalog and newsletter for TI 99/4 users. Included in the catalog are software programs for education and science, business and professional applications, games, music, utilities, and languages. Many accessories are listed. The newsletter contains news and reviews of software packages. The free catalog and newsletter is available from Microcomputers Corporation, POB 191, Rye NY 10580, (914) 967-8370.

Circle 542 on inquiry card.

Free Courseware Catalog

The MicroMedia catalog contains over 400 kindergarten through grade 12 instructional programs, games, packages, and books for use with Apple, Atari, PET, and TRS-80 microcomputers. Organized by subject and grade level, each entry includes program name, type, functional description, and memory requirements. Contact MicroMedia, 686 Sierra Vista Ln, Valley Cottage NY 10989, (914) 358-2582.

Circle 543 on inquiry card.

Adventure Games Brochure

If you are looking for something to do on sleepless nights, try an adventure game from Adventure International. Its catalog describes dozens of fantasy and role-playing games available for TRS-80, Apple, PET, Atari, and Sorcerer microcomputers. For a copy, contact Adventure International, POB 729, Casselberry FL 32707, (800) 327-7172; in Florida (305) 862-6917.

Circle 544 on inquiry card.

MISCELLANEOUS

Programmable Memory Has 8 K

The 8112 static programmable memory is pin-for-pin compatible with the 2716 EPROM (erasable programmable read-only memory). Built into the design of the 8112 is a delatched write function that allows incoming data to be controlled by the write-enable function. This arrangement provides for a delayed write. Power-consumption requirements are lower with the 8112 because the device operates in an enabled and disabled mode. It requires a single +5 V supply. Organized as 1024 words by 8 bits, the 8112 is available in access times of 200, 300, and 400 ns. In lots of 100, prices for the 8112 range from $10.70 to $14.70. Contact GTE Microcircuits, 2000 W 14th St, Tempe AZ 85281, (602) 968-4431.

Circle 545 on inquiry card.

Computer Stands

Comstand computer stands hold microcomputers and small-business systems. They have a table height of 66.5 cm (26½ inches), the same as a typewriter stand. A storage shelf is mounted below the table. There are additional shelves above the table for monitors, disk drives, or other items. The Model 2036, priced at $150, is 90.5 by 137 cm (36 by 54 inches) and the Model 2048, priced at $165, is 123 by 120 cm (48 by 47 inches). Both styles have 50-centimeter- (20-inch) wide tables. An optional printer stand with two shelves and a middle slot for paper feed is priced at $140. Contact Ever Roll, 3988 Troy Rd, Springfield OH 45504, (513) 964-1322.

Circle 546 on inquiry card.

Low-Power LCD



A 3½-digit LCD (liquid-crystal display) panel meter has been introduced by Datel-Intersil. The DM-LX3 has a ¾-inch-high display. Using CMOS (complementary metal-oxide semiconductor) circuitry, the meter uses 17.5 mW (+5 V at 3.5 mA). The device can operate continuously for several months on a battery of four AA alkaline cells. The meter displays digits with an accuracy of ±0.1%. The board measures 10.5 by 5 by 1 cm (4 by 2 by ⅜ inches).

The DM-LX3 features balanced differential inputs, high-impedance inputs with low-bias currents, autozeroing, selectable display and hold, and blank circuit pads for attenuation or shunt resistors. The DM-LX3 sells for $57.50. Contact Datel-Intersil Inc, 11 Cabot Blvd, Mansfield MA 02048, (617) 339-9341.

Circle 547 on inquiry card.

EAROM from General Instrument

The ER4201 EAROM (electrically alterable read-only memory) is an N-channel device for applications that require a small memory and where ease of use and speed are important. The 128- by 8-bit ER4201 features +5 V operation in read mode, 350 ns maximum access time, in-circuit electrical word alterability, and on-board address, mode, and data latching. A program command will place the device in the busy mode and initiate an erase followed by a write. This allows the processor and system bus to be freed during the EAROM's 10 μs reprogramming operation.

In quantities of 250, the EAROM price is approximately $11.50 each. For more information, contact General Instrument Corporation, Microelectronics Division, 600 W John St, Hicksville NY 11802, (516) 733-3120.

Circle 549 on inquiry card.

Keep It Quiet

Vitech Inc has a sound enclosure that blocks noise pollution from printers, word processors, and Telex machines. The interior and exterior panels are covered with plastic laminate, and the acrylic tops are transparent. Custom covers can be made for any printer. Models start at $275.

For more details, contact Vitech Inc, 4555 W 77th St, Minneapolis MN 55435, (612) 831-8757. Circle 548 on inquiry card.

Multistrike Ribbon Cartridge

Aspen Ribbons Inc has a version of the multistrike ribbon cartridge required by NEC (Nippon Electric Company) printers. The used ribbons can be returned to the company for replacement. Each ribbon costs $5. For additional details, contact Aspen Ribbons Inc, 1700 N 55th St, Boulder CO 80301, (800) 525-0646; in Colorado, (303) 444-4054.

Circle 550 on inquiry card.

What's New?

MISCELLANEOUS

Cross Reformatter for CP/M and DEC Files

MicroTech Exports' Reformatter conversion software allows CP/M users to exchange data files with DEC (Digital Equipment Corporation) computers using a floppy disk as the transfer medium. Reformatter runs under CP/M and reads and writes in the DEC RT-11 format. Data files can be transferred bidirectionally, and any fields in the directory can be altered. Reformatter lists the DEC directory and displays the unused areas of the disk. The price of the program is $195 from MicroTech Exports, 467 Hamilton Ave, Palo Alto CA 94301, (415) 324-9114.

Circle 551 on inquiry card.

Datapro Offers a Catalog of Reports

Information processing professionals can look to the 1981 **Datapro Report** catalog for information comparing electronic data processing, word processing, office, and data communications products. Datapro's free catalog describes studies on fifty-two categories of popular equipment and management methods. The reports contain narratives, comparison charts, prices, specifications, and characteristics on products and services. User ratings are included in many reports, which are priced at $15 each. The catalog is available from Datapro Research Corporation, 1805 Underwood Blvd, Delran NJ 08075, (609) 764-0100.

Circle 553 on inquiry card.

All-CMOS Microcomputer

The Model PPS-12 is an all-CMOS (complementary metal-oxide semiconductor) microcomputer system. The system employs an IM6100 CMOS microprocessor, and has been designed for applications where only battery or solar power is available. Operation requires only a 5 V power supply at less than 0.5 mW. The board includes three parallel I/O (input/output) ports, one RS-232C serial port, a programmable real-time clock, 4 K 12-bit words of CMOS EPROM (erasable programmable read-only memory) and read/write memory, a memory-expansion controller, and an on-board monitor and debugger. The board is also supported by parallel and serial I/O modules, memory-expansion modules, an all-CMOS A/D (analog-to-digital) converter, and bubble memory. The modules can be plugged into any Multibus card cage.

The 12-bit IM6100 microprocessor uses a binary instruction set identical to Digital Equipment Corporation's PDP-8 and VT-78 DECstation minicomputers. The single-quantity price for the PPS-1201 is $999. For more information, contact Pacific Cyber/Metrix Inc, 6800 Sierra Ct, Dublin CA 94566, (415) 829-8700.

Circle 554 on inquiry card.

Computer Cable and Interface Catalog

A computer cable and interface catalog is available from CCP Computer Cable Products Division, 147 Gazza Blvd, Farmingdale NY 11735, (800) 645-9434; in New York (516) 293-1610. Described are specifications for RS-232C, EIA 449 assemblies, and bulk cable. Accessories described in the catalog include ribbon, coaxial kits, switching boxes, plenum and molded assemblies, adapters, and isolated power supplies. Request catalog H10.

Circle 552 on inquiry card.

High-Speed Memory

The CI-6800-2 dynamic memory board is designed for Motorola's EXORcisor I and II and Rockwell's System 65. The memory is available in 16 K-, 32 K-, 48 K-, or 64 K-byte configurations. The board features hidden-refresh control logic. The access time is 225 ns and cycle time is 400 ns, which allows the unit to operate as a static programmable-memory device at clock rates in excess of 1.5 MHz. For 2 MHz operation, the memory board can be configured to utilize a cycle-stealing refresh operation.

Memory selection is available in 4 K-byte increments up to 64 K bytes. The memory has on-board even parity, with output jumper-selectable to the system bus as a parity error or nonmaskable interrupt. Power consumption is under 7 W.

The prices are $565 for the 16 K-byte board and $750 for the 64 K-byte board. Contact Chrislin Industries Inc, 31352 Via Colinas #102, Westlake Village CA 91361, (213) 991-2254.

Circle 555 on inquiry card.

Anti-Static Mats

Anti-static floor and table mats can protect terminals, computers, and disk drives from electrostatic discharge. Pervel Industries' mats can be placed on tables and floors and connected to ground.

For more information, contact Pervel Industries Inc, POB 61, Plainfield CT 06374, (203) 564-2741. **Circle 556 on inquiry card.**

What's New?

MISCELLANEOUS



Robot for Hobbyists

The Robot Unit RU-II is a package of mechanical modules that includes the base transport (legs), structural unit (body), and manipulator units (shoulders, arms, and hands). Also included are the relay controls required to drive the motors and a manual pushbutton control box to drive the relays. RU-II comes in kit form, including all parts, except a 12 V battery. There is room inside the body unit for more mechanical and electrical accessories. All the components can be used separately for experiments. The robot can be controlled by remote-control transmitter/receiver systems or by interfacing a computer into the relay control units.

RU-II weighs less than 100 pounds and can carry more than 50 pounds of batteries, computers, and other external loads. Speed of the unit is approximately two feet per second, fully loaded. Each arm can grasp, lift, and move more than 15 pounds.

RU-II comes with a one-year update, manual, and a free subscription to the **Amateur Robotics Designer Newsletter**. The price of the RU-II is $1495, plus 5% shipping and handling. Contact Hobby Robotics Company, 4055 Lawrenceville Hwy, Suite 410, POB 997, Lilburn GA 30247, (404) 923-5650.

Circle 557 on inquiry card.

Digital Multimeter Uses LCD Display

A hand-held 3½-digit LCD (liquid-crystal display) digital multimeter has been introduced by Eico Electronic Instrument Company. Priced at $89.95, the Eico 274 measures AC and DC voltages, DC current, and resistance in twenty-one ranges. It features single-circuit LSI (large-scale integration) logic, automatic decimal point, and overload protection. Up to 200 hours of operation time are possible from a 9 V transistor power cell. An automatic low-power indicator is provided. Accuracy is better than 0.8%. Input impedance is 10 megohms. The Eico 274 comes with a 9 V power cell, test probes, carrying case, and a spare fuse. Contact Eico Electronic Instrument Company Inc, 108 New South Rd, Hicksville NY 11801, (516) 681-9300.



Circle 558 on inquiry card.



Portable Design Kit

The LD-1 Pencil Box Logic Designer is a portable logic-design and breadboarding device. Among its features are a variable clock, two pulsers, eight LED (light-emitting diode) displays, eight logic-level switches, and E & L Instruments' SK-10 breadboarding socket. Power is supplied through batteries or an optional AC supply. All of this is contained within a portable molded-plastic case with a hinged cover.

The LD-1 kit is $75 and the assembled unit is $99.50. For more information, contact E & L Instruments Inc, 61 First St, Derby CT 06418, (203) 735-8774.

Circle 559 on inquiry card.

Headcleaning FlexyDisks from BASF

BASF Headcleaning FlexyDisks clean read/write heads on floppy-disk drives in one minute. The disks, available in 5- and 8-inch sizes, are for single-sided floppy-disk drives only. Each FlexyDisk can be used up to thirty times. A package of three retails for $45 from BASF Systems Corporation, Crosby Dr, Bedford MA 01730, (617) 271-4000.

Circle 560 on inquiry card.

INCREDIBLE? BELIEVE IT!

PRINTERS

150 cps bidirectional-9x9 dot matrix, quietized case, 136 col, vertical form control and many other functions **$1195**
We feel this printer offers the best price/performance ratio available.
RS-232 serial to 19,200 baud supporting X-ON, X-OFF or Current Loop — add $40

Teletype 40, 300 LPM-typewriter quality, RS-232 interface. This quality printer is available in many configurations including forms access, quietized case, etc. **Only** from **$3095**

Teletype 43	from **$995**
NEC Spinwriter-55 cps, bidirectional, letter quality R.O./tractors **$2795** KSR/tractors	**$3050**
DIABLO 630-40 cps, bidirectional, daisy wheel, plot/graph	**$2270**
C. ITOH Starwriter, 25 cps, daisy wheel	**$1575**
C. ITOH Starwriter, 45 cps, daisy wheel	**$1849**
EPSON MX-80, 80 cps, 9x9 dot matrix	**$545**
ANAOEX 9500/9501, up to 200 cps, high resolution dot	**$1349**
OKIDATA Microline 80, 80 cps, 9x7 dot matrix	**$490**
Microline 82, bidirectional, friction/pin feed	**$599**
Microline 83, bidirectional, 120 cps, uses 15" paper	**$875**
TI-810, 150 cps, Basic	**$1695**
Package-Compressed print, vertical form control	**$1830**
CENTRONICS 704-9,180 cps, 9x9 dot matrix, 132 col, RS-232	**$1595**
704-11,180 cps, 9x9 dot matrix, 132 col, parallel	**$1695**
730,100 cps, 7x7 dot matrix, same as R.S. LPII	**$560**
737,80 cps, nx9 dot matrix, same as R.S. LPIV proportional spacing	**$699**
DEC LA-34	**$1085**

S-100 SPECIALTIES

DELTA PRODUCTS: We offer all of Delta's systems — from their cost effective single user system to extensive multi-user networks of computers and terminals.
Many disk, tape and Winchester configurations are available.

Systems Group: Call us for best prices on these high quality 2nd generation boards and systems.

California Computer Systems: These high quality, reliable products have made CCS defacto industry standard for S-100 products
Assembled and tested:

		list	only
2200	H.D. Mainframe, 20 a. P.S., 12 slot MB	**$434**	**$399**
2065C	64K dynamic RAM/Bank Select	**$720**	**$580**
2810A	Z-80 CPU, serial port, ROM monitor	**$310**	**$259**
2422A	Floppy Cont, CP/M 2.2, ROM monitor	**$425**	**$345**

SSM:

CB2 Z-80 CPU	**$344**	**$295**
2P + 2S I/O interface	**$290**	**$249**

Similar savings on the full S-100 and Apple lines of **CCS, SSM, NNC, MORROW, DELTA, NORTHSTAR, ITHACA INTERSYSTEMS** and **GODBOUT**.

8" DISK DRIVE SALE

8" SHUGART SA801R	**$439**
Premium double sided drives: **8" SHUGART SA851R**	**$625**
QUME DATATRACK 8	2 for **$1199**
Enclosure, power supply for 2 8" drives (horizontal) A&T	**$299**
NNC industrial grade enclosure for 2 drives with P.S.	**$415**
POWER 1, power supply for 2 8" drives	**$135**
MORROW Discus 2D + CP/M®	**$963**
Discus 2+2+CP/M®	**$1259**

HARD DISK SPECIALS

	List	only
CORVUS 10MB and controller	**$5350**	**$call**
20MB and controller	**$6450**	**$call**
Constellation Network Multiplexer	**$750**	**$call**
Mirror Video Tape Disk Backup	**$790**	**$call**
MORROW 29MB+controller+CP/M 2.2®	**$4995**	**$3995**
CAMEO cartridge drive controller	**$1500**	**$1275**
controller, CDC Hawk Drive (5 fix, 5 rem)	**$6995**	**$5995**
controller, Western Dynex (5 fix, 5 rem)	**$5995**	**$5099**

XCOMP: Winchester 5¼ drives complete with case, P.S., cable, software, S-100 controller. Adapter avail. for use with any Z-80 system.

	List
5MB	**$2898**
10MB	**$3398**

Quantity discounts available!
We carry the full line of KONAN disk and tape controllers and subsystems.

FULLY CONFIGURED BUSINESS SYSTEMS

The following are some examples of the fully assembled and tested business and scientific computer systems which we offer. All include CP/M 2.2, 64K bytes dynamic RAM, Z-80A 4mh CPU. We offer a full line of quality, tested software.

CCS 2210A w/floppy controller, 1 serial port	**$1849**
CCS 300-1A w/1.2MB floppy drives, 2 serial, 2 parallel ports	**$4849**
CCS 400-1A w/10MB hard disc, 2 serial, 2 parallel ports	**$6999**
Optional CP/M for CCS 300, 400 (OASIS available)	**$150**
NNC 80 w/1MB floppy drives, 2 serial, 3 parallel ports	**$3799**
NNC 80W w/.5MB floppy, 8.4MB hard disc, (OASIS optional)	**$6693**
ALTOS single and multi-user systems	**$call**
MORROW Decision 1, MICROSOFT basic, UNIX	**$call**

TERMINALS

TELEVIDEO 912 C	**$950**	**$725**
920 C	**$1030**	**$789**
950	**$1195**	**$995**
SOROC IQ 120	**$995**	**$729**
IQ 140	**$1395**	**$1149**
INTERTUBE III or **EMULATOR** (multi-terminal)	**$895**	**$799**
DEC VT-100	**$2050**	**$1575**

Similar savings for our **HAZELTINE** and **LEAR SIEGLER** lines

LOOK HERE!

NNC 2 board set Z-80A CPU, CP/M 2.2, floppy disc controller **2 serial, 3 parallel ports**, PROM, I/O cable	**$765**
SUPERBRAIN	**$call**

ALL OF OUR PERIPHERALS CAN BE CONFIGURED FOR RADIO SHACK® MODEL II

DEALER and INTERNATIONAL INQUIRIES WELCOME

WASHINGTON COMPUTER SERVICES

an affiliate of WASHINGTON ELECTRIC COMPANY INCORPORATED est. 1912

CUSTOM COMPUTER ROOM WIRING SINCE 1960
97 Spring Street
New York, N.Y. 10012
Hours: 8AM-5:30PM (EST) Mon.-Fri.

TO ORDER: CALL OUR TOLL-FREE NUMBER: ★(800) 221-5416★ In N.Y. State and for technical information call 1-(212) 226-2121

For fast delivery, send certified checks, money order or call to arrange direct bank wire transfers. Personal or company checks require two to three weeks to clear. All prices are mail order only. Prices subject to change without notice; call for latest prices. Prices include 2% cash discount. N.Y. residents add sales tax.

Radio Shack® is a trademark of the Tandy Corp.
CP/M® is a trademark of Digital Research

VISA MasterCard

Circle 422 on inquiry card.

What's New?

MISCELLANEOUS

Wire-Wrapping Tool

The ST-100 cuts and strips wire and automatically generates the proper strip length for wire wrapping. The stripping blade is replaceable. The ST-100 is available for wire sizes from 20 to 30 AWG from OK Machine and Tool Corporation, 3455 Conner St, Bronx NY 10475, (212) 994-6600 for $9.84.

Circle 561 on inquiry card.



V300 Daisy-Wheel Printers

The V300 series of daisy-wheel printers is available in 25 and 40 cps (characters per second) models. Both models are impact printers that produce letter-quality printing using standard Diablo- or Qume-type 96-character print wheels. The printers can accommodate paper widths of up to 15 inches and can print up to 136 columns. Character spacing is 1/120 inch minimum, and line spacing is 1/48 inch minimum.

The V300 series are available with Centronics parallel or RS-232C interfaces. Seven- or eight-bit character lengths, single or double stop bits, odd or even parity, and 300, 600, 1200, or 2400 bps (bits per second) data rates are all switch-selectable. Form lengths of up to 66 lines with top-of-form and vertical-tab justification are programmable. Indicators are provided for power on, on-line status, and for paper and ribbon out. Multistrike fabric or carbon-film Diablo-type cartridge ribbons can be used. The V300-25 is priced at $1895, and the V300-45 is $2195. For complete details, contact Vista Computer Company, 1317 E Edinger Ave, Santa Ana CA 92705, (714) 953-0523.

Circle 562 on inquiry card.

Programmable Memory and Disk Protector

When the AC power is interrupted for more than a few milliseconds, most microcomputers using the CP/M operating system attempt to bootstrap CP/M from the disk. Sometimes the disk controller destroys the operating system's tracks rather than reading them. To prevent this disaster, the AMC Protector allows the computer to be initialized in the proper sequence by powering up the computer, then calling up the operating system from disk. The programmable memory and other circuitry is protected by a capacitive reactive RFI (radio-frequency interference) filter. This provides protection from lower-voltage RFI that



causes semiconductor circuits to change state. The standard AMC Protector has a 20 A, 115 V capacity, reset and off-momentary switches, a power-on light, and is housed in a steel box with six grounded AC outlets. Prices start at $110. Contact American Microcomputer Company, 465 Jillana Ave, Livermore CA 94550, (415) 449-0323.

Circle 564 on inquiry card.

64 K-Bit Memory Circuit

The MSM3764 is a 64 K-bit programmable-memory integrated circuit. It is offered in three operating speeds: 200, 150, and 120 ns. The MSM3764 is a fully decoded dynamic circuit organized as 65,536 one-bit words. Soft-error protection is featured.

The MSM3764 has noncritical clock-timing requirements. It needs a single +5 V supply with ±10% tolerance. All inputs and outputs are TTL- (transistor-transistor logic) compatible. Each 200 ns device (ie: MSM3764-20) is priced at $50.70. The 150 ns unit (ie: MSM3764-15) is $62.40 for one, and the 120 ns memory (ie: MSM3764-12) is $107.25 for one unit. OKI will be introducing a 256 K-bit programmable memory device that will be pin-compatible with these 64 K-bit memories. Contact OKI Semiconductor Inc, 1333 Lawrence Expy, Santa Clara CA 95051, (408) 984-4842.

Circle 563 on inquiry card.

WE WILL NOT BE UNDERSOLD

DISK DRIVES

FOR TRS-80* Model I		
CCI-100	5¼", 40 Track (102K)	$314
CCI-280	5¼", 80 Track (204K)	$429

ADD-ON DRIVES FOR ZENITH Z-89		
CCI-189	5¼", 40 Track (102K)	$394
CCI-289	5¼", 80 Track (204K)	$499
Z-87	Dual 5¼" system	$995

External card edge and power supply included. 90 day warranty/one year on power supply.

RAW DRIVES 8" SHUGART 801R			$395
5¼" TEAC or TANDON	**$ CALL**	POWER SUPPLIES	**$ CALL**

DISKETTES — Box of 10

5¼"	Scotch	$30	Maxell	$40	BASF/Verbatim	$26.95
8"	Scotch	$45	Maxell	$55	BASF/Verbatim	$36.00

PLASTIC FILE BOX-Holds 50 5¼" diskettes			$19.00
PLASTIC LIBRARY CASE	5¼" $3.00	3"	$ 4.00
HEAD CLEANING DISKETTE			$25.00
FLOPPY SAVER	$11.95	RINGS	$ 6.95

16K RAM KITS — 2 for $37 — $19

200 ns for TRS-80,* Apple II, (specify): **Jumpers** **$2.50**

SYSTEM SPECIAL

Apple II Plus 48K w/drive and controller. Epson MX-80 printer and interface. SUP-R Mod RF Modulator: List $2965 You Pay **$2299**

COMPUTERS/TERMINALS

ARCHIVES	64K, 2-Drives, 77 Track			$5495
ALTOS	ACS8000 Series			$ CALL
TRS-80*	II-64K	$3499	III-16K	$ 899
ZENITH	48K, all-in-one computer			$2200
ZENITH	Z-19			$ 735
TELEVIDEO	920C	$ 748	950	$1049
IBM	3101 Display Terminal			$1189
ATARI	400	$ 479	800	$ 795
APPLE PERIPHERALS				$ CALL

MONITORS

APF	9" B & W TVM-10			$115
BELL & HOWELL	9" B & W BHD911			$195
LEEDEX	12" B & W	$ 129	13" Color	$329
SANYO	9" B & W VM4509			$155
SANYO	12" B & W DM5012			$226
SANYO	12" Green Screen DM5112			$238
SANYO	13" Color DMC6013			$406
ZENITH	13" Color			$349

TELECOMMUNICATIONS

LIVERMORE STAR MODEM 2-year guarantee	$125
UNIVERSAL DATA SYSTEMS UDS-103	$179
D-CAT HARD WIRED DIRECT MODEM	$189
AUTO-CAT Auto Answer, Direct Connect Modem	$249
D.C. HAYES MICRO-MODEM	$295
CCI Telnet Communications Package	$135

PRINTERS



NEC Spinwriter
Letter Quality High Speed Printer

R.O.	$2395
R.O. with tractor feed	$2555
KSR with tractor feed	$2795

C.ITOH	Starwriter	**$1575**	Starwriter II	**$1849**
EPSON	MX-80	**$CALL**	MX-70	**$CALL**
PAPER TIGER				
IDS 445	Graphics & 2K buffer			$ 699
IDS 460	Graphics & 2k buffer			$1050
IDS 560	Graphics			$1450
ANADEX	DP-8000	$ 849	DP-9500/01	$1295
OKIDATA				
Microline 80	Friction & pin feed			$ 415
Microline 80	Friction, and pin & tractor feed			$ 500
Microline 82	Friction & pin feed feed			$ 615
Microline 83	120 cps, uses up to 15" paper			$ 849
CENTRONICS	730 $ 595	799 $ 969	737	$ 749
TI-810				
TRS-80* software, compressed print & vert. form control				$1865

PRINTER SPECIAL

SEIKOSHA GP-80M List $399 You Pay **$319**

S-100 CALIFORNIA COMPUTER SYSTEMS





MAINFRAME	Model 2200A	$349
Z80 CPU	Model 2810	$259
MOTHER BOARD	Model 2501	$106
16K STATIC RAM, 200ns	Model 2116C	$309
32K STATIC RAM, 200ns	Model 2032C	$619
64K DYNAMIC RAM	Model 2065C	$580
FLOPPY DISC CONTROLLER	Model 2422A	$345
EXTENDER BOARD	Model 2520K	$ 52
2P + 2S I/O	Model 2718A	$309

APPLE ACCESSORIES AND SOFTWARE



VISICALC	$119.00
DB MASTER	$159.00
Z-80 SOFTCARD	$269.00
VIDEX BOARD	$259.00
16K CARD	$169.00
APPLE JOYSTICK	$ 49.00
SUP-R MOD	$ 25.00
CCS CARDS	$ CALL
GALAXIAN	$ 22.95
SPACE ALBUM	$ 35.00
ASTEROIDS	$ 17.95
FLIGHT SIMULATOR	$ 29.00
WIZARD & PRINCESS	$ 28.00
SARGON 2	$ 29.00
HI-RES FOOTBALL	$ 35.00
MYSTERY HOUSE	$ 24.00

For fast delivery, send certified checks, money orders or call to arrange direct bank wire transfers. Personal or company checks require two to three weeks to clear. All prices are **mail order only** and are subject to change without notice. **Call for shipping charges.**

DEALER (NATIONAL/INTERNATIONAL) INQUIRIES INVITED **Send for FREE Catalogue**

The CPU SHOP

TO ORDER CALL TOLL FREE 1-800-343-6522
TWX: 710-348-1796 Massachusetts Residents call 617/242-3361

5 Dexter Row, Dept. B07M
Charlestown, Massachusetts 02129
Hours 10AM-6PM (EST) Mon.-Fri. (Sat. till 5)

Technical Information call 617/242-3361
Massachusetts Residents add 5% Sales Tax
Tandy Corporation Trademark/® Digital Research

master charge THE INTERBANK CARD

VISA®

Circle 103 on Inquiry card.

What's New?

MISCELLANEOUS

Universal Socket Jumpers

A P Great Jumper Company's keyed socket jumpers are interchangeable replacements for all industry-standard IDC socket-cable assemblies. The socket jumpers mate with dual-row male headers, dual-row plugs with 0.635 mm square or round posts on 2.54 mm spacing. Slotted ends are also built in. Sizes offered include 10, 14, 16, 20, 26, 34, 40, 50, and 60 contacts. They supply slot-keyway, tab-key, and insertable-key sockets. The socket jumpers are designed for jumpering within a board; interconnecting between boards, backplanes, and motherboards; interfacing I/O (input/output) signals to the system; and for testing and checking equipment. For more information, contact The A P Great Jumper Company, POB 938, 72 Corwin Dr, Painesville OH 44077, (216) 354-0925.



Circle 565 on inquiry card.



Speech Evaluation Kits

The first two of a series of speech-synthesis evaluation kits have been announced by Texas Instruments Inc. The TMSK101 and TMSK201 provide a means of evaluating the TMS5100 and TMS5200 speech-synthesis integrated circuits for speech applications. Both kits use TI's linear predictive coding (LPC) technique.

The TMSK101 kit provides evaluation capability for 4-bit microprocessors. It includes a TMS5100 device and a TMS6100 ROM (read-only memory) with 204 LPC analysis-synthesis words.

The TMSK201 kit is designed for 8- or 16-bit microprocessors. It includes a TMS5200 voice-synthesis processor and a TMS2532 EPROM (erasable programmable ROM). The EPROM is programmed with a set of thirty-five items (thirty-two words, two phrases, and one tone).

Both kits are available for $140 each. Contact Texas Instruments Inc, Inquiry Answering Service, (Attn: TMSK101/201), POB 225012, M/S 308, Dallas TX 75265.

Circle 567 on inquiry card.

Disk-Copying Service

ALF Products is offering a disk-copying service for Apple-compatible floppy disks. Prices range from $2.60 each for a minimum of 50 copies to $2.10 each for 5000 copies. Memorex disks are used, but other brands can be specified. Copying can be done on customer-supplied disks for $0.60 to $0.20 each. The one-time setup charge for standard 13- or 16-sector disks is $10; special formats have a higher setup charge. A service for making standard DOS 3.2 or 3.3 disks copy-resistant is available for $25 and up. Copying of different disks can be combined to take advantage of the quantity discounts. Masters are kept on file for reorder.

For more information, contact ALF Products Inc, 1448 Estes, Denver CO 80215, (303) 234-0871.

Circle 566 on inquiry card.

12-Bit A/D Converter

The MN5245 is a 12-bit A/D (analog-to-digital) converter that offers a conversion time of less than 1 μs. Linearity is ± 0.5 LSB (least significant bit), and no missing of codes is guaranteed over the full operating-temperature range. Absolute accuracy error is 0.3% of full-scale maximum over the working temperature range. The converter can be used in spectrum analyzers, transient analysis, radar, video digitizing, and data-acquisition systems. Sample quantities are priced at $339 from Micro Networks, 324 Clark St, Worcester MA 01606, (617) 852-5400.

Circle 568 on inquiry card.

Products from Gimix

Gimix Inc, makers of memories, microprocessors, interfaces, and graphics boards for the SS-50 bus system, has published a brochure of its products. Descriptions and prices of all its items, including complete motherboard enclosures for SS-50 systems, are included. For your copy, contact Gimix Inc, 1337 W 37th Pl, Chicago IL 60609, (312) 927-5510.

Circle 569 on inquiry card.

TRS-80™ Quality Lasts . . .
OUR SALE DOESN'T!

SALE ENDS JULY 31ST, 6:00 P.M. CENTRAL TIME


Model II

SAVE UP TO $459 NOW
on Radio Shack® Microcomputers

Now you can own a great little computer at a great big discount off the manufacturer's list price. For home or office use, the Radio Shack line of computers is first in quality, performance and price:

- **FREE SHIPPING** in the 48 continental contigious states.
- **NO SALES TAX** collected on out-of-state orders.
- **CHARGE** it with your MasterCard or Visa card.
- **CONVENIENT ORDERING** Call us **TOLL FREE.**

Pan American Discounts - Compare & Save

Catalog Number	Description	List Price	Charge By Phone	Cashier's Check Or Money Order	CASH PRICE YOU SAVE
Radio Shack® TRS-80 Model II					
26-4001	32K 1-Disk Model II	3,450.00	3,167.10	3,100.00	350.00
26-4002	64K 1-Disk Model II	3,899.00	3,579.30	3,440.00	459.00
Radio Shack® TRS-80 Model III					
26-1061	Model III 4K Level-I	699.00	629.10	629.10	69.90
26-1062	Model III 16K	999.00	888.00	888.00	111.00
26-1063	Model III 32K	2,495.00	2,269.50	2,225.00	270.00
Radio Shack® TRS-80 Color Computer					
26-3001	4K Color Computer	399.00	359.10	359.10	39.90
26-3002	16K Color Computer	599.00	539.10	539.10	59.00
Radio Shack® TRS-80 Printers™					
26-1158	Daisy Wheel II	1,960.00	1,789.00	1,789.00	171.00
26-1165	Line Printer V	1,860.00	1,674.00	1,674.00	186.00
26-1166	Line Printer VI	1,160.00	1,044.00	1,044.00	116.00
26-1167	Line Printer VII	399.00	359.10	359.10	39.90

Color Computer

CALL TOLL FREE 1-800 531-7466 TO ORDER


Model III

To Order Call Toll Free 800-531-7466, Ask for Operator 17
Texas & Principle Number 512/581-2765
Telex 767339

Pan American Electronics

Dept. 17 1117 Conway Avenue Mission, Texas 78572

SEE OUR NEW Showroom & Warehouse in Dallas - Ft. Worth Metroplex
2912 North Main, Ft. Worth, Texas 76106

Circle 303 on inquiry card.

What's New?

MISCELLANEOUS



Carrying Cases

The Computer Case Company has developed five new computer-carrying cases. The cases feature padded handles, brass hardware, and key locks. The tops are removable, so the equipment can be operated in the case. Provisions are made for cords to exit the case even when the top is on and locked. Storage space is provided for manuals, cords, working papers, and supplies.

The AP104 carrying case is for the Apple III. The AP104 holds the computer, two disk drives, and a Silentype printer. It costs $139. For a video monitor, there is the AP105, which retails for $99. For the TRS-80 Model III, there's the RS204. It sells for $129. The RS205 is a $99 carrying case for the TRS-80 Color Computer. The P403 is designed for the Epson MX-80 and MX-70 printers. It costs $99.

For further details, contact Computer Case Company, 5650 Indian Mound Ct, Columbus OH 43213, (614) 868-9464.

Circle 570 on inquiry card.



16-Channel, 12-Bit Data-Acquisition Circuit

The AD364 is a 16-channel, 12-bit integrated-circuit data-acquisition system that allows users to mix single-ended and differential signals and to select either without hard-wiring. It is packaged in two hermetic DIPs (dual-inline packages), guarantees no missing codes over the working temperature range, and offers 20 kHz throughput rate.

The packages include two 8-channel multiplexers, a differential amplifier, a sample-and-hold circuit, a latched channel-address register, an input mode control, control logic, and a 12-bit A/D (analog-to-digital) converter. Inputs can be sixteen single-ended, eight differential, or a combination. Switching between single-ended and differential-signal sources or two single-ended inputs is accomplished by the use of the input mode control.

Other features include a 50 μs maximum total acquisition and conversion time per channel and input voltage ranges of ±2.5, ±5.0 and ±10 V; 0 to +5 V, and 0 to ±10 V. Output can be in either 8-bit bytes or 12-bit words. The price is $198 for single units. Contact Analog Devices, Rt 1, Industrial Park, POB 280, Norwood MA 02062, (617) 935-5565.

Circle 572 on inquiry card.



SS-50 Memory Board

Boaz Company has introduced a 64 K-byte programmable memory board for the SS-50 bus. The board features transparent refresh at 1 MHz, operation with 6800 and 6809 systems, compatibility with the 20-bit extended addressing mode, memory selection and relocation for testing, and a 200 ns access time. Power-supply requirements are +12 V at 150 mA, +5 V at 500 mA, and −5 V at 7 mA.

For complete details, contact Boaz Company, POB 18081, San Jose CA 95158.

Circle 571 on inquiry card.

16K Memory 8/$19.95

4116 200ns

ALL MERCHANDISE 100% GUARANTEED! CALL US FOR VOLUME QUOTES

LS SERIES

74LS00	.32	74LS155	1.19
74LS01	.28	74LS156	.95
74LS02	.38	74LS157	.79
74LS03	.32	74LS158	.82
74LS04	.35	74LS160	.94
74LS05	.28	74LS161	.99
74LS08	.38	74LS162	.99
74LS09	.38	74LS163	.99
74LS10	.32	74LS164	.99
74LS11	.29	74LS165	.99
74LS12	.29	74LS166	2.40
74LS13	.38	74LS168	1.79
74LS14	.99	74LS169	1.79
74LS15	.35	74LS170	1.89
74LS20	.26	74LS173	.82
74LS21	.30	74LS174	1.19
74LS22	.34	74LS175	1.09
74LS26	.40	74LS181	2.19
74LS27	.35	74LS190	1.15
74LS28	.39	74LS191	1.31
74LS30	.35	74LS192	.88
74LS32	.39	74LS193	.98
74LS33	.54	74LS194	1.80
74LS37	.78	74LS195	1.39
74LS38	.39	74LS196	.82
74LS40	.25	74LS197	.82
74LS42	.79	74LS221	1.28
74LS47	.78	74LS240	1.89
74LS48	.78	74LS241	1.89
74LS51	.35	74LS242	1.89
74LS54	.35	74LS243	1.89
74LS55	.32	74LS244	1.79
74LS73	.44	74LS245	2.89
74LS74	.48	74LS251	1.32
74LS75	.58	74LS253	.89
74LS76	.50	74LS257	.89
74LS78	.59	74LS258	.89
74LS83	.90	74LS259	2.89
74LS85	1.23	74LS260	.68
74LS86	.45	74LS266	.68
74LS90	.70	74LS273	1.69
74LS92	.82	74LS275	3.39
74LS93	.71	74LS279	.59
74LS95	1.11	74LS283	1.03
74LS96	.86	74LS290	1.25
74LS107	.43	74LS293	1.89
74LS109	.49	74LS295	1.09
74LS112	.48	74LS298	1.24
74LS113	.48	74LS352	1.59
74LS114	.55	74LS353	1.59
74LS122	.55	74LS363	1.39
74LS123	.99	74LS365	.99
74LS124	2.99	74LS366	.99
74LS125	.99	74LS367	.99
74LS126	.88	74LS368	.99
74LS132	.69	74LS373	1.85
74LS136	.58	74LS374	1.81
74LS138	.79	74LS377	1.48
74LS139	.79	74LS385	1.90
74LS145	1.19	74LS386	.65
74LS148	1.39	74LS390	1.90
74LS151	.79	74LS393	1.90
74LS153	.79	74LS395	1.69
74LS154	2.39	74LS670	2.20

16K STATIC

TMM 2016	200ns	19.95ea

64K DYNAMIC

8164	200ns SINGLE SUPPLY	29.95ea

RAMS

			100pcs
2101	(450ns)	2.49	2.29
2102-1	(450ns)	.99	.95
21L02-1	(450ns)	1.29	1.15
2111	(450ns)	2.99	2.49
2112	(450ns)	2.99	2.79
2114	(450ns)	2.95	2.85
2114L-2	(200ns)	8/29.95	3.10
2114L-3	(300ns)	8/24.95	2.95
4027	(250ns)	4.95	3.95
4116-15	(150ns)	8/21.95	2.65
4116-20	(200ns)	8/19.95	2.35
4116-30	(300ns)	8/18.99	2.00

EPROMS

			8pcs
1702	(1us)	4.95	4.75
2708	(450ns)	4.95	4.75
2758	(5v) (450ns)	9.95	Call
2716	(5v) (450ns)	7.95	6.95
2716-1	(5v) (350ns)	12.95	10.95
TMS2716	(450ns)	9.95	8.95
2732	(5v) (450ns)	19.95	Call
2532	(5v) (450ns)	21.95	Call

ORDER TOLL FREE

800-538-5000 Cont. USA
800-662-6233 In Calif.

6502

6502	10.95
6522	11.95
6532	19.95

MISC.

2560	12.85
3242	9.95
1771	24.95
AY5-1013	4.95
TR1602	4.95
IM6402	7.95
8T26	2.49
8T28	2.49
8T97	1.69
8T98	1.69
1488	1.39
1489	1.39

Z80

Z80	9.95
Z80A	12.95
Z80B	19.95
Z80-PIO	7.60
Z80A-PIO	8.60
Z80-CTC	7.65
Z80A-CTC	8.65
Z80-DMA	18.00
Z80A-DMA	25.95
Z80-SIO	21.95
Z80A-SIO	25.95

6800

6800	11.75
6802	17.95
6809	37.95
6810	4.60
6820	5.75
6821	6.40
6828	9.95
6834	19.95
6847	19.95
6850	5.75
6852	5.75
6875	6.95

8080

8035	16.95
8039	19.95
8080A	3.95
8085	12.95
8086	99.95
8088	39.95
8741	49.95
8748	59.95
8755	64.95
8155	11.95
8156	11.95
8185	29.95
8185-2	39.95
8202	45.00
8205	4.95
8212	2.75
8214	5.25
8216	2.75
8224	2.95
8226	3.49
8228	4.95
8238	5.50
8243	6.50
8251	6.95
8253	12.95
8253-5	13.95
8255	6.50
8255-5	7.50
8257	16.95
8259	14.95
8275	49.95
8279	15.95
8279-5	16.95
8282	6.50
8283	6.50
8284	5.80
8286	6.65
8287	6.65
8288	24.95
8289	49.95

T.V. CIRCUITS

MC1330	1.89
MC1350	1.29
MC1358	1.79
LM380	1.29
LM565	.99
LM741	.29
LM1310	2.90
LM1800	2.99
LM1889	2.49

7400 SERIES

7400	.19	7450	.19	74123	.59
7402	.19	7472	.29	74151	.69
7404	.24	7473	.34	74153	.59
7406	.29	7474	.35	74154	1.49
7407	.29	7475	.49	74156	.69
7408	.24	7476	.35	74157	.69
7410	.19	7483	.65	74161	.79
7420	.19	7486	.35	74163	.89
7430	.19	7490	.49	74164	.89
7432	.29	7491	.69	74173	1.39
7440	.19	7492	.59	74174	.89
7442	.49	7493	.49	74175	.89
7445	.69	7496	.74	74176	.89
7446	.69	74100	1.19	74192	.79
7447	.59	74107	.34	74193	.79
7448	.69	74121	.34	74196	.79

IC SOCKETS

8 pin ST	10/1.29	8 pin WW	.59
14 pin ST	10/1.49	14 pin WW	.69
16 pin ST	10/1.69	16 pin WW	.69
18 pin ST	10/1.99	18 pin WW	.99
20 pin ST	10/2.89	20 pin WW	1.09
22 pin ST	10/2.99	22 pin WW	1.39
24 pin ST	10/2.99	24 pin WW	1.49
28 pin ST	10/3.99	28 pin WW	1.69
40 pin ST	10/4.99	40 pin WW	1.99

ST = SOLDERTAIL WW = WIREWRAP

VOLTAGE REG's

7805T	.89	7905T	.99
7812T	.89	7912T	.99
7815T	.99	7915T	1.19
7824T	.99	7924T	1.19
7805K	1.39	7905K	1.49
7812K	1.39	7912K	1.49
78L05	.69	79L05	.79
78L12	.69	79L12	.79
78L15	.69	79L15	.79

T = TO-220 K = TO-3 L = TO-92

TRANSISTORS

PN2222	10/1.00	100/8.99
2N3904	10/1.00	100/8.99
2N3906	10/1.00	100/8.99
2N3055	.79	10/6.99
IN4148		25/1.00
IN4004		10/1.00

LEDS

Jumbo Red	10/1.00
Jumbo Green	6/1.00
Jumbo Yellow	6/1.00
5082-7760 .43'CC	.79
MAN74 .3'CC	.99
MAN72 .3'CA	.99

74S00 SERIES

74S00	.50	74S124	3.95	74S288	4.75
74S02	.50	74S174	1.49	74S387	5.75
74S04	.50	74S188	4.75	74S471	18.75
74S08	.50	74S195	1.95	74S472	18.75
74S37	.55	74S240	2.95	74S474	19.95
74S74	.80	74S260	1.80	74S570	7.80
74S113	.79	74S287	4.75	74S571	7.80

CMOS

4001	.35	4024	.99	4070	.49
4002	.39	4025	.29	4071	.49
4007	.25	4027	.65	4072	.49
4009	.49	4040	1.29	4081	.39
4010	.49	4042	.99	4093	.99
4011	.35	4046	1.79	4098	2.49
4012	.29	4047	2.49	4503	.69
4013	.49	4049	.49	4508	3.95
4016	.59	4050	.69	74C04	.39
4017	1.19	4060	1.39	74C14	1.49
4020	1.19	4066	.79		
4023	.29	4069	.39		

LINEAR

LM301V	.34	LM555V	.39	LM1414	1.59
LM308V	.98	LM556	.69	LM1458V	.69
LM309K	1.49	LM565	.99	LM1488	1.39
LM311V	.64	LM566V	1.49	LM1489	1.39
LM317T	2.29	LM567V	1.29	LM1800	2.99
LM318V	1.49	LM723	.49	LM1889	2.49
LM323K	4.95	LM733	.98	LM3900	.59
LM324	.59	LM741V	.29	75451V	.39
LM339	.99	LM747	.79	MC1330V	1.89
LM377	2.29	LM748V	.59	MC1350V	1.29
LM380	1.29	LM1310	2.90	MC1358	1.79

T = TO-220 V = 8 PIN K = TO-3

DIP SWITCHES

4 position	.99
5 position	1.02
6 position	1.06
7 position	1.09
8 position	1.14

master charge THE INTERBANK CARD

VISA®

JDR MICRODEVICES, INC.
1101 South Winchester Blvd.
San Jose, California 95128
800-538-5000 408-247-4852
800-662-6233 (Calif.)

TERMS: For shipping include $2.00 for UPS Ground; $3.00 for UPS Blue Label Air; $10.00 minimum order. Bay Area Residents add 6½% sales tax Calif. Residents add 6% sales tax. We reserve the right to limit quantities and substitute manufacturer. Prices subject to change without notice.

Circle 196 on inquiry card.

What's New?

MISCELLANEOUS

Laboratory System for the Apple



Applab is a microcomputer system designed for laboratory applications. When used with an Apple II Plus, Applab can control or collect data from spectrophotometers, chromatography systems, pH meters, strip-chart recorders, and temperature controllers.

Applab's hardware interface features 12-bit D/A (digital-to-analog) and A/D (analog-to-digital) converters with ranges of ±0.5 to ±4.0 V, differential input, and automatic zeroing.

The I/O (input/output) subsystem features 8 bits each of input and output, handshaking signals, interrupt circuitry, and TTL- (transistor-transistor logic) compatible signal levels. A real-time clock permits timing of events to an accuracy of 0.1 second. Two 16-bit timers can be configured as an interval timer, pulse counter, pulse generator, square-wave frequency generator, or shift register.

Included is the QuickI/O program, which makes it easy to write BASIC programs to control scientific instruments. The Applab interface card, QuickI/O software on floppy disk, three cables, a self-test adapter board, diagnostic software, and two manuals are available for $495. For further information, contact Interactive Microware Inc, POB 771, State College PA 16801, (814) 238-8294.

Circle 573 on inquiry card.

Multichannel Video Controller



The MCV-1023 multichannel video controller is Multibus-compatible. It is designed for on-line information, graphics, and data-processing applications. An on-board microprocessor performs control and logic functions, providing intermixable text and graphics display. Three software-selectable character fonts, user-defined custom characters, an addressable cursor, an independently addressed status line, and an on-board date and time clock are also included. Characters of differing sizes can be intermixed on the screen. Underlining, strike through, blinking, boxing, reverse, and dual-intensity video fields are included. A paging feature switches the video on a single display between two sources, allowing screen updating.

Typical graphics operations, such as animation, facsimile presentation, vector lines, point plots, and box or block generation, can be performed with minimal software overhead. In graphics operations, the display is treated as 512 horizontal dots by 256 vertical lines. Communication between the MCV-1023 and the host system is done through programmed input/output and a shared 2 K-byte block of programmable memory. The MCV-1023 evaluation board is $695. It is available from Metacomp Inc, 7290 Engineer Rd, Suite F, San Diego CA 92111, (714) 278-0635.

Circle 574 on inquiry card.

INTELLIGENT VIDEO I/O FOR S-100 BUS



VIO-X

The VIO-X I/O Interface for the S-100 bus provides features equal to most intelligent terminals both efficiently and economically. It allows the use of standard keyboards and CRT monitors in conjunction with existing hardware and software. It will operate with no additional overhead in S-100 systems regardless of processor or system speed.

Through the use of the Intel 8275 CRT controller with an onboard 8085 processor and 4k memory, the VIO-X interface operates independently of the host system and communicates via two ports. The screen display rate is effectively 80,000 baud.

The VIO-X1 provides an 80 character by 24 line format using a 7 × 9 dot matrix to display the full upper and lower case ASCII alphanumeric 96 printable character set (including true descenders) with special characters for escape and control characters. An optional 2732 character generator is available which allows an alternate 7 × 9 contiguous graphics character set.

The VIO-X2 offers an 80 character by 25 line format using a 9 × 9 dot matrix allowing high-resolution characters to be used. This model also includes expanded firmware for block mode editing.

Both models support a full set of control characters and escape sequences, including controls for video attributes, cursor location and positioning, cursor toggle, light pen location, and scroll speed.

Video attributes provided by the 8275 in the VIO-X include:

- FLASH CHARACTER
- INVERSE CHARACTER
- UNDERLINE CHARACTER or
- ALTERNATE CHARACTER SET
- DIM CHARACTER

The above functions may be toggled together or separately.

The board may be addressed at any port pair in the S-100 host system. Status and data ports may be swapped if necessary. Inputs are provided for parallel keyboard and for light pen as well as an output for audio signalling. The interrupt structure is completely compatible with Digital Research's MP/M

FEATURES

- HIGH SPEED OPERATION
- PORT MAPPED S-100 INTERFACE
- FORWARD/REVERSE SCROLL or
- PROTECTED SCREEN FIELDS
- CONVERSATIONAL or BLOCK MODE
- INTERRUPT OPERATION
- CUSTOM CHARACTER SET
- CONTROL CHARACTERS
- ESCAPE CHARACTER COMMANDS
- INTELLIGENT TERMINAL EMULATION
- TWO PAGE SCREEN MEMORY

VIO-X1 80 × 24 7 × 9 A & T **$295.00**
Conversational & Limited Block Modes
VIO-X2 80 × 25 9 × 9 A & T **$345.00**
Conversational & Block Modes



VIO-X S-100 I/O INTERFACE

FULCRUM™
COMPUTER PRODUCTS

Distributed by:
WW COMPONENT SUPPLY INC. 1771 JUNCTION AVENUE • SAN JOSE, CA 95112 • (408) 295-7171

Circle 429 on inquiry card.

Circle 197 on inquiry card.

LOBO Add-On Disk Drive Subsystems For Apple, TRS-80, S-100 Based Computers



Expansion and **enhanced capabilities** are key words in achieving full utilization of your computer system. Our complete line of LOBO disk drive subsystems are the ideal, cost-effective way to provide the expansion capabilities you need to meet your system growth requirements. All of our subsystems are complete, thoroughly-tested, 100% burned-in, and feature a 1 year 100% parts/labor warranty.

APPLE

*Double Density Controller

3101	Minifloppy, $399 3101I Minifloppy w/interface card $489
8101CA	One SA800 in cabinet w/power, DDC* Controller, cable and manual $1449
8202CA	Two SA800 in cabinet w/power, DDC* Controller, cable and manual $1889
5101CA	One SA850 in cabinet w/power, DDC* Controller, cable and manual $1759
5202CA	Two SA850 in cabinet w/power, DDC* Controller, cable and manual $2364
LCA-22	Double Density Controller only $599

S-100 BASED COMPUTERS

MODEL NO.	DESCRIPTION
4101C	SA400 in cabinet w/power $369
8212C	Two SA801 in cabinet w/power $1329
5212C	Two SA851 in cabinet w/power $1799

GENERAL

MODEL NO.	DESCRIPTION
8212C	Two SA801 in cabinet w/power $1329
5212C	Two SA851 in cabinet w/power $1799

TRS80

MODEL NO.	DESCRIPTION
4101C	SA400 in cabinet w/power $369
8101C II	One SA800 in cabinet w/power for Mod. II $909
8202C II	Two SA800 in cabinet w/power for Mod. II $1349
LX80	Double density expansion interface $641
RS232	Dual Serial Port Option $75

master charge THE INTERBANK CARD   VISA®

JR INVENTORY CO.,
P.O. Box 185, Santa Ynez, Ca., 93460
(805) 688-8781

FLOPPY DISK DRIVES



Qume DT-8 ....$599 – 2/$1150
Virtually the industry standard. High quality/reliability. Full featured, double-sided, double density.

Mitsubishi!!!!!! $649
Up & coming potential giant of the double sided/double density realm.

Shugart 851R $649
Double sided/double density

Shugart 800/801R. . . . .$425 - 2/$820

Siemens FDD100-8D$395 – 2/$755

Tandon double sided mini-floppy. Shugart compatible, double density. ....$350 – 2/$640

SA400 mini-floppy. 35 track, double density......................$299 – 2/$525

CONTROLLERS

Tarbell single density kit $210
Tarbell single density A & T $290
Tarbell double density A & T $450
MDA LSI-11 floppy controller $1095



SPECIAL!! CCS 2422A floppy disk controller with CP/M version 2.2 $375



FLOPPY POWER SUPPLY: Handles two units with the greatest of ease. $109



CABLE KITS:
One drive $30
Two $35
Three $40
Four $45
Includes all wire, cable + connectors to hook up most drive systems.

DISKETTES: Single sided $39/10 – Double sided $59/10

SPECIAL SPECIALS (very limited supply)

SBC 80/30 CPU card (used)	$475.
SBC 604	$150.
SBC 614	$150.
UDS 103J modem card (used)	$100.
UDS 801A dialer card (used)	$100.

all used gear here comes with 90 day warranty.

CRYSTALS ... most major values. Call for case size, etc.
$2.75/ea. .... 25/$2.50 .... 100/$2.20
3.57954/$.99 ea – 100/$.80

CONNECTORS... many types in stock. IDC, etc. all connectors $3.00 ea. 50/$2.75 – 100/$2.50
– call for particulars –

Qume S/5 – Daisy Wheel Printer

Sprint 5/45 RO	$2699
Sprint 5/55 RO	2829
Sprint 5/45 KSR	3029
Sprint 5/55 KSR	3159
Forms Tractor	210
Pinfeed platen	155
Paper Guide	30
Paper Basket	50

many print wheels, ribbons, & more available.

Terms of sale: cash or checks, purchase orders from qualified firms and institutions. Minimum order $25. CA residents add 6% tax. Prices subject to change without notice. All goods subject to prior sale. Minumum shipping/handling charge $4.00.

Electrolabs
POB 4436, Stanford, CA 94305 (415) 321-5601

Circle 137 on inquiry card.

Quest ELECTRONICS

P.O. Box 4430X
Santa Clara, CA 95054
Will calls: 2322 Walsh Ave.
(408) 988-1640 TWX 910-338-2139

Same day shipment. First line parts only. Factory tested. Guaranteed money back. Quality IC's and other components at factory prices.

INTEGRATED CIRCUITS

7400TTL
7400N .19
7402N .20
7404N .25
7409N .27
7410N .25
7414N .70
7420N .25
7422N .39
7430N .25
7442N .58
7445N .82
7447N .63
7448N .77
7450N .25
7474N .35
7475N .49
7485N .88
7489N 1.70
7490N .43
7492N .43
7493N .43
7495N .69
74100N 1.35
74107N .35
74121N .34
74123N .59
74125N .45
74145N .77
74150N 1.20
74151N .69
74154N 1.25
74157N .69
74161N .87
74162N .85
74163N .87
74174N .96
74175N .85
74190N 1.15
74192N .87
74193N .85
74221N 1.25
74296N 1.65
74365N .75
74366N .75
74367N .75

74LS00TTL
74LS00N .29
74LS02N .29
74LS04N .35
74LS05N .25
74LS08N .35
74LS10N .35
74LS13N .55
74LS14N 1.00
74LS20N .35
74LS22N .35
74LS28N .35
74LS30N .35
74LS33N .60
74LS38N .50
74LS74N .45
74LS75N .65
74LS90N .60
74LS93N .75
74LS95N 1.00
74LS107N .45
74LS112N .45
74LS113N .45
74LS132N .89
74LS136N .50
74LS151N .75
74LS155N .79
74LS157N 1.10
74LS162N 1.10
74LS163N 1.10
74LS174N 1.15
74LS190N 1.25
74LS221N 1.25
74LS258N 1.00
74LS367N .89

LINEAR
CA3045 .90
CA3046 1.10
CA3081 1.80
CA3082 1.90
CA3089 3.40
LM301AN/AH .35
LM305H .87
LM307N .35
LM308N 1.00
LM309K 1.25
LM311H/N .90
LM317T 1.65
LM317K 3.75
LM318 1.50
LM320K-5 1.35
LM320K-12 1.35
LM320K-15 1.35
LM320T-5 .95
LM320T-8 .95
LM320T-12 .95
LM320T-15 .95
LM323K-5 5.95
LM324N 1.00
LM339N 1.00
LM340K-5 1.35
LM340K-8 1.35
LM340K-12 1.35
LM340K-15 1.35
LM340K-24 1.35
LM340T-5 .85
LM340T-8 .85
LM340T-12 .85
LM340T-15 .85
LM340T-18 .85
LM340T-24 .85
LM350 5.50
LM377 2.95
LM379 5.00
LM380N 1.00
LM381 1.60
LM382 1.60
LM709H .59
LM723H/N .50
LM733N .85
LM741CH .35
LM741N .38
LM747H/N .75
LM748N .50
LM1303N 1.75
LM1304 1.10
LM1305 1.27
LM1307 2.00
LM1310 1.95
LM1458 .55
LM1812 7.50
LM1889 3.00
LM2111 1.75
LM2902 2.25
LM3900N .60
LM3905 1.75
LM3909N .95
MC1458V .55
NE550N 1.35
NE555V .39
NE556A .85
NE565A 1.00
NE566V 1.50
NE567V 1.00
NE570B 4.75
78L05 .60
78L08 .60
78M05 .85
75108 1.75
75491CN .50
75492CN .55
75494CN .89

A to D CONVERTER
8038B 4.50
8700CJ 13.95
8701CN 22.00
8750CJ 13.95
LD130 9.95
9400CJV/F 7.40
ICL7103 9.50
ICL7107 14.25

CMOS
CD4000 .25
CD4001 .35
CD4002 .35
CD4006 1.10
CD4007 .35
CD4008 1.20
CD4009 .45
CD4010 .45
CD4011 .35
CD4012 .28
CD4013 .47
CD4014 1.25
CD4015 1.00
CD4016 .55
CD4017 1.05
CD4018 .94
CD4019 .45
CD4020 1.02
CD4021 1.35
CD4022 1.10
CD4023 .28
CD4024 .75
CD4025 .28
CD4026 2.50
CD4027 .66
CD4028 .85
CD4029 1.35
CD4030 .45
CD4035 1.00
CD4040 1.35
CD4042 .85
CD4043 .85
CD4044 .85
CD4046 1.67
CD4049 .45
CD4050 .60
CD4051 1.13
CD4060 1.42
CD4066 .71
CD4068 .40
CD4069 .40
CD4070 .50
CD4071 .45
CD4072 .45
CD4073 .45
CD4075 .45
CD4076 1.45
CD4078 .40
CD4081 .35
CD4082 .35
CD4116 .47
CD4490 5.50
CD4507 1.00
CD4508 2.85
CD4510 1.00
CD4511 .94
CD4515 2.52
CD4516 1.10
CD4518 1.50
CD4520 1.02
CD4527 1.51
CD4528 1.60
CD4553 3.50
CD4566 2.45
CD4583 2.35
CD4585 1.10
CD40192 3.00
74C00 .35
74C04 .40
74C10 .35
74C14 .89
74C20 .35
74C30 .35
74C48 1.95
74C74 .85
74C76 1.25
74C90 1.25
74C93 1.25
74C154 3.50
74C160 2.75
74C175 1.35
74C192 1.65
74C221 1.90
74C905 6.00
74C906 .75
74C914 1.95
74C922 5.00
74C923 5.50
74C925 7.50
74C926 6.95
74C927 6.95

INTERFACE
8095 .65
8096 .65
8097 .65
8098 .65
8T09 1.25
8T10 4.50
8T13 3.00
8T20 5.50
8T23 3.10
8T24 3.50
8T25 3.20
8T26 1.69
8T28 2.75
8T97 1.69
8T98 1.69

MOS/MEMORY RAM
2101-1 2.95
2102-1 .95
2102AL-4 1.45
2102AN-2L 1.65
2104A-4 4.95
2107B-4 3.75
2111-1 3.75
2112-2 3.95
2114 3.75
2114L 300ns 4.25
2114L 450ns 4.00
4116 200ns 3.95
8/4116 200ns 18.40
MM5262 .40
MM5280 3.00
MM5320 9.95
MM5330 5.94
PD411D-3 4.00
PD411D-4 5.00
P5101L 8.95
4200A 9.95
82S25 2.90
91L02A 1.50
HD0165-5 6.95
MM57100 4.50
GIAY38500-1 9.95
MCM66751A 9.95
9368 3.50
4100 10.00
416 16.00

CLOCKS
MM5311 5.50
MM5312 3.90
MM5314 3.90
MM5369 2.10
MM5841 14.45
MM5865 7.95
CT7010 8.95
CT7015 8.95
MM5375AA/N 3.90
MM5375AG/N 4.90
7205 16.50
7207 7.50
7206 15.95
7209 4.95
DS0026CN 3.75
DS0056CN 3.75
MM53104 2.50

MICROPROCESSOR
6502 10.95
6504 9.95
6522 9.95
6800 6.95
6802 11.95
6820 4.95
6650 5.95
8080A 3.95
8085 12.95
8086 75.00
Z80 9.95
Z80A 11.95
8212 2.90
8214 3.95
8216 2.90
8224 3.45
8228 4.95
8251 6.95
8253 15.00
8255 5.75
8257 10.95
8259 14.95
1802CP plas 13.95
1802DP plas 17.95
1861P 9.50
CDP1802CD 28.95
CDP1802D 35.00
CDP1816P 7.95

UART/FIFO
AY5-1013 5.50
AY5-1014 7.50
3341 6.95

PROM
1702A 5.85
2708 6.10
2716T1 12.00
2716 5 Volt 10.50
8/2716 5 Volt 64.00
2732 19.95
2758 14.00
8741A 55.00
8746 55.00
8748-8 55.00
8755A 55.00
N82S23 2.95
N82S123 4.95
N82S126 4.75
N82S129 4.95
N82S131 4.95
N82S136 8.75
N82S137 8.75
DM8577 2.90
8223 3.50

CONNECTORS
30 pin edge 2.50
44 pin edge 2.75
86 pin edge 4.00
100 pin edge 4.50
100 pin edge WW 5.25

IC SOCKETS

Solder Tin Low Profile PIN	1 UP	PIN	1UP
8	.15	22	.30
14	.14	24	.35
16	.16	28	.42
18	.27	36	.58
20	.29	40	.57

2 level 14 pin ww .20

WIRE WRAP LEVEL 3

PIN		PIN	
14	.55	24	.93
16	.57	28	1.00
18	.67	40	1.59

CRYSTALS
1 MHz 4.50
2 MHz 4.50
4 MHz 4.25
5 MHz 4.25
10 MHz 4.25
18 MHz 3.90
20 MHz 3.90
32 MHz 3.90
32768 Hz 4.00
1.8432 MHz 4.50
3.5795 MHz 1.20
2.0100 MHz 1.95
2.097152 MHz 4.50
2.4576 MHz 4.50
3.2768 MHz 4.50
5.0686 MHz 4.50
5.185 MHz 4.50
5.7143 MHz 4.50
6.5536 MHz 4.50
14.31818 MHz 4.25
18.432 MHz 4.50
22.1164 MHz 4.50

KEYBOARD ENCODERS
AY5-2376 $12.50
AY5-3600 17.95
AY5-9100 10.50
AY5-9200 16.50
74C922 5.50
74C923 5.50
HD0165-5 6.95
AY5-9400 10.50

D Connectors RS232
DB25P 3.62
DB25S 5.20
Cover 1.67
DE9S 1.95
DA15P 2.10
DA15S 3.10
Complete Set 9.50

Hickok 3½ DigitLED multimeter 89.95
Stopwatch Kit 26.95
Auto Clock Kit 17.95
Digital Clock Kit 14.95

8K/16K Eprom Kit (less PROMS) $89.00
Motherboard $39.00
Extender Board $15.00

RESISTORS ¼ watt 5%
10 per type .03
25 per type .025
100 per type .015
1000 per type .012
350 piece pack
5 per type 6.75
½ watt 5% per type .05

Televideo Terminal
Model 912 $785.00
Model 920 $885.00

KEYBOARDS
56 key ASCII keyboard kit $67.50
Fully assembled 77.50
53 key ASCII keyboard kit 60.00
Fully assembled 70.00
Enclosure Plastic 14.95
Metal Enclosure 29.95

LEDS
Red T018 .15
Green, Yellow T018 .20
Jumbo Red .20
Green, Orange, Yellow Jumbo .25
Cliplite LED Mounting Clips 8/$1.25
(specify red, amber, green, yellow, clear)

CONTINENTAL SPECIALTIES in stock
Complete line of breadboard test equip.
MAX-100 8 digit Freq. Ctr. $149.95

OK WIRE WRAP TOOLS in stock
Portable Multimeter $18.00

Complete line of AP Products in stock.

SPECIAL PRODUCTS
MM5865 Stopwatch Timer with 10 pg. spec 9.00
PC board 7.50
Switches Mom. Pushbutton .27
3 pos. slide .25
Encoder HD0165-5 6.95
Paratronics
Model 10 Trigger Expander Kit $229.00
Model 150 Bus Grabber Kit $369.00
Clock Calendar Kit $23.95
2.5 MHz Frequency Counter Kit $37.50
30 MHz Frequency Counter Kit $47.75

TRANSFORMERS
6V 300 ma 3.25
12 Volt 300 ma transformer 1.25
12.6V CT 600 ma 3.75
12V 250 ma wallplug 2.95
12V CT 250 ma wall plug 3.75
24V CT 100 ma 3.95
10V 1.2 amp wall plug 4.85
12V 6 amp 12.95
12V 500 ma wall plug 4.75
12V 1 amp wall plug 6.50
10/15 VAC 8/16 VA wall plug 9.75

DISPLAY LEDS

MAN1	CA	.270	2.90
MAN3	CC	.125	.39
MAN72/74	CA/CA	.300	1.00
DL704	CC	.300	1.25
DL707/DL707R	CA	.300	1.00
DL727/728	CA/CC	.500	1.90
DL747/750	CA/CC	.600	1.95
FND359	CC	.357	.70
FND500/507	CC/CA	.500	1.35
FND503/510	CC/CA	.500	.90
FND800/807	CC/CA	.800	2.20
3 digit Bubble			.60
10 digit display			1.25
7520 Clairex photocells			.39
TIL311 Hex			9.50
MAN3640	CC	.30	1.10
MAN4610	CA	.40	1.20
MAN4640	CC	.40	1.20
MAN4710	CA	.40	.95
MAN4740	CC	.40	1.20
MAN6640	CC	.56	2.95
MAN6710	CA	.60	1.35
MAN6740	CC	.60	1.35

MA1002A, C, E 8.95
MA1012A 8.95
102P3 transformer 2.25
MA1012A Transformer 2.25

DIP Switches
4-position S .95
5-position 1.00
6-position 1.00
7-position 1.00
8-position 1.05

4116 200ns Dynamic RAM 8/$18.40



RCA Cosmac 1802 Super Elf Computer $106.95

Compare features before you decide to buy any other computer. There is no other computer on the market today that has all the desirable benefits of the **Super Elf** for so little money. The Super Elf is a small single board computer that does many **big** things. It is an excellent computer for training and for learning programming with its machine language and yet it is easily **expanded** with **additional memory, Full Basic, ASCII Keyboards, video character generation, etc.**

Before you buy another small computer, see if it includes the following features: ROM monitor; State and Mode displays; Single step; Optional address displays; Power Supply; Audio Amplifier and Speaker; Fully socketed for all IC's; Real cost of in warranty repairs; Full documentation.

The **Super Elf** includes a **ROM** monitor for program loading, editing and execution with **SINGLE STEP for program debugging** which is not included in others at the same price. With **SINGLE STEP** you can see the microprocessor chip operating with the **unique Quest** address and data bus displays **before, during** and **after** executing instructions. Also, CPU mode and instruction cycle are decoded and displayed on 8 LED indicators.

An RCA 1861 **video graphics** chip allows you to connect to your own TV with an inexpensive video modulator to do graphics and games. There is a **speaker system** included for writing your own music or using many music programs already written. The speaker amplifier may also be used to drive relays for control purposes.

A 24 key **HEX keyboard** includes 16 HEX keys plus **load, reset, run, wait, input, memory protect, monitor select** and **single step.** Large, on board displays provide output and optional **high and low address.** There is a 44 pin standard connector slot for PC cards and a 50 pin connector slot for the Quest Super Expansion Board. Power supply and sockets for **all** IC's are included in the price plus a detailed 127 pg. instruction manual which now includes over 40 pgs. of software info. including a series of lessons to help get you started and a music program and graphics target game. Many schools and universities are using the Super Elf as a course of study. OEM's use it for training and R&D.

Remember, other computers only offer Super Elf features at additional cost or not at all. **Compare before you buy. Super Elf Kit $106.95, High address option $8.95, Low address option $9.95. Custom Cabinet** with drilled and labelled plexiglass front panel **$24.95.** All metal Expansion Cabinet, painted and silk screened, with room for 5 S-100 boards and power supply **$57.00. NiCad Battery Memory Saver Kit $6.95.** All kits and options also completely assembled and tested.

Questdata, a software publication for 1802 computer users is available by subscription for $12.00 per 12 issues. Single issues $1.50. Issues 1-12 bound $16.50.

Free 14 page brochure.

Moews Video Graphics **$3.50.** Games and Music **$3.00,** Chip 8 Interpreter **$5.50.**

Super Expansion Board with Cassette Interface $89.95

This is truly an astounding value! This board has been designed to allow **you** to decide how you want it optioned. **The Super Expansion Board comes with 4K of low power RAM** fully addressable anywhere in 64K with built-in memory protect and a **cassette interface.** Provisions have been made for all other options on the same board and it fits neatly into the hardwood cabinet alongside the **Super Elf.** The board includes slots for up to 6K of **EPROM** (2708, 2758, 2716 or **TI** 2716) and is **fully socketed.** EPROM can be used for the monitor and Tiny Basic or other purposes.

A 1K Super ROM Monitor $19.95 is available as an on board option in 2708 EPROM which has been preprogrammed with a program loader/editor and error checking multi file cassette read/write software, (relocatable cassette file) another exclusive from Quest. It includes register save and readout, block move capability and video graphics driver with blinking cursor. Break points can be used with the register save feature to isolate program bugs quickly, then follow with single step. If you have the **Super Expansion Board** and **Super Monitor** the monitor is up and running at the push of a button.

Other on board options include **Parallel Input and Output Ports** with **full handshake.** They allow easy connection of an ASCII keyboard to the input port. **RS 232 and 20 ma Current Loop** for teletype or other device are on board and if you need more memory there are two **S-100** slots for static RAM or video boards. Also a 1K Super Monitor version 2 with video driver for full capability display with Tiny Basic and a video interface board. **Parallel I/O Ports $9.85, RS 232 $4.50, TTY 20 ma I/F $1.95, S-100 $4.50.** A **50 pin connector set** with ribbon cable is available at $15.25 for easy connection between the **Super Elf** and the **Super Expansion Board.**

Power Supply Kit for the complete system (see Multi-volt Power Supply).

Quest Super Basic V5.0

A new enhanced version of **Super Basic** now available. Quest was the first company worldwide to ship a full size Basic for 1802 Systems. A complete function **Super Basic** by **Ron Cenker** including floating point capability with scientific notation (number range $\pm .17E^{38}$), 32 bit integer ±2 billion; multi dim arrays, string arrays; string manipulation; cassette I/O; save and load, basic, data and machine language programs; and over 75 statements, functions and operations.

New improved faster version including **renumber** and essentially **unlimited variables.** Also, an exclusive user expandable command library.

Serial and Parallel I/O included.

Super Basic on Cassette $55.00.

Ohio Scientific Computers

CIP Series 2 **$447.00.** Like an Apple at less than half the price! CIPMF Series 2 **$1199.00.** Minifloppy version with additional RAM/ROM. Complete software and peripherals available. Send for free brochure.

Elf II Adapter Kit $24.95

Plugs into Elf II providing Super Elf **44** and 50 pin plus S-100 bus expansion. (With Super Expansion). High and low address displays, state and mode LED's optional **$18.00.**

Gremlin Color Video Kit $69.95

32 x 16 alpha/numerics and graphics; up to 8 colors with 6847 chip; 1K RAM at E000. Plugs into Super Elf 44 pin bus. No high res. graphics. On board RF Modulator Kit **$4.95**

Super Color S-100 Video Kit $129.95

Expandable to 256 x 192 high resolution color graphics. 6847 with all display modes computer controlled. Memory mapped. 1K RAM expandable to 6K. S-100 bus 1802, 8080, 8085, Z80 etc.

Dealers: Send for excellent pricing/margin program.

1802 16K Dynamic RAM Kit $149.00
Expandable to 32K. Hidden refresh w/clocks up to 4 MHz w/no wait states. Addl. 16K RAM **$25.00**

Tiny Basic Extended on Cassette $15.00
(added commands include Stringy, Array, Cassette I/O etc.) S-100 4-Slot Expansion $ 9.95
Super Monitor VI.I Source Listing $15.00

Editor Assembler $25.00
(Requires minimum of 4K for E/A plus user source)
1802 Tiny Basic Source listing $19.00
Super Monitor V2.0/2.1 Source Listing $20.00

PROM Eraser

assembled. 25 PROM capacity **$37.50** (with timer **$69.50**). 6 PROM capacity OSHA/UL version **$69.50** (with timer **$94.50**).

Z80 Microcomputer

16 bit I/O, 2 MHz clock, 2K RAM, ROM Breadboard space. Excellent for control. Bare Board **$28.50.** Full Kit **$99.00.** Monitor **$20.00.** Power Supply Kit **$35.00. Tiny Basic $30.00**

S-100 Computer Boards

8K Static Godbout Econo IIA Kit	149.00
16K Static Godbout Econo XIV Kit	269.00
24K Static Godbout Econo XX-24 Kit	414.00
32K Static Godbout Econo XX-32 Kit	537.00
16K Dynamic RAM Kit	289.00
32K Dynamic RAM Kit	328.00
64K Dynamic RAM Kit	399.00
Video Interface Kit	**$161.00**
Color Video Kit	129.95

81 IC Update Master Manual $79.95

Comp. IC data selector, 2 vol. master reference guide. Over 51,000 cross references. Free update service through 1981. Domestic postage $4.75.

Modem Kit $60.00

State of the art, orig., answer. No tuning necessary. 103 compatible 300 baud. Inexpensive acoustic coupler plans included. Bd. only $17.00. Article in May *Radio Electronics*.

LRC 7000+Printer $389.00

64/40/32/20 column dot matrix impact, std. paper. Interface all personal computers.

LRC 7000 printer interface cable for Super Elf with software $35.00

NiCad Battery Fixer/Charger Kit

Opens shorted cells that won't hold a charge and then charges them up, all in one kit w/full parts and instructions. **$9.95**

Rockwell AIM 65 Computer

6502 based single board with full ASCII keyboard and 20 column thermal printer. 20 char. alphanumeric display, ROM monitor, fully expandable. **$405.00.** 4K version **$450.00.** 4K Assembler **$85.00,** 8K Basic Interpreter **$100.00.**

Special small power supply for AIM65 assem. in frame **$54.00.** Complete AIM65 in thin briefcase with power supply **$499.00.** Molded plastic enclosure to fit both AIM65 and power supply **$47.50.** Special Package Price: 4K AIM, 8K Basic, power supply, cabinet **$625.00.**

AIM65/KIM/VIM/Super Elf 44 pin expansion board; 3 female and 1 male bus. Board plus 3 connectors **$22.95.**

60 Hz Crystal Time Base Kit $4.40

Converts digital clocks from AC line frequency to crystal time base. Outstanding accuracy.

Video Modulator Kit $9.95

Convert TV set into a high quality monitor w/o affecting usage. Comp. kit w/full instruc.

Multi-volt Computer Power Supply

8v 5 amp, ±18v .5 amp, 5v 1.5 amp, −5v .5 amp, 12v .5 amp, −12v option. ±5v, ±12v are regulated. Basic Kit **$35.95.** Kit with chassis and all hardware **$51.95.** Add $5.00 shipping. Kit of hardware **$16.00.** Woodgrain case **$10.00.** $1.50 shipping.

TERMS: $5.00 min. order U.S. Funds. Calif residents add 6% tax.
$10.00 min. BankAmericard and Master Charge accepted. $1.00 insurance optional.
Postage: Add 5%. C.O.D. $10.00 min. order.

FREE: Send for your copy of our NEW 1981 QUEST CATALOG. Include 48¢ stamp.

Circle 331 on inquiry card.

Circle 142 on inquiry card.

ELECTRONICS CENTER

CALL TOLL FREE

1-800-228-4097

Call Toll Free For
"Unbelievable"
Low Low
Prices On These
Lines:



APPLE — ATARI — BASE 2
CENTRONICS
COMMODORE — DC HAYES
HAZELTINE — LEEDEX
MACROTRONICS — MAXELL
MOUNTAIN HARDWARE
NORTH STAR — PANASONIC
SANYO — SYNCOM

YOUR ELECTRONICS PLAYGROUND

master charge THE INTERBANK CARD

1840 "O" Street Lincoln, Nebraska 68508
In Nebraska Call (402) 476-7331

VISA

SUNNY LOW LOW COST POWER SUPPLIES

FOR S-100, FLOPPY DISKS.



KIT 1, 2 & 3 For S-100



R3 For Three 8" or 5¼" Disk Drives



S3 2 in 1 Unit for S-100 and two 8" or 5¼" Disk Drives. It fits most Disk System Mainframes.

S-100 POWER SUPPLY KITS (OPEN FRAME WITH BASE PLATE, 3 HRS. ASSY. TIME)

ITEM	USED FOR	@ + 8 Vdc	@ − 9 Vdc	@ + 16 Vdc	@ − 16 Vdc	@ + 28 Vdc	SIZE W × D × H	PRICE
KIT 1	15 CARDS SOURCE	15A	————	2.5A	2.5A	————	12" × 5" × 4⅞"	52.95
KIT 2	SYSTEM SOURCE	25A	————	3A	3A	————	12" × 5" × 4⅞"	59.95
KIT 3	DISK SYSTEM	15A	1A	2A	2A	4A	14" × 6" × 4⅞"	67.95

DISK DRIVE POWER SUPPLY "R3" REGULATED, OPEN FRAME, ASSY. & TESTED 67.95

SPECS: + 5V @ 5A OVP, −5V @ 1A + 24V@ 5A, SHORTS PROTECT. 2 SIZES AVAIL., 1.) 9" (W) × 6¼" (D) × 4⅜" (H), 2) 9" (W) × 5⅜" (D) × 5¼" (H)
OPTION: 1.) REPLACE + 24V BY + 12V, 2.) FOR SIZE 1 ONLY, ADD ± 12V @ 1A, AT AN ADDITIONAL $12.00.
IDEAL FOR THREE 8" or 5¼ FLOPPY DISK DRIVES, SUCH AS SHUGART 801/851, SIEMANS FDD 100-8/200-8 OR 100-5 ETC.

DISK SYSTEM PWR SUPPLY "S3" OPEN FRAME, ASSY. & TESTED. COMPACT SIZE: 10"(W) × 6" (D) × 5" (H) 92.95

REGULATED OUTPUTS FOR DISK DRIVES: +5V @ 4A, −5V @ 1A, +24V @ 4A (OR + 12V @ 4A). SHORTS PROTECT.
UNREGULATED OUTPUTS FOR S-100: +8V @ 14A, ± 16V @ 3A. (OPTION: ADD OVP FOR +5V, ADD $5.00)
A COMPLETE UNIT FOR DISK SYSTEM WITH THE MAINFRAME CONTAINING 12 SLOTS & TWO 8" or 5¼" DISK DRIVES.

POWER TRANSFORMERS (WITH MOUNTING BRACKETS)

ITEM	PRIMARY	SECONDARY #1	SECONDARY #2	SECONDARY #3	SIZE W × D × H	PRICE
T_1	110/120	2 × 8 Vac, 15A	28 Vac, CT, 2.5A	————	3¾" × 3⅝" × 3⅛"	21.95
T_2	110/120	2 × 8 Vac, 25A	28 Vac, CT, 3.5A	————	3¾" × 4⅜" × 3⅛"	27.95
T_3	110/120	2 × 8 Vac, 15A	28 Vac, CT, 2.5A	48 Vac, CT, 2A	3¾" × 4⅜" × 3⅛"	29.95
T_4	110/120	2 × 8 Vac, 6A	28 Vac, CT, 1.5A	48 Vac, CT, 3A	3¾" × 3⅝" × 3⅛"	22.95
T_5	110/120	2 × 8 Vac, 6A	28 Vac, CT, 2A	————	3" × 3" × 2½"	14.95

SHIPPING For each power supply $5.50 in Calif., $7.50 in other states, $14.00 in Canada. For each Transformer $5.00 in all States, $10.00 in Canada. Calif. Residents add 6% Sales Tax.

BANKAMERICARD VISA

MAILING ADDRESS:
P.O. BOX 4296
TORRANCE, CA 90510
TELEX: 830-5010
ANSWER BACK FOR TELEX SUNYCO TRUC

SUNNY INTERNATIONAL
(TRANSFORMERS MANUFACTURER)
(213) 328-2425 MON-SAT 9-6

SHIPPING ADDRESS:
22129½ S. VERMONT AVE
TORRANCE, CA 90502

master charge

Circle 372 on inquiry card.

DIGITAL RESEARCH COMPUTERS
(214) 271-3538

32K S-100 EPROM CARD

NEW!



$79.95
KIT

USES 2716's

Blank PC Board - $34

ASSEMBLED & TESTED
ADD $30

SPECIAL: 2716 EPROM's (450 NS) Are $9.95 Ea. With Above Kit.

KIT FEATURES:
1. Uses +5V only 2716 (2Kx8) EPROM's.
2. Allows up to 32K of software on line!
3. IEEE S-100 Compatible.
4. Addressable as two independent 16K blocks.
5. Cromemco extended or Northstar bank select.
6. On board wait state circuitry if needed.
7. Any or all EPROM locations can be disabled.
8. Double sided PC board, solder-masked, silk-screened.
9. Gold plated contact fingers.
10. Unselected EPROM's automatically powered down for low power.
11. Fully buffered and bypassed.
12. Easy and quick to assemble.

32K SS-50 RAM

$329.00 KIT

For 2MHZ
Add $10

Blank PC Board
$50

For SWTPC
6800 - 6809 Buss

Support IC's
and Caps
$19.95

Complete Socket Set
$21.00

Fully Assembled,
Tested, Burned In
Add $30

NEW!

At Last! An affordable 32K Static RAM with full 6809 Capability.

FEATURES:
1. Uses proven low power 2114 Static RAMS.
2. Supports SS50C - EXTENDED ADDRESSING.
3. All parts and sockets included.
4. Dip Switch address select as a 32K block.
5. Extended addressing can be disabled.
6. Works with all existing 6800 SS50 systems.
7. Fully bypassed. PC Board is double sided, plated thru, with silk screen.

16K STATIC RAM KIT-S 100 BUSS

PRICE CUT!

$169.95 KIT

FOR 4MHZ
ADD $10



KIT FEATURES:
1. Addressable as four separate 4K Blocks.
2. ON BOARD BANK SELECT circuitry. (Cromemco Standard!). Allows up to 512K on line!
3. Uses 2114 (450NS) 4K Static Rams.
4. ON BOARD SELECTABLE WAIT STATES.
5. Double sided PC Board, with solder mask and silk screened layout. Gold plated contact fingers.
6. All address and data lines fully buffered.
7. Kit includes ALL parts and sockets.
8. PHANTOM is jumpered to PIN 67.
9. LOW POWER: under 1.5 ampsTYPICAL from the +8 Volt Buss.
10. Blank PC Board can be populated as any multiple of 4K.

BLANK PC BOARD W/DATA-$33
LOW PROFILE SOCKET SET-$12
SUPPORT IC'S & CAPS-$19.95
ASSEMBLED & TESTED-ADD $35

OUR #1 SELLING
RAM BOARD!

16K STATIC RAM SS-50 BUSS

PRICE CUT!

$159 KIT

FULLY STATIC!

FOR 2MHZ
ADD $10



FOR SWTPC
6800 BUSS!

ASSEMBLED AND
TESTED - $35

KIT FEATURES:
1. Addressable on 16K Boundaries
2. Uses 2114 Static Ram
3. Fully Bypassed
4. Double sided PC Board. Solder mask and silk screened layout
5. All Parts and Sockets included
6. Low Power Under 1.5 Amps Typical

BLANK PC BOARD—$35   COMPLETE SOCKET SET—$12
SUPPORT IC'S AND CAPS—$19.95

STEREO! S-100 SOUND COMPUTER BOARD

NEW!   NEW!

At last, an S-100 Board that unleashes the full power of two unbelievable General Instruments AY3-8910 NMOS computer sound IC's. Allows you under total computer control to generate an infinite number of special sound effects for games or any other program. Sounds can be called in BASIC, ASSEMBLY LANGUAGE, etc.

COMPLETE KIT!
$84.95
(WITH DATA MANUAL)

BLANK PC
BOARD W/DATA
$31

KIT FEATURES:
* TWO GI SOUND COMPUTER IC'S.
* FOUR PARALLEL I/O PORTS ON BOARD.
* USES ON BOARD AUDIO AMPS OR YOUR STEREO.
* ON BOARD PROTO TYPING AREA.
* ALL SOCKETS, PARTS AND HARDWARE ARE INCLUDED.
* PC BOARD IS SOLDERMASKED, SILK SCREENED, WITH GOLD CONTACTS.
* EASY, QUICK, AND FUN TO BUILD. WITH FULL INSTRUCTIONS.
* USES PROGRAMMED I/O FOR MAXIMUM SYSTEM FLEXIBILITY.

Both Basic and Assembly Language Programming examples are included.

SOFTWARE:

SCL™ is now available! Our Sound Command Language makes writing Sound Effects programs a SNAP! SCL™ also includes routines for Register-Examine-Modify, Memory-Examine-Modify, and Play-Memory. SCL™ is available on CP/M* compatible diskette or 2708 or 2716. Diskette - **$24.95** 2708 - **$19.95** 2716 - **$29.95**. Diskette includes the source. EPROM'S are ORG at E000H.

SPECIAL PURCHASE!

UART SALE!

TR1602B — SAME AS TMS6011, AY5-1013, ETC.   40 PIN DIP

TR1602B

$2.95 EACH   **4 For $10.00**

CRT CONTROLLER CHIP

SMC #CRT 5037. PROGRAMMABLE FOR 80 x 24, ETC. VERY RARE SURPLUS FIND. WITH PIN OUT. $12.95 EACH.

4K STATIC RAM

National Semi. MM5257. Arranged 4K x 1. +5V, 18 PIN DIP. A Lower Power, Plug in Replacement for TMS 4044. 450 NS. Several Boards on the Market Will Accept These Rams. SUPER SURPLUS PURCHASE! **PRIME NEW UNITS!**

8 FOR $16   32 FOR $59.95

NEW! G.I. COMPUTER SOUND CHIP

AY3-8910. As featured in July, 1979 BYTE! A fantastically powerful Sound & Music Generator. Perfect for use with any 8 Bit Microprocessor. Contains: 3 Tone Channels, Noise Generator, 3 Channels of Amplitude Control, 16 bit Envelope Period Control, 2-8 Bit Parallel I/O, 3 D to A Converters, plus much more! All in one 40 Pin DIP. Super easy interface to the S-100 or other busses. **$11.95**   **PRICE CUT!**

SPECIAL OFFER: ~~$14.95~~ **each**   Add $3 for 60 page Data Manual.

Digital Research Computers
(OF TEXAS)

P.O. BOX 401565 • GARLAND, TEXAS 75040 • (214) 271-3538

TERMS: Add $2.00 postage. We pay balance. Orders under $15 add 75¢ handling. No C.O.D. We accept Visa and MasterCharge. Tex. Res. add 5% Tax. Foreign orders (except Canada) add 20% P & H. Orders over $50, add 85¢ for insurance.

ALL SALES ARE MADE SUBJECT TO THE TERMS OF OUR 90 DAY LIMITED WARRANTY. A COPY OF THIS WARRANTY IS AVAILABLE FREE, ON REQUEST.

*TRADEMARK OF DIGITAL RESEARCH.   WE ARE NOT ASSOCIATED WITH DIGITAL RESEARCH OF CALIFORNIA, THE SUPPLIERS OF CPM SOFTWARE.

Circle 124 on inquiry card.

Circle 256 on inquiry card.

CALIFORNIA COMPUTER SYSTEMS

32K RAM BOARD A&T.
450 NSEC ....$579.95, 200 NSEC $629.95
16K RAM A&T.
450 NSEC ....$255.95, 200 NSEC $285.95
64K DYNAMIC A&T.
200 NSEC $548.95
Z80 PROCESSOR A&T. $259.00
DISC CONTROLLER $339.95
APPLE IEEE INSTRUMENTATION INTERFACE KIT 7490. A & T $275.00
ARITHMETIC PROCESSOR FOR APPLE 7811A. A & T $342.80
APPLE ASYNCHRONOUS SERIAL INTERFACE 7710A. A & T..............................$137.10
APPLE SYNCHRONOUS SERIAL INTERFACE 7712A. A & T $153.95
ALL OTHER CCS PRODUCTS AVAILABLE

SSM

PB-1 2708 & 2716 Programming Board with provisions for 4K or 8K EPROM. No external supplies required. Textool sockets. Kit $143.00
CB-1A 8080 Processor Board. 2K of PROM 256 BYTE RAM power on/rest Vector Jump Parallel port with status. Kit .... $146.00 PCBD $31.95
VB-3 80x24 VIDEO BOARD. Graphics included. 4MHZ. Kit $379.95
IO-4 Two serial I/O ports with full handshaking 20/60 ma current loop: Two parallel I/O ports. Kit ....$168.00 PCBD $31.95
VB-IC 64 x 16 video board, upper lower case Greek composite and parallel video with software, S-100. Kit $143.00
CB-2 Z80 CPU BOARD. Kit $199.95
AIO APPLE SERIAL/PARALLEL Kit $144.95
ALL OTHER SSM PRODUCTS AVAILABLE

wmc inc. WAMECO INC.

MEM-3 32K STATIC RAM 2114 24 bit addressing $36.95
FDC-1 FLOPPY CONTROLLER BOARD will drive shugart, pertek, remic 5" & 8" drives up to 8 drives, on board PROM with power boot up, will operate with CPM™ (not included). PCBD $43.95
FPB-1 Front Panel. IMSAI size, hex displays. Byte, or instruction single step. PCBD $48.50
QM-12 MOTHER BOARD, 13 slot, terminated, S-100 board only $39.95
CPU-1 8080A Processor board S-100 with 8 level vector interrupt. PCBD $28.95
CPU-2 Z80 Processor S-100, on board ROM, power on jump. PCBD $31.95
EPM-2 2708/2716 16K/32K EPROM CARD. PCBD $28.95
QM-9 MOTHER BOARD. Short Version of QM-12. 9 Slots. PCBD $33.95
MEM-1 8K x 8 RAM 2102. Buffered PCBD $31.95
PTB-1 POWER SUPPLY AND TERMINATOR BOARD. PCBD $28.95
IOB-1 SERIAL AND PARALLEL INTERFACE. 2 parallel, one serial and cassette. PCBD $28.95

2708	$7.50	2114L 450 NSEC	$4.99
2716	$25.95	2114L 200 NSEC	$5.99

JULY SPECIAL SALE ON PREPAID ORDERS
(Charge cards not included on this offer)

SSM IO2, PCBD $28.00
IO2, KIT $51.00
WAMECO MEM-1 WITH 250 NSEC LOW POWER RAM (NEC OR AMD). A & T $99.99

MIKOS PARTS ASSORTMENT WITH WAMECO AND CYBERCOM PCBDS

MEM-3 less RAM ....$ 95.95
CPU-1 with MIKOS #2 8080A CPU $99.95
QM-12 with MIKOS #4 13 slot mother board $110.95
CPU-2 with MIKOS #19. Z80 Processor $119.95
EPM-2 with MIKOS #11 16-32K EPROMS less EPROMS $65.95
QM-9 with MIKOS #12 9 slot mother board $99.95
FPB-1 with MIKOS #14 all parts for front panel $144.95

MIKOS PARTS ASSORTMENTS ARE ALL FACTORY MARKED PARTS. KITS INCLUDE ALL PARTS LISTED AS REQUIRED FOR THE COMPLETE KIT LESS PARTS LISTED. ALL SOCKETS INCLUDED.

LARGE SELECTION OF LS TTL AVAILABLE
PURCHASE $50.00 WORTH OF LS TTL AND GET 10% CREDIT TOWARD ADDITIONAL PURCHASES.
PREPAID ORDERS ONLY.

MIKOS

MONDAY - FRIDAY, 8:00 TO 12:00, 1:00 TO 5:30
THURSDAYS, 8:00 TO 9:00 P.M.
(415) 728-9121
P. O. Box 955 • El Granada, CA 94018
Please send for IC, Xistor and Computer parts list

VISA or MASTERCHARGE. Send account number, interbank number, expiration date and sign your order. Approx. postage will be added. Check or money order will be sent post paid in U.S. If you are not a regular customer, please use charge, cashier's check or postal money order. Otherwise there will be a two-week delay for checks to clear. Calif. residents add 6% tax. Money back 30-day guarantee. We cannot accept returned IC's that have been soldered to. Prices subject to change without notice. $10 minimum order. $1.50 service charge on orders less than $10.00.

B+K PRECISION

Microcomputer-Controlled Autoranging DMM Model 2845

- **Computer stabilized accuracy to 0.1%**
- **Auto-perfection**
  Selects range for maximum resolution
- **Audible continuity indicator**
  Built-in audible tone generator
- **G-MOV overload protection**
  Provides AC and DC voltage range protection to 1000 VDC or AC peak
- **Shielded in RF fields**
  Accuracy maintained in RF fields
- **Long life, high reliability**
  Four hermetically sealed reed relays perform range switching with virtually no contact wear.
- **Microcomputer intelligence**
  Designed around 4-bit microcomputer. Analyzes stored data and range that provides greatest display resolution. Program memory capacity 1024 x 8 bits of ROM supported by 48 x 4 bits of data memory RAM

... in stock and available for immediate delivery.

Dual Trace 5" 30 MHz Triggered Scope Model 1479A

Sweep/Function Generator Model 3020

Semiconductor Transistor Tester Model 520B

Portable Digital Capacitance Meter Model 820



Order with Confidence and get the Fordham Advantage!

Call for our prices TOLL FREE
(800)645-9518
in N.Y. State call (516) 752-0050

FORDHAM
855 Conklin St. Farmingdale, N.Y. 11735

- Master Charge
- BankAmericard
- VISA ▪ COD
- Money Order
- Check
- COD's extra

Circle 153 on inquiry card.

COMPUTER STOP

2545 W. 237 St. Torrance, CA. 90505

ORDER BY PHONE
MON.—SAT.
10-6

(213) 539-7670 PST
TELEX: 678401 TAB IRIN

LOWEST PRICES IN THE WEST, NORTH, SOUTH & EAST

apple computer
Sales and Service

APPLE /// OPTION A: 3850
APPLE /// 96K
Information Analyst Package
12″ B/W Monitor

APPLE /// OPTION B: 4350
SAME AS OPTION A PLUS:
DISK II for APPLE ///

APPLE /// OPTION C: 4800
SAME AS OPTION A PLUS:
DISK II FOR APPLE ///
SILENTYPE Thermal Printer

APPLE][Plus
16K $1075
48K $1193
Disk][Drive .. $529
with Controller & Dos. 3.3
PASCAL SYSTEM
$425
Z-80 Softcard
$299

APPLE HARDWARE

Parallel Printer Interface Card	160
Communications Card	195
High Speed Serial Interface	175
Pascal Language System	425
Centronics Printer Interface	185
Applesoft Firmware Card	160
Integer Firmware Card	160
Disk][with Controller DOS 3.3	529
Disk][only	475
Graphics Tablet	625

OTHER HARDWARE

Alf Music Synthesizer (3 Voice)	245
9 voice	175
ABT Numeric Keypad	119
Micromodem][	295
Apple Clock	245
Rom Plus with Keyboard Filter	175
Introl/X-10 System	250
Romwriter	150
DoubleVision 80 x 24 Video Interface	245
CCS Arithmetic Processor	399
CCS Parallel Interface	119
16K Ram Card	145
Microworks DS-65 Digisector	339
SVA 8 inch Disk Controller	335
Sup-R-Mod	30
CCS Synchronous Serial Interface	159
CCS Asynchronous Serial Interface	159
Corvus 10 Meg. Hard Disk	4395
Corvus Constellation	595

MISCELLANEOUS/SUPPLIES

16K RAM (200-250 NS)	49
Verbatium Datalife Diskette (Box of 10)	30
Dysan Diskettes (Box of 5)	22
Apple Diskettes (Box of 10)	45
Verbatim Diskette Boxes (Holds 50 Disks)	18
Silentype Paper (Box of 10 rolls)	40

MONITORS/DISPLAYS

Leedex Video 100 12″	140
Sanyo 9″ Monitor	195
KG-12C Green Phos. Monitor	275
Sanyo 12″ Green Phosphor. Monitor	275
NEC 12″ Green Phosphor. Monitor	275
Sanyo 12″ B/W Monitor	250

PRINTERS

Apple Silentype with Interface	525
IDS 445 (Paper Tiger) with Graphics	695
IDS 460 with Graphics	1099
IDS 560 with Graphics 10)	1295
Centronics 737	795
NEC Spinwriter (RO, Serial)	2650

SOFTWARE

The Controller	525
Apple Post (Mailing List Program)	40
Easywriter Professional System	195
Apple Pie 2.0	95
DB Master Data Management	150
The Cashier	210
Apple Writer	65
Visicalc	125
CCA Data Management System	90
Full Screen Mapping for CCA DMS	59
Pascal Interactive Terminal Software (PITS)	29
Basic Interactive Terminal Software (BITS)	29
Data Capture	29
Data Factory DMS	95
Apple Plot	55
Apple Pilot	120
Magic Wand Word Processor (Needs Z-80 Softcard)	345
Dow Jones Portfolio Evaluator	45
Fortran	140

ORDERING INFORMATION: Phone orders invited using VISA, MASTERCARD or bank wire transfers. VISA & MC credit card service charge of 2%. AE credit card service charge of 5%. Mail order may send charge card number (include expiration date), cashier's check, money order or personal check (allow 10 business days to clear.) Please include a telephone number with all orders. Foreign orders (excluding Military PO's) add 10% for shipping. All funds must be in U.S. dollars (letters of credit permitted). Shipping, Handling and insurance in U.S. add 3% (minimum $4.00). California residents add 6% sales tax. Our low margins prohibit us to send COD or on purchase orders or open account (please send for written quotation). All equipment is subject to price change and availability. Equipment is new and complete with the manufacturer warranty. We do not guarantee merchantibility of products sold. All returned equipment is subject to a 15% restocking fee. We ship most orders within 2 days.

WE ARE A MEMBER OF THE CHAMBER OF COMMERCE. **RETAIL STORE PRICES MAY DIFFER FROM MAIL ORDER PRICES.**

PLEASE SEND ORDERS TO:
COMPUTER STOP, 2545 W. 237 St., TORRANCE, CA 90505

Circle 83 on inquiry card.

NEW, VERSATILE, EASY TO USE DIGI-LINK

DIGITAL RF-LINK



FOR COMPUTER HOBBYISTS
ROBOTICS
REMOTE DATA ACQUISITION
CONTROL PROJECTS
TOYS
AND MANY-MANY MORE CREATIVE APPLICATIONS

This digital RF transmitter and receiver links your computer's intelligence to robots, appliances, remote stations, peripherals and toys without any wires, cables, physical attachments.

- USABLE WITH ANY COMPUTER
- SERIAL INTERFACE (RS232)
- SMALL SIZE, LOW POWER
- SINGLE 9 VOLT BATTERY
- COMPLETELY DOCUMENTED
- EASY TO BUILD
- APPLICATION NOTES

Receiver and Transmitter .... $ 34.95
Receiver (w/ UART) and Transmitter .... $ 49.95
Receiver only .... $ 19.95
Receiver (w/ UART) only .... $ 35.95
Transmitter only .... $ 18.95

MAIL YOUR ORDER NOW ! ENJOY THE DIGI-LINK !

Kits contain PCB, components, hardware, antenna, instructions and application notes.
CA residents add 6.5% tax.
Check or money-order only.

E/Z ASSOCIATES
5589 STARCREST DR.
SAN JOSE, CA 95123
(408) 578-8096

Circle 135 on inquiry card.

ATTENTION: Apple Users!
WANT BETTER COLOR...MORE STABILITY?

Ever question the quality of your computer display. If so, you've probably been told "That's the best you can expect from an RF modulator...buy a color monitor".

WE CHALLENGE THAT STATEMENT!

DON'T BE SATISFIED WITH EXISTING QUALITY. See for yourself what our "new concepts" modulator can do for your picture...MICRO-VERTER Model MVX-500, $35 PP. Phone orders welcomed.

HOT LINE DIAL: 402-987-3771

13B BROADWAY **ATV Research** DAKOTA CITY, NE. 68731

DEALERSHIPS AVAILABLE
CATALOG UPON REQUEST

DISK DRIVES
REMEX

Compatible with IBM and Shugart.
Double sided, Double Density
.... 1600 K Bytes.
RFD 4000 .... $595
Double Sided, Double Density
.... 800K Bytes
RFD 2000 .... $395

For fast delivery, send certified checks, money orders or call to arrange direct bank wire transfers. Personal or company checks require two weeks to clear. California Res. add 6% sales tax. Minimum shipping charge $10.00. No C.O.D.

Electronic Equipment Unlimited
3845 Birch Street
Newport Beach, CA 92660
PH: (714) 540-5231

Pricing and availability subject to change without notice.

Circle 139 on inquiry card.

WANTED:
APPLE, PET, TRS-80, CP/M
SOFTWARE

Westico is a publisher and distributor of professional software for microcomputers. If you have a new program ready for distribution or want your existing programs to reach a larger market, contact:

Phillip Woellhof, V.P. Mktg.
Westico, Inc.
25 Van Zant Street
Norwalk, CT 06855
(203) 853-6880

To increase your profits, take advantage of Westico's worldwide promotion and distribution.

WESTICO
The Software Express Service

INTERFACE EXPANSION BOARD

*For the TRS 80**

MD MICRO-DESIGN

The Interface Expansion Board gives your computer these features

Phone Modem
2K E-PROM OPTION
32 K Memory
Real-Time Clock
Parallel Port
RS-232 Port
Dual Cassette Line
*Floppy Disk Controller**
On Board Supply
Silk Screen
Solder Mask
Expansion Port
Manual

In Stock Now
PC Board & user manual
MDX-1
64.95

MDX-2*
74.95

Add 5.00 for shipping & handling Texas residents add 5% sales tax
MANUALS $7.95

FREE PAMPHLET AVAILABLE
Call or write
MICRO-DESIGN
P.O. Box 748
Manchaca, Texas 78652
512-282-0225

master charge VISA

**TRS 80 is a Trademark of Tandy Corp.*

Circle 232 on inquiry card.

9 TRACK TAPE DRIVES

800 BPI
45 IPS
FULL MANUAL
$4850 VALUE



$2400
NEW IN ORIGINAL BOXES

PERTEC Model 8840A-9-45
INDUSTRY STANDARD INTERFACE
CAPABLE OF IND. STD. ANSI-IBM DATA FORMAT

- **READ/WRITE DATA IN STANDARD ANSI-IBM COMPATIBLE FORMAT**
- **DUMP WINCHESTERS AND HARD DISKS; 10 inch reels hold up to 3600' of tape = 34.56 Megabytes unblocked.**
- **EXCHANGE DATA & PROGRAMS WITH LARGE MAIN FRAMES AT SCHOOL, WORK, SERVICE BUREAUS ETC.**
- **BARGAIN PRICED MINI-COMPUTER UPGRADE. OEM List $4850**

A large OEM overstock makes these industry standard drives available at a fraction of their current list price. Full size drives handle up to 10.5 inch reels of standard inexpensive 1/2 inch mag tape. 19 inch rack mount or use right out of the box on steel shipping frame.

SPECIFICATION SUMMARY: 9-track, 800 BPI, dual head (read after write), 45 IPS read/write, 200 IPS rewind, BOT/EOT sensing, 110 VAC/60-Hz, solid state, recent manufacture, all I/O signals TTL/DTL compatible, tension arm tape buffering, full control panel. Call or write for full set of technical specifications.

INTERFACES: Electrovalue encourages the development of interfaces to popular systems. Interfaces exist for popular minis and are being developed for several hobby computers. If you'd like to develop and document an interface to a popular small system call to discuss discounts.

ELECTROVALUE INDUSTRIAL INC.
P.O. BOX 157-B
MORRIS PLAINS, NJ 07950
Formerly Electravalue Industrial

Phone reservations and questions are welcome.
201/267-1117

IPEX *NEW!*

Interface Converts Your Typewriter into Printer



- Finest print quality
- Low cost
- Easy installation
- Quick delivery
- Fits IBM SELECTRIC® typewriter with **no modification.**
- For TRS-80®, Apple®, or **any** parallel or RS232 port.
- Write or phone for more information, today!

— U.S. and worldwide sales —

IPEX INTERNATIONAL INC.
16140 Valerio St.
Van Nuys, CA 91406 USA

TEL: 213/781-0020 TLX/TWX: 910-495-1767

Circle 192 on inquiry card.

COMPUTERS!

apple

OHIO SCIENTIFIC

C1P SERIES II
CALL FOR OUR PRICE
other OSI discounts available

COMPUTERS PLUS

2749 S. 108th St.
MILWAUKEE, WI 53227
(414) 321-1770
IN WISCONSIN
CALL NOW TOLL FREE
1-800-558-4236

Circle 89 on inquiry card.

Close-Out!!

Desk Top Computer

This unit is a computerized Electronic Secretary. It keeps time, date, calendar, message, and meeting files. Originally sold thru a major mail order house for over $450.

Technically, it's a 6507 MICRO, ROM, RAM, Panaplex Alpha Display, Ni-Cad battery, Power Supply, Keyboard, Wood and Aluminum Case with Schematic and operating instructions.

Most of these Computers are warranty returns. We are offering Refurbished, like new, units for **$99.95** and AS IS (most have minor problems) units for **$44.95.** Add **$4.95** for shipping and handling. All units are complete as described. All sales are final. California Residents add 6.5% sales tax.

Send Payment with order or call our Order Line 408-272-2320 and use your **MC** or **VISA** card.

Solid State Surplus
P.O. Box 32418/San Jose, CA 95152

Circle 359 on inquiry card.

commodore SERIES 8000

BUSINESS COMPUTER

Putting together your own powerful business computer system is as easy as 1 — 2 — 3!

NEW!

commodore

VIC-20

. . . Introducing the first

full featured, expandable color computer priced under $300.

- **COLOR:** 8 charactor, 8 border and 16 screen colors.
- **LANGUAGE:** PETBASIC
- **SOUND:** 4 internal amplifiers including 3 tone (music) generators and 1 sound (noise & sound effects) generator. Each amplifier has 3 octaves. Sound uses a television or monitor speaker.
- **MEMORY:** 5K RAM (random access memory) expandable externally to 32K RAM.
- **FULL COMPUTER ACCESSORIES:** disk drive, printer, tape cassette, game controls & more.
- **KEYBOARD:** Full typewriter keyboard with special screen editing keys & PET graphics.
- **PROGRAMMABLE FUNCTION KEYS:** 4 programmable function keys(8 separate functions).
- **PLUG-IN PROGRAM & MEMORY EXPANSION CARTRIGES:** (programs plug directly into the back of the computer....each program can be up to 27K).
- **GRAPHICS:** Full PET keystroke graphics.
- **CONNECTS TO ANY TV SET/MONITOR:** (Built-in RF Modulator).

available from ANCRONA only $299.95

❶ CBM8032
32K RAM
80 Column Screen

The new Commodore 8000 series business computers offer a wide screen display to show up to 80-characters per line of information. Text editing and report formatting are faster and easier with the new wide-screen display. The 8000 series also provides a resident Operating System with expanded functional capabilities. You can use BASIC on the 8000 computers in both interactive and program modes, with expanded commands and functions for arithmetic, editing, and disk file management. The CBM8000 series computers are well suited for the business marketplace computing needs. **$1795.00**

❷ CBM8050
Dual Drive Floppy Disk
Over 950K Bytes Net User Storage

The CBM 8050 Dual Drive Floppy Disk is an enhanced version of the intelligent CBM2040 Disk Drive. The 8050 has all the features of the 2040 with more powerful software capabilities, as well as over 950K bytes of online user storage capacity. The CBM8050 supplies relative record files and automatic diskette initialization. It can copy all the files from one diskette to another without copying unused space. The CBM8050 also offers improved error recovery and the ability to append to sequential files. **$1795.00**



❸ CBM4022
80 Column Dot Matrix Printer

The Tractor Feed Printer adds versitility and convience to your Business Computing System. The tractor feed printer accepts mailing lists, prints checks, invoices, and standard or customized business forms. Plus, it will print not only alpha and numeric characters, but also all of the graphic characters in both normal or reverse, so you you can add emphasis to parts of your printout. Varying character size allows you to create headlines and titles. And programmable line spacing means a perfect match-up on your customized forms. You can set left and right margins, page length, justification, and decimal position as well. **$795.00**

APPLICATION SOFTWARE

WORD PRO 4 PLUS state-of-the-art word processor. Best seller of all word proscessors for the Commodore computer. **Check these features:** Exceptional text editing, inserting, deleting, margin control, tab setting, document storage & printing, global search & replace, automatic page numbering, repagination, ability to link files of text to produce long continuous documents, subscripts, superscripts, boldface type, varible pitch, varible line spacing, exit to basic, pause, start print from any page, view documents on screen for appearance prior to final printing. Now add simultaneous input/output, math functions and ability for multi-user sytems and you can see why it sells best. **$450.00**

500020	WORDCRAFT 80.	$395.00
500010	OZZ The Info Wizard.	395.00
500030	Tax Preparation System. . .	495.00
50003t	Personal Tax Calculator. . . .	69.95
900040	Information Retrieval and Management Aid	$495.00
500040	Dow Jones Portfolio Management System	149.95

For additional software for your Commodore order a copy of . . .

COMMODORE SOFTWARE ENCYCLOPEDIA

Contains a complete listing of the software available for Commodore computers plus a brief description on each program and available sources

900030 . . . . **$4.95**

OTHER COMMODORE COMPUTERS, PERIPHERALS AND SOFTWARE.

CBM4016N	16K RAM, 40 column x 25 line CRT display, terminal styled keyboard with separate numeric pad and graphic keys	$ 995.00
CBM4016B	16K RAM, 40 column CRT display, typewriter styled keyboard with separate numeric pad	995.00
CBM4032N	32K RAM, 40 column CRT display, terminal styled keyboard with separate numeric pad and graphic keys	1295.00
CBM4032B	32K RAM, 40 column CRT display, typewriter styled keyboard with separate numer pad	1295.00
CBM8032	32K RAM, 80 column CRT display, business keyboard with separate numeric pad and new screen editor functions	1795.00
CBM4040	Intelligent 5¼" mini-floppy dual drive with 343K byte net user storage	1295.00
CBM8050	Intelligent 5¼" mini-floppy dual drive with over 950K byte net user storage	1795.00
CBM4022	80 column dot matrix printer with forms handling tractor feed. Full PET graphics, and varible line spacing	795.00
CBM4010	Voice Synthesizer, features phoneme sythesis for vocabulary construction rather than digital techniques	395.00
CBM8010	High performance 300 BAUD IEEE interfaced modem features accurate teleprocessing communication	279.95
CBMC2N	Cassette input/output unit to use with PET/CBM computers	95.00
IEEE to IEEE	Use this cable when connecting more than one peripheral (Floppy and Printer) to any PET/CBM computer	49.95
PET to IEEE	Use this cable to connect your Floppy or Printer to any PET/CBM computer	39.95

SOFTWARE

400010	Pascal Development Pkg	$295.00	321004	Treasure Trove of Games	$9.95
400020	Assembler Development Pkg	99.95	321006	Galaxy Games	9.95
321005	Basic BASIC	14.95	321008	Draw Poker	9.95
321046	Strathclyde BASIC	14.95	321009	Blackjack	9.95
321066	Pet Pilot	14.95	321010	Spaceflight/Spacetalk	9.95
700010	Galaxy One (disk based)	49.95	321011	Spacetrek	9.95
321001	Reversal/Number Reverse	9.95	321035	Bowling/Awari	9.95
321002	Diet Planner/Biorhythm	14.95	321041	Backgammon	9.95

MANUALS (Please add 75¢ per manual for shipping)

321604	**Users' Reference Manual Basic 4.0** geared to teaching the functions and capabilities of the 8n, 16n and 32n terminal styled keyboards. Can also be a supplement for CBM model 16B and 32B with typewriter styled keyboards	$ 9.95
320877	**CBM User Guide** CBM features are described in an easy-to-understand, nontechnical manner	7.95
320838	**CBM Printer Manual 4022** applies to Tractor Feed Printer Model 2022. This manual contains all the information you need to check out, connect and operate your printer	7.95
320899	**5¼" Floppy Disk Manual for 2040, 4040 and 8050** contains the information you need to connect and operate all floppys	7.95
320524	**MOS Hardware Manual** tells you how the 65XX family of microprocessor chips function and the support chips needed	6.95
320525	**MOS Programming Manual** this manual is designed to work in conjunction with the Hardware Manual which describes the basic hardware consideration when using the MOS Technology, Inc. microcomputer family	6.95
900010	**The PET Revealed** is a collection of discoveries about Commodore Computers, how and why they work, and how to use these facts to write better programs and perform more interesting functions	19.95
900020	**Library of PET Subroutines** makes the process of writing an applications program considerably easier for the average Commodore Computer User. It contains the logical framework on which to build, plus aids in the form of std. subroutines	19.95

ANCRONA

STORES DO NOT ACCEPT MAIL ORDERS

MAIL ORDER

P.O. BOX 2208Y CULVER CITY, CA 90230

PHONE ORDERS (213) 641-4064

Minimum Order $10.00. Add $2.00 to cover postage and handling. Master Charge and VISA welcomed. Please include your charge card number, interbank number and expiration date. Some items are subject to prior sale. Not responsible for typos. Store pricing may vary from Mail Order pricing. We reserve the right to substitute manufacturer.

VISIT A STORE NEAR YOU TODAY - We stock a large selection of Technical Books, Discrete Components, Integrated Circuits, Test Equipment and Electronic Supplies.

ATLANTA	CULVER CITY	HOUSTON	PORTLAND	SANTA ANA	SUNNYVALE	TUCSON
3330 Piedmont Rd. N.E.	11080 Jefferson Blvd.	2649 Richmond	1125 N.E. 82nd Ave.	1300 E. Edinger Ave.	1054 E. El Camino Real	4518 E. Broadway
Atlanta, GA 30305	Culver City, CA 90230	Houston, TX 77098	Portland, OR 97220	Santa Ana, CA 92705	Sunnyvale, CA 94087	Tucson, AZ 85711
(404) 261-7100	(213) 390-3595	(713) 529-3489	(503) 254-5541	(714) 547-8424	(408) 243-4121	(602) 881-2348

Circle 26 on inquiry card.

EAST COAST COMPUTERS
P.O. BOX 295
WHITEHOUSE STA., NJ 08889

VERBATIM 5" DISKETTES	22.00
MEMOREX 5" DISKETTES	21.00
PLASTIC BOX	3.00
LEEDEX MONITOR	107.00
16K MEMORY KIT	35.00
CAT MODEM	144.00
ATARI 400	479.00
MX-80	459.00
TRS-80 16K MODEL III	859.00

TRS-80 is a registered trademark of Tandy Corp.

TERMS: MASTERCHARGE, VISA, CHECK, MONEY ORDER, U.S. FUNDS ONLY. NJ RESIDENTS ADD SALES TAX. ADD 5% FOR SHIPPING AND HANDLING.

Circle 161 on inquiry card.

REWARD
The Best Computer Game Program

If you don't have the very best program for games such as Chess, Checkers, Backgammon, Bridge, Go, etc; we aren't interested

- but -

If you do, then we are interested in talking with you and helping you turn that program into profit. We are a high technology company which markets the very finest in electronic games, and would like to hear from you.

Respond by sending a letter describing your program and why you consider your program to be the best, to;

EXTEMPORE, INC.
2301 Ohio Drive
Plano, TX 75075
Attn: J. Gray

HEADERS


PRINTED CIRCUIT
RIGHT ANGLE MOUNT

34 PIN HEADER
3M 3413—1003 $1.25 EA
40 PIN HEADER
ALPHA $1.50 EA
50 PIN HEADER
3M 3433—1002 $1.75 EA
40 PIN CONNECTOR
3M 3417 $1.50 EACH

22/44 EDGE CONNECTOR
TIN SOLDERTAIL .156"x .200"

LARGE QUANTITIES AVAILABLE
$1.35 each 10 for $12.50

8 POLE DIP SWITCH

$1.50 each

RFI LINE FILTER
for line to line & line to ground noise suppression
CORCOM # 10K6
Rated: 10 amp 115/250 v 50-400 hz
$ 3.75 ea.
10 for $35.00

SUB MINI L.E.D.
20 MA at 1.75 volt
.075" x .098"
10 for $1.00
PACKAGE of 200 PCS. $18.00
400 for $32.00
1000 for $70.00

ALL ELECTRONICS CORP.
905 S. Vermont Ave.
P.O. BOX 20406
Los Angeles, Calif. 90006
(213) 380-8000
Mon. - Fri. 9 AM - 5 PM
Saturday 10 AM - 3 PM

TERMS
- Quantities Limited
- Min. Order $10.00
- Add $2.00 Shipping USA
- Calif. Res. Add 6%
- Prompt Shipping

SEND FOR FREE CATALOG

Circle 12 on inquiry card.

COMPUTER CASSETTES

LENGTH	10 PACK	100 PACK
C-10	7.00	63.00
C-20	8.50	77.00
C-60	12.00	108.00
C-90	15.00	135.00

CASSETTE DUPLICATION
Software Duplication for TRS-80, Apple & Atari. Completed cassettes are guaranteed to load. For info call (305) 898-3382.

ACTS AUDIO, INC.
2304 E Robinson St
Orlando FL 32803

Circle 3 on inquiry card.

SLUDER
SALL FOR QUALITY COMPONENTS

```
QT System+I 64K,1MB,NEC765,8"DRS,Z80A® $2995
QT SBC2/4MHz Z80A® $225 QT 1/O+ 2s2pA&T 225
QT Clock Calenders  110 RAM 16 4MHz A&T  195
RAM 65 4MHz Bank A&T 210 RAM 16 & RAM 65 16K
Boards avail. in 5MHz CMOS low power design
RAM 65 CMOS BANKA&T 259 RAM 16 CMOS A&T 249
GODBOUT ELECTRONICS ALL A&T BOARDS(CSC CaLL)
CPU Z 6MHz, Disk 1, (2)RAM 20 32K, Inter-
facer 1/1I, CPM 2.2, Special for        1557
CPU Z 4MHz A&T DMA  229 CPU 8085/88 DMA 329
Disk 1 A&T BIOS DMA 386 CPM®80 w/D1     135
System Support 1    308 4MHz 9511(8231) 235
Interfacer I or II  194 Interfacer3(5)  467
Interfacer3(8)ports 547 Spectrum color  308
RAM 17 64K Static  1088 RAM 20 32K      547
Enclosure 2 Desk    643 Enclosure 2 RK  697
Televideo 920C      710 Televideo 950   950
Ampex Dialogue 30   795 Ampex Dial 80   950
EPSON MX80 par      473 DMB6400 64K     740
Systems Group 2800 Series Computer Boards
CPD2800 Z80A DMA    599 CPC2810 Z80A    395
FDC Disk Contr DMA  416 FDC Disk Ctr    370
ALL BOARDS IN THIS AD ASSEMBLED & TESTED
SLUDER ACCTG PKG    100 WORD STAR       300
```

All Prices Subject to Change, Minimum Shipping $3., Outside USA $10. Airmail for Brds
CPM® and Z80® are Registered Trademarks of Digital Research and Zilog Inc. Respectively

PO BOX 951
WESTMINSTER CA 92683
714 895 1746

Circle 353 on inquiry card.

COMPUTER EQUIPMENT & SOFTWARE BARGAINS

EVERY MONTH

BUY, SELL OR TRADE ALL TYPES OF COMPUTER EQUIPMENT AND SOFTWARE (pre-owned and new) among 20,000 readers nationwide in BIG (11x14") pages. Classified ads are *only* 10¢ per word and are indexed for *easy* and *fast* location. Subscription: $10 a year / 12 issues. Money back guarantee. Sample copy, $1.50.

COMPUTER SHOPPER
P.O. Box F-14
Titusville, FL 32780
(305) 269-3211
MasterCard or VISA subscription orders only, call **TOLL FREE 1-800-528-6050 Ex. 184**.

Circle 80 on inquiry card.

CP/M ➧ 68XX CROSS-SOFTWARE including source code in "C"

ASSEMBLER FEATURES:
- 2-pass absolute assembly
- Full instruction set, Motorola-compatible
- Free-format input
- Unlimited length labels
- Arithmetic expressions in operands
- Sorted symbol table output
- Intel format hex output

PACKAGE A6800	MC6800/MC6802/MC6808
PACKAGE A6801	MC6801/MC6803
PACKAGE A6809	MC6809

8" soft-sectored disk format, w/manual	$100.00
5" North Star disk format, w/manual	$100.00
Manual and listing alone	$ 85.00

(Wisconsin residents please add 4% tax)

introl corp
647 W. Virginia St.
Milwaukee, WI 53204
(414) 276-2937

Visa and Master Charge Accepted

CP/M is a trademark of Digital Research

Circle 191 on inquiry card.

ALPHA MICRO USERS: Are you looking for professional quality word processing at an affordable price? Ours is easy to use, with a well-written 110 page manual which has many examples, and has an on-line help facility. It finds spelling errors and typos with an on-line 70,000 word dictionary and helps you correct them. The screen editor has global search & replace, block move, wraparound, file merge, and virtual memory to edit large documents. It can do proportional spacing, bold printing, underlining, form letters, tables, fancy titles with page numbering (even in Roman numerals), centering, table of contents, sorted index, and automatic hyphenation using the dictionary, and MUCH MORE! $599 and worth it! Available on floppy, Hawk, and Phoenix disks. (Add $100 or $400 for Hawk or Phoenix, respectively, or supply your own). Manual alone is $15. If you have questions phone us at (408) 496-0855. Toxen Computer Systems, 950 Meridian Ave., Suite 34, San Jose, CA 95126.

Circle 401 on inquiry card.

16-K MEMORY 8/17.95

RAM	$	100PcS
4116 200ns	8/17.95	$1.90
2114L 300ns	8/21.25	$2.35
4164 200ns	$27.00	$27.00

Eproms		100PcS
2716 (5v) 450ns	$6.95	8/6.35ea
2732 (5v) 450ns	$17.75	8/15.00ea

CHIPS & DALE

all Chips are fully guaranteed
Add $2.00 Shipping & Handling
C.O.D. $2.00, Wash. residents add 5.4% Sales Tax
CHIPS & DALE, P.O. Box 31607
Seattle Washington Zip 98103
1-206-524-9126

Circle 59 on inquiry card.

What's New at John Bell Engineering, Inc.

HARDWARE



6502 JBE I Micro-Computer

John Bell Engineering is announcing their JBE I Micro-Computer. This computer is available partially or fully populated or as a bare board. The fully populated version includes:

1	6502 CPU	8	2114 RAMS (4K)
4	6522 VIA (8 Parallel Ports)	2	2716 EPROM (with monitor & tiny basic)
1	AY5-1013 (Serial I/O Port)		

The partially populated version includes:

1	6502 CPU	2	2114 RAMS (1K)
1	6522 VIA (2 parallel ports)	1	2716 EPROM (with monitor)
1	AY5-1013 (Serial I/O port)		

Both versions include sockets for 4 2716s or 2732s, 8 16 pin sockets for I/O interfacing and a DB25 connector for RS232.

All address and data lines, power supply, RDY, interrupts, DMA, phase 1 & phase 2 clocks, read/write, reset and NMI and IRQ are brought off the board to the 50 pin connector.

This board also features power on reset and cassette interface.

Documentation includes 6502 programming manual and complete documentation for the 6522 VIA. Also included is documentation for interfacing with JBE A-D and D-A converter, solid state switches and EPROM programmer.

Pricing:

81-030C	Fully populated assembled & tested	**$349.95**
81-030M	Partially populated assembled & tested	**$249.95**
81-030B	Bare board (includes documentation)	**$ 89.95**
2716	EPROM with monitor	**$ 19.95**
2716	EPROM with tiny basic	**$ 19.95**

EPROM Substitution Card

NEW

This board looks like RAM to the Apple® II and like an EPROM to the computer being programmed. It features 2K or 4K of RAM and emulates a 2716 or 2732. A 24 pin ribbon cable connects the computer being programmed to the EPROM sub. board. Documentation includes disk with basic & pascal utility routines including save, write, CMP, error checking. Complete Source Code User Manual also included. This board allows you to test programs without burning your EPROM. Three control lines from the board are used to control the computer being programmed (reset etc.).

81-085K2 Kit - 2K RAM	**$149.95**
81-085K4 Kit - 4K RAM	**$159.95**
81-085A2 Assm. - 2K RAM	**$159.95**
81-085A4 Assm. - 4K RAM	**$169.95**
Ribbon Cable with Connectors	**$ 9.95**

Speech Synthesizers

JBE's Speech Synthesizer for the Apple® II uses the Votrax SC-01 Phoneme Synthesizer. The SC-01 phonetically synthesizes continuous speech of unlimited vocabulary. The SC-01 contains 64 different phonemes and 4 levels of inflection accessed by an 8 bit code. Requires 10 bytes/sec for continuous speech. The board has an audio amp for direct connection to an 8 Ω speaker.

Documentation includes disk with basic user programs, phoneme chart & a listing of coded words to help you get started.

**Because of the high cost of the SC-01 at this time, it will be sold separately. This way as the price goes down we can pass the savings on directly to you.

81-088	Assm & tested	**$79.95**
81-120	Parallel Input Speech Synthesizers	**$89.95**

(On board power supply, wall trans. incl.)

SC-01 Phoneme Synth. (Call for current pricing)

EPROM Expansion Card



JBE EPROM Expander for the Apple II holds six 5 volt 2716s for a total of 12K bytes of ROM. This board takes the place of the on board ROM in the Apple. It is software switchable by the same technique used by the Apple® II firmware card. Solder jumpers are for reset to the Apple ROM or 2716s on the card. (EPROMs available separately). Use JBE EPROM programmer and parallel I/O cards to program your EPROMs.

81-070K	Kit	**$49.95**
81-070A	Assm.	**$59.95**
81-070B	Bare Board	**$39.95**

JOHN BELL ENGINEERING, INC.

MC

ALL PRODUCTS ARE AVAILABLE FROM **JOHN BELL ENGINEERING** • P.O. BOX 338
REDWOOD CITY, CA 94064 • ADD 6% SALES TAX IN CALIFORNIA • ADD 5% SHIPPING & HANDLING 10% OUTSIDE U.S.A.
(415) 367-1137

VISA

DEALS □ DEALS □ DEALS

OUR BUYERS ARE IN CONTACT WITH EVERY MAJOR SUPPLIER AND O.E.M. BUY HERE AT 1000 PIECE

QUANTITY PRICES

ALL MERCHANDISE 100% GUARANTEED! 15 DAY FULL CASH REFUND!

U.S. MICRO SALES

11 EDISON DRIVE ★ NEW LENOX ★ ILLINOIS 60451
CALL TOLL FREE: 1-800-435-9357 ★ MONDAY thru SATURDAY
(ILLINOIS RESIDENTS CALL: 815-485-4002) ★ 8:00 a.m. to 6:30 p.m.

TERMS: Prepayment – C.O.D. up to $100.00 – M/C Visa
$5.00 Processing and Handling added to each order PLUS Shipping Charges. Please allow personal check to clear before shipment.

JUST HOT STUFF

POWER SUPPLIES

If you can beat these prices we will be truly amazed. OEM's at 500 lot pay more than this. Call or write for full spec. sheets.

DISK POWER SUPPLIES				
PRIAM–SHUGART–CENTURY–MICROPOLIS				
+5V @ 9A	–5V @ .8A	+24V @ 7A	US-384	89.00
SHUGART – SIEMANS – MPI 5¼"				
+5V @ .5A	+12V @ .9A		US-340	33.50
+5V @ 2A	+12V @ 4A		US-323	56.25
SHUGART – SIEMANS – CDC 8"				
+5V @ 1A	–5V @ .5A	+24V @ 1.5A	US-205	52.50
+5V @ 2A	–5V @ .5A	+24V @ 3A	US-206	69.00
+5V @ 3A	–5V @ .6A	+24V @ 5A	US-162	89.00
+5V @ 1.7A	–5V @ 1.5A	+24V @ 2A	US-272	69.00
+5V @ 2A	+12V @ .4A	–12V @ .4A	US-HTAA	37.50

TELEVIDEO 950

Televideo 950 –$950.00
Televideo 912C– 665.00
Televideo 920C– 720.00
ADDS R-25 – 710.00



Also have 920C, SOROC, HAZELTINE, etc. What we don't have is room on this page. Call Toll Free 800 number for prices.

C-ITOH PRINTER

$499.00

Look closely at the photo and see other adds in this rag at $995.00. Perfect units, warranteed. Only 500 pcs. Same story, manufacturerer had too many.

S-100 CARD EXTENDER

$12.50
(Gold Contacts)

As long as there is a price war, we will fight your battle. Compare at your local Dept. store and buy U$ MICRO.

MEMOREX – VERBATUM – WABASH
BASF FLOPPIES

BOX OF 10 ONLY:

5¼"	SOFT	$2.65 ea.
5¼"	HARD 10	2.65 ea.
5¼"	HARD 16	2.65 ea.
8"	SOFT 1D	3.25 ea.
8"	SOFT 2D	3.85 ea.
8"	SOFT 2DDS	5.00 ea.

SPECIAL OF THE QUARTER

S1-MOD (KIT)

$189.00 MADE IN USA

Complete S-100 12 Slot Computer. Ample system power with regulated power for drives. Excellent for Subsystem or Hobby use. 4 hours to build. (6 conn. incl., less fans)

DUAL DRIVE SUBSYSTEM

$995.00
$195.00 w/no Drives

If this looks like a Lobo Drive System, don't be fooled. Just because it looks like one, works like one, smells like one, and tastes like one (?) doesn't mean it has to cost like one!

2 SHUGART 801R POWER SUPPLY

TWIN VERTICAL DRIVE$

5" $550.00 – 8" $980.00

Attractive, convenient and compact Two Drive Mass Storage includes Power Supply, Drives, Cabinets and Cables. Double Sided, Double Track available too!

$145.00 Kit (Less Cable)

Z-80 CPU (KIT)



The first time this world popular CPU offered in Kit. 2 serial, 3 parallel, CTC, EProm Z-80 at 4 mhz. Software buad rate, etc. (less Prom & cable) $212.00

EXPANDABLE RAM

★SPECIAL★SPECIAL★SPECIAL★

This is the best all around 64K board you can buy. If after you see it, you don't agree return for full refund. Bank Select by extended address lines or I.O. 40H.



★$389.00 A&T★

U$ – D$K $255.00

Double Density 8" and 5" Disk Controller disigned for S-100 IEEE standards. Uses Western Digital 1795, 1691 2143 Chip Set.



FANS $14.95

These are brand new, in the box fans. Not noisey bearing pullouts. Never again at these low prices!

3-1/8"

4-5/8"

SPECIALS OF THE MONTH

4116s

$3.25
200 NS

Expansion 16K Dynamic RAMs for Apple, TRS-80 S-100 systems. T.I., Mostek Intel, Call for manufacturer.

INTEL

8251 $4.95
8255 $6.50

VERY POPULAR I.O. CHIPS BY LEADING MANUFACTURER

2114s

$2.95
200 NS

One of the world's two most popular STATIC RAMs. Factory prime tested units. Sold in lots of 8 only. FUJITSU, HITACHI, etc.

TMS-4044 / MM-5257 / INTEL 2147

$4.25
250 NS

CMOS Version $4.50!

The other of the world's most popular STATIC RAMs. This one is 4K by 1 organization. Don't buy Gold, buy these, the price won't last!

2716s $7.50 (450 NS)
2708s $6.95 (450 NS)

Remember when 2716s were $50.00 and hard to get? These units are so beautiful it's hard to part with them. But we will, for a small price. Guaranteed!

SHUGART DRIVE

8" 801R **$395.00**

8" 851R $585.00

Manufacturer had too many, buys at 1000 piece rate, sales dropped, so we got'em. Fantastic buy, get them while they last! Full warranty.

SIEMANS DRIVE

8" 100-8 **$375.00**

Very Special Price on these BRAND NEW current production units Add $10.00 for Extended 1 Year Warrantee!

Circle 407 on inquiry card.

POWER



THE AE-85 SINGLE CARD COMPUTER FOR DEDICATED CONTROL

The AE-85 with the many features listed below is ideal for dedicated control applications since all the necessary features are provided on-board. Even the interrupt control logic and space for custom electronics is provided so as to further reduce development costs. So save time with the simple solution and discover the AE-85.

Standard
- Standard 6 MHz 8085 MPU with serial port
- 22 programmable bidirectional I/O pins
- 256 bytes of RAM
- 14 bit crystal controlled counter/timer
- Up to 4K EPROM (accepts 2708, 2716 or 2732)
- Provisions for 190 wire wrap pins for various sockets and connectors
- On-board jumper definable logic allowing easy combining of interrupt requests for the 4 hardware interrupts
- 6 by 6 inches with four 3/16 inch holes for easy mounting
- Assembled and tested $179.00 singles

Optional-an extra
- 22 programmable bidirectional I/O pins
- 1280 bytes of RAM
- 14 bit crystal controlled counter/timer

Call today for more information. Phone: 614-221-3060
Adroit Electronics, Inc., **5 East Long Street, Suite 1012, Columbus, Ohio 43215**

Circle 5 on inquiry card.

☆ BARGAINS ☆

Measurement Systems

64K Ram Board	$480.00
64K Bank Select Board	$650.00
(compat. w/Alpha Micro, Cromix)	
CPU Z80, 2 Serial I/O	$285.00
Floppy Disk Controller	$300.00
Shugart SA-801R Drives	$400.00
CP/M 2.2	$110.00
Dysan Diskettes (S.S.—D.D.)	$63.00
4116 Ram chips each	$3.00
MC 3480 chips each	$7.00

All orders are prepaid-cashiers check or MC—Visa. Add 5% for shipping & handling, California residents add 6% sales tax. Write for more information

Micro-Spot Electronics
1234 Collins Avenue
Orange, California 92667

Circle 243 on inquiry card.

PROCAP

EAGLES ?
COWBOYS ?

RAIDERS ?
RAMS ?

If you'd like to know NOW, before the big game

With **PROCAP** and your TRS-80*, you can use statistics and probability theory to predict the results of this week's big games. And more. **PROCAP**

- Gives offensive and defensive ratings for every National Football League team
- Predicts range of results and probable score for each game
- Allows computer matchup of any two teams (Great for playoffs!)
- Gives "up-to-the-minute" standings, statistics, and ratings for each NFL Division

PROCAP is easy to use and comes with extensive documentation

Disk or cassette version is only $49.95

To order, call our toll free number NOW. Money back guarantee so you can't lose

Dial (800) 543-3000 operator 400
In Ohio dial (800) 582-1364, operator 400

*Please specify TRS-80 Model I (16K or 32K cassette version only) or TRS-80 Model III (16K cassette or 32K floppy disk)

The Trinity Computer Group • Software Agent/Publisher

Circle 405 on inquiry card.

ONE DISEASE YOU CAN'T CATCH!

H

HUNTINGTON'S DISEASE

NATIONAL **HUNTINGTON'S DISEASE** ASSOCIATION
Suite 501, 1441 Broadway
New York, N.Y. 10018
212-966-4320

CONTROL-Z™

SINGLE BOARD Z-80A* COMPUTER FOR CONTROL USES



USES: Industrial Test Equipment; Intelligent Peripheral Controller; Automatic Dialing Equipment; Solar Heating & Power Systems; Machine Control; Security Systems; Traffic Signal Control; Appliance Control; Robotics; OEM Products; Etc!

FEATURES: 4 MHZ Z-80A* (on board crystal), 1k RAM, sockets for 2 2716's (4K PROM), 3-8 bit parallel TTL output ports, 2-8 bit parallel TTL input ports, 8 analog input ports (100 μ sec conversion time), 6 high current output lines (open collector), 4 opto-isolated input lines, extra single bit TTL output for serial I/O, Z-80 control lines brought to edge connector, extra port decodes brought to edge connector, 1 input port doubles as bus for port expansion, on board 5v regulator, 4½x8 PC board, uses standard 72 pin edge connector, fully socketed, requires +8 to 10 volts, 500 mA

PRICE: $295 — Monitor PROM $45 Full function monitor program with download capacity, software serial driver & selftest feature

TERMS: CHECK, MC, VISA, or C.O.D. Cal. Res. add 6% tax. First Class Shipping Included.

*Registered Trademark of Zilog, Inc

COMPUTER-AID
1122 DE LA VINA SANTA BARBARA, CA 93101 (805) 966-3077

Circle 70 on inquiry card.

CP/M COMMUNICATIONS

LYNC™

THE BEST AVAILABLE PROGRAM FOR CP/M COMMUNICATIONS

LYNC is extremely powerful and easy to use and a must for every computer user that wants to communicate with time-sharing systems or other CP/M computers

TERMINAL MODE
In this mode your system acts as a terminal. Can send to or receive from a timesharing system. When receiving data from a remote system, received data is buffered to your maximum memory, then can be saved as a disk file.

LYNC MODE
Communicate on-line with another computer similarly equipped. Both ends can type messages that appear simultaneously on both screens.

SEND: AUTOMATIC ERROR DETECTION & RETRY
LYNC sends block of information with 16 bit checksums. In case of error it will keep retrying until successful.

FETCH
Once both systems are in LYNC mode, either operator can FETCH files from other system.

REMOTE AND LOCAL DIRECTORY
Can display both local and remote directories.

BAUD RATES: UP TO 9600 BAUD

SELF GENERATING I/O ROUTINES REQUIRE NO PATCHING

PRICE: $95 TERMS: MONEY ORDER, CHECK, COD, M.C. OR VISA

PLEASE SPECIFY DESIRED FORMAT: 8" Single Density; 5" Micropolis; TRS-80 Mod II with CP/M; North Star single or double density; Superbrain 3.0 DOS or later; Cromenco 5" single density.

COMPUTER-AID
1122 DE LA VINA • SANTA BARBARA, CA 93101
(805) 966-3077

Circle 71 on inquiry card.

Atari 800 16K • $789

THIS is only one of hundreds of unusual values . . . Get your **FREE CATALOG** today!

TOLL FREE 1-800-343-8124

computer plus
Dept. C
245A Great Road
Littleton, MA
01460

Radio Shack's Color Computer 4K • $310

THIS is only one of hundreds of unusual values . . . Get your **FREE CATALOG** today!

TOLL FREE 1-800-343-8124

computer plus
Dept. I
245A Great Road
Littleton, MA
01460

Circle 78 on inquiry card.

TRS-80* TI-99/4**

New ready-to-run interactive programs and subroutines in basic or fortran for Education-Science-Astronomy-Mathematics-Forecasting-Statistics-Graphics-Curve Fitting-Finance-Music Analysis and Synthesis-Linear System Solutions

Listings are well commented and most programs convert easily to other machines

Write for new free catalog.

Custom programming available in Basic, Fortran and Assembler

BENCHMARK COMPUTING SERVICES
P.O. Box 385
Providence, Utah 84332

VISA MASTERCHARGE

*Trade Mark copyright Tandy Corporation
**Trade Mark copyright Texas Instruments

Circle 43 on inquiry card.

AVAILABLE NOW!

THE INTERNATIONAL MICROCOMPUTER SOFTWARE DIRECTORY

ONLY $28.95 + $2.95 post.

5000 entries, cross-referenced by machine, O/S, application, vendor and program name.

Phone or write for details. All major credit cards accepted.

IMPRINT SOFTWARE
US - 420 South Howes St., Ft. Collins, CO 80521 - Tel 303 482 5574
UK - 16 Milton Avenue, Highgate, London N6 - Tel 01 348 3998

Circle 154 on inquiry card.

BETA COMPUTER DEVICES

ADDS VIEWPOINT TERMINAL $629.00

- Detachable keyboard weighs only 2 lbs.
- 110-19,200 Baud - RS-232C
- Cursor control keys - audible tone
- 24 x 80 characters - 12" screen
- 14 key numeric keypad
- 7 switch selectable character sets
- Addressable cursor
- 2 position screen tilt
- Normal or reverse video
- Half or zero intensity
- 3 function keys (six functions)
- Lightweight (22 lbs. with keyboard)
- Switch select block or underline cursor
- Switch select blinking or steady cursor

S-100 PRODUCTS



QUALITY RAM FROM SYSTEMS GROUP

- Z-80 4MHZ operation with no wait states
- IEEE compatible timing - 200ns 4116's
- Factory assembled, tested & burned in

DMB6400 64K....................................$749.00
DM6400 64K (shown)..........................545.00
DM4800 48K....................................520.00
DM3200 32K....................................495.00

CPC-2810



CONFIGURE A COMPLETE S-100 SYSTEM WITH 2nd GENERATION* PRODUCTS FROM SYSTEMS GROUP.

- CPC 2810 (shown) Z-80A processor board (4MHZ) with 4 serial & 2 parallel ports..$369.00
- CPC2813 - same as CPC2810 but 2 serial ports only..................................$345.00
- FDC2801/8 - 8" floppy disk controller board, up to 4 single/double sided drives, single or double density.................$349.00
- INO-2804 - 4 channel serial I/O......$329.00
- CRA-100 - Cromix* adaptor board..$ 45.00

CALL US FOR OUR MOST CURRENT PRICES!

• Trademarks of Cromemco, Inc. and Wabash Tape Corp.

16K MEMORY EXPANSION KIT $29.00

For **Apple**, **TRS-80** keyboard, **Exidy**, and all other systems using 4116 dynamic rams or equivalent. All IC's are prime Mitsubishi MK 4116-3.

- 200 NSEC access, 375 NSEC cycle
- Burned-in and fully tested
- 1 full year parts replacement guarantee

wabash



8" or 5¼" flexible diskettes certified 100% error free with manufacturers 5 year limited warranty on all 8" media. Soft sectored in tilt-back* boxes of 10.
(Add $3.00 for plastic library cases)

8" single sided, single density................$29.95
8" single sided, double density............... 37.95
8" double sided, double density............. 48.95
5¼" single sided, single density............ 27.95
5¼" single sided, double density............ 29.95

8" DISK DRIVES

Shugart 801R.................................$390.00
NEC FD1160 (double sided)..............$595.00
Memorex MRX-101 8" Winchester style, hard disk drive, 10 megabytes........... ONLY $2,200.00

TERMS: *Minimum order $15.00. Minimum shipping and handling $3.00. Calif. residents add 6% sales tax. Cash, checks, Mastercard, Visa and purchase orders from qualified firms and institutions are accepted. Product availability and pricing are subject to change without notice.*

INTERNATIONAL ORDERS: *Add 15% to purchase price for all orders. Minimum shipping charge is $20.00. Orders with insufficient funds will be delayed. Excess funds will be returned with your order. All prices are U.S. only.*

6502 PRODUCTS



BETA 32K BYTE MEMORY
RELIABLE/COST EFFECTIVE
EXPANDABLE RAM FOR
6502 AND 6800 SYSTEMS —
AIM 65 KIM SYM PET S44-BUS

- Plug compatible with the AIM-65/SYM expansion connector by using a right angle connector (supplied) mounted on the back of the memory board.
- Memory board edge connector plugs into the 6800 S44 bus.
- Connects to PET or KIM using an adaptor cable.
- Reliable, dynamic ram with on board transparent refresh. Looks like dynamic ram but costs less and uses a fraction of the power of static boards.
- Uses +5V only, supplied from the host computer.
- Full documentation. Assembled and tested boards are guaranteed for one full year. Purchase price is fully refundable if board is returned undamaged within 14 days.

Assembled with 32K Ram.....................$349.00
& Tested with 16K Ram.................... 329.00
Bare board, manual & hard-to-get parts... 99.00
PET interface kit. Connects the 32K ram board to a 4K or 8K PET. Contains: interface cable, board standoffs, power supply modification kit and complete instructions..............................$ 49.00

ROCKWELL AIM 65



AIM 65 with 1K ram........................$425.00
AIM 65 with 4K ram........................ 485.00
AIM power supply........................... 125.00
Professional AIM enclosure................. 169.00
Budget AIM enclosure....................... 50.00
KIM enclosure............................... 40.00
SYM enclosure............................... 30.00

BETA COMPUTER DEVICES
1230 W.COLLINS AVE.
ORANGE, CA 92668
(714) 633-7280

master charge VISA

Buy By Mail and Save!

COMPUTERS

ZENITH | data systems

List
$2895
OUR PRICE
$2295

SUPERBRAIN
By INTERTEC



w/64K Dbl Density, List $3495 $2595
w/64K Quad Density, List $3995 $2995

CROMEMCO
SYSTEM THREE



64K List $7995 OUR PRICE $6395

NORTH STAR
HORIZON TWO

Horizon 2 32DD List $3095 $2289

Call for latest NorthStar and Intersystem Prices

TERMINALS

TeleVideo

Televideo 912C $679
920C $799
950 . . . . $999

SOROC



Soroc 120 List $995 . . . . $689
IQ135 . . . . $719
140 . . . . $994

ZENITH Z19

$719

INTERTUBE III

Intertube III List $895 . . . . $729

PRINTERS

CENTRONICS



739-1, List $995 . . . . $769
704-9 RS232 . . . . $1495
704-11 Parallel $1569

TI 810



TI 810, List $1895 . . . . $1489

DISK SYSTEMS

MORROW



Thinker Toys Discus 2D $939
Dual Discus 2D $1559
Discus 2 + 2, List $1549 . . . . $1259
M26 Hard Disk, List $4995 . . . . . . $3949

COMPUTERS WHOLESALE

VISA P.O. Box 144 Camillus, NY 13031 master charge

(315) 472-2582

Most items in stock for immediate delivery. Factory sealed cartons. w/full factory warranty. NYS residents add appropriate sales tax. Prices do not include shipping. VISA and Master Charge add 3%. C.O.D. orders require 25% deposit. Prices subject to change without notice.

Circle 91 on inquiry card.

ONE BOARD CP/M SYSTEM!



only $750
Assm., Tested
& Burned-In
for one week

Features:

- 8½ by 12 inches
- 10 MHZ 8085 CPU
- 64K RAM
- 3 RS-232 channels
- 8272 Floppy Disk Controller
- Handles Single/Double Density
- One to Four Drives. 801R or 850R.

Documentation $15.
CP/M Floppy Disk Operating System $150
Check or Money Order

autocontrol
INCORPORATED
11744 Westline Industrial Drive
St. Louis, MO 63141
(314) 432-1313

Circle 36 on inquiry card.

AC-85 CP/M® SYSTEM

Assm., Tested
& Burned In
for one week

$2450

Features:

- One board 8085 Computer
- 2 - SA800R* (1.2 megabytes)
- CBIOS Diskette
- Installed and wired in a cabinet with P/S and Fan ready to plug-in
- Manual
- 17½" W x 17" D x 10" H
- * SYSTEM with 2 SA850R (2.4 mbytes)

$2750.00
CP/M Floppy Disk Operating System $150
Check or Money Order

autocontrol
INCORPORATED
11744 Westline Industrial Drive
St. Louis, MO 63141
(314) 432-1313

® CP/M is a registered trademark of Digital Research, Inc.

Circle 37 on inquiry card.

INDUSTRIAL CROSS-MACRO ASSEMBLERS

written in FORTRAN IV

New, two-pass macro assemblers for all popular micros can be run on any general-purpose computer with standard FORTRAN. Each assembler supports macros, conditional assembly, and relocatable object code. All the original mnemonics and addressing modes, many assembler directives, long error messages and more. Produces printed assembly listing, and object code file.

PROGRAM NO.	FOR MACHINE	PKG. PRICE
MASM68E3	MC68000	$500
MASM6809	MC6809	400
MASM6805	MC6805	400
MASM6801	MC6801	350
MASM6800	MC6800	300
MASM6502	MCS65xx	375
MASM8085	8080/8085	350
MASM1802	CDP1802	300

Packages include detailed users' manual, printed source listing (well commented), source on magnetic tape, and IDM's Software Support Service. Card decks also available. Dealer inquiries invited.

IDM intelligent devices of minnesota
p.o. box 492 anoka, mn. 55303
(612) 427-0787

Circle 190 on inquiry card.

MEMOREX

5¼" Floppy Discs
SAVE 40% Write for our complete list.

Prices per box of 10

One side, sgl. dens. 24.60
Same with hub-ring 27.20
One side, dbl. dens. 27.80
Two sides, dbl. dens. 34.30

Specify soft, 10 or 16 hard sectors

Add $2.00 shipping - Michigan add 4% tax
Pay by check, Master Charge or VISA

LYBEN COMPUTER SYSTEMS
(313) 777-7780
27204 Harper
St. Clair Shores, MI 48080

Circle 213 on inquiry card.

ZEN is HERE

FAST SCREEN EDITING for CP/M & NORTH STAR
OPEN PROGRAMS WITH SOURCE FILES

ZEN™ offers you very fast screen editing without line numbers. You are in control and ZEN may be reassembled to change or add custom features. Call system and return without losing the file. Justify even old disc files to any line length. Save, append, find, print & much more, with ease. Monitor functions are built in, extensions can be added. A 32K system with console is necessary but addressable cursor is not required.

CPM version for 1.4 thru MPM releases, uses their assembler and line command conventions which can include multiple command lines.

North Star DOS versions have a disc assembler, an extensive monitor and some Basic utilities. They use the N.S. line editing conventions.

Specify version #	ZEN1.1 5" SD NS 2000
ZEN2.1 8" SD SS CPM	ZEN1.2 5" DD NS 2000
ZEN2.2 5" DD NS CPM	ZEN1.3 5" DD NS 0100
Disc and Manual $75	Manual alone $15
CA residents add 6%	Send check to:

Dealer Enquiries welcome.

ZENRAD CONTROLS CO
1575 A.P.S.
Santa Barbara CA 93103

Circle 435 on inquiry card.



OAE's PP-Series EPROM Programmers plug directly into any vacant EPROM socket and allow you to transfer data directly from RAM to EPROMs. No additional power supplies are required. All timing & control sequences are handled by the programmer. Each unit includes internal DC to DC switching regulator, ZIF socket and 4 ft. ribbon cable terminated with a 24 pin plug. Programmers are available for all EPROMs from 2708's thru 2532's.

Oliver Advanced Engineering, Inc.
676 W. Wilson Ave., Glendale, CA 91203
(213) 240-0080 or Telex 194773.
PP SERIES PROGRAMMERS
See us at NCC, booth 770

Circle 284 on inquiry card.

PRINTERS

BASE 2	
800B	$585
850	$699
APPLE INTF.	$140
OKIDATA	
μ 80	$ CALL $
μ 82	$ CALL $
EPSON	
MX-80	$ CALL $
MX-70	$ CALL $
ANACOM	
150	$ CALL $

PLEASE ADD 3% FOR S & H AND $2 FOR INS TO ORDER

TECHNICAL INNOVATIONS
P.O. BOX 803
HILLSBORO, OR 97123
503-648-6423

Circle 384 on inquiry card.

ZAS Z-8000

SOFTWARE DEVELOPMENT PACKAGE

A professional Z-8000 assembly language package now available for 8080 & Z-80 based microcomputers which use the CP/M® or ISIS-II® operating system.
The package includes:

ZAS Full featured relocatable cross assembler. Uses Zilog syntax, supports segmented and non-segmented code, symbol names to 64 characters, 26 directives, including nested conditional assembly, "include" files, and named program, data and absolute sections. Outputs: object and listing files.

ZLK Task Builder. The most powerful linker you've ever used! Sections can be combined in any order and optionally "located" at fixed address. ZLK can also handle complicated overlay arrangements.

ZLD Object Loader. Loads an absolute object file for execution by a Z-8000 CPU on the bus. Includes host OS interface.

ZAS, ZLK, ZLD CP/M® ..$395
ISIS-II® ..$495
Manual Only..................$25
Supplied on Single Density 8" Disk
CP/M® Digital Research, Inc. ISIS-II® Intel Corp.

WESTERN WARES
Box 48 Placerville, CO 81430

Circle 423 on inquiry card.

DATAPOINT

1134 Diskette Systems

16k Processor with Four Diskettes (1 Megabyte). 80 CPS Matrix Printer. Nationwide maintenance available.

$2,645

SOFTWARE AVAILABLE
DISK OPERATING SYSTEM
SORT UTILITY
ISAM UTILITY
ALSO AVAILABLE FOR $250 EACH.
A/P, A/R, GENERAL LEDGER, PAYROLL, TIME ACCOUNTING, AND INVENTORY

AMERICAN COMPUTER EXCHANGE
100 N. MAIN ST. BOX 52
CHAGRIN FALLS, OH 44022
216-247-2103

Circle 440 on inquiry card.

1858 Evergreen Street, Duarte, California 91010 Phone 213-357-5005

page
DIGITAL INC.

INSULATION DISPLACEMENT SOCKETS

RIGHT ANGLE HEADERS



Pins	PC Mounting		WireWrap	
10	IDH10SR	.80	IDH10WR	1.75
20	IDH20SR	1.25	IDH20WR	2.75
26	IDH26SR	1.85	IDH26WR	3.60
34	IDS34SR	2.15	IDH34WR	4.15
40	IDH40SR	2.50	IDH40WR	4.90
50	IDH50SR	3.15	IDH50WR	6.15

EJECTOR EARS .25 EACH

CARD EDGE CONNECTORS



Pins	Part No.	
10	IDE10	3.25
20	IDE20	3.50
26	IDE26	4.05
34	IDE34	4.85
40	IDE40	5.65
50	IDE50	5.90

RIBBON CABLE



Conductors:	Solid Color 10 ft.	Solid Color 100 ft.	Color Coded 10 ft.	Color Coded 100 ft.
10	2.90	17.00	4.00	30.00
14	3.40	23.80	5.00	42.00
16	3.70	27.20	5.60	48.00
20	4.40	34.00	7.00	60.00
24	5.00	40.80	8.00	72.00
26	5.40	44.20	8.60	78.00
34	6.80	57.80	11.00	102.00
40	7.80	68.00	13.00	120.00
50	9.50	85.00	16.00	150.00

25 PIN "D" CONNECTORS



Style	Part #	
SOLDER STYLE		
Male	DB25P	2.25
Female	DB255	3.00
Hood	DB25C	1.10
INSULATION DISPLACEMENT		
Male	IDC25P	4.95
Female	IDC255	5.25
Hood	IDC25C	1.35

SOCKETS



Pins	Part No.		Stain Relief
10	IDS10	1.25	.25
20	IDS20	2.02	.25
26	IDS26	2.65	.25
34	IDS34	3.50	.25
40	IDS40	4.05	.25
50	IDS50	5.06	.25

CABLE PLUGS



Pins	Part No.	
14	IDP14	1.25
16	IDP16	1.40
24	IDP24	2.25
40	IDP40	3.65

WIRE WRAP WIRE

Length	100/Bag	500/Bag	1K/Bag	Length	100/Bag	500/Bag	1K/Bag
2.5"	$1.25	$3.58	$ 6.19	6.5"	$1.92	$6.44	$11.81
3.0"	1.30	3.86	6.78	7.0"	1.99	6.76	12.44
3.5"	1.37	4.15	7.37	7.5"	2.08	7.07	13.09
4.0"	1.42	4.44	7.94	8.0"	2.14	7.38	13.73
4.5"	1.48	4.74	8.54	8.5"	2.18	7.69	14.36
5.0"	1.54	5.04	9.13	9.0"	2.24	8.11	15.01
5.5"	1.58	5.38	9.72	9.5"	2.30	8.32	15.65
6.0"	1.65	5.66	10.31	10.0"	2.39	8.71	16.28

Kynar precut wire. All lengths are overall, including 1" strip on each end. Colors and lengths cannot be mixed for quantity pricing. Choose from colors Red, Blue, Black, Yellow, White, Green, Orange, and Violet.

WIRE KITS

Kit No. 1	$9.95		
250	3"	100	4½"
250	3½"	100	5"
100	4"	100	6"

Kit No. 2	$24.95		
250	2½"	250	5"
500	3"	100	5½"
500	3½"	250	6"
500	4"	100	6½"
250	4½"	100	7"

Kit No. 3	$32.95		
500	2½"	500	4½"
500	3"	500	5"
500	3½"	500	5½"
500	4"	500	6"

Kit No. 4	$59.95		
1000	2½"	1000	4½"
1000	3"	1000	5"
1000	3½"	1000	5"
1000	4"	1000	6"

ORDERING INFORMATION:

- Orders under $25 include $2 handling
- All prepaid orders shipped UPS Ppd.
- Visa, MC & COD's charged shipping.
- All prices good through cover date.
- Most orders shipped same day.
- Byte must be mentioned to get sale price.

Write or call for 1981 catalog

- IC Sockets
- Vector Board & Pins
- Bishop Drafting Aids
- OK Tools
- RN IDC Crimp Connectors

"NEW" WIRE WRAP SOCKETS

FEATURING A SELECTIVE PLATING METHOD THAT WILL SAVE YOU MONEY BY HAVING GOLD ONLY WHERE IT COUNTS.



3 Level closed entry.

RN Side Wipe contact design gives twice the contact area for high reliability.

Size	Quantity/Tube	Price ea.*	Price/Tube
8	52	.41	21.32
14	30	.47	14.10
16	26	.51	13.26
18	23	.70	16.10
20	21	.87	18.27
22	19	.94	17.86
24	17	.96	16.32
28	15	1.25	18.75
40	10	1.70	17.00

*FOR REFERENCE. MUST BE ORDERED IN TUBE QUANTITIES.

TOLL FREE ORDERING NUMBER 1-(800)-423-7144

Circle 301 on inquiry card.

NEW! for the '89 from

MAGNOLIA MICROSYSTEMS

DOUBLE DENSITY DISK CONTROLLER

for both 5¼" & 8" drives

only **$595** complete

including CP/M™2.2

MAGNOLIA MICROSYSTEMS, INC.
2812 Thorndyke W., Seattle 98199
(206) 285-7266 (800) 426-2841

CP/M is a trademark of Digital Research.

Circle 216 on inquiry card.

RS-232 PROBLEMS?



LET THE RS-232 TESTER HELP YOU SOLVE YOUR COMPUTER INTERFACE PROBLEMS. DESIGNED TO CONNECT IN SERIES WITH ANY RS-232 INTERFACE, IT DISPLAYS THE STATUS OF SEVEN OF THE MOST IMPORTANT LINES: TRANSMIT DATA, RECEIVE DATA, REQUEST TO SEND, CLEAR TO SEND, DATA SET READY, CARRIER DETECT, AND DATA TERMINAL READY. THE RS-232 TESTER REQUIRES NO POWER AND MAY BE LEFT IN THE LINE PERMANENTLY.

$39.95 POST PAID

B & B ELECTRONICS

BOX 475/MENDOTA, IL 61342

Circle 40 on inquiry card.

BUDGET SOFTWARE

For as little as 15% down you can have custom designed software, write BUDGET SOFTWARE, 8517 Nestle Ave., Northridge, CA., 91325 or phone (213) 701-0734 8:00 - 6:00 (pst)

Circle 46 on inquiry card.

H8 OWNERS

APU-H ARITHMETIC PROCESSOR CARD

- ADDS POWERFUL MATH CAPABILITY TO H8
- 32 BIT FLOATING POINT OPERATION
- 16 AND 32 BIT FIXED POINT OPERATION
- ADD, SUBTRACT, MULTIPLY AND DIVIDE
- TRIG, LOG, EXP, SQUARE ROOT AND MORE
- BASIC AND ASSEMBLER SOFTWARE PROVIDED
- FULL DOCUMENTATION
- ASSEMBLED AND TESTED
- VISA AND MASTER CHARGE ACCEPTED

New Reduced Price
$345.00

CCM, INC

P.O. BOX 2308 RESTON VA 22091
Phone orders (703) 620-3403

Circle 81 on inquiry card.

The Time Machine™

FOR YOUR apple®

$135 REAL TIME CLOCK AND CALENDAR

Introducing an intelligent real time clock and calendar peripheral for the Apple II*

- Read and set time routines in 2K EPROM driver.
- Counts seconds, minutes, hours, days, days of week, month and years.
- Six date formats including: 12-JUN-1981
- Two interrupt programs in EPROM.
- Nicad battery and applications diskette.
- Basic, Pascal, and Machine language compatable.

FOR FREE BROCHURE CALL (801) 486-4839

CREATIVE Software Dev.

DISTRIBUTED BY
The COMPUTER ROOM
1879 South Main Street
Salt Lake City, Utah 84115
(801) 486-4839

*TRADEMARK OF APPLE COMPUTER CORPORATION.

Circle 105 on inquiry card.

ADVANCE High Quality
COMPUTER & AUDIO
CASSETTES

are manufactured to the highest possible standards using 5 screw high-strength shells which will give long life to your data cassette. Unconditionally guaranteed or your money back.

Credit Card Buyers May Call
714-277-2540

Length	10 Pack	50 Pack	100 Pack
C-10	$ 7.00	$30.00	$ 55.00
C-20	$ 8.50	$37.00	$ 70.00
C-62	$12.00	$55.00	$ 95.00
C-92	$16.00	$74.00	$135.00

WHOLESALE INQUIRIES WELCOME

Please allow 4-6 weeks for delivery. UPS shipment in continental USA included. We can not ship to P.O. boxes. CA RESIDENTS ADD 6% SALES TAX. Please send check, money order or your VISA or Master Charge number, with expiration date, to:

Advance Sargam Corporation
4290 Rueda Drive
San Diego, CA 92124
(714) 277-0338 or (714) 277-2540

Circle 9 on inquiry card.

H·8 H·89 Z·89 V-8 VOICE SYNTHESIZER

ALL NEW MODEL II

EASY TO PROGRAM ---- EXCITING TO USE

NOW CLEAR INTELLIGIBLE SPEECH WITH UNLIMITED VOCABULARY

FULL SOFTWARE SUPPORT GAMES,UTILITIES ENGLISH 'TYPE AND TALK' FOREIGN LANGUAGES AND MORE

USES THE LATEST IN SPEECH TECHNOLOGY WITH "automatic" INFLECTION

KIT $ 249.95
V-8 $ 349.95 Assembled / Tested

MI-8
822 E. County Rd. 30
Ft. Collins, Colo. 80525

VISA FREE CATALOG master charge

Phone orders: (303) 669-4116
Enclose $2.00 for voice sample cassette

Circle 102 on inquiry card.

floppy disks.

From the inventors of magnetic recording tape

BASF

100% certification - every single disk is tested at thresholds 2-3 times higher than system requirements, to be 100% error-free.

Immediate off the shelf delivery . . . one box or quantity orders welcome.

SPECIAL INTRODUCTORY OFFER!!

THIS MONTH ONLY! **10%** OFF OUR LOW DISCOUNT PRICES

CALL OUR ORDER DESK NOW! 805-985-2793
MASTERCARD — VISA — C.O.D.

NATIONAL DATA SUPPLIES, INC.

Circle 274 on inquiry card.



NEW! S-100

8048 IN-CIRCUIT EMULATOR

- Up to 11 Mhz Real Time Emulation.
- S-100, CP/M compatible.
- Emulates 8035, 8039, 8048, 8049, 8748, 8040, 8050, 80C48 CMOS.
- Unlimited number of breakpoints.
- Single Stepping by Instruction Cycle.

MICE-48 comes on one S-100 type board with a ribbon cable that plugs into the user's microprocessor socket. The price is $950.00 and it includes Allen Ashley's MACRO ASSEMBLER. (213) 451-5382.

SIGNUM SYSTEMS
726 Santa Monica Blvd.
SANTA MONICA, CA. 90401

Circle 352 on inquiry card.

THE STAR MODEM

From Livermore Data Systems

RS232 MODEM	SALE $135
IEEE 488 MODEM	**SALE $199**
RS232 CCITT	$170
IEEE 488 CCITT	$280

STAR Modem is the price performance leader with a full 2 YEAR FACTORY WARRANTY.

MIPLOT Intelligent Plotter
by Watanabe Instruments (Digiplot)

SPECIAL $1195

Has all intelligent functions for producing graphs and drawings including 8 vector and 4 character commands. Solid and broken lines can be specified. Character generator for alpha, numeric, and symbols. Characters can be rotated in 4 orientations, and can be 16 sizes. Coordinate axes drawn by specifying graduation interval and number of repetitions. Parallel ASCII interface, 11 x 17 paper.

We carry Apple II+ from Bell & Howell

REVERSAL (Spracklen) 32K Apple	28.00
Super FORTH 48K Apple	40.00
Energy Miser – 32K Apple	24.50
Data Manager (Lutus) 24K Apple	40.00
Histo-Graph (Boyd) 48K Apple	24.50
Data-Graph (Boyd) 48K Apple	40.00
Apple II User's Guide (Osborne)	12.00
Introduction to Pascal (Sybex)	10.30
Pascal Handbook (Sybex)	12.00
Graphics Cookbook for Apple	9.90
Musical Applications of Micros (Chamberlin)	20.00
Basic FORTRAN (Coan)	7.25

SPECIALS

EPSON MX-80 Printer	
EPSON MX-70 Printer	
STARWRITER Daisy Wheel Printer	$1445
Centronics 737 Printer	725
NEC Spinwriter	2500
Diablo 630 Daisy Wheel	2150
Leedex Video 100 12" Monitor	135
ZENITH DATA SYSTEMS	
Z19 Video Terminal (factory assem.)	729
Z89 with 48K (factory assem.)	2150
SYM-1	209
SYM BAS-1 BASIC or RAE-1/2 Assembler	85
KTM-2/80 Synertek Video Board	349
Seawell Motherboard - 4K RAM	195
Seawell 16K Static RAM - KIM, SYM, AIM	320

PROGRAM YOUR OWN EPROMS
Branding Iron for PET/CBM — $79
EPROM Programmer with software for all ROM versions. Includes all necessary hardware and software to program or copy 2716 and 2532 EPROMS.

Paper-Mate Word Processor — $39.95
PET/CBM full featured 60 command system by Michael Riley. Uses either tape or disk and any printer. Includes in-text commands, floating cursor, scrolling, etc.

FLEX-FILE Data Base for CBM/PET — $60
Random file handling system with Report Writer and Mail Label Handler. By Michael Riley.

KMMM Pascal for PET — $75
Subset of standard Pascal with true machine language translator for faster execution. 16K with tape or disk.

EARL for PET (disk file based) — $65
Editor, Assembler, Relocator, Linker to generate relocatable object code.

FORTH for PET/CBM or Apple — $65
A full-featured FORTH with extensions conforming to Forth Interest Group standards. Includes assembler, string processing capabilities, disk virtual memory multiple dimensioned arrays, floating point and integer processing.

6502	7.45	10/6.95	50/6.55	100/6.15
6502A	8.40	10/7.95	50/7.35	100/6.90
6520 PIA	5.15	10/4.90	50/4.45	100/4.15
6522 VIA	6.45	10/6.10	50/5.75	100/5.45
6532	7.90	10/7.40	50/7.00	100/6.60
2114-L200 ns RAM		3.75	25/3.50	100/3.25
2114-L300 ns RAM		3.15	25/2.90	100/2.65
2716 EPROM (5 volt)		9.90	5/9.45	10/8.90
TMS 2532 EPROM				20.00
4116-200 ns RAM				**8 for 24.00**
S-100 Wire Wrap				2.65

CASSETTES — AGFA PE-611 PREMIUM
High output, low noise, 5 screw housing, labels.

C-10	10/5.65	50/25.00	100/48.00
C-30	10/7.30	50/34.00	100/66.00

All other lengths available. Write for price list.



4 PART HARMONY MUSIC SYSTEM for PET
The Visible Music Monitor, by Frank Levinson, allows you to easily enter, display, edit, and play 4 part harmony music. Includes whole notes thru 64ths (with dotted and triplets), tempo change, key signature, transpose, etc. The KL-4M unit includes D to A converter and amplifier (add your own speaker).
KL-4M Music Board with VMM Program — $59.90

commodore

CBM-PET SPECIALS

FREE — Up to $375 free merchandise with purchase of one of following CBM-PET items:

		FREE
8032 32K - 80 Column CRT	$1795	375
8050 Dual Disk Drive - 950,000 bytes	1795	375
4016 Full Size Graphics Keyboard	995	170
4032 Full Size Graphics Keyboard	1295	260
8096 96K - 80 Column CRT		
2040/4040 Dual Disk Drive - 340K	1295	260
4022 Tractor Feed Printer	795	140
CBM Voice Synthesizer	395	50
C2N External Cassette Deck	95	12
Used CBM/PET Computers		CALL
VIC Personal Computer	300	25

WRITE FOR SYSTEM PRICES

***** EDUCATIONAL DISCOUNTS *****
Buy 2 PET/CBM Computers, receive 1 FREE

WordPro 3+ – 32K CBM, disk, printer	250
WordPro 4+ – 8032, disk, printer	385
OZZ Data Base System for CBM 8032	335
VISICALC for PET or ATARI	170
BPI General Ledger, A/P, A/R for PET/CBM	270
Programmers Toolkit – PET ROM Utilities	34.90
PET Spacemaker II ROM Switch	36.00
2 Meter PET to IEEE or IEEE to IEEE Cable	40.00
Dust Cover for PET	6.90
IEEE-Parallel Printer Interface for PET	110.00
IEEE-RS232 Printer Interface for PET	120.00
The PET Revealed	17.00
Library of PET Subroutines	17.00
Source Hookup over 1000 programs/services	88

DISK SPECIALS

SCOTCH (3M) 5¼"	10/2.85	50/2.75	100/2.65
SCOTCH (3M) 8"	10/2.90	50/2.80	100/2.70
Verbatim 5¼"	10/2.45	50/2.40	100/2.35
(add 1.00 for 5¼" Verbatim plastic storage box)			
Verbatim 8" Dbl. Dens.	10/3.45	50/3.35	100/3.25
BASF 5¼"	10/2.60	20/2.50	100/2.40
BASF 8"	10/2.65	20/2.55	100/2.45

WE STOCK MAXELL DISKS

Diskette Storage Pages		10 for 3.95
Disk Library Cases	8" - 2.85	5" - 2.15

ATARI 800 $745
All Atari Modules 20% OFF

ATARI EDUCATIONAL PLAN — **Write for details.**

A P Products 15% OFF
A P Hobby-Blox 15% OFF

ALL BOOK and SOFTWARE PRICES DISCOUNTED

The 8086 Book (Osborne)	14.00
Z8000 Assembly Language Programming	16.90
PET Personal Computer Guide (Osborne)	12.75
PET and the IEEE-488 Bus (Osborne)	13.60
6502 Assembly Language (Osborne)	14.45
Programming the 6502 (Zaks)	10.45
6502 Applications Book (Zaks)	10.45
6502 Software Cookbook (Scelbi)	9.45
CP/M Handbook (w/ MP/M) Zaks	11.85
Practical BASIC Programs (Osborne)	13.60
Some Common BASIC Programs (Osborne)	12.75

252 Bethlehem Pike
Colmar, PA 18915

215-822-7727 **A B Computers**

WRITE FOR CATALOG.
Add $1.25 per order for shipping. We pay balance of UPS surface charges on all prepaid orders. Prices listed are on cash discount basis. Regular prices slightly higher.

Circle 1 on inquiry card.

7400					
SN7400N	.25			SN74156N	.79
SN7401N	.20			SN74157N	.69
SN7402N	.25	SN7472N	.29	SN74160N	.89
SN7403N	.25	SN7473N	.35	SN74161N	.89
SN7404N	.25	SN7474N	.35	SN74162N	.89
SN7405N	.29	SN7475N	.49	SN74163N	.89
SN7406N	.35	SN7476N	.35	SN74164N	.89
SN7407N	.35	SN7479N	5.00	SN74165N	.89
SN7408N	.29	SN7480N	.50	SN74166N	1.25
SN7409N	.29	SN7482N	.99	SN74167N	2.79
SN7410N	.25	SN7483N	.69	SN74170N	1.95
SN7411N	.29	SN7485N	.89	SN74172N	4.95
SN7412N	.35	SN7486N	.35	SN74173N	1.39
SN7413N	.40	SN7489N	1.75	SN74174N	.99
SN7414N	.69	SN7490N	.49	SN74175N	.89
SN7416N	.29	SN7491N	.59	SN74176N	.79
SN7417N	.29	SN7492N	.45	SN74177N	.79
SN7420N	.25	SN7493N	.45	SN74179N	1.49
SN7421N	.29	SN7494N	.69	SN74180N	.79
SN7422N	.45	SN7495N	.69	SN74181N	2.25
SN7423N	.29	SN7496N	.69	SN74182N	.79
SN7425N	.29	SN7497N	3.00	SN74184N	2.49
SN7426N	.29	SN74100N	1.49	SN74185N	2.49
SN7427N	.25	SN74107N	.35	SN74190N	1.25
SN7428N	.49	SN74109N	.39	SN74191N	1.25
SN7430N	.25	SN74116N	1.95	SN74192N	.89
SN7432N	.29	SN74121N	.39	SN74193N	.89
SN7437N	.25	SN74122N	.55	SN74194N	.89
SN7438N	.40	SN74123N	.59	SN74195N	.69
SN7439N	.25	SN74125N	.49	SN74196N	.89
SN7440N	.20	SN74126N	.49	SN74197N	.89
SN7441N	.89	SN74132N	.75	SN74198N	1.49
SN7442N	.59	SN74136N	.75	SN74199N	1.49
SN7443N	1.10	SN74141N	.99	SN74221N	1.25
SN7444N	1.10	SN74142N	3.25	SN74251N	.99
SN7445N	.89	SN74143N	3.49	SN74276N	1.95
SN7446N	.79	SN74144N	3.49	SN74279N	.79
SN7447N	.69	SN74145N	.79	SN74283N	1.49
SN7448N	.79	SN74147N	1.95	SN74284N	3.95
SN7450N	.20	SN74148N	1.29	SN74285N	3.95
SN7451N	.20	SN74150N	1.25	SN74365N	.69
SN7453N	.20	SN74151N	.69	SN74366N	.69
SN7454N	.20	SN74152N	.69	SN74367N	.69
SN7459A	.25	SN74153N	.79	SN74368N	.69
SN7460N	.20	SN74154N	1.25	SN74390N	1.49
SN7470N	.29	SN74155N	.79	SN74393N	1.49

74LS					
74LS00	.29			74LS192	1.15
74LS01	.29			74LS193	1.15
74LS02	.29	74LS92	.75	74LS194	1.15
74LS03	.29	74LS93	.75	74LS195	1.15
74LS04	.35	74LS95	.99	74LS197	1.19
74LS05	.35	74LS96	1.15	74LS221	1.19
74LS08	.29	74LS107	.45	74LS240	1.95
74LS09	.35	74LS109	.45	74LS241	1.95
74LS10	.29	74LS112	.45	74LS242	1.95
74LS11	.75	74LS113	.49	74LS243	1.95
74LS12	.35	74LS114	.49	74LS244	1.95
74LS13	.59	74LS122	.89	74LS245	2.95
74LS14	.99	74LS123	1.25	74LS247	1.19
74LS15	.35	74LS125	.89	74LS248	1.19
74LS20	.29	74LS126	.55	74LS249	1.19
74LS21	.35	74LS132	.99	74LS251	1.49
74LS22	.35	74LS133	.89	74LS253	.99
74LS26	.35	74LS136	.49	74LS257	.89
74LS27	.35	74LS138	.89	74LS258	.99
74LS28	.35	74LS139	.89	74LS260	.69
74LS30	.29	74LS151	.89	74LS266	.69
74LS32	.35	74LS153	.89	74LS273	1.95
74LS33	.59	74LS154	1.75	74LS279	.75
74LS37	.45	74LS155	1.19	74LS283	1.09
74LS38	.49	74LS156	1.19	74LS290	.99
74LS40	.35	74LS157	.89	74LS293	.99
74LS42	.89	74LS158	.99	74LS298	1.25
74LS47	.89	74LS160	1.15	74LS352	1.29
74LS48	1.15	74LS161	1.15	74LS353	1.29
74LS49	1.15	74LS162	1.15	74LS365	.75
74LS51	.29	74LS163	1.15	74LS366	.75
74LS54	.29	74LS164	1.25	74LS367	.75
74LS55	.29	74LS165	1.25	74LS368	.75
74LS73	.45	74LS168	1.19	74LS373	1.95
74LS74	.45	74LS169	1.19	74LS374	1.95
74LS75	.59	74LS170	2.49	74LS375	.89
74LS76	.45	74LS173	1.39	74LS386	.69
74LS78	.49	74LS174	.99	74LS393	2.49
74LS83	.89	74LS175	.99	74LS399	2.49
74LS85	1.25	74LS181	2.95	74LS670	2.49
74LS86	.45	74LS190	1.25	81LS95	1.95
74LS90	.59	74LS191	1.25	81LS97	1.95

74S					
74S00	.50			74S243	3.25
74S02	.50			74S244	3.25
74S03	.50	74S124	2.49	74S251	1.45
74S04	.55	74S133	.55	74S253	1.45
74S05	.55	74S134	.69	74S257	1.35
74S08	.50	74S135	1.19	74S258	1.35
74S09	.50	74S136	1.75	74S260	.79
74S10	.50	74S138	1.35	74S280	2.95
74S11	.50	74S139	1.35	74S287	4.95
74S15	.50	74S140	1.15	74S288	4.95
74S20	.50	74S151	1.35	74S373	3.49
74S22	.50	74S153	1.35	74S374	3.49
74S30	.50	74S157	1.35	74S387	5.95
74S32	.55	74S158	1.35	74S471	19.95
74S38	.69	74S160	1.95	74S472	19.95
74S40	.55	74S174	1.59	74S473	19.95
74S51	.50	74S175	1.59	74S474	21.95
74S64	.50	74S188	4.95	74S475	21.95
74S65	.50	74S194	1.95	74S570	7.95
74S74	.79	74S195	1.95	74S571	7.95
74S86	.79	74S196	3.95	74S572	19.95
74S112	.79	74S240	2.95	74S573	19.95
74S113	.79	74S241	2.95	74S940	3.15
74S114	.79	74S242	3.25	74S941	3.15

CA–LINEAR					
CA3010H	1.07			CA3089N	3.75
CA3013H	2.15	CA3060N	3.25	CA3096N	3.95
CA3023H	3.25	CA3080H	1.25	CA3130H	1.39
CA3035H	2.48	CA3081N	2.00	CA3140H	1.25
CA3039H	1.35	CA3082N	2.00	CA3160H	1.25
CA3046N	1.30	CA3083N	1.60	CA3401N	.59
CA3059N	3.25	CA3086N	.85	CA3600N	3.50

CD–CMOS					
CD4000	.39			CD 4098	2.49
CD4001	.39			CD4506	.75
CD4002	.39			CD4507	.99
CD4006	1.19	CD4041	1.49	CD4508	3.95
CD4007	.25	CD4042	.99	CD4510	1.39
CD4009	.49	CD4043	.89	CD4511	1.29
CD4010	.49	CD4044	.89	CD4512	1.49
CD4011	.39	CD4046	1.79	CD4514	3.95
CD4012	.25	CD4047	2.50	CD4515	2.95
CD4013	.49	CD4048	1.35	CD4516	1.49
CD4014	1.39	CD4049	.49	CD4518	1.79
CD4015	1.19	CD4050	.69	CD4519	.89
CD4016	.59	CD4051	1.19	CD4520	1.29
CD4017	1.19	CD4052	1.19	CD4526	1.79
CD4018	.99	CD4053	1.19	CD4528	1.79
CD4019	.49	CD4056	2.95	CD4529	1.95
CD4020	1.19	CD4059	9.95	CD4543	2.79
CD4021	1.39	CD4060	1.49	CD4562	11.95
CD4022	1.19	CD4066	.79	CD4566	2.79
CD4023	.29	CD4068	.39	CD4583	2.49
CD4024	.79	CD4069	.45	CD4584	.75
CD4025	.23	CD4070	.55	CD4723	1.95
CD4026	2.95	CD4071	.49	CD4724	1.95
CD4027	.69	CD4072	.49	MC14409	14.95
CD4028	.89	CD4073	.39	MC14410	14.95
CD4029	1.49	CD4075	.39	MC14411	14.95
CD4030	.49	CD4076	1.39	MC14412	11.95
CD4034	3.49	CD4078	.55	MC14419	4.95
CD4035	.99	CD4081	.39	MC14433	13.95
CD4040	1.49	CD4082	.39	MC14538	2.49
		CD4093	.99	MC14541	1.95

A P PRODUCTS

DIP JUMPERS



- Matewith Standard IC Sockets
- Fully Assembled and Tested
- Integral Molded-On Strain Relief
- Line-By-Line Probeability

DipJumpersareused for jumpering within a PC Board; interconnectingbetweenPC Boards, backplanes andmother boards; and interfacing input/output signals.

Part Number	No of contacts	Description	Wire Length	Price
924102-12	14	single end	12"	$1.61
924102-24	14	single end	24"	1.92
92410236	14	single end	36"	2.33
924106-12	14	double end	12"	2.61
924106-24	14	double end	24"	3.02
924106-36	14	double end	36"	3.43
924112-12	16	single end	12"	1.67
924112-24	16	singleend	24"	2.13
924112-36	16	singleend	36"	2.59
924116-12	16	double end	12"	2.83
924116-24	16	doubleend	24"	3.34
92411636	16	double end	36"	3.80
924122-12	24	single end	12"	2.60
92412224	24	single end	24"	3.30
92412236	24	single end	36"	4.00
924126-12	24	double end	12"	4.50
924126-24	24	double end	24"	5.20
924126-36	24	double end	36"	5.90
924132-12	40	single end	12"	4.35
924132-24	40	single end	24"	5.53
924132-36	40	singleend	36"	6.71

DISCRETE LEDS

XC556R	.200"	red	5/$1	MV50	.085"	red	6/$1	XC111R	.190"	red	5/$1
XC556G	.200"	green	4/$1	XC209R	.125"	red	5/$1	XC111G	.190"	green	4/$1
XC556Y	.200"	yellow	4/$1	XC209G	.125"	green	4/$1	XC111Y	.190"	yellow	4/$1
XC556C	.200"	clear	4/$1	XC209Y	.125"	yellow	4/$1	XC111C	.190"	clear	4/$1
XC22R	.200"	red	5/$1	XC526R	.185"	red	5/$1				
XC22G	.200"	green	4/$1	XC526G	.185"	green	4/$1				
XC22Y	.200"	yellow	4/$1	XC526Y	.185"	yellow	4/$1				
MV10B	.170"	red	4/$1	XC526C	.185"	clear	4/$1				

XC556 RED LED, METAL MTG. HDW. 2-6" LEADS.
RL-2 . . $.39 ea. or 3/$1.00

DISPLAY LEDS

C.A. — Common Anode C.C. — Common Cathode

Type	Polarity	Ht	Price	Type	Polarity	Ht	Price
MAN 1	C.A.—red	.270	2.95	DLG507	C.A.—green	.500	1.25
MAN 2	5x7 D.M.—red	.300	4.95	DL704	C.C.—red	.300	1.25
MAN 3	C.C.—red	.125	.25	DL707	C.A.—red	.300	1.25
MAN 52	C.A.—green	.300	1.25	DL728	C.C.—red	.500	1.49
MAN 54	C.C.—green	.300	1.25	DL741	C.A.—red	.600	1.25
MAN 71	C.A.—red	.300	.75	DL746	C.A.—red ± 1	.630	1.49
MAN 72	C.A.—red	.300	.75	DL747	C.A.—red	.600	1.49
MAN 74	C.C.—red	.300	1.25	DL750	C.C.—red	.600	1.49
MAN 82	C.A.—yellow	.300	.49	DLO847	C.A.—orange	.800	1.49
MAN 84	C.C.—yellow	.300	.99	DLO850	C.C.—orange	.800	1.49
MAN 3620	C.A.—orange	.300	.49	DL33B	C.C.—red	.110	.35
MAN 3630	C.A.—orange ± 1	.300	.99	FND358	C.C. ± 1	.357	.99
MAN 3640	C.C.—orange	.300	.99	FND359	C.C.	.357	.75
MAN 4610	C.A.—orange	.400	.99	FND503	C.C. (FND500)	.500	.99
MAN 6610	C.A.—orange—DD	.560	.99	FND507	C.A. (FND510)	.500	.99
MAN 6630	C.A.—orange ± 1	.560	.99	HDSP-3401	C.A.—red	.800	1.50
MAN 6640	C.C.—orange—DD	.560	.99	HDSP-3403	C.C.—red	.800	1.50
MAN 6650	C.C.—orange ± 1	.560	.99	5082-7751	C.A.,R.H.D.—red	.430	1.25
MAN 6660	C.A.—orange	.560	.99	5082-7760	C.C.,R.H.D.—red	.430	1.75
MAN 6710	C.A.—red—DD	.560	.99	5082-7300	4x7sgl.dig. RHD	.600	22.00
MAN 6750	C.C.—red ± 1	.560	.99	5082-7302	4x7 sgl. dig. LHD	.600	22.00
MAN 6780	C.C.—red	.560	.99	5082-7304	Overnge. char. (± 1)	.600	19.95
DLO304	C.C.—orange	.300	1.25	4N28	Photo XsistorOpto-Isol.		.99
DLO307	C.A.—orange	.300	1.25	LIT-1	Photo Xsistor Opto-Isol.		.69
DLG500	C.C.—green	.500	1.25	MOC3010	Optically Isol.Triac Driver		1.25

SOCKETS — Test TEXTOOL Sockets — RECEPTACLES

ZERO INSERTION FORCE

- Nickel Boron Plating
- G.F. PSF Plastic Body
- For testing IC's

Part No.	Pins	Price	Part No.	Pins	Price
214-3339	14 pin	5.95	222-3343	22 pin	9.95
216-3340	16 pin	6.49	224-3344	24 pin	9.75
218-3341	18 pin	7.95	228-3345	28 pin	11.95
220-3342	20 pin	8.95	240-3346	40 pin	12.95

- Nickel Boron Plating
- G.F. PSF Plastic Body
- Wire Wrap Contacts

Part No.	Pins	Price	Part No.	Pins	Price
214-3592	14 pin	9.75	222-3596	22 pin	12.95
216-3593	16 pin	9.95	224-3597	24 pin	12.75
218-3594	18 pin	10.95	228-3598	28 pin	13.95
220-3595	20 pin	11.95	240-3599	40 pin	15.95

LOW PROFILE (TIN) SOCKETS

	1-24	25-49	50-100
8 pin LP	.17	.16	.15
14 pin LP	.20	.19	.18
16 pin LP	.22	.21	.20
18 pin LP	.29	.28	.27
20 pin LP	.34	.32	.30
22 pin LP	.37	.36	.35
24 pin LP	.38	.37	.36
28 pin LP	.45	.44	.43
36 pin LP	.60	.59	.58
40 pin LP	.63	.62	.61

SOLDERTAIL STANDARD (TIN)

	1-24	25-49	50-100
14 pin ST	.27	.25	.24
16 pin ST	.30	.27	.25
18 pin ST	.35	.32	.30
24 pin ST	.49	.45	.42
28 pin ST	.99	.90	.81
36 pin ST	1.39	1.26	1.15
40 pin ST	1.59	1.45	1.30

SOLDERTAIL (GOLD) STANDARD

	1-24	25-49	50-100
8 pin SG	.39	.35	.31
14 pin SG	.49	.45	.41
16 pin SG	.54	.49	.44
18 pin SG	.59	.53	.48
24 pin SG	.79	.75	.69
28 pin SG	1.10	1.00	.90
36 pin SG	1.65	1.40	1.26
40 pin SG	1.75	1.59	1.45

WIRE WRAP SOCKETS (GOLD) LEVEL #3

	1-24	25-49	50-100
8 pin WW	.59	.54	.49
10 pin WW	.69	.63	.58
14 pin WW	.79	.73	.67
16 pin WW	.85	.77	.70
18 pin WW	.99	.90	.81
20pin WW	1.19	1.08	.99
22 pin WW	1.49	1.35	1.23
24 pin WW	1.39	1.26	1.14
28 pin WW	1.69	1.53	1.38
36 pin WW	2.19	1.99	1.79
40 pin WW	2.29	2.09	1.89

1/4 WATT RESISTOR ASSORTMENTS – 5%

ASST. 1	5ea.	10 Ohm 27 Ohm	12 Ohm 33 Ohm	15 Ohm 39 Ohm	18 Ohm 47 Ohm	22 Ohm 56 Ohm	50pcs.	$1.95
ASST. 2	5ea.	68 Ohm 180 Ohm	82 Ohm 220 Ohm	100 Ohm 270 Ohm	120 Ohm 330 Ohm	150 Ohm 390 Ohm	50pcs.	$1.95
ASST. 3	5ea.	470 Ohm 1.2K	560 Ohm 1.5K	680 Ohm 1.8K	820 Ohm 2.2K	1K 2.7K	50pcs.	$1.95
ASST. 4	5ea.	3.3K 8.2K	3.9K 10K	4.7K 12K	5.6K 15K	6.8K 18K	50pcs.	$1.95
ASST. 5	5ea.	22K 56K	27K 68K	33K 82K	39K 100K	47K 120K	50pcs.	$1.95
ASST. 6	5ea.	150K 390K	180K 470K	220K 560K	270K 680K	330K 820K	50pcs.	$1.95
ASST. 7	5ea.	1M 2.7M	1.2M 3.3M	1.5M 3.9M	1.8M 4.7M	2.2M 5.6M	50pcs.	$1.95

ASST. 8R Includes Resistor Assts. 1-7 (350 pcs.) $10.95 ea.

$10.00 Min. Order — U.S. Funds Only
Calif. Residents Add 6% Sales Tax
Postage—Add 5% plus $1 Insurance

Spec Sheets — 25¢
Send 52¢ Postage for your
FREE 1981 JAMECO CATALOG

NEW 1981 CATALOG

Jameco ELECTRONICS

PHONE ORDERS WELCOME (415) 592-8097

MAIL ORDER ELECTRONICS — WORLDWIDE
1355 SHOREWAY ROAD, BELMONT, CA 94002
PRICES SUBJECT TO CHANGE

7/81

INTERSIL

Part No.	Function		Price
7045IPI	CMOS Precision Timer		14.95
7045EV/Kit*	Stopwatch Chip, XTL		22.95
7106CPL	3½ Digit A/D (LCD Drive)		16.95
7106EV/Kit*	IC, Circuit Board, Display		34.95
7107CPL	3½ Digit A/D (LED Drive)		15.95
7107EV/Kit*	IC, Circuit Board, Display		28.95
7116CPL	3½ Digit A/D LCD Dis. HLD.		18.95
7117CPL	3½ Digit A/D LED Dis. HLD.		17.95
7201IDR	Low Battery Volt Indicator		2.25
7205IPG	CMOS LED Stopwatch/Timer		12.95
7205EV/Kit*	Stopwatch Chip, XTL		19.95
7206CJPE	Tone Generator		5.15
7206CEV/Kit*	Tone Generator Chip, XTL		9.95
7207AIPD	Oscillator Controller		6.50
7207AEV/Kit*	Freq. Counter Chip, XTL		11.10
7208IPI	Seven Decade Counter		17.95
7209IPA	Clock Generator		3.95
7215IPG	4 Func. CMOS Stopwatch CKT		13.95
7215EV/Kit*	4 Func. Stopwatch Chip, XTL		19.95
7216AIJI	8-Digit Univ. Counter C.A.		32.00
7216CIJI	8-Digit Freq. Counter C.A.		26.95
7216DIPI	8-Digit Freq. Counter C.C.		21.95
7217IJI	4-Digit LED Up/Down Counter		12.95
7218CIJI	8-Digit Univ. LED Drive		10.95
7224IPL	LCD 4½ Digit Up Counter DRI		11.25
7226AIJL	8-Digit Univ. Counter		31.95
7226AEV/Kit*	5 Function Counter Chip, XTL		74.95
7240IJE	CMOS Bin Prog. Timer/Counter		4.95
7242IJA	CMOS Divide-by-256 RC Timer		2.05
7250IJE	CMOS BCD Prog. Timer/Counter		6.00
7260IJE	CMOS BCD Prog. Timer/Counter		5.25
7555IPA	CMOS 555 Timer (8 pin)		1.45
7556IPD	CMOS 556 Timer (14 pin)		2.20
7611BCPA	CMOS Op Amp Comparator	5MV	2.25
7612BCPA	CMOS Op Amp Ext. Cmvr.	5MV	2.95
7621BCPA	CMOS Dual Op Amp Comp.	5MV	3.95
7631CCPE	CMOS Tri Op Amp Comp.	10MV	5.36
7641CCPD	CMOS Quad Op Amp Comp.	10MV	7.50
7642CCPD	CMOS Quad Op Amp Comp.	10MV	7.50
7660CPA	Voltage Converter		2.95
8038CCPD	Waveform Generator		4.95
8048CCPE	Monolithic Logarithmic Amp		21.60
8069CCQ	50ppm Band—GAP Volt Ref. Diode		2.50
8211CPA	Volt Ref/Indicator		2.50
8212CPA	Volt Ref/Indicator		2.50

74C					
74C00	.39			74C195	1.59
74C02	.39			74C221	1.95
74C04	.39			74C240	2.25
74C08	.39	74C106	.75	74C244	2.25
74C10	.39	74C107	1.89	74C373	2.49
74C14	.75	74C151	2.95	74C374	2.59
74C20	.39	74C154	3.95	74C901	.89
74C30	.39	74C157	2.25	74C903	1.15
74C42	1.39	74C160	1.69	74C911	10.95
74C48	1.95	74C161	1.60	74C912	10.95
74C73	.79	74C162	1.49	74C915	1.69
74C74	.79	74C163	1.69	74C917	10.95
74C85	1.95	74C164	1.59	74C922	5.49
74C86	.99	74C173	1.39	74C923	5.75
74C89	6.95	74C174	1.39	74C925	7.50
74C90	1.29	74C175	1.39	74C926	7.50
74C93	1.29	74C192	1.69	80C95	.79
74C95	1.59	74C193	1.69	80C97	.79

LINEAR					
LH0002CN	6.85			LM702H	.79
LM10CLH	4.50			LM703CN	.89
LM11CLH	4.75	LM340T-5	1.25	LM709N	.49
LH0070-OH	6.05	LM340T-12	1.25	LM710N	.79
TL071CP	.79	LM340T-15	1.25	LM711N	.79
TL072CP	1.39	LM341P-5	.75	LM723N	.69
TL074CN	2.49	LM341P-12	.75	LM733N/H	1.00
LH0082CD	35.80	LM341P-15	.75	LM739N	1.19
TL082CP	1.19	LM342P-5	.69	LM741CN	.35
TL084CN	2.19	LM342P-12	.69	MC1741SCG	3.00
LH0094CD	36.80	LM342P-15	.69	LM747N/H	.79
LM300H	.99	LM348N	1.25	LM748N/H	.59
LM301CN/H	.35	LM350K	5.75	LM1014N	2.75
LM302H	1.95	LF351N	.60	LM1310N	1.95
LM304H	1.95	LF353N	1.00	LM1458CN	.59
LM305H	.99	LF355N	1.10	LM1488N	1.25
LM307CN/H	.45	LF356N	1.10	LM1489N	1.25
LM308CN/H	1.00	LM358N	1.00	LM1496N	1.95
LM309H	1.95	LM359N	1.79	LM1556V	1.75
LM309K	1.25	LM370N	4.49	LM1800N	2.95
LM310CN	1.75	LM373N	3.25	LM1877N-9	3.25
LM311H/CN	.90	LM377N	2.95	LM1889N	3.20
LM312H	2.49	LM380N	1.25	LM1896N	1.75
LM317MP	1.15	LM381N	1.95	LM2002T	1.49
LM317T	1.75	LM382N	1.79	LM2877P	2.05
LM317K	3.95	LM384N	1.95	LM2878P	2.25
LM318CN/H	1.95	LM386N-3	1.29	LM2896P-1	2.25
LM319N	1.95	LM387N	1.45	LM3189N	2.95
LM320K-5	1.35	LM389N	1.35	LM3900N	.69
LM320K-12	1.35	LM392N	.69	LM3905CN	1.25
LM320K-15	1.35	LF398N	4.00	LM3909N	1.15
LM320T-5	1.25	LM399H	5.00	LM3914N	3.95
LM320T-12	1.25	TL494CN	4.49	LM3915N	3.95
LM320T-15	1.25	TL496CP	1.75	LM3916N	3.95
LM323K-5	5.95	NE510A	6.00	RC4136N	1.25
LM324N	.99	NE529A	4.95	RC4151NB	3.95
LM329DZ	.65	NE531H	3.95	RC4194TK	5.95
LM331N	3.95	NE536H	6.00	RC4195TK	5.49
LM334Z	1.30	NE540H	6.00	KB4428	4.25
LM335Z	1.40	NE544N	4.95	KB4429	5.95
LM336Z	1.75	NE550A	1.30	LM4500A	3.25
LM337T	1.95	NE555V	.39	ICL8038B	4.95
LM337MP	1.15	LM556N	.99	LM13080N	1.29
LM338K	6.95	NE564N	3.95	LM13600N	1.49
LM339N	.99	LM565N	1.25	75138N	1.95
LM340K-5	1.35	LM566CN	1.95	75450N	.89
LM340K-12	1.35	LM567V	1.25	75451CN	.39
LM340K-15	1.35	NE570N	4.95	75492	.89

CAPACITOR CORNER

50 VOLT CERAMIC DISC CAPACITORS

Value	1-9	10-99	100+	Value	1-9	10-99	100+
10 pf	.08	.06	.05	.001µF	.08	.06	.05
22 pf	.08	.06	.05	.0047µF	.08	.06	.05
47 pf	.08	.06	.05	.01µF	.08	.06	.05
100 pf	.08	.06	.05	.022µF	.09	.07	.06
220 pf	.08	.06	.05	.047µF	.09	.07	.06
470 pf	.08	.06	.05	.1µF	.15	.12	.10

100 VOLT MYLAR FILM CAPACITORS

.001mf	.12	.10	.07	.022mf	.13	.11	.08
.0022mf	.12	.10	.07	.047mf	.21	.17	.13
.0047mf	.12	.10	.07	.1mf	.27	.23	.17
.01mf	.12	.10	.07	.22mf	.33	.27	.22

+20% DIPPED TANTALUMS (Solid) CAPACITORS

.1/35V	.39	.34	.29	1.5/35V	.41	.37	.29
.15/35V	.39	.34	.29	2.2/35V	.51	.45	.34
.22/35V	.39	.34	.29	3.3/25V	.53	.47	.37
.33/35V	.39	.34	.29	4.7/25V	.63	.56	.45
.47/35V	.39	.34	.29	6.8/25V	.79	.69	.55
.68/35V	.39	.34	.29	15/25V	1.39	1.25	.95
1.0/35V	.39	.34	.29	22/6V	.79	.69	.55

MINI. ALUMINUM ELECTROLYTIC CAPACITORS

Axial	1-99	100-499	500+	Radial	1-99	100-499	500+
.47/50V	.16	.14	.10	.47/25V	.15	.13	.12
1.0/50V	.19	.16	.12	.47/50V	.16	.14	.13
3.3/50V	.17	.15	.11	1.0/16V	.15	.13	.12
4.7/25V	.18	.15	.11	1.0/25V	.16	.14	.13
10/25V	.18	.15	.11	1.0/50V	.17	.15	.14
10/50V	.19	.16	.12	4.7/16V	.15	.13	.12
22/25V	.19	.16	.12	4.7/25V	.16	.14	.13
22/50V	.24	.20	.18	4.7/50V	.17	.15	.14
47/25V	.25	.21	.19	10/16V	.15	.13	.12
47/50V	.29	.25	.23	10/25V	.16	.14	.13
100/25V	.28	.24	.22	10/50V	.17	.15	.14
100/50V	.41	.37	.34	47/50V	.25	.21	.19
220/25V	.39	.34	.33	100/16V	.21	.17	.14
220/50V	.49	.45	.41	100/25V	.25	.23	.21
470/25V	.54	.49	.45	100/50V	.37	.34	.31
1000/16V	.79	.69	.61	220/16V	.25	.21	.19
2200/16V	.89	.79	.69	470/25V	.35	.31	.27

Circle 195 on inquiry card.

National Semiconductor Clock Modules



12VDC AUTOMOTIVE/ INSTRUMENT CLOCK

APPLICATIONS:
- In-dash autoclocks
- After-market auto/ RV clocks
- Aircraft-marine clks.
- 12VDC oper. instru.
- Portable/battery powered instrumnts.

Features: Bright 0.3" green display. Internal crystal time-base. ± 0.5 sec./day accur. Auto.display brightness control logic. Display color filterable to blue, blue-green, green & yellow. Complete—just add switches and lens.

MA1003 Module $16.95

CLOCK MODULES

MA1023	.7" Low Cost Digital LED Clock Module	8.95
MA1026	.7" Dig. LED Alarm Clock/Thermometer	18.95
MA5036	.3" Low Cost Digital LED Clock/Timer	6.95
MA1002	.5" LED Display Dig. Clock & Xformer	9.95

TRANSFORMERS

102-P20	Xformer for MA1023 Clock Modules	3.49
102-P22	Xformer for MA1026 Clock Modules	3.49
102-P20	Xformer for MA5036 Clock Modules	3.49

Transistor Checker



The *ASI Transistor Checker* is capable of checking a wide range of transistor types, either "In circuit" or out of circuit. It has been specially designed to take advantage of the newest concept of dynamic testing under current amplifier conditions. To operate, simply plug the transistor to be checked into the front panel socket, or connect it with the alligator clip test leads providad. No preliminary set-up is needed. The unit safely and automatically identifies low, medium and high-power PNP and NPN transistors. The ASI Transistor Checker also permits matching similar transistors in actual operating circuits, and provides a reliable GD/NO-GD test at practical collector currents (from 5mA on small signal types to 50mA and more on power types.) Match similar type transistors by observing and comparing dial readings; the higher the reading, the higher the gain. Completely assembled — battery operated. ("C" cell battery not included.)

CLOSE-OUT

Trans-Check $9.95

EPROM Erasing Lamp

- Erases 2708, 2716, 1702A, 5203Q, 5204Q, etc.
- Erases up to 4 chips within 20 minutes.
- Maintains constant exposure distance of one inch.
- Special conductive foam liner eliminates static build-up.
- Built-in safety lock to prevent UV exposure.
- Compact — only 7-5/8" x 2-7/8" x 2"
- Complete with holding tray for 4 chips.

UVS-11E $79.95

JOYSTICKS

JS-5K



JVC-40

JS-5K	5K Linear Taper Pots	$5.25
JS-100K	100K Linear Taper Pots	$4.95
JVC-40	40K (2) Video Controller in case ...	$5.95

6-Digit Clock Kit

- Bright .300 ht. comm. cathode display
- Uses MM5314 clock chip
- Switches for hours, minutes and hold modes
- Hrs. easily viewable to 20 ft.
- Simulated walnut case
- 115 VAC operation
- 12 or 24 hr. operation
- Incl. all components, case & wall transformer
- Size: 6¾" x 3-1/8" x 1¾"

JE701 .... $19.95

NEW! JE215 Adjustable Dual Power Supply

General Description: The JE215 is a Dual Power Supply with independent adjustable positive and negative output voltages. A separate adjustment for each of the supplies provides the user unlimited applications for IC current voltage requirements. The supply can also be used as a general all-purpose variable power supply.



FEATURES:
- Adjustable regulated power supplies, pos. and neg. 1.2VDC to 15VDC.
- Power Output (each supply): 5VDC @ 500mA, 10VDC @ 750mA, 12VDC @ 500mA, and 15VDC @ 175mA.
- Two, 3-terminal adj. IC regulators with thermal overload protection.
- Heat sink regulator cooling
- LED "on" indicator
- Printed Board Construction
- 120VAC input
- Size: 3-1/2"w x 5-1/16"L x 2"H

JE215 Adj. Dual Power Supply Kit (as shown) . . $24.95

(Picture not shown but similar in construction to above)

JE200 Reg. Power Supply Kit (5VDC, 1 amp) . .	$14.95
JE205 Adapter Brd. (to JE200) ±5, ±9 & ± 12V.	$12.95
JE210 Var. Pwr. Sply. Kit, 5-15VDC, to 1.5amp.	$19.95

MICROPROCESSOR COMPONENTS

8080A/8080A SUPPORT DEVICES

INS8080A	CPU	6.50
DP8212	8-Bit Input/Output	3.25
DP8214	Priority Interrupt Control	5.95
DP8216	Bi-Directional Bus Driver	3.49
DP8224	Clock Generator/Driver	3.95
DP8226	Bus Driver	3.49
DP8228	System Controller/Bus Driver	4.95
DP8238	System Controller	5.95
INS8243	I/O Expander for 48 Series	9.95
INS8250	Asynchronous Comm. Element	16.95
DP8251	Prog. Comm. I/O (USART)	7.95
DP8253	Prog. Interval Timer	14.95
DP8255	Prog. Peripheral I/O (PPI)	9.95
DP8257	Prog. DMA Control	19.95
DP8259	Prog. Interrupt Control	14.95
DP8275	Prog. CRT Controller	49.95
DP8279	Prog. Keyboard/Display Interface	19.95
DP8300	Octal Bus Receiver	6.95
DP8303	System Timing Element	6.95
DP8304	8-Bit Bi-Directional Receiver	3.95
DP8307	8-Bit Bi-Directional Receiver	3.95
DP8308	8-Bit Bi-Directional Receiver	3.95

6800/6800 SUPPORT DEVICES

MC6800	MPU	14.95
MC6802CP	MPU with Clock and RAM	19.95
MC6810API	128x8 Static RAM	4.95
MC6821	Peripheral Inter. Adapt (MC6820)	7.49
MC6828	Priority Interrupt Controller	10.95
MC6830L8	1024x8-Bit ROM (MC68A30-8)	14.95
MC6850	Asynchronous Comm. Adaptar	6.95
MC6852	Synchronous Serial Data Adapter	6.95
MC6860	0-600bps Digital MODEM	10.95
MC6862	2400bps Modulator	12.95
MC6880A	Quad 3-State Bus. Trans. (MC8T26)	2.25

MICROPROCESSOR CHIPS

Z80 (780C)	CPU (MK3880N) (2MHz)	13.95
Z80A (780-1)	CPU (MK3880N-4) (4MHz)	15.95
CDP1802	CPU	19.95
2650	MPU	16.95
IDM2901ADC	CPU—4-Bit Slice (Com. Temp. Grade)	19.95
MCS6502	MPU w/Clock (65K Bytes Memory)	11.95
INS8035N 6	MPU—8-Bit (6MHz)	16.95
INS8039N-6	CPU—Sgl. Chip 8-Bit (128 bytes RAM)	19.95
INS8040N-6	CPU (256 Bytes RAM)	24.95
INS8070N	CPU—64 Bytes RAM	24.95
INS8073N	CPU w/Basic Micro Interpreter	29.95
P8085	CPU	19.95
INS8900	CPU—16-Bit	29.95
TMS9900JL	MPU—16-Bit	49.95

SHIFT REGISTERS

MM500H	Dual 25-Bit Dynamic	.50
MM503H	Dual 50-Bit Dynamic	.50
MM506H	Dual 100-Bit Static	.50
MM510H	Dual 64-Bit Accumulator	.50
MM1402	256-Bit Dynamic	3.95
MM5013	1024-Bit Dynamic/Accumulator	1.95
MM5016H	500/512-Bit Dynamic	.89
MM5034N	Octal 80-Bit	9.95
MM5035N	Octal 80-Bit	9.95
2504V(1404A)	1024-Bit Dynamic	3.95
2518N	Hex 32-Bit Static	4.95
2522V	Dual 132-Bit Static	2.95
2524V	512-Bit Dynamic	.99
2525V	1024-Bit Dynamic	2.95
2527V	Dual 256-Bit Static	2.95
2528V	Dual 250-Bit Static	4.00
2529V	Dual 240-Bit Static	4.00
2532N	Quad 80-Bit Static	2.95
3341PC	Fifo (Dual 80)	6.95

DATA ACQUISITION

AF100-1CN	Universal Active Filter 2.5%	5.95
AF121-1CJ	Touch Tone Low pass Filter	19.95
AF122-1CJ	Touch Tone Low pass Filter	19.95
LM308AH	Super Gain Op Amp	1.00
LM334Z	Constant Current Source	1.30
LM335Z	Temperature Transducer	1.40
LF356N	JFET Input Op Amp	1.10
LF398N	Sample & Hold Amplifiers	3.95
LM399H	Temp. Comp. Prec. Ref. (.5pPm/C°)	4.95
ADC0804LCN	8-Bit A/D Converter (1 LSB)	4.95
DAC0806LCN	8-Bit D/A Converter (0.78% Lin.)	2.25

DATA ACQUISITION (CONTINUED)

ADC0809CCN	8-Bit A/D Converter (8-Ch. Multi.)	5.25
ADC0817CCN	8-Bit A/D Converter (16-Ch. Multi.)	10.95
DAC1000LCN	10-Bit D/A Conv. Micro. Comp. (0.05%)	13.95
DAC1008LCN	10-Bit D/A Conv. Micro. Comp. (0.20%)	8.95
DAC1020LCN	10-Bit D/A Converter (0.05% Lin.)	8.49
DAC1022LCN	10-Bit D/A Converter (0.20% Lin.)	5.95
DAC1222LCN	12-Bit D/A Converter (0.20 Lin.)	9.95
CD4051N	8-Channel Multiplexer	1.19
AY-5-1013	30K BAUD UART	5.95

RAM'S

1101	256x1 Static	1.49
1103	1024x1 Dynamic	.99
2101 (8101)	256x4 Static	3.95
2102	1024x1 Static	1.75
21L02	1024x1 Static	1.95
2111 (8111)	256x4 Static	3.95
2112	256x4 Static MOS	4.95
2114	1024x4 Static 450ns	5.95
2114L	1024x4 Static 450ns Low Power	6.95
2114-3	1024x4 Static 300ns	7.49
2114L-3	1024x4 Static 300ns Low Power	7.95
2117	16,384x1 Dynamic 550ns (housemarked)	4.95
4116N-4 (UPD416)	16K Dynamic 250ns (MM5290N-4)	3.95
4164	64K Dynamic 250ns	49.95
MM2147J	4096x1 Fast 70ns	19.95
5101	256x4 Static	7.95
MM5261	1024x1 Dynamic Fully Decoded	.99
MM5262	2Kx1 Dynamic	.25
MM5280/2107	4096x1 Dynamic	4.95
MM5290N-2 (4116)	16K Dynamic 150ns (UPD416C-3)	5.25
MM5298J-3A	8K Dyn. 200ns (lower ½ of MM5290J)	4.95
MM5799NAA/N	Controller Oriented Processor	9.95
UPD414/MK4027	4K Dynamic 16-Pin	4.95
TMS4044-45NL	4K Static	14.95
TMS4045	1024x4 Static	14.95

PROMS/EPROMS

1702A	2K UV Erasable PROM	5.95
2708	8K EPROM	5.95
TMS2716	16K EPROM (-5V, +5V, +12V)	19.95
2716 Intel (2516) TI	16K EPROM (Single +5V)	10.95
2732 Intel (2532) TI	32K EPROM	19.95
2758	8K EPROM (450ns) (Single +5V)	7.95
5203	2048 PROM	14.95
82S23 (74S188)	32x8 PROM (Open Collector)	4.95
82S115	4096 Bipolar PROM	19.95
82S123 (74S288)	32x8 Tri-State Bipolar PROM	4.95
82S185	8K PROM	29.95

ROM'S

2513 (2140)	Character Generator (Upper Case)	9.95
2513 (3021)	Character Generator (Lower Case)	9.95
2516N	Character Generator	10.95
MM5230N	2048-Bit Read Only Memory	1.95

NMOS READ ONLY MEMORIES

MCM66710P	128x9x7 ASCII Shifted w/Greek	13.50
MCM66740P	128x9x7 Math Symbol & Pictures	13.50
MCM66750P	128x9x7 Alpha. Control Char. Gen.	13.50

MICROPROCESSOR MANUALS

M-Z80	User Manual	7.50
M-CDP1802	User Manual	7.50
M-2650	User Manual	5.00

SPECIAL FUNCTION

DS0025CN	Dual MOS Clock Driver (5MZ)	3.50
DS0026CN	Dual MOS Clock Driver (5MZ)	1.95
INS1771N-1	Floppy Disc Controller	24.95
INS2651N	Communication Chip	19.95
MM58167N	Microprocessor Real Time Clock	8.95
MM58174N	Microprocessor Compatible Clock	11.95
COP402N	Microcontroller with 64-Digit RAM and Direct LED Drive	6.95
COP402MN	Microcontroller with 64-Digit RAM & Direct LED Drive w/N Buss Int.	7.49
COP470N	32-Seg. VAC Fluor. Driver (20-pin pkg.)	3.25

TELEPHONE/KEYBOARD CHIPS

AY-5-9100	Push Button Telephone Dialer	14.95
AY-5-9200	Repertory Dialer	14.95
AY-5-9500	CMOS Clock Generator	4.95
AY-5-2376	Keyboard Encoder (88 keys)	11.95
HD0165-5	Keyboard Encoder (16 keys)	7.95
74C922	Keyboard Encoder (16 keys)	5.49
74C923	Keyboard Encoder (20 keys)	5.75
MM53190N	Push Button Pulse Dialer	7.95
MM57499N	96/144-Key Serial Keyboard Encoder	8.95

ELECTRONIC TOY MOTORS

Typical Power Source	Operating Voltage Range	Voltage	NO LOAD Speed RPM	NO LOAD Current AMP	AT MAXIMUM EFFICIENCY Speed RPM	AT MAXIMUM EFFICIENCY Current AMP	AT MAXIMUM EFFICIENCY Torque OZ. IN.	AT MAXIMUM EFFICIENCY Output W	AT MAXIMUM EFFICIENCY Eff. %	SMALL TORQUE OZ. IN.
DRY CELL	1.5-6.0	3.0	9,200	0.20	6,750	0.90	0.260	1.30	57.0	0.97

.937 O.D. X 1.201 Length

MABUCHI RE280 $.99 each . . . 10/$7.50 . . . 100/$50.00

DESIGNERS' SERIES
Blank Desk-Top Electronic Enclosures



CONSTRUCTION:
The "DTE" Blank Desk Top Electronic Enclosures are designed to blend and complement today's modern computer equipment and can be used in both industrial and home. The end pieces are precision molded with an internal slot (all around) to accept both top and bottom panels. The panels are then fastened to ¼" thick tabs inside the end pieces to provide maximum rigidity to the enclosure. For ease of equipment servicing, the rear/bottom panel slides back on slotted tracks while the rest of the enclosure remains intact. Different panel widths may be used while maintaining a common profile outline. The molded end pieces can also be painted to match any panel color scheme.



Enclosure Model No.	Panel Width	PRICE
DTE-8	8.00"	$29.95
DTE-11	10.65"	$32.95
DTE-14	14.00"	$34.95

$10.00 Min. Order — U.S. Funds Only
Calif. Residents Add 6% Sales Tax
Postage—Add 5% plus $1 Insurance

Spec Sheets — 25¢
Send 52¢ Postage for your FREE 1981 JAMECO CATALOG

NEW 1981 CATALOG

Jameco ELECTRONICS

PHONE ORDERS WELCOME (415) 592-8097

MAIL ORDER ELECTRONICS — WORLDWIDE
1355 SHOREWAY ROAD, BELMONT, CA 94002
PRICES SUBJECT TO CHANGE

7/81

Bourns Potentiometer



3/4 Watt Single Turn
(TOP ADJUSTMENT)

Values: 500Ω 1K 2.5K 5K 10K 25K 50K 100K 250K 500K 5Meg

INDIVIDUAL PRICING:

1-49	50-99	100-999	1K-up
.19	.17	.15	.12

GB174 ...... $1.95/lot
(25 pieces all 11 asst. values)

To order: Specify Bourns 3355 — (Value desired)

AC and DC Wall Transformers

Ideal for use with clocks, games, power supplies or any other type of AC or DC application.

Part No.	Input	Output	Price
AC 250	117V/60Hz	12 VAC 250mA	$3.95
AC 500	117V/60Hz	12 VAC 500mA	$4.95
AC1000	117V/60Hz	12 VAC 1 amp	$5.95
AC1700	117V/60Hz	9 VAC 1.7 amp	$6.95
DV 9200	117V/60Hz	9 VDC 200mA	$3.25
DC 900	120V/60Hz	9 VDC 500mA	$3.95

CONNECTORS

DB25P	D-Subminiature Plug	$2.95
DB25S	D-Subminiature Socket	$3.50
DB51226	Cover for DB25P/S	$1.75
22/44SE	P.C. Edge (22/44 Pin)	$2.95
UG88/U	BNC Plug	$1.79
UG89/U	BNC Jack	$3.79
UG175/U	UHF Adapter	$ .49
SO239	UHF Panel Recp.	$1.29
PL258	UHF Adapter	$1.60
PL259	UHF Plug	$1.60
UG260/U	BNC Plug	$1.79
UG1094/U	BNC Bulkhead Recp.	$1.29

TRS-80 16K Conversion Kit

Expand your 4K TRS-80 System to 16K.
Kit comes complete with:
★8 ea. MM5290 (UPD416/4116) 16K Dyn. Rams (*NS)
★ Documentation for Conversion

TRS-16K2 *150NS	$39.95
TRS-16K4 *250NS	$29.95

JE610 ASCII Encoded Keyboard Kit

The JE610 ASCII Keyboard Kit can be interfaced into most any computer system. The kit comes complete with an industrial grade keyboard switch assembly (62-keys), IC's, sockets, connector, electronic components and a double-sided printed wiring board. The keyboard assembly requires +5V @ 150mA and −12V @ 10 mA for operation. Features: 60 keys generate the 126 characters, upper and lower case ASCII set. Fully buffered. Two user-define keys provided for custom applications. Caps lock for upper-case-only alpha characters. Utilizes a 2376 (40-pin) encoder read-only memory chip. Outputs directly compatible with TTL/DTL or MOS logic arrays. Easy interfacing with a 16-pin dip or 18-pin edge connector. Size: 3½"H x 14½"W x 8¾"D

JE610/DTE-AK (After assembled as pictured above) ... **$124.95**

JE610 Kit 62-Key Keyboard, PC Board, & Components (no case) ..... **$ 79.95**
K62 62-Key Keyboard (Keyboard only) ... **$ 34.95**
DTE-AK (case only — 3¼"Hx11"Wx8¾"D) **$ 49.95**

NEW! JE212 — Negative 12VDC Adapter Board Kit for JE610 ASCII KEYBOARD KIT
Provides -12VDC from incoming 5VDC . . $9.95

JE600 Hexadecimal Encoder Kit

FULL 8-BIT LATCHED OUTPUT 19-KEY KEYBOARD

The JE600 Encoder Keyboard Kit provides two separate hexadecimal digits produced from sequential key entries to allow direct programming for 8-bit microprocessor or 8-bit memory circuits. Three additional keys are provided for user operations with one having a bistable output available. The outputs are latched and monitored with 9 LED readouts. Also included is a key entry strobe. Features: Full 8-bit latched output for microprocessor use. Three user-define keys with one being bistable operation. Debounce circuit provided for all 19 keys. 9 LED readouts to verify entries. Easy interfacing with standard 16-pin IC connector. Only +5VDC required for operation. Size: 3½"H x 8¼"W x 8¾"D

JE600/DTE-HK (After assembled as pictured above) **$99.95**

JE600 Kit 19-Key Hexadec. Keyboard, PC Board & Cmpnts. (no case) . . **$59.95**
K19 19-Key Keyboard (Keyboard only) **$14.95**
DTE-HK (case only —3½"Hx8¼"Wx8¾"D) **$44.95**

Circle 195 on inquiry card.

Lower Prices,

Printers



MX-80 - Epson
132 column, 9 x 9 dot matrix, multiple fonts
PRM-27080 *Save $100.00* .... Call

MX-70
PRM-27070 With Graftrax II .... Call
Interface & Cable for Apple $110.00



SPINWRITER - NEC
65 cps, bi-directional, letter quality printer with deluxe tractor mechanism, both parallel and serial interfaces on-board, 16K buffer, ribbon, print thimble, graphics, micro-space justification, data cable, and self test/diagnostic ROM.
PRD-55511 *without 16K buffer* ... $2795.00
PRD-55512 *with 16K buffer* $2895.00

Accessories for TRS-80



DISK DRIVES for TRS-80
23% more storage, 8 times faster, 40 track with free patch, 120 day warranty.
MSM-12410C *Save $125.00 !!!* $325.00

8" DISK DRIVES for MODEL II
2 double density drives with cabinet, power supply, & cables
END-000433 *Kit* $1050.00
END-000434 *Assembled* $1250.00
WCA-5036A *Cable (required)* $29.95

Special Purchase - Save $50.00
Novation Cat Modem
300 baud, answer and originate

(We have only ~~700~~ 265 availible at this special price)

IOM-5200A *List price $189.95* $139.95
D-CAT 300 baud, direct connect modem
IOM-5201A *Special sale price* $189.00
AUTO-CAT Auto answer/origiate, direct connect
IOM-5230A *Special sale price* $239.95

Accessories for Apple

16K MEMORY UPGRADE
Add 16K of RAM to your TRS-80, Apple, or Exidy in just minutes. We've sold thousands of these 16K RAM upgrades which include the appropriate memory chips (as specified by the manufacturer), all necessary jumper blocks, fool-proof instructions, and our 1 year guarantee.
MEX-16100K *TRS-80 kit* $29.00
MEX-16101K *Apple kit* $29.00
MEX-16102K *Exidy kit* $29.00

16K RAM Card - Microsoft
(There is life after 48K)
MEX-16300A *A & T* $174.95

Z-80* CARD for APPLE
Two computers in one, Z-80 & 6502, more than doubles the power & potential of your Apple, includes Z-80 CPU card, CP/M 2.2, & BASIC-80*
CPX-30800A *A & T* $279.95

32K Atari 800 ....$799.95

APPLE CLOCK - Cal Comp Sys
Real time clock w/battery back-up
IOK-2030A *A & T* $109.95

APPLE STICK - Micromate
Joy stick with pots for Apple II
SYA-1510A *A & T* $49.95

VISICALC - Personal Sftwr
The ultimate program for your Apple II
SFA-24101005M *Complete package* $139.95

DOS 3.3 UPGRADE - Apple
Upgrade your old DOS to the improved 3.3
IOD-2233A *Complete kit* $64.95

DISK DRIVE for APPLE
5¼" disk drive with controller for your Apple
MSM-12310C *with controller* $475.00
MSM-123101 *w/out controller* $375.00

8" DRIVES for APPLE
Controller, DOS, two 8" double densisty drives, cabinet, power supply, & cables
Special Package Price *Kit* $1399.95

PRINTER INTERFACE - C.C.S.
Centronics type I/O card w/ firmware
IOI-2041A *A & T* $99.95

AIO, ASIO, APIO - S.S.M.
Parallel & serial interface for your Apple (see Byte pg 11)
IOI-2050K *Par & Ser kit* $139.95
IOI-2050A *Par & Ser A & T* $169.95
IOI-2052K *Serial kit* $89.95
IOI-2052A *Serial A & T* $99.95
IOI-2054K *Parallel kit* $69.95
IOI-2054A *Parallel A & T* $89.95

A488 - S.S.M.
IEEE 488 controller, uses simple basic commands, includes firmware and cable, 1 year guarantee. (see April Byte pg 11)
IOX-7488A *A & T* $399.95

Disk Drives

JADE's new dual disk sub-assemblies include: ***Handsome** metal cabinet with **proportionally balanced** air flow system, **assembled & tested** dual drive power supply, **quiet whisper type** cooling fan, power-cable kit, lighted power switch, approved fuse assembly, line cord, **Never-Mar** rubber feet, and all necessary hardware to mount 2-8" disk drives - it's **all American made, guaranteed for six months**, and it's in stock!*

Dual 8" Sub-Assembly Cabinet
END-000421 *Cabinet kit* $225.00
END-000420 *Bare cabinet* $59.95

Single sided, double density disk drive sub-system
END-000423 *Kit w/2 8" drives* $975.00
END-000424 *A & T w/2 8" drives* $1195.00

Double sided, double density disk drive sub-system
END-000426 *kit w/2 8" drives* $1495.00
END-000427 *A & T w/2 8" drives* $1695.00

8" DISK DRIVES
Highly reliable double density floppy disk drives
Shugart 801R single sided, double density
MSF-10801R *SA-801R* $425.00
Special Sale Price .... **2 for $790.00**

Shugart 851R double sided, double density
MSF-10851R *SA-851R* $595.00
Special Sale Price .... **2 for $1150.00**

Siemens FDD100-8D2 single sided, double density
MSF-201120 *6 mo warranty* $385.00
Special sale price .... **2 for $750.00**

Qume Datatrak 8 double sided, double density
MSF-750080 *SA-851R compatible* .. $599.95
Special sale price .... **2 for $1160.00**

JADE DISK PACKAGE
Double density controller, two 8" double density floppy disk drives, CP/M 2.2 (configured for controller), hardware and software manuals, boot PROM, cabinet, power supply, fan, & cables
Special Package Price *Kit* $1395.00

Diskettes

DISKETTES - Jade
Bargain prices on magnificent magnetic media
5¼" single sided, single density, box of 10
MMD-5110103 *Soft sector* $27.95
MMD-5111003 *10 sector* $27.95
MMD-5111603 *16 sector* $27.95
5¼" double sided, double density, box of 10
MMD-5220103 *Soft sector* $39.95
8" single sided, single density, box of 10
MMD-8110103 *Soft sector* $33.95
8" single sided, double density, box of 10
MMD-8120103 *Soft sector* $39.95
8" double sided, double density, box of 10
MMD-8220103 *Soft sector* $49.95

Video Monitors

13" COLOR MONITOR - Zenith
The hi res color you've been promising yourself
VDC-201301 .... $449.00

12" GREEN SCREEN - NEC
20 MHz, P31 phosphor video monitor with audio, exceptionally high resolution - A fantastic monitor at a very reasonable price
VDM-651200 *12" monitor* $259.95

Leedex / Amdek
Reasonably priced video monitors
VDM-801210 *Video 100 12" B&W* .. $149.95
VDM-801230 *Video 100-80 12" B& W* $189.95
VDM-801250 *12" Green Phospor* $189.95
VDC-801310 *13" Color I* $399.95

Faster Service.

S-100 CPU



CB-2 Z-80 CPU - S.S.M.
2 or 4 MHz Z-80 CPU board with provision for up to 8K of ROM or 4K of RAM on board, extended addressing. IEEE S-100, front panel compatible.

CPU-30300K *Kit* $239.95
CPU-30300A *A & T* $299.95

THE BIG Z* - Jade
2 or 4 MHz switchable Z-80 CPU with serial I/O, accomodates 2708, 2716, or 2732 EPROM, baud rates from 75 to 9600*

CPU-30201K *Kit* $145.00
CPU-30201A *A & T* $199.00
CPU-30200B *Bare board* $35.00

2810 Z-80* CPU - Cal Comp Sys
2/4 MHz Z-80A CPU with RS-232C serial I/O port and on-board MOSS 2.2 monitor PROM, front panel compatible.*

CPU-30400A *A & T* $269.95

SBC-200 - SD Systems
4 MHz Z-80 CPU with serial & parallel I/O ports, up to 8K of on-board PROM, software programmable baud rate generator, 1K of on-board RAM, Z-80 CTC.*

CPC-30200K *Kit* $339.95
CPC-30200A *Jade A & T* $399.95

S-100 I/O



S.P.I.C. - Jade
Our new I/O card with 2 SIO's, 4 CTC's, and 1 PIO

IOI-1045K *2 CTC's, 1 SIO, 1 PIO* .. $169.95
IOI-1045A *A & T* $244.95
IOI-1046K *4 CTC's, 2 SIO's, 1 PIO* $219.95
IOI-1046A *A & T* $319.95
IOI-1045B *Bare board w/ manual* .. $59.95
IOI-1045D *Manual only* $20.00

I/O-4 - S.S.M.
2 serial I/O ports plus 2 parallel I/O ports

IOI-1010K *Kit* $179.95
IOI-1010A *A & T* $249.95
IOI-1010B *Bare board* $35.00

Motherboards

ISO-BUS - Jade
Silent, simple, and on sale - a better motherboard

6 Slot (5¼" x 8⅝")

MBS-061B *Bare board* $19.95
MBS-061K *Kit* $39.95
MBS-061A *A & T* $49.95

12 Slot (9¾" x 8⅝")

MBS-121B *Bare board* $29.95
MBS-121K *Kit* $69.95
MBS-121A *A & T* $89.95

18 Slot (14½" x 8⅝")

MBS-181B *Bare board* $49.95
MBS-181K *Kit* $99.95
MBS-181A *A & T* $139.95

S-100 Memory



EXPANDORAM II - S D Systems
4 MHz RAM board expandable from 16K to 64K

MEM-16630K *16K kit* $275.95
MEM-32631K *32K kit* $295.95
MEM-48632K *48K kit* $315.95
MEM-64633K *64K kit* $335.95
Assembled & tested .... add $50.00

64K RAM - Calif Computer Sys
4 MHz bank port / bank byte selectable, extended addressing, 16K bank selectable. PHANTOM line allows memory overlay, 8080 / Z-80 / front panel compatible.

MEM-64565A *A & T* $575.00

MEMORY BANK - Jade
4 MHz, IEEE S-100, bank selectable, 8 or 16 bit, expandable from 16K to 256K

MEM-99730B *Bare board* $55.00
MEM-99730K *Kit, no RAM* $219.95
MEM-16730K *16K kit* $249.95
MEM-32731K *32K kit* $289.95
MEM-48732K *48K kit* $324.95
MEM-64733K *64K kit* $359.95
Assembled & tested .... add $50.00

32K STATIC RAM - Jade
2 or 4 MHz expandable static RAM board uses 2114L's

MEM-16151K *16K 4 MHz kit* $169.95
MEM-32151K *32K 4 MHz kit* $299.95
Assembled & tested .... add $50.00

16K STATIC RAM - Mem Merchant
4 MHz 16K static RAM board, IEEE S-100, bank selectable, Phantom capability, addressable in 4K blocks, "disable-able" in 1K segments, extended addressing, low power

MEM-16171A *A & T* $174.95

S-100 PROM Boards



PB-1 - S.S.M.
2708, 2716 EPROM board with built-in programmer

MEM-99510K *Kit* $154.95
MEM-99510A *A & T* $219.95

PROM-100 - SD Systems
2708, 2716, 2732, 2758, & 2516 EPROM programmer

MEM-99520K *Kit* $219.95
MEM-99520A *Jade A & T* $269.95

EPROM BOARD - Jade
16K or 32K uses 2708's or 2716's, 1K boundary

MEM-16230K *Kit* $79.95
MEM-16230A *A & T* $119.95

Mainframes

MAINFRAME - Cal Comp Sys
12 slot S-100 mainframe with 20 amp power supply

ENC-112105 *Kit* $379.95
ENC-112106 *A & T* $409.95

S-100 Disk Controller



DOUBLE-D - Jade
Double density controller with the inside track, on-board Z-80A, printer port, IEEE S-100, can function on an interrupt driven buss*

IOD-1200K *Kit* $299.95
IOD-1200A *8" A & T* $389.95
IOD-1205A *5¼" A & T* $389.95
IOD-1200B *Bare board* $65.00

DOUBLE DENSITY - Cal Comp Sys
5¼" and 8" disk controller, single or double density, with on-board boot loader ROM, and free CP/M 2.2 and manual set.*

IOD-1300A *A & T* $369.95

VERSAFLOPPY II - SD Systems
New double density controller for both 8" & 5¼"

IOD-1160K *Kit* $339.95
IOD-1160A *A & T* $379.95

S-100 Video

VB-3 - S.S.M.
80 characters x 24 lines expandable to 80 x 48 for a full page of text, upper & lower case, 256 user defined symbols, 160 x 192 graphics matrix, memory mapped, has key board input.

IOV-1095K *4 MHz kit* $349.95
IOV-1095A *4 MHz A & T* $439.95
IOV-1096K *80 x 48 upgrade* $39.95

VDB-8024 - SD Systems
80 x 24 I/O mapped video board with keyboard I/O, and on-board Z-80A.*

IOV-1020K *Kit* $399.95
IOV-1020A *Jade A & T* $459.95

VIDEO BOARD - Jade
64 characters x 16 lines, 7 x 9 dot matrix, full upper/lower case ASCII character set, numbers, symbols, and greek letters, normal/reverse/blinking video, S-100.

IOV-1050K *Kit* $99.95
IOV-1050A *A & T* $125.00
IOV-1050B *Bare board* $29.95

2114L Low Power 4MHz

1 - 19	20 - 99	100 or more
$3.35	$2.99	$2.50

Place Orders Toll Free

Continental U.S. 800-421-5500
Inside California 800-626-1710

For Technical Inquires or Customer Service call:
213-973-7707

JADE
Computer Products
4901 W. Rosecrans, Hawthorne, Ca 90250

TERMS of SALE: Cash, checks, credit cards, or Purchase Orders from qualified firms and institutions. **Minimum Order $15.00.** California residents add 6% tax. Minimum shipping & handling charge $3.00. **Pricing & availibility subject to change**

Circle 194 on inquiry card.

Circle 164 on inquiry card.

California Digital

Post Office Box 3097 B • Torrance, California 90503



DISKETTES

FREE PLASTIC LIBRARY CASE INCLUDED WITH THE PURCHASE OF EVERY BOX OF DISKETTES

Private labeled for California Digital by one of the most respected producers of magnetic media. Each diskette is certified double density at 40 tracks. To insure extended media life each diskette is manufactured with a reinforced hub-hole. And of course, a plastic library case is included with every box of diskettes. MMD-CD5(01)(10) Please specify computer or required sectors.

$24.95 BOX

Ten boxes $22.75   One hundred boxes $21.50

MINIDISKETTES	Box	10 boxes		Box	10 boxes
Memorex 3401	$27.00	$25.00	Scotch 744(0)(10)(16)	$31.00	$29.00
Verbatim 525(01)(10)	29.00	27.00	Dysan	45.00	43.00

EIGHT INCH	Scotch	box	10 bx.	Dysan	box	10 bx.	MRX	box	10 bx.
Single side/single den.	740-0	$35.	$33.	3740/1	$49.	$47.	3060	$-5.	$-3.
Single side/double den.	741-0	45.	43.	3740/1d	75.	73.	3090	37.	35.
Single side/32 sector	740-32	35.	33.	na.			na.		
Double side/double D.	743-0	65.	59.	na.			3115	49.	45.

SCOTCH brand head cleaning kit. $24.95 MMA-CK(5)(8) please specify 5 1/4 8"
Prices available on request for: tape, cartridges, diskpacks, volumn diskettes.

MEMORY

TRS-80 APPLE II $25
16k memory (8) 4116's

Factory prime. Unconditionally guarenteed for one full year. Add $3.00 for TRS-80 jumpers and instructions.

DYNAMIC

	ea.	32+	100+	1K+
4116- 200ns	3.25	3.00	2.75	2.50
4116 150ns	3.75	3.50	3.25	3.00
4164 64K	49.50	45.00		

STATIC

21L02 450ns.	1.19	1.05	.99	
21L02 250ns	1.49	1.45	1.39	
2114L4 450ns	3.95	2.95	2.75	2.50
2114L3 300ns	4.25	3.75	3.00	2.75
4044-4 450ns	4.95	4.50	4.25	4.00
4044-2 250ns	5.50	4.95	4.50	4.35
5257-3 300ns	4.47	4.25	4.05	3.75

EPROM

2708 450ns	4.95	4.50	3.75	3.25
2716 5V.	7.95	6.50	5.00	4.50
2716 tri-volt	9.95	9.00	8.25	7.50
2732 Intel	19.00	17.50	16.00	
2532 TI	21.50	19.00		
2764	*			

direct connect MODEM   **Your Choice $169**

Direct connect modems eliminate loss of information due to the carbon compression associated with acoustic modems. Choose either of these two great units.

The Universal Data Systems 103LP is switch selectable between answer and originate modes. Fully Bell 103 compatable. Directly connects to the new modular telephone jack. 100% powered from the telephone line. No need to locate modem in proximity to A.C. power recepticle. MOD-103LP 2 pounds.

Novation "D" Cat connects to most of the new "Bell" modular handsets. Ideal for multiple line office telephones. Requires external A.C. power. MOD-DCAT 2 Lb.

UDS 103J/LP AUTO ANSWER $219



26 Megabyte Hard Disk Drive from GEORGE MORROW'S Thinker Toys

$3950

Other Morrow Products.			
Additional hard disk	$3650	Disc Jockey 2D controller	$345
Discus 2D 1 drive	950	Disk Jockey 1 Controller	195
Discus 2D 2 drives	1627	M26 hard disk Controller	625
Discus 2+2 1 drive	1250	Switchboard interface	219
Discus 2+2 2 drives	2237	"New" Multiboard	275
		M-10 Ten Megabyte hard	2550

HEWLETT PACKARD

$2650

The Hewlett Packard HP-85 is a complete, low cost portable computer system. This self contained package includes CPU, keyboard, printer, CRT display and cassette tape drive. SYS-HP85 30 lbs.

BSR SYSTEM X-10

The new BSR timer runs your home just like clockwork. Turns on lamps and appliances while your away from home. Completely compatible with your existing System X-10 devices.

BSR Timer eight channel	$65.00	Appliance Module 500 W.	$13.95
Master control console	34.95	Lamp Module 300 Watts	13.95
Ultrasonic Controller	19.95	NEW full control wall switch	14.50

S-100 Mother Board $35

Quiet Buss™

8803-18
18 slot
IMSAI



SWITCHES

DIP SWITCHES pos.	ea.	100+	1K+
4	.88	.75	.69
7	.99	.83	.79
8	1.05	.91	.87
12	1.19	.99	.91

TOGGLE		ea.	100+
7101	on/on	1.19	.98
7103	on/off/on	1.39	1.19
7107	mnt. on	1.39	1.19
7108	mnt. on	1.39	1.19
7205	dpdt mnt	1.85	1.65

CONNECTORS

GOLD EDGE CONNECTORS

S-100 .125" centers	each	10+
Imsai solder .250" row	$2.95	$2.50
Imsai wire wrap (TI)	3.95	3.50
Sullins Hi-Rel. .250"	4.50	4.00
Sullins Hi-Rel. W/W	5.35	4.90
Sullins /Altair .140"	4.95	4.50
.156" Centers (standard)		
22/44 Kim Eyelet	2.50	2.15
36/72 Digital Group S/T	5.95	5.50
36/72 Digital Group W/W	6.60	6.15
43/86 Motorola 6800 S/T	6.60	6.15
43/86 Moto. 6800 W/W	7.00	6.85

INTEGRATED CIRCUIT SOCKETS

	Low Profile each	Low Profile 100+	Wire Wrap each	Wire Wrap 100+
8 pin	$.10	$.09	$.46	$.41
14 pin	.10	.09	.45	.41
16 pin	.12	.11	.50	.45
18 pin	.15	.13	.68	.61
24 pin	.26	.24	.94	.87
40 pin	.42	.40	1.60	1.47

"D" Type	each	10-24	25+
DE9P male	$1.50	$1.40	$1.30
DE9S female	2.25	2.00	1.90
DE hood	1.50	1.35	1.20
DA15P male	2.35	2.15	2.00
DA15S female	3.25	3.10	2.90
DA hood 2/P	1.60	1.35	1.30
DB25P male	2.50	2.35	2.25
DB25S female	3.35	3.15	3.05
DB hood 2/P	1.35	1.15	1.05
DC37P male	4.20	4.00	3.70
DC37S female	6.00	5.75	5.50
DC hood 2/P	2.25	2.00	1.75
DD50P male	5.50	5.10	4.75
DD50S female	9.40	8.60	8.00
DD50 hood 2/P	2.60	2.40	2.10
CENTRONICS			
57-30360	7.95	6.75	5.75
RIBBON CABLE CONNECTORS			
17/34 5" disk	4.85	4.15	3.95
20/40 TRS-80	5.65	5.05	4.70
25/50 8" disk	5.90	5.15	4.90

SPECIAL $295

SHUGART SA800/1

Your Choice 115V. 60Hz or 230V. 50Hz.

These Shugart eight inch disk drives were originally purchased by major computer manufacturers. Upon failing incoming inspection the drives were sent back to Shugart for realigment.

California Digital has negotiated an extremely attractive agreement to purchase the entire inventory of the SA800's We are offering the drives on a first come basis at only $295. (Subject to remaining inventory on hand.) Installation manual $10 additional. Warranty 30 days from date of receipt. NOTE: The SA800/1 is standard mount and not the "R" suffix rack mount unit.
SPC-800/115 or SPC-800/230 16 Lbs.

Shugart Associates



$395

801/ R Disk Drive 15 lbs.

Shugart 801/R with CP 206 power supply, muffin exhaust fan, complete in dual enclosure with all the necessary harnessing cables. Documentation included. 36 pounds. MSD-1801 **$795**

Same as above but with two Shugart 801R disk drives. 50 pounds. MSD-2801 **$1195**

Disk drive cable. 6 feet 50 conductor with edge card connector at both ends. WCA-650S $25.00
Export Disk drives. 220V. 50MHz add $50.00 per disk drive.

NEW from Shugart Technology 5 Megabyte Hard Disk Drive



Packaged in the same physical size as the industry standard 5 1/4" minifloppy disk drive. The micro-Winchester stores thirty times as much data (6.38 megabytes unformatted), accesses data twice as fast (170 milliseconds) and transfers data twenty times faster (5.0 megabits per second.)

The ST506 is factory sealed to protect the media from environmental contaminates. Requires only DC voltage.

Dual California Digital 5 1/4" enclosure, ST506 drive and power supply. **$1500**

Shugart Associates SA400 removable media disk drive for above package. add: **$300**
S-100 & Apple controller scheduled for spring release.

DATA INPUT TERMINAL

This Keystation terminal was recently acquired from the CMC division of the Pertec Corporation. The unit was originally designed for inputing data directly onto magnetic tape.

The system is comprised of a premium cast aluminium and fiberglass enclosure, along with a Honeywell / Microswitch hall effect keyboard. Thirty display lamps advise the operator of the systems status. Four inch loud speaker acknowledges acceptance of data and alerts the operator of pending problems.

But most of all this "USED" terminal, with a little imagination, can be engineered to make the perfect home for an S-100 computer and video display; or with slight modification will accept the Rockwell AIM-65 micro/computer.

Five volt regulated power supply is available for an additional $20. (see June Byte) All units are in excellent condition. Original acquisition over $700. 22 lbs.

Regulated Power Supply 5 VOLT 5 AMP

$11.95



This USED surplus power supply was removed from working equipment. Pass transistor regulation outputs five volts at a conservative five amps. Suitable for TTL hobby applications. SPC-PS1 8 pounds.

VISA
master charge

All merchandise sold by California Digital is premium grade.
Shipping: First five pounds $2.00; each additional add $.40
Foreign orders 10% shipping. Excess will be refunded.
California residents add 6% sales tax. COD's discouraged.
Open accounts extended to state supported educational institutions and companies with a "Strong Dun & Bradstreet."
Warehouse: 15608 Inglewood Blvd. Visitors by appointment.

Circle 51 on inquiry card.

TOLL FREE ORDER LINE
(800) 421-5041
TECHNICAL & CALIFORNIA
(213) 679-9001
TWX 910 325-6212

7400

SN7400N	19	SN74123N	.59
SN7401N	22	SN74125N	.39
SN7402N	22	SN74126N	44
SN7403N	22	SN74128N	.59
SN7404N	22	SN74132N	.69
SN7405N	23	SN74136N	.95
SN7406N	23	SN74139N	95
SN7407N	23	SN74141N	69
SN7408N	.26	SN74142N	2.95
SN7409N	23	SN74143N	2.95
SN7410N	22	SN74144N	2.95
SN7411N	29	SN74145N	62
SN7412N	29	SN74147N	1.95
SN7413N	39	SN74148N	1.20
SN7414N	59	SN74150N	99
SN7416N	29	SN74151N	67
SN7417N	.29	SN74152N	67
SN7420N	22	SN74153N	67
SN7421N	35	SN74154N	1.19
SN7422N	29	SN74155N	82
SN7423N	29	SN74156N	89
SN7425N	29	SN74157N	69
SN7426N	29	SN74158N	1.65
SN7427N	29	SN74160N	95
SN7429N	45	SN74161N	.95
SN7430N	23	SN74162N	.89
SN7432N	29	SN74163N	87
SN7437N	29	SN74164N	97
SN7438N	29	SN74165N	.97
SN7439N	29	SN74166N	1.20
SN7440N	.24	SN74167N	1.95
SN7441N	79	SN74170N	1.69
SN7442N	.57	SN74172N	5.95
SN7443N	79	SN74173N	.79
SN7444N	79	SN74174N	89
SN7445N	79	SN74175N	89
SN7446N	79	SN74176N	85
SN7447N	.59	SN74177N	.85
SN7448N	79	SN74179N	1.80
SN7450N	23	SN74180N	.75
SN7451N	23	SN74181N	1.75
SN7453N	23	SN74182N	.75
SN7454N	.23	SN74184N	1.95
SN7459N	.29	SN74185N	1.95
SN7460N	.23	SN74186N	9.95
SN7470N	39	SN74188N	3.90
SN7472N	34	SN74190N	1.15
SN7473N	.38	SN74191N	1.15
SN7474N	.36	SN74192N	.85
SN7475N	38	SN74193N	.85
SN7476N	.36	SN74194N	.85
SN7479N	4.60	SN74195N	.85
SN7480N	.59	SN74196N	.85
SN7481N	1.10	SN74197N	.85
SN7482N	1.10	SN74198N	1.39
SN7483N	55	SN74199N	1.39
SN7485N	.65	SN74221N	1.39
SN7486N	39	SN74251N	.95
SN7489N	1.75	SN74273N	1.05
SN7490N	.39	SN74279N	89
SN7491N	65	SN74283N	2.15
SN7492N	52	SN74284N	3.90
SN7493N	49	SN74285N	3.90
SN7494N	72	SN74290N	1.25
SN7495N	.65	SN74298N	.95
SN7496N	.72	SN74365N	.68
SN7497N	3.10	SN74366N	.68
SN74100N	.99	SN74367N	.79
SN74107N	.32	SN74368N	.79
SN74109N	53	SN74390N	1.90
SN74116N	1.95	SN74393N	1.90
SN74121N	.29	SN74490N	1.90
SN74122N	.39		

CMOS

CD4000	.35	CD4093	99
CD4001	.35	CD4094	2.95
CD4002	.35	CD4098	2.49
CD4006	1.39	CD4099	2.25
CD4007	.29	MC14408	12.95
CD4008	1.39	MC14409	12.95
CD4009	.49	MC14410	12.95
CD4010	.49	MC14412	12.95
CD4011	.35	MC14415	8.95
CD4012	29	MC14419	4.95
CD4013	.49	CD4501	39
CD4014	1.39	CD4502	1.65
CD4015	1.15	CD4503	.69
CD4016	.59	CD4505	8.95
CD4017	1.19	CD4506	.75
CD4018	99	CD4507	95
CD4019	49	CD4508	3.95
CD4020	1.19	CD4510	1.39
CD4021	1.19	CD4511	1.39
CD4022	1.15	CD4512	1.39
CD4023	.38	CD4515	3.95
CD4024	.79	CD4516	1.69
CD4025	.38	CD4518	1.39
CD4027	.65	CD4520	1.39
CD4028	.85	CD4555	4.95
CD4029	1.29	CD4556	99
CD4030	.45	CD4566	2.25
CD4031	3.25	74C00	.39
CD4032	2.15	74C02	.39
CD4034	3.25	74C04	39
CD4035	.95	74C08	.49
CD4037	1.95	74C10	49
CD4040	1.29	74C14	1.65
CD4041	1.25	74C20	.39
CD4042	.95	74C30	39
CD4043	.85	74C32	.99
CD4044	.85	74C42	1.85
CD4046	1.75	74C48	2.39
CD4047	1.25	74C73	.85
CD4048	99	74C74	85
CD4049	.69	74C85	2.49
CD4050	69	74C89	4.95
CD4051	1.10	74C90	1.85
CD4052	1.10	74C93	1.85
CD4053	1.10	74C95	1.85
CD4055	3.95	74C107	1.19
CD4056	2.95	74C151	2.49
CD4059	9.95	74C154	3.50
CD4060	1.39	74C157	2.10
CD4066	.75	74C160	2.39
CD4069	.35	74C161	2.30
CD4070	.49	74C163	2.39
CD4071	.35	74C164	2.39
CD4072	.35	74C173	2.59
CD4073	.35	74C174	2.75
CD4075	.35	74C175	2.75
CD4076	1.29	74C192	2.39
CD4077	.35	74C193	2.39
CD4078	.35	74C195	2.39
CD4081	.35	74C922	7.95
CD4082	.35	74C923	6.95
CD4085	1.95	MM80C95	1.50
CD4089	2.95	MM80C97	1.25

74LS00

74LS00N	35	74LS164N	1.19
74LS01N	28	74LS165N	89
74LS02N	28	74LS166N	2.48
74LS03N	28	74LS168N	1.89
74LS04N	39	74LS169N	1.89
74LS05N	28	74LS170N	1.99
74LS08N	39	74LS173N	89
74LS09N	39	74LS174N	99
74LS10N	28	74LS175N	.99
74LS11N	39	74LS181N	2.20
74LS12N	39	74LS190N	1.15
74LS13N	47	74LS191N	1.15
74LS14N	1.25	74LS192N	98
74LS15N	39	74LS193N	98
74LS20N	26	74LS194N	1.15
74LS21N	38	74LS195N	95
74LS22N	.38	74LS196N	89
74LS26N	39	74LS197N	89
74LS27N	39	74LS221N	1.49
74LS28N	39	74LS240N	1.95
74LS30N	26	74LS241N	1.90
74LS32N	39	74LS242N	1.95
74LS37N	79	74LS243N	1.95
74LS38N	39	74LS244N	1.95
74LS40N	26	74LS245N	4.95
74LS42N	79	74LS247N	1.10
74LS47N	79	74LS248N	1.10
74LS48N	79	74LS249N	1.69
74LS51N	26	74LS251N	1.79
74LS54N	35	74LS253N	98
74LS55N	35	74LS257N	98
74LS73N	.45	74LS258N	.98
74LS74N	.59	74LS259N	2.95
74LS75N	68	74LS260N	.69
74LS76N	45	74LS261N	2.49
74LS78N	.65	74LS266N	59
74LS83AN	99	74LS273N	1.75
74LS85N	1.19	74LS275N	4.40
74LS86N	45	74LS279N	.59
74LS90N	75	74LS283N	1.10
74LS92N	75	74LS290N	1.29
74LS93N	75	74LS293N	1.95
74LS95N	88	74LS295N	1.10
74LS96N	.98	74LS298N	1.29
74LS107N	45	74LS324N	1.75
74LS109N	.45	74LS347N	1.95
74LS112N	.49	74LS348N	1.95
74LS113N	49	74LS352N	1.65
74LS114N	.55	74LS353N	1.65
74LS122N	55	74LS363N	1.49
74LS123N	1.19	74LS365N	99
74LS124N	1.35	74LS366N	99
74LS125N	89	74LS367N	.73
74LS126N	.89	74LS368N	73
74LS132N	.79	74LS373N	2.75
74LS136N	59	74LS374N	2.75
74LS138N	89	74LS375N	69
74LS139N	.89	74LS377N	1.95
74LS145N	1.25	74LS385N	1.95
74LS148N	1.49	74LS386N	65
74LS151N	79	74LS390N	1.95
74LS153N	.79	74LS393N	1.95
74LS154N	2.49	74LS395N	1.70
74LS155N	1.19	74LS399N	2.95
74LS156N	99	74LS424N	2.95
74LS157N	99	74LS668N	1.75
74LS158N	75	74LS670N	2.29
74LS160N	.98	81LS95N	1.99
74LS161N	1.15	81LS96N	1.99
74LS162N	98	81LS97N	1.99
74LS163N	.98	81LS98N	1.99

LINEAR

78H05	5.95	LM1414N	1.90
78M06	1.49	LM1458CN/N	.49
78M.G	1.49	MC1488N	1.49
LM105H	.99	MC1489N	1.49
LM108AH	2.95	LM1496N	89
LM300H	.79	LM1556N	1.50
LM301CN/H	35	LM1800N	.79
LM304H	.98	LM1820N	95
LM305H	.89	LM1850N	.95
LM306H	3.25	LM1889N	3.95
LM307CN/H	29	LM2111N	1.75
LM308CN/H	98	LM2900N	99
LM309K	1.49	LM2901N	2.50
LM310CN	1.25	LM2917N	2.95
LM311D/CN/H	98	CA3013T	2.29
LM312H	1.75	CA3018T	1.99
LM317T	2.75	CA3021T	3.49
LM318CN/H	1.49	CA3023T	2.99
LM319N/H	1.25	CA3035T	2.75
LM320K-XX*	1.49	CA3039T	1.49
LM320T-XX*	1.25	CA3046T	1.29
LM320H-XX*	1.25	LM3053N	1.49
LM323K	4.95	CA3059N	3.25
LM324N	1.25	CA3060N	3.25
LM339N	95	CA3062N	4.95
LM340K-XX*	1.49	LM3065N	1.49
LM340T-XX*	1.25	CA3080N	1.29
LM340H-XX*	1.25	CA3081N	1.69
LM344H	1.95	CA3082N	1.69
LM348N	1.85	CA3083N	1.99
LM358CN	.98	CA3086N	1.29
LM360N	1.49	CA3089N	2.75
LM372N	1.95	CA3096N	2.49
LM376N	3.75	CA3097N	1.99
LM377N	3.75	CA3130T	2.49
LM380CN/N	1.25	CA3140T	2.49
LM381N	1.79	CA3146N	2.49
LM383T	1.95	CA3160T	1.49
LM386N	1.49	CA3190N	1.95
LM387N	1.49	CA3401N	.69
LM390N	1.95	MC3423N	1.49
NE531V/T	3.75	MC3460N	3.95
NE555V	.39	SG3524N	3.95
NE556N	98	CA3600N	3.50
NE561T	19.95	LM3900N	.59
NE562B	7.95	LM3905N	1.49
NE565N/H	1.25	LM3909N	.98
NE566H/V	1.75	RC4131N	2.95
NE567V/H	1.50	RC4136N	1.10
NE592N	2.75	RC4151N	4.50
LM702H	2.99	RC4194	4.95
LM709N/H	.29	RC4195	4.40
LM710N/H	98	ULN2001	1.25
LM711N/H	.39	ULN2003	1.50
LM715N	1.95	SN75450N	.59
LM723N/H	.75	SN75451N	49
LM733N/H	.98	SN75452N	49
LM739N	1.15	SN75453N	.49
LM741CN/H	.33	SN75454N	.49
LM741CN-14	.19	SN75491N	.89
LM747N/H	.79	SN75492N	.89
LM748N/H	.39	SN75493N	.89
LM760CN	2.95	SN75494N	.89
LM1310N	1.90		

16K UPGRADE ONLY $24.95 SPECIFY COMPUTER

ADVANCED COMPUTER PRODUCTS

NON-LINEAR SYSTEMS, INC. NLS

TOUCH-TEST 20

DIGITAL MULTIMETER

The NLS Model Touch/Test 20 is a 3½ digit digital multimeter with capability of measuring 10 parameters including 20 functions and 44 ranges. Features touch selection and annunciator lamp indication of control settings which include function, range and on-off power **$319.95**

BECKMAN

Digital Multimeters

MODELS TECH 300 AND TECH 310

AS LOW AS $100

Choice of Models – The TECH 310 has all above features, 7 functions, 29 ranges, plus 0.25% Vdc accuracy

The TECH 300 has a 0.5% Vdc accuracy and all the above features, but without Insta-Ohms™ continuity function or the 10 amp current ranges

TECH 300 Digital Multimeter	$110
TECH 310 Digital Multimeter	$140
TECH 330 Digital Multimeter	$189
VC-201 Vinyl Carrying Case	$10
DC-202 Deluxe Carrying Case	$24
HV-211 High Voltage Probe	$35
RP-221 RP Probe	$35
CT-231 AC Current Clamp	$42
DL-241 Deluxe Test Lead Kit	$10
TL-242 Spare Test Leads	$6

VISTA COMPUTER CO.

Model A800



Double-Density Eight-Inch Floppy Disk Controller $595.00

FEATURES:
- High speed DMA transfer of data (1 microsecond/byte)
- Complete documentation provided — includes theory of operation, source code for DOS enhancement utilities, schematics and diskette
- Uses all standard Apple DOS commands (OPEN, CATALOG, LOCK DELETE, LOAD etc.) Except for INIT which has been improved and enhanced in a Vista format routine
- Compatible with AppleDOS 3.2/3.3, Pascal 1.1 and CPM 2.2 (with the Z80 soft card by Microsoft)
- Interfaces to all Shugart/ANSI standard eight-inch floppy disk drives
- 2Kx8 PROM contains autoboot functions and all eight-inch floppy driver code allowing complete memory usage map compatibility with Apple DOS 3.2/3.3
- 120 days parts and labor waranty

CSC CONTINENTAL SPECIALTIES

Model LM-3 40-channel Logic Monitor	585.00
Model LM-1 Logic Monitor	60.00
Model LM-2 Logic Monitor	147.00
MAX-100 100 MHz Portable Frequency Counter	149.00
Model LP-1 Digital Logic Probe	50.00
Model LP-2 Economy Logic Probe	28.00
Model LP-3 High Speed Logic Probe	77.00
Model LPK-1 Logic Probe Kit	21.95
Model LTC-1, LTC-2 Logical Analysis Kits	220/250

Proto Clips

14-Pin Clip	PC-14	$ 4.25
16-Pin Clip	PC-16	$ 4.50
24-Pin Clip	PC-24	$ 9.50
40-Pin Clip	PC-40	$14.95

Proto Boards

PB-6	16.95	PB-104	54.00
PB-100	18.00	PB-203	97.00
PB-101	21.00	PB-203A	149.00
PB-102	25.00	PB-203A-Kit	129.00
PB-103	43.00		

SEMICONDUCTORS SPEAK ☆☆☆☆☆☆

DIGITALKER™

Speech Synthesis System

The DIGITALKER is a speech synthesis system consisting of multiple N-channel MOS integrated circuits. It contains a speech processor chip (SPC) and speech ROM and when used with external filter, amplifier, and speaker, produces a system which generates high quality speech including the natural inflection and emphasis of the original speech. Male, female, and children's voices can be synthesized.

- Completely independent system, not requiring a processor controller
- Designed to be easily interfaced to most popular microprocessors
- 256 possible addressable expressions
- Male, female, and children's voices
- Natural inflection and emphasis of original speech
- Addresses 128k of ROM directly
- Communicates with static or clocked dynamic ROMs
- TTL compatible
- MICROBUS™ compatible

DIGITALKER™ DT1000. Self contained board that – with just a speaker and a power supply – can rattle off any desired combination of 144 words. $485.00

DIGITALKER™ DT1050. Chip set for building Digitalker into your own evaluation design. $95.00

National Semiconductor

Apple® II 48K
Apple® II Plus
DISK SYSTEM SPECIAL

Apple II Plus w/48K Supermod Video Modulator
Disk II w/Controller Integer Based ROM Card.

CALL FOR PRICES

Hi-Speed Serial I/O	$189.00	DS65 Digi-Sector	$349.00	Integer ROM Card	
Centronics Printer I/O	180.00	Apple Graphics Tablet		Proto Card	21.95
Applesoft II Firmware		DC Hayes Modem II	349.95	M & R Modulator	29.95
Apple Clock	269.00	Disk II w/Controller & Dos 3.3		Cassette	54.95
Introl X-10 System	179.95	Disk II		16K Upgrade Kit	54.95
Introl X-10 Controller	269.95	Pascal Lang System		Desktop Plan	98.00
Alf Music Synthesizer	259.95	Parallel Printer Card	165.00	8" Floppy Controller	350.00
16 Ch Analog Input	249.95	Communications Card	189.00	Heuristics Speechlab	179.00
2 Ch Analog Output	164.95	Business Software Pkg	625.00	Romplus +	169.00
13-Key Keypad	119.95	Corvus 10 Megabyte Drive	4625.00	Supertalker	279.00
Visi-Calc	125.00			Cashier	250.00

apple ///



CALL FOR PRICES

- Apple III Option A: Apple II 96K, Information Analyst Package, 12" B/W Monitor ....
- Apple III Option B: Same as Option A Plus: Disk II for Apple III ....
- Apple III Option C: Same as Option A Plus: Disk II for Apple III, Silentype Thermal Printer ....
- To substitute 128K Apple III for 96K Apple III. ....

NEW APPLE PRODUCTS

- "APPLE FAN" – Cures thermal problems from overcrowded machines designed specifically for Apple $49.95
- "BIT3" – New 80 x 24 Video Board for Apple. Completely compatible with Pascal $329.95
- "BARWAND" Hewlett Packard HEDS-3000 Bar Code interfaced to Apple $199.00
- "SEC APPLE A/D" – 8 Channel A/D interface completely assembled and tested $99.50
- "APPLE FORTRAN" $175.00
- "APPLE CRYPTEXT" for data encryption and security $449.00
- "B2/A2" Graphics Interface Card by Base 2 $159.95
- 8" Disk Drives for Apple. Controller, DOS, Two 8" drives cabinet and cable $1450.00
- "MICROMODEM" – DC Hayes $319.95
- "DIGISECTOR" Converts video input to Hi-Res graphics $349.95
- California MicroProducts VisiCalc Keypads Numberic keypad with space, space ESC - and - keys for VisiCalc compatibility $169.00
- DOS 3.3 Upgrade Kits 23% more storage in 16-sector format $65.00
- Mountain Hardware Music Board, best yet – 16 channels $550.00
- Controller 1.1 Revision Kit 20% overall processing speed increase and supports standard printers. Reduced disk handling. Additional error checking. Improved manual. Vendor file expanded $145.00
- Pascal Revision Kit. Adds executive and chaining capabilities to Pascal environment $65.00
- Mountain Hardware Expansion chassis. 8 more slots for Apple. Hardware or software selectable. Includes power supply Avail Soon
- Smart Term Apple 80 x 24 Video Card $619.00
- Syntex X-10 $349.00
- Apple Silentype With Apple Intelligent Interface Card $549.00
- NEW! California Computer Systems APPLE Clock Only $124.95
- NEW! Z-80 Softcard for APPLE CPM 2.2 & M BASIC 5.0 $325.00
- SEC ECHO II Speech Synthesizer $249.95

NEW APPLE SOFTWARE

1. CYBERSTRIKE – Apple II version of Star Raiders from Atari on disk $34.95
2. RTR Stock Market Analysis – Hi-Res, Trend Lines, etc. $109.95
3. ASTEROIDS $29.95
4. "Both Barrels" – Hi-Res simulation of Western Gunfight and Skeet Shooting. Same author as Nasir $29.95
5. "Apple Tax Panner Package" $89.95
6. "New-DOS Tool Kit" $64.95
7. NEW! Apple Z-80 CP/M Software Call for Price

NEW Locksmith Ver 3.1 — Back up your valuable master diskettes! **only $74.95.** Prevent the loss of your expensive software.

MICROSOFT

16K ON A PLUG-IN CARD. $175

Microsoft's new RAMCard simply plugs into your Apple II and adds 16K bytes of dependable buffered read/write storage.
Until now the only way to get this much memory was to have an Apple Language Card installed. VisiCalc and other Apple software packages can take advantage of RAMCard. Even with the RAMCard in place you can still access your ROM BASIC and monitor routines.

Z80 SOFTCARD $299.00

MOUNTAIN COMPUTER EXPANSION CHASSIS

By popular demand! Eight more slots for your Apple. Attractive sturdy enclosure. Its own heavy duty power supply. Easy to use. Address cards in Expansion Chassis the same way as in your Apply. Only one additional command to specify in Apple or in Expansion Chassis.

$699.00

ATARI® 800 & 400

Personal Computer System

ATARI 800 $799.00
ATARI 400 $449.00

ATARI 800 Includes: Computer Console, BASIC Lang. Cartridge, BASIC Language Programming Manual, 800 Operator's Manual w/Notebook, 16K RAM Module, Power Supply, TV Switch Box.

Peripherals		**Education System Cassette Programs**		Spelling	35.00
Disc Drive	599.00	US History	35.00	Basic Electricity	35.00
Printer	499.00	US Government	35.00	Basic Algebra	35.00
Program Recorder	69.00	Supervisory Skills	35.00	**Basic Game and Program Cassettes**	
Software – ROM Cartridges		World History (Western)	35.00	Guide to BASIC Programming	18.00
Education System Master Cartridge	28.00	Basic Sociology	35.00	BASIC Game Programs	19.00
Atari BASIC	55.00	Counseling Procedures	35.00	**Add-On Memory**	
Assembler Debug	55.00	Principles of Accounting	35.00	8K RAM Memory Module	110.00
Basketball	42.00	Physics	35.00	16K RAM Memory Module	225.00
Life	42.00	Great Classics (English)	35.00	**Diskettes**	
Super Breakout™	42.00	Business Communications	35.00	Blank Diskettes	
Music Composer	55.00	Basic Psychology	35.00	Disk File Manager	5.00
Super Bug™	42.00	Effective Writing	35.00	**Accessory Controllers**	
Computer Chess	55.00	Auto Mechanics	35.00	Driving Controller Pair	18.00
Home Finance	55.00	Principles of Economics	35.00	Paddle Controller Pair	18.00
				Joystick Controller Pair	18.00

SINGLE BOARD COMPUTER SELECTION GUIDE

BOARD	PROCESSOR	ACP PRICE	ENCLOSURE	BOARD	PROCESSOR	ACP PRICE	ENCLOSURE
DIG RSCH BIG BOARD	Z-80 64K	649.00	N/A	SC-SBC 100	Z80	239.00	N/A
SYM-1	6502	239.00	Add 39.95	AIM 65	6502	375.00	Add 49.95
Cromemco	Z80	409.00	N/A	Cosmac Vip	1802	199.00	Inc

TEXAS INSTRUMENTS INCORPORATED

99/4 PERSONAL COMPUTER

Superior Color, Music, Sound & Graphics – & a Powerful Extended Basic – All Built-In.

Now! Special T.V. Adapter lets you use your existing T.V. set as a computer display.

$499.00 Console only.

MATTEL ELECTRONICS® INTELLIVISION

ACP LOW PRICE **$259.95**

GAME CARTRIDGES $26.95

BASEBALL	HOCKEY	POKER/BLACKJACK
FOOTBALL	BASKETBALL	ROULETTE
AUTO RACE	MOTOCROSS	HORSE RACING
TENNIS	ADVENTURE	SUB BATTLE
GOLF	CHECKERS	ARMOR BATTLE
SOCCER	CHESS	SPACE BATTLE
SKIING	MATH FUN	SEA BATTLE
BOXING	BACKGAMMON	ARCADE
BOWLING	WORD FUN	

RETAIL STORES OPEN MON-SAT

STORE #1: 1310 "B" E. Edinger, Santa Ana CA 92705 Showrooms, Retail, Warehouse
STORE #2: 542 W. Trimble Road, San Jose, CA 95131 • (408) 946-7010

P.O. Box 17329 Irvine, Calif. 92713
Direct Order Lines: (714) 558-8813
(800) 854-8230 or (800) 854-8241

DRIVER'S LICENSE # OR MAJOR CREDIT CARD # IS REQUIRED ON ALL CHECKS. MONEY ORDER OR CASHIER CHECK WILL FACILITATE THE SHIPMENT OF YOUR PURCHASE.

Circle 7 on inquiry card.

ADVANCED COMPUTER PRODUCTS

FIRST TO OFFER PRIME PRODUCTS TO THE HOBBYIST AT FAIR PRICES!

1. Proven Quality Factory tested products only.
2. Guaranteed Satisfaction
Call For Special School Discounts



Vista "V-DRIVE"

THE LAST WORD IN 8" FLOPPY-DISK ENCLOSURES

THE VISTA V-1000 FLOPPY DISK DRIVE SUBSYSTEM
● Deluxe chassis with internal slide easy access for drive positioning and mounting ● Built to mechanically and electrically accomodate single sided drives—including the most popular 8-inch Winchester and Shugart floppy disk drives, and 8-inch streaming tape units ● Storage capacity from 0.5 to 40 megabytes ● Industrial quality cabinet with die cast front bezel ● Meets all UL and OSHA standards ● Additional Savings! Front and rear retma rail mounts provided at no extra charge (no external slides) ● Desk or rack mountable ● Features modular construction with removeable sub-assembly that allows easy cabinet positioning and mounting ● Drives pull out for easy service and maintenance

CABINET with power supply	$ 395
CABINET with (2) single sided drives (including power supply & cable)	$1595
CABINET with (2) double sided drives (including power supply & cable)	$2295

Vista V-80 5¼" DISK

NOW SAVE ON TRS 80 ADD-ON
ONLY $299.00

2 DRIVE CABLE..... 29.95 2 FOR 279.00 ea.
4 DRIVE CABLE..... 39.95

MINIATURE COMPUTER

MicroAce — A COMPLETE COMPUTER
Z-80 BASED
1K KIT..........149.00
2K KIT..........169.00
Manual..........10.00

ATTENTION VIDEO HOBBYISTS!!!

★ BOX BUILDERS
★ USE AS REMOTE TUNER/TIMER
★ FULL SCHEMATICS AVAILABLE
★ FOR ONLY $5.90! – FREE W/PURCHASE

A Recent Special Purchase Allows Us To Present The Following

NEW. UNUSED COMPONENTS
From The Magnavox Video Cassette Recorder

1. UHF VHF Tuner Subassembly with all knobs and Video Demodulator
2. RF Modulator with Audio & Video inputs Channel 3 or 4 Output

ALL FOR 74.95

Call For Volume Discounts

HEWLETT PACKARD — HP-41: Powerful, Yet Easy to Use

HP 41-CV

HP-41C 198.00
HP-41CV 275.00



- The HP-41 communicates with you in words as well as numbers
- You can customize the HP-41 to your own design
- Programming is fast and easy
- Continuous Memory saves everything
- Optional Peripherals allow you to expand capabilities

HP-41 System I	39800
HP-41 System II	675.00
HP-Card Reader	178.00
HP-Optical Wand	105.00
HP-Plotter/Printer	315.00
HP-Quad RAM	85.00

RAM BOARDS SPECIAL 16K

16K Altair Mits Dynamic RAM Boards
Assem. & Tested $119.95 Untested $59.95

FLOPPY DISK DRIVES

Tandom TM100-1 5¼" Disk Drive	249.95
MPI B51-5¼", 40 tracks	239.95
Shugart SA400-5¼" 35 tracks	295.00
Shugart 800/801R 8"	449.00
Siemens Shugart Compatible Model FDD-120-8D	429.00
PERSCI Model 277 Dual	1195.00
WANGO/SIEMENS 5¼" Drive	290.00
MPI B52 5¼" Dual	348.00
WANGO/SIEMENS 282 Dual 5¼"	395.00
WANGO/SIEMENS 82	290.00
MPI 91 Double Track Density Single Side, 80 Tracks	375.00
MPI 92 Double Track Density Double Side, 160 Track	475.00

6800 MICROMODULE™ PRICE LIST

MODEL NO	DESCRIPTION	PRICE
9600A	Single Board Microcomputer	$495.00
9609	Advanced Single Bd. Comp (6809)	595.00
9601	16 Slot Mother Board	175.00
9602	Card Cage	75.00
9603	8 Slot Mother Board	100.00
9604	Power Supply	275.00
9605	DC Input Power Supply	325.00
9610	Utility Proto Board	39.00
9611	Arith. Proc/Memory Module	495.00
9612	Buffered Utility Proto Board	49.00
9616	32K EPROM/RAM Module	250.00
9617	EPROM Programming Head	250.00
9620	16 Channel Parallel I/O Module	295.00
9622	Serial-Parallel I/O Module	325.00
9627	16K Static RAM Module 470ns	395.00
9629	32K Static RAM 450ns	695.00
9629A	32K Static RAM 200ns	895.00
9630	Card Extender	68.00
9640	Multiple Programmable Timer	395.00
9650	8 Channel Duplex Serial I/O Mod	395.00
9655	Intelligent Tape Controller	550.00
96103	32/32 I/O Module	275.00
96702	Contact Closure Module	350.00

UNPOPULATED BOARDS (Also Available)

The Vista V300 Printer

- 25 CPS printspeed
- Static print impact
- 136 printable columns
- 1/120 inch min. char. spacing
- 1/48 inch min. line spacing
- 1000 msec. return time
- 40 msec. line feed time
- 381mm (15") max. paper width
- Multistrike fabric black ribbon
- 96 print characters
- Standard 96 character wheel
- Standard parallel or RS232 C compatible
- 115V ±10 50/60 Hz 70 W power requirements

$1895.00

HEWLETT PACKARD

HP-85 $2695.00

HP 7225 Graphics Plotter	1795.00
HP 16K Memory Module	265.00
HP 5 1/4" Dual Master Flex Disk Drive	2100.00
HP 5 1/4" Single Master Flex Disc Drive	1295.00
HP Personality Module	700.00
HP ROM Drawer	40.00
HP Plotter/Printer ROM	130.00
HP Input/Output ROM	260.00
HP Matrix ROM	130.00
HP Serial Interface (RS-232C)	350.00

HP-83 $1895.00

$24.95 TRS-80/APPLE $24.95

MEMORY EXPANSION KITS.
4116's, 16K (200/250 ns.)
16K 8 pcs for $24.95 w/instructions & jumpers **RAM**
Call For Volume Pricing

★ Special: TRS80 Schematic....... $ 4.95
★ Expansion Interface Schematic.. $ 4.95
★ Expansion Interface Connector... 7.95

CENTRONICS PRINTER

Model 737

- Centronics complete printer
- The 737 has everything. Check and compare the features.
- New low price

$835.00

32K STATIC RAM BOARD

S-100

16K 4MHz Kit	159.95
16K 4MHz A&T	217.95
32K 4MHz	289.95
Bare Board	39.95
Bare Board w/all parts less mem	99.95

ADD GRAPHICS TO YOUR EPSON



- Add six printing sizes
- Add tabs
- Add software definable symbols

Order PR12 Upgrade

$235.00

UV "Eprom" Eraser

Model UVs-11E $69.95
Holds 4 Eproms at a time
Backed by 45 years experience
Model S-52T... $325.00
Professional Industrial Model

S-100 MOTHERBOARD SPECIAL

8 slot expandable w/9 conn.
reg $69.95..................NOW $52.95

SHUGART DRIVE 449.00

SA801R
- Special buy while supply lasts
- 8" Drive with Double-Density
- 90 Day Warranty

★CHECK OUR FLOPPY DISK PRICING! ON THIS PAGE

ALSO 8" SIEMENS FD 120-8 419.00

CHARACTER GENERATORS

MCM66710P	128×9×7 ASCII shift	13.00
MCM66714P	128×9×7 MCM6591 Downcnt	13.00
MCM66720P	128×9×7 ASCII non-shift	13.00
MCM66730P	128×9×7 Kata Kana Japanese	13.00
MCM66740P	128×9×7 Math Symbol	15.50
MCM66750P	128×9×7 Alpha cntrl chara	13.00
MCM66760P	128×9×7 MCM6674 British	13.00
MCM66770P	128×9×7 MCM6674 German	17.00
MCM66780P	128×9×7 MCM6674 French	13.00
MCM66790P	128×9×7 Gen European Prod	13.00
MCM6581	128×9×7 ASCII Shifted w Greek	13.50
MCM6583	128×9×7 Kata Kana Japanese	13.00

DATA BOOKS • COMPUTER BOOKS

1981 IC Master	$6_.95
INTEL Data Book	7.50
INTEL MCS 85 Manual	7.50
SALE • OSBORNE BOOKS • SALE	**Sale**
Intro to Micros Vol 0	12.50
Intro to Micros Vol I	12.50
8080A Programming	12.50
6800 Programming	12.50
Z80 Programming	16.00
Vol II Some Real Microprocessors w/Binder	27.50
Vol III Some Real Support Devices w/Binder	27.50
Intro to Micros Vol III	18.50
8086 Programming	14.95
Z8000 Programming	14.95
Intro to Pascal	14.95

SALE • SYBEX COMPUTER BOOKS • SALE

6502 Games	$12.95
Intro to Personal & Business Computing	12.95
Microprocessors From Chips to Systems	12.95
Microprocessor Interfacing Techniques	12.95
Programming the Z80	12.95
Programming the Z8000	12.95
Programming the 6502	12.95
6502 Applications Book	12.95
CPM* Handbook	12.95

*CPM is a Registered Trademark of Digital Research Corp

MICROPROCESSORS

Z8001 16 bit to 8Mb	$189.00
Z8002 16 bit to 64K	149.00
Z80	10.75
Z80A	14.50
F-8 (3850)	16.95
2650	18.95
CD1802	13.95
8080A	8.50
8080A-4MHz	19.95
SALE 8085	14.95
8008-1	14.95
2901	9.90
2901A	14.95
2903 4-bit Superslice	29.95
TMS 9900JL	49.95
CP1600	39.95
6502	11.50
6502A	16.95
IM6100	29.95
6800	11.75
6800B 2.0 MHz	19.95
6802P	17.95
8035	19.95
8039	19.95
8755	49.95
8748	69.95
6809	37.95
8086	69.95

ADVANCED SUPPORT

AM9511 Arith. Processor	175.00
9512 Arith. Processor	175.00
9513 Univ. Timing	79.95
AM9517 DMA Controller	18.95
AM9519 Universal Interrupt	18.95

Z-80 SUPPORT CHIPS

Z80-PIO	2.5 MHz	8.75
Z80A-PIO	4.0 MHz	12.95
Z80-CTC	2.5 MHz	8.75
Z80A-CTC	4.0 MHz	12.95
Z80-DMA	2.5 MHz	29.95
Z80A-DMA	4.0 MHz	36.95
Z80-SIO/0	2.5 MHz	35.95
Z80A-SIO/0	4.0 MHZ	39.40
Z80-SIO/1	2.5 MHz	35.95
Z80A-SIO/1	4.0 MHz	39.40
Z80-SIO/2	2.5 MHz	35.95
Z80-SIO/2	4.0 MHz	39.40

8080/8085 SUPPORT

8155/8156 I/O	24.95
8755 I/O with Eprom	64.95
8202 Dyn. Ram Cont.	34.95
8205/74S 138 Decoder	3.95
8212 8 bit I/o	2.75
8214 Priority Int.	5.25
8216 Bus Driver	2.75
8224 Clock Gen.	2.95
8224-4 (4MHz)	9.75
8226 Bus Driver	3.95
8T26 Bus Driver	2.95
8228 Sys. Control	5.50
8238 Sys. Cont.	5.50
8251 Prog. I/O	6.95
8253 Int. Timer	12.95
8255 Prog. I/O	6.50
8257 Prog. DMA	16.95
8259 Prog. Int.	17.95
8275 CRT Controller	49.95
8279 Prog. Keyboard	15.95

6800 SUPPORT CHIPS

6810 128 x 8 Ram	4.75
6820 PIA	5.95
6821 PIA	6.50
6828 Priority Int.	19.95
6834-1 512 x 8 Eprom	16.95
6845/HD46505 CRT Cont.	39.95
6847 Color CRT	49.95
6850 ACIA	5.95
6852 Serial Adapter	5.95
6860 Modem	10.95
6862 Modulator	11.95
6871A 1.0MHz OSC	25.95
6875	6.95
6880 Bus Driver	2.95
MC68488	19.95
68047	24.95

SHIFT REGISTER SALE

2504V	1.49	2525	1.49
2507V	1.49	2527	1.49
2517V	1.49	2528	1.49
2524V	1.49	2529	1.49
		2533	1.49

6502 SUPPORT CHIPS

6520PIA	7.50
6522 Mult.	11.95
6530-002,003,004,005	21.95
6532	19.95
6551	19.95

PROMS

2708 450 ns	9.25
2708-6 650 ns	7.50
1702A	4.95
2732	44.95
2716-5V	14.95
2716-5V, 12V	19.95
2758-5V	19.95
5203AQ	13.95
5204AQ	14.95
IM 5610	3.90
82S115 512 x 8 (TS)	16.95
82S123 32 x 8	4.90
82S126 256 x 4	4.90
82S129 256 x 4 (TS)	4.90
82S130 512 x 4 (OC)	6.50
82S23	6.95
82S131	14.95
82S137	14.95
74S387	8.50
74S471	12.95
74S472	12.95
74S570	14.95
74S571	14.95

NOTE: WE PROGRAM PROMS

CHARACTER GEN.

2513-001 (5V) Upper	9.50
2513-005 (5V) Lower	10.95
2513-ADM3 (5V) Lower	14.95
MCM6571	11.75
MCM6571A	11.75
MCM6574	14.50
MCM6575	14.50
MCM 6674	14.95

UARTS/BAUD RATE

TR1602B (5V 12V)	3.95
AY51013 (5V 12V)	4.95
AY51014A/1612 (5-14V)	6.95
AY51015A/1863 (5V)	6.95
TMS 6011 (5V 12V)	5.50
IM6402	7.95
IM6403	8.95
2350 USRT	9.95
1671B Astros	24.95
SALE TR1472B	9.95
MC14411	11.95
4702	14.95
WD1941	9.95
COM 5016	16.95
AMI1883	7.95
INS 8250	15.95

KEYBOARD ENCODERS

AY5-2376	13.75
AY5-3600	13.75
HD0165	9.95
74C922	9.95
74C923	9.95

STATIC RAMS

SALE 2102 .89

	1-24	25-99	100
21L02 450ns	1.30	1.25	.99
21L02 250ns	1.59	1.55	1.15
2111	3.75	3.65	3.55
2112-1	2.95	2.85	2.65
2101-1	2.90	2.70	2.55
2114L-250ns (4045)	6.50	5.95	5.50
2114L-450ns (4045)	5.50	5.25	**4.75**
4044 250 ns	8.95	7.50	6.90
4044 450ns	5.95	5.95	**4.75**
EMM4200A	9.75	8.75	7.95
EMM4402	7.95	7.25	6.25
AMD9140 41	10.95	10.25	9.25
AMD9130 31	12.95	11.95	10.25
1101	1.95	1.75	1.25
P2125 93425 (45ns)	9.95	8.35	8.25
6518 1K x 1 CMOS	7.95	7.95	7.25
2147 Low Power 4K Static	19.95	18.95	16.95
93415	9.95	8.95	8.50
TMS4046	11.95	10.95	10.50

DYNAMIC RAMS

416/4116 16K (16 Pin)	8.75
Set of 8 416's	49.95
4115 8K (16 Pin)	6.95
4050 4K x 1 (18 Pin)	4.95
4060 4K x 1 (22 Pin)	4.95
4096 4K x 1 (16 Pin)	3.95
2104 4K x 1 (16 Pin)	4.75
4027 4K x 1 (16 Pin)	4.95

64K RAMS $159.95

5261	1.95	1103	1.95
5262	1.95	4008L	4.95
5270	4.95	6605	7.95
5280	4.95	6604	4.95
5290	12.45	6002	1.50

SOCKETS

# Pins	Lo-Pro Soldertail	Wire Wrap 3 Level Tin	Wire Wrap 3 Level Gold
8	15	32	45
14	19	36	59
16	20	38	62
18	24	59	84
20	29	69	99
22	24	79	1.10
24	38	85	1.20
28	43	1.10	1.49
36	58	1.25	1.69
40	60	1.40	1.89

ZERO INSERTION FORCE

16 Pin $5.50 24 Pin $7.50 40 Pin $10.25

LED READOUTS

Part No	Size	Color	Description	Price
DL704	300	Red	Comm. Cathode	99
DL707	300	Red	Comm. Anode	99
FND357	357	Red	Comm. Cathode	99
FND501	500	Red	Comm. Cathode (+1)	99
FND503 (500)	500	Red	Comm. Cathode	99
FND507 (510)	500	Red	Comm. Anode	99
FND508	500	Red	Comm. Anode (+1)	99
FND530	500	Green	Comm. Cathode	1.49
FND550	500	Orange	Comm. Cathode	1.49
FND803 (800)	800	Red	Comm. Cathode	1.75
FND807 (810)	800	Red	Comm. Anode	1.75
HP5082-7340	600	Red	4 x 7 Hexidecimal	20.95
HP5082-7300	600	Red	4 x 7 Sgl. Digit RHD	18.95
HP5082-7731	300	Red	Comm. Anode	75
TIL305	–	Red	Array 5 x 7	7.95
TIL308	270	Red	Numerical Display	10.95
TIL309	270	Red	Numerical Display	9.95
TIL311	270	Red	4 x 7 Hexidecimal	10.95
MAN2A	320	Red	Array	5.95
MAN10A	270	Red	Alpha Numeric	8.95
XAN3061	300	Red	Comm. Anode Right DP	1.25
XAN3062	300	Red	Comm. Anode Left DP	1.25
XAN3063	300	Red	Overflow CA Left DP	1.25
XAN3064	300	Red	Comm. Cathode Right DP	1.25
XAN3051	300	Green	Comm. Anode Right DP	1.99
XAN3052	300	Green	Comm. Anode Left DP	1.99
XAN3053	300	Green	Overflow CA Left DP	1.99
XAN3054	300	Green	Comm. Cathode Right DP	1.99
XAN3081	300	Yellow	Comm. Anode Right DP	2.10
XAN3082	300	Yellow	Comm. Anode Left DP	2.10
XAN3083	300	Yellow	Overflow CA Left DP	2.10
XAN3084	300	Yellow	Comm. Cathode Right DP	2.10

IC SPECIAL PURCHASE

LF 13508 JFET Analog Multi 8 bit	8.95
ICM 7045 Precision StopWatch	23.95
CMOS LED Stopwatch/Timer	19.95
ICM 7207 Oscillator Controller	7.50
Seven Decade Counter	18.95
ICM 7209 Clock Generator	6.9_
ICL 7107 3½ Digit A/D (LED)	14.95
MC14433P 3½ Digit A/D Converter	13.95
ICL8211 Voltage Reference	1.95
LM 1850N Ground Fault IC	3/1.00
LM 2900N Quad Amplifier	2/1.00
LM 2917N Freq. to Volt Conv	2/1.99
AY-3-3550 4½ digit DMM	24.95
AY-5-3507 40MHz DVM	9.95
MEM 4963 Mosfet Smoke Detector	11.95
27S08 32 x 8 Prom (IM 5600)	2.95
G115M 6 channel Mosfet	1.49
ULN 2003A 7 channel Driver	.99
2101AL-4	1.95
MCM 14505 64 bit Static Ram	6.95
MOC 1003 (4N28) Opto Coupler	3/1.00
SPX33 Opto Coupler	3/1.00
IH 5045 CMOS Switch DBST	4.50
VA3045 Trans. Array	1.25
TR 1402A UART	1.95
MR 1007 Dyn. Mem. Shift Reg.	3.95
5736 Calc. Con. Circuit	2/1.99
5763 Calc. Con. Circuit	1.95
5318 TV Ch. Disp. Circuit	4.50
8080A 8 Bit CPU	4.95
82S21 32 x 2 Static RAM	2/1.99
8700 CJ 8 Bit A/D	9.95
2758 5V-2708 EPROM	8.95
MM5280/VPD 411/C2 107/TMS 4060/ 4Kx1 Dynamic 22 Pin RAM	1.75
6604/VPD 414/4027/2660/MK 4096/ 4Kx1 Dynamic 16 Pin	1.95

7520/25	50	LM 387	1.25
1488/1489	2/1.99	LM 3302	3/1.99
MK5014 Calc	3/1.99	LM 4558	3/1.99
LM320K	4.95	RC4136	2/1.99
MC1372	8.95	RC 4131	2/1.99
MM5298-4A/B	2.95	COM 5027	39.95
LM 377	1.25	COM 5037	49.95
LM380	1.25	DAC100	15.95

VERBATIM DISKETTES

100% CERTIFIED ERROR-FREE!

• 35 TRACKS DOUBLE DENSITY SINGLE-SIDED 5¼

TYPE	DESCRIPTION	PRICE BOX 10
525-01	Soft Sectored TRS 80 etc	$29.95
525-10	10 Hole Hard NS Apple etc	$29.95
525-16	16 Hole Hard Micropolis	$29.95

• 40 & 77 TRACK DOUBLE DENSITY – SINGLE SIDED 5¼ w/HUB REINFORCEMENT RING

577-01	Soft Sectored TRS 80 etc	$32.25
577-10	10 Hole Hard NS Apple etc	32.25
577-16	16 Hole Hard Micropolis	32.25

• 40 TRACKS DOUBLE SIDED DOUBLE DENSITY 5¼

550-01	Soft Sectored SA 450 MPI 52	$39.95
550-10	10 Hole Hard B45F WANGCO	$39.95
550-16	16 Hole Hard Micro	$39.95

• 8" 100% CERTIFIED DISKETTES

FD800-01	Soft Single Density 3740	$33.50
FD800-32	32 Hard Single Density Shug	33.50
FD802-01	Soft Double Density 3740	44.80
FD850-01	Soft Double Sided Double Density 3740	49.80

VOLUME DEALER PRICING AVAILABLE
WE ALSO STOCK DYSAN-CALL

FLOPPY DISK I/O

1771-01 8" & Minifloppy	24.95
uPd372 Nec Floppy	49.95
1781 Dual Floppy	29.95
1791-01 Dual Floppy	36.95
uPd765 Floppy	49.95
1793/1797 DD Floppy	49.95

A/D CONVERTERS

8700 8 bit Binary	13.50
8701 10 bit Binary	22.00
8703 8 bit TS	13.50
9400 Volt to Freq. Conv.	7.25
8750 3½ Digit BCD	13.95
1408L6 6 bit	3.95
1408L8 8 bit	5.95
DAC01 D to A	5.95
DAC08	9.95
DAC 100	15.95

TV CHIPS/SOUND

AY38500-1 6 Games B/W	4.95
AY38515 Color Converter	2.95
AY38603-1 Roadrace Game	8.95
AY38606-1 Wipeout Game	9.50
AY38607-1 Shooting Gallery	8.95
AY38910 Sound Generator	12.95
SN76477 TI Sound Generator	3.95
MM5320/21 TV SynchGen	9.95
MM5369 Prescaler	3.95
LM1889 RF Modulator	3.95
MM57100 NSC Color TV	6.95
MM57104 Clock Gen	3.75
M&R Modulator	29.95

WAVEFORM GEN.

8038 Function Gen	3.95
MC4024VCO	2.95
LM566 VCO	1.95
XR2206 Function Generator	5.25

SHIFT REGISTERS

MM500H Dual 25	50
MM5056N Dual 256	2.95
MM5060N Dual 126	2.95
2510A Dual 100	1.95
2847 Quad 80	4.95
3341 Dual 80	4.95
3351 40 x 9 FIFO	17.95
3357 Quad 80	6.95
9403 16 x 4 FIFO	24.95
9408 10 Bit Sequencer	9.95
3347	5.95

CTS DIPSWITCHES

CTS206-2	1.75	CTS206-7	1.75
CTS206-4	1.75	CTS206-8	1.95
CTS206-5	1.75	CTS206-9	1.95
CTS206-6	1.75	CTS206-10	1.95

CONNECTORS (GOLD)

DB25P (RS232)	3.25
DB25S Female	3.75
Hood	1.25
Set w/Hood, Sale	$7.50
22/44 W/W, S/T, KIM	2.95
43/86 W/W, S/T, MOT	6.50
50/100 S-100 Connector w/w	4.95
50/100 S-100 Connector s/t	3.95

NAKED PC

S-100 Sound Board	$34.95
Z-80 CPU/(Ithaca)	44.95
8080A CPU	34.95
16K Static RAM (2114)	29.95
32K Static RAM (2114)	39.95
8K Eprom (2708)	24.95
2708/2716 Eprom	34.95
ACP Proto Bd (3M Conn.)	27.95
Vector 8800 Proto	22.20
Vector 8803 11 slot MB	29.95
ACP Extender w/Conn.	18.95
13 Slot Mother Board (WMC)	32.95
9 Slot Mother Board (WMC)	29.95
8 Slot Mother (Expandable)	34.95
Floppy PCB (8" SHUGART)	39.95
S100 (AY5-8910) Sound Bd	34.95
Apple Sound Bd.	24.95

MONTHLY SPECIALS

★ S100 Wire Wrap Connector $3.00 each
★ 2708's 8 for $30.00

ACOUSTIC MODEM

NOVATION CAT™ 0-300 Baud
Bell 103 Answer, Originate

'D' CAT MODEM NOW AVAILABLE $199.00

MONITORS

Sanyo 5112CX Green Phosphor	$279.00
Sanyo 5012 CX B/W	279.00
Sanyo VM 4509 9" B/W	169.00
Sanyo VM 4212 15" B/W	249.00
Sanyo 6013 13" Color	429.00
Leedex 12"	149.00

SOCKET SPECIALS

14, 16, 18 & 22 Pin Soldertail
.12 each
100 for $12.00

TERMS: Use check, M/C, VISA, AMEX, CB, or COD. COD requires 25% deposit. Charge Orders please include expiration date. Foreign pay US Funds. Order by phone, mail or TWX. MINIMUM $10.00. Please include magazine issue and phone no. SHIPPING: U.S.A. add $2.00 for first 2 lbs. For surface add 30¢ for additional lbs. For air add 70¢ for additional lbs. FOREIGN: Add 10% shipping and handling. COD's $1.85 extra. Not responsible for typos. Some items subject to prior sale. We reserve the right to limit quantities, some items subject to precious metal adder. Retail pricing may vary from Mail Order. We reserve the right to substitute manufacturer.

RETAIL STORES OPEN MON-SAT
STORE #1: 1310 "B" E. Edinger, Santa Ana, CA 92705 Showrooms, Retail, Warehouse
STORE #2: 542 W. Trimble Road, San Jose, CA 95131 • (408) 946-7010

P.O. Box 17329 Irvine, Calif. 92713
Direct Order Lines: (714) 558-8813
(800) 854-8230 or (800) 854-8241

FOR INTERNATIONAL ORDERS:
1310 E. Edinger (714) 953-0604
Santa Ana, CA 92705 TWX: 910-595-1565

Circle 7 on inquiry card.

MOVING SALE MOVING SALE

DETACH OUR CATALOG FROM THE MAY BYTE

MODEM SALE

$129.00

THE STAR MODEM from LIVERMORE

FEATURE FITS GTE HANDSETS!

2 YEAR WARRANTY

EXCLUSIVE ACOUSTIC CHAMBERS

The exclusive triple seal of Livermore's new flat mounted cups locks the handset into the acoustic chamber yielding superior acoustic isolation and mechanical cushioning. Designed to adapt to most common handsets used throughout the world, the STAR offers the utmost in flexibility and transmission reliability.

Specifications:
- **Data Rate:** 0 to 300 baud
- **Compatibility:** Bell 103 and 113; CCITT
- **Frequency Stability:** ±0.3 percent. Crystal controlled
- **Receiver Sensitivity:** −50 dBm ON, −53 dBm OFF
- **Modulation:** Frequency shift keyed (FSK)
- **Carrier Detect Delay:** 1.2 seconds ON; 120 msec OFF
- **EIA Terminal Interface:** Compatible with RS 232 specifications
- **Teletype Interface:** 20 milliampere current loop
- **Optional Interfaces:** IEEE 488; TTL; TTY 43
- **International (CCITT) frequencies available**
- **Switches:** Originate/Off/Answer; Full Duplex/Test/Half Duplex
- **Indicators:** Transmit Data, Receive Data, Carrier Ready, Test
- **Power:** Supplied by 24 VAC/150 MA UL/CSA listed wall-mount transformer. Input 115 VAC, 2.5 watts. (A 220 VAC, 50 Hz adaptor is available upon request.)
- **Dimensions:** 10″ x 4″ x 2″
- **Weight:** 1.74 lbs. (3 lbs. shipping weight including AC adaptor.)
- **Warranty:** Two years on parts and labor, excluding the AC adaptor which carries the manufacturer's warranty

Part No.	Description	List Price	SALE PRICE
LIV-STAR	RS232, TTL, 20 MA Current Loop	$199.00	$129.00

CABLES

Part No.	Description	Price
CND-RS2328F	RS232 8 Cond 8 ft.	$19.95

RS232 and "D" SUB-MINIATURE CONNECTORS



P = Plug, Male Type - S = Socket, Female Type - C = Cover, Hood

PART NO.	DESCRIPTION	PRICE 1-9	10-24	25-99
CND-DE9P	9 PIN MALE	$ 2.10	$ 1.90	$ 1.70
CND-DE9S	9 PIN FEMALE	$ 2.70	$ 2.40	$ 2.10
CND-DE9C	9 PIN COVER	$ 1.50	$ 1.25	$ 1.10
CND-DA15P	15 PIN MALE	$ 2.75	$ 2.45	$ 2.15
CND-DA15S	15 PIN FEMALE	$ 3.95	$ 3.60	$ 3.20
CND-DA15C	15 PIN COVER	$ 1.50	$ 1.30	$ 1.10
CND-DB25P	25 PIN MALE	$ 3.00	$ 2.75	$ 2.60
CND-DB25S	25 PIN FEMALE	$ 4.00	$ 3.75	$ 3.50
CNO-0851212	1 PC. GREY HOOD	$ 1.60	$ 1.45	$ 1.30
CND-P25H	2 PC. GREY HOOD	$ 1.50	$ 1.25	$ 1.10
CNO-0851226	2 PC. BLACK HOOD	$ 1.90	$ 1.65	$ 1.45
CND-DC37P	37 PIN MALE	$ 5.80	$ 5.10	$ 4.45
CND-DC37S	37 PIN FEMALE	$ 8.70	$ 7.70	$ 6.70
CND-DC37C	37 PIN COVER	$ 1.80	$ 1.55	$ 1.30
CNO-0050P	50 PIN MALE	$ 8.75	$ 7.75	$ 6.70
CNO-0050S	50 PIN FEMALE	$11.65	$10.25	$ 8.90
CNO-0050C	50 PIN COVER	$ 2.00	$ 1.80	$ 1.60
CNO-D20418	HARDWARE SET 2 PR.	$ 1.00	$ 0.80	$ 0.70
CND-RS2328F	RS232, DB25P, EIA CLASS 1 CABLE 8 CON 8 FT	$19.95	$17.95	$15.95
CNO-5730360	CENT. 700 SERIES PRINTER CONNECTOR	$ 9.00	$ 7.50	$ 6.00

GOLD S-100 CONNECTORS

SOLDER TAIL PRICE

Part No.	1-9	10-24	25-99	100-249
S100 STG	3.20	2.90	2.50	2.20

WIRE WRAP PRICE

Part No.	1-9	10-24	25-99	100-249
S100 WWG	4.00	3.75	3.50	3.25

2016P3

2Kx8 L/P STATIC RAM

8/$100.00

2708 $8.50 EA.

450ns 8K EPROM

8/$32.00

2716 $11.95 EA

450ns 5 Volt only 16 K EPROM

8/$48.00

2114-3L

4096 BIT (1024x4) 300ns LOW POWER STATIC RAM

8/$30.00

100 + $3.00

5257-3L

(TMS 4044)
4096x1 300ns LOW POWER STATIC RAM

8/$50.00

100 pcs. + $4.75

TRS-80/APPLE

MEMORY EXPANSION KITS

4116's RAMS

from Leading Manufacturers

(16Kx1 200ns)

100% GUARANTEED — 1,000's SETS SOLD

8 for $24.00

ADD $3.00 FOR PROGRAMMING JUMPERS FOR TRS-80 KEYBOARD

4116's 100 pcs & UP $2.75 each

1000 pcs & UP $2.50 each

PROTECT YOUR INVESTMENT
PROTECT YOUR DATA WITH

ISOBAR



GOF-IBAR46
- Inductively isolated grounds
- Sockets individually filter isolated
- Each socket isolated from power line

LIST PRICE $79.95

SALE PRICE $39.95



6 OUTLET MULTI USE CORD REEL

SH. WT. 5 LBS.

THE CONVENIENCE OF AN EXTENSION CORD AND POWER DISTRIBUTION PANEL IN ONE COMPACT, SELF-STORING UNIT!

- SIX GROUNDED 3-PRONG OUTLETS!
- 7 M (22 FT. or 50 FT.) 14 GAUGE, 3-CONDUCTOR POWER CORD - RATED FOR INDOOR/OUTDOOR USE!
- CIRCUIT BREAKER FOR SAFETY'S SAKE — GUARDS AGAINST OVERLOADS ABOVE 10 AMPS
  INDESTRUCTIBLE SPACE-AGE PLASTIC CASE DESIGNED FOR YEARS OF HEAVY USE!

GOF-CR21 22 Ft. - 5 lbs. **$24.95**
GOF-CR50 50 ft. - 10 lbs. **$39.95**

THE EXPANDABLE 1™



THE UNIVERSAL IEEE-S100 DYNAMIC MEMORY CARD

THE EXPANDALBE 1 TM 64K Dynamic Ram board provides your S-100 system with 64K of reliable, high-speed dynamic RAM. Compatible with most of the major S-100 systems on the market, including those with front panels, it supports DMA operations and requires no Wait states with current microprocessors.

- *User expandable from 16 to 64 K*
- *2 or 4 MHz operation*
- *North Star compatible*
- *Cromemco Compatible*
- *Designed to IEEE proposed S-100 bus standards*
- *Supports IMSAI-type front panels*
- *Operates with either an 8080 or Z-80 based S-100 system, providing processor-transparent refreshes with both*
- *Bank-select system allows system memory expansion and is compatible with Cromemco products*
- *Bank select port's address is jumper selectable*
- *Any 16K block can be made bank-independent*
- *All 64K can be made bank-enabled on power-on and reset*
- *Configuration as a 16K, 32K, or 48K board without the removal of RAMs*
- *Fully buffered address and data lines*
- *Fail-safe refresh circuitry for extended Wait states*
- *Board configuration with reliable, easy-to-configure Berg jumpers*
- *Supports DMA*
- *Jumper-selectable Phantom input*
- *Uses Popular 4116 RAMS*
- *Assembled & tested*
- *All ICs in sockets*
- *Power supply: Unregulated +8, + 16, and − 16 volts*
  Maximum power draw: 400 mA at + 8 volts
  175 mA at + 16 volts
  5 mA at − 16 volts
  Dissipation: less than 8 watts
- *Temperature: 0 to 70 degrees Celsius*
- *Humidity: 0 to 90% noncondensing*
- *PC Board*
- *FR-4 glass epoxy*
- *Solder mask on both sides*
- *Gold-plated connector fingers*
- *Silk screen component outlines, reference numbers, and part designations*

PRI-EXP1-16

$299.00

Factory Assembled and Tested 16K Board. For additional memory order 1 set of 8 4116's at the left for each additional 16K. *PRIORITY ONE ELECTRONICS* can supply the board A&T populated to 32K, 48K, or 64K at additional cost, see our catalog or call for pricing.

Ciarcia's Circuit Cellar

MICROMOUTH

SPEECH PROCESSOR

AS FEATURED IN JUNE BYTE, PAGE 46



- 144 expression vocabulary
- Assembled and Tested
- Complete Documentation
- Connect to a speaker or Power Amplifer
- Plugs into Apple II
- Plug compatable with TRS-80 Model 1
- May be adapted to run on the S-100, H-8, or any parallel part.

		OUR PRICE
MMI-94VOAPL	For use with APPLE II, or modified to run with other parallel parts	$149.00
MMI-94VOTRSI	TRS-80 Model I compatable, complete with interface cable and AC Adapter, less enclosure	$169.00

PRIORITY ONE ELECTRONICS

9161-B DEERING AVE. • CHATSWORTH, CA 91311

Terms: U.S.; VISA, MC, BAC, Check, Money Order, U.S. Funds Only. CA. residents add 6% Sales Tax. MINIMUM PREPAID ORDER $15.00. Include MINIMUM SHIPPING & HANDLING of $2.50 for the first 3 lbs., plus 25¢ for each additional pound. Orders over 50 lbs. sent freight collect. Just in case...please include your phone no. Prices subject to change without notice. We will do our best to maintain prices thru JULY, 1981. SOCKET and CONNECTOR prices based on GOLD, not exceeding $700.00 per oz.

Sales Prices are for prepaid orders only. Credit Card orders will be charged appropriate freight.

DETACH OUR CATALOG FROM THE MAY BYTE

ORDER TOLL FREE 1-800-423-5922 CA., AK., HI., (213) 709-5464

Circle 320 on inquiry card.

VISIT OUR GIANT NEW RETAIL STORE

DETACH OUR CATALOG FROM THE MAY BYTE

SCOPE SALE

OUR LOWEST PRICES OF THE YEAR!

HITACHI
Hitachi Denshi,Ltd.

Single and dual trace, 15 thru 100 MHz. All high sensitivity Hitachi oscilloscopes are built to demanding Hitachi quality standards and are backed by a 2-year warranty. They're able to measure signals as low as 1mV/division (with X5 vertical magnifier). It's a specification you won't find on any other 15 or 30 MHz scopes. Plus: Z-axis modulation, trace rotation, front panel X-Y operation for all scope models, and X10 sweep magnification. And, 30 thru 100 MHz oscilloscopes offer internal signal delay lines. For ease of operation, functionally-related controls are grouped into three blocks on the color coded front panel. Now here's the clincher: For what you'd expect to pay more, you actually pay less. Check our scopes before you decide. All scopes complete with probes.

Hitachi...The measure of quality.
HITV302B

30MHZ DUAL TRACE OSCILLOSCOPE
List $995.00
SALE $819.00



- TV sync-separater circuit
- High-sensivity 1mV/div (5MHz)
- Sweep-time magnifier (10 times)
- Z-axis input (intensity modulation)
- Signal delay line
- Complete with 2 probes
- CHI, CH2, DUAL, ADD, DIFF, Vertical Deflection Modes
- X-Y operation
- Trace Rotation

HITV152B DUAL TRACE 15MHZ (no delay)
LIST $735.00 **SALE $629.00**



HIT-V202
20MHz DUAL TRACE
LIST PRICE: $850
SALE PRICE: $775.00

- Dynamic range 8 div.
- TV sync-separator circuit
- Built-in signal delay line (V-352)
- X-Y operation
- Sweep-time magnifier (10 times)
- Trace rotation system
- Fine-adjusting, click-positioning function

HIT-V352
35MHz DUAL TRACE WITH DELAY
LIST PRICE: $1150.00
SALE PRICE $950.00

- Economically priced dual trace oscilloscope
- Square CRT with internal graticule (illuminated scale)
- High-accuracy voltage axis & time axis set at ± 3% (certified at 10° to 35°C)
- High-sensitivity 1mV/div.
- Low drift
- 2 Year Warranty

50MHz & 100 MHz DUAL TRACE WITH CALIBRATED TIME DELAY

HIT V550B
50MHz with 3rd TRACE TRIGGER VIEW
LIST $1745.00
SALE
$1495.00

HIT V1050
100MHz with 3rd & 4th TRACE TRIGGER VIEW
LIST $2390.00
SALE
$1995.00

The HITACHI V550B (50mHz) and V1050 (100mHz) offer all the capabilities you might expect from a lab grade oscilloscope. Capabilities such as 3rd trace trigger view, a bright 6" square CRT, and a max. sweep rate of 2ns/div (V1050) 5ns/div (V550B). Also, features you may not expect like, sensitivity of 1mv/div (V550B) .5mv/div (V1050) @ 10mHz, automatic focus correction.

EPSON MX-80 PRINTERS



Among its features, the MX-80 prints 96 ASCII, 64 graphics and 8 international character in tack-sharp 9x9 matrix. It prints bidirectionally at 80 CPS with a logical seeking function to maximize all of these capabilities. And it has the world's first disposable print head, with a life expectancy of over 50 million characters. When it wears out, just snap it out and throw it away! A newone costs less than $30., and you can install it yourself...with one hand.

The most revolutionary thing about he Epson MX-80 isn't the bidirectional printing or the logical seeking function. It isn't even the disposable print head -although that's pretty revolutionary. The most revolutionary thing about the MX-80 is the price.

EPN-MX80	MX80 Tractor Feed List $649.00 Sale Price	$475.00
EPN-MX80V2	MX80 with Graphics option	$525.00
EPN-MX80TF	MX80 with both tractor and friction feed	$575.00
EPN-MX82	MX80 with high density graphics option	$575.00

Vector

S-100 COMPATIBLE PLUGBOARDS FOR INTERFACE, MEMORY EXPANSION, EXPERIMENTATION



VCT-8800V
Universal Microcomputer/processor plugboard, use with S-100 bus. Complete with heat sink & Hardware. 5.3" x 10" x 1/16."

1 - 4	5 - 9	10 - 24
$22.48	$20.37	$18.26



VCT-8801-1
Plain no etched circuitry except contacts. Produces maximum flexibility.

1 - 4	5 - 9	10 - 24
$15.67	$14.24	$12.82

TEI MicroFrame®



From the power supply through the sturdy chassis, TEI constructs and assembles each mainframe with great care. Every TEI mainframe utilizes a constant voltage transformer (CVT) which delivers clean, regulated power at the proper level, reducing the heat in the computer cards. The output voltage on the transformer remains nearly even with the input voltage varying from approximately 85V to 140V. This means the mainframe will never notice voltage variations or even a brownout. It also provides 100 dB noise rejection to protect the computer from voltage spikes and line noise.

No need for a dedicated line or expensive noise filters. TEI was the first manufacturer to offer the CVT in it's complete computer product line and is still one of few manufacturers to offer the CVT as standard equipment.



TEI 22 slot and 12 slot mainframes offer a S-100 motherboard which is grounded, shielded and actively terminated for high speed operation now or for later upgrading. Each mainframe is shipped completely assembled, tested and burned in, with fan, washable filter, all connectors and card guides. Rackmount models are available in both 22 and 12 slot mainframes. The combination of the lowest noise bus, a regulated CVT power system and a rugged chassis produces a mainframe without equal.

S-100 MAINFRAMES		LIST PRICE	OUR PRICE
TEI-MCS 112	12 Slot Desk	$685.00	$615.00
TEI-MCS 122	22 Slot Desk	$845.00	$760.00
TEI-RM 12	12 Slot Rackmount	$800.00	$720.00
TEI-RM 22	22 Slot Rackmount	$945.00	$850.00
Shipping Weight:	On 12 Slot Mainframes	35 Lbs.	
	On 22 Slot Mainframes	50 Lbs.	

12 slot; +8V @ 17A, ±16V @ 2A; 35 lbs.
22 slot; +8V @ 30A, ±16V @ 4A; 50 lbs.
Shipping Weight: On 12 Slot Mainframes 40 Lbs
On 22 Slot Mainframes 55 Lbs



S-100 MAINFRAME WITH 12 SLOT MOTHERBOARD AND CUTOUTS FOR 3 5¼" FLOPPY DISK DRIVES
WITH INTERNAL POWER CABLES

		LIST PRICE	OUR PRICE
TEI-TF12	12 slot desk	695.00	625.00
TEI-RF12	12 slot rackmount	795.00	715.00

DUAL 8" DISK DRIVE CHASSIS
For Shugart 800/801R with internal power cables provided

		LIST PRICE	OUR PRICE
TEI-DFDO	Desk Top	669.00	599.00
TEI-RFDO	Rack Mount	819.00	749.00

**Priority 1 Electronics* is a master stocking distributor for T.E.I. Dealers & O.E.M.'s. Call for quantity pricing.

DETACH OUR CATALOG FROM THE MAY BYTE

PRIORITY ONE ELECTRONICS

master charge

9161-B DEERING AVE. • CHATSWORTH, CA 91311

VISA

Terms: U.S.: VISA, MC, BAC, Check, Money Order, U.S. Funds Only. CA. residents add 6% Sales Tax. MINIMUM PREPAID ORDER $15.00. Include MINIMUM SHIPPING & HANDLING of $2.50 for the first 3 lbs., plus 25¢ for each additional pound. Orders over 50 lbs. sent freight collect. Just in case...please include your phone no. Prices subject to change without notice. We will do our best to maintain prices thru JULY, 1981. SOCKET and CONNECTOR prices based on GOLD, not exceeding $700.00 per oz.
Sales Prices are for prepaid orders only. Credit Card orders will be charged appropriate freight.

ORDER TOLL FREE 1-800-423-5922 CA., AK., HI., (213) 709-5464

Circle 320 on inquiry card.

THE BEST PRODUCTS AT THE BEST PRICES FROM PRIORITY ONE ELECTRONICS WE INVITE YOU TO SHOP & COMPARE

TOLL FREE 1-800-423-5922

S-100 CPU

CPU-Z - GODBOUT
2/4 MHZ Z80 CPU 24 Bit Addressing

GBT 160U	UnKit	$225.00
GBT 160A	A&T	$280.00
GBT 160C	CSC 3-6 MHZ	$375.00

DUAL PROCESSOR 8085-8088 - GODBOUT
5 MHZ Provides true 16 Bit Power with a standard 8 bit S-100 bus.

GBT 1612U	UnKit	$295.00
GBT 1612A	A&T	$399.00
GBT 1612C	CSC	$498.00

BOARD WITH 8085 ONLY

GBT 161U	UnKit	$235.00
GBT 161A	A&T	$305.00
GBT 161C	CSC	$399.00

2810 Z80 CPU-CA. COMP. SYST.
2/4 MHZ Z80A CPU with RS-232C Serial I/O Port complete with Monitor PROM for 2422 Disk Controller

CCS 2810	A&T	$280.00

CB2 Z80 CPU - S.S.M.
2/4 MHZ will accept 2716, or 2732, or RAM RUN/STOP and single step switches

SSMCB2K	Kit	$260.00
SSMCB2A	A&T	$310.00
SSMZ80M	SSM Z80 Monitor	$89.00

CBIA 8080 CPU - S.S.M.
8080CPU, 1K RAM, Holds 1 2708, 1 8 Bit parallel input port.

SSMCB1A	Kit	$183.00
SSMCB1A	A&T	$225.00
SSM8080M	SM 8080 Monitor	$59.00

S-100 RAM

64K STATIC RAM - GODBOUT
RAM 17, 10 MHZ, 2 Watt, DMA Compatable

GBT-175A48	A&T 48K	$950.00
GBT-175C48	CSC 48K	$1050.00
GBT-175A64	A&T 64K	$995.00
GBT-175C64	CSC 64K	$1395.00

64K DYNAMIC RAM - CCS
4 MHZ, on board refresh, DMA compatable, 24 bit address.

CCS-2065A	A&T	$599.00

32K STATIC RAM - GODBOUT
RAM 20 10 MHZ, 4K byte block disable, available 16, 24, or 32K

GBT-164A16	A&T 16K	$319.00
GBT-164C16	CSC 16K	$418.00
GBT-164A24	A&T 24K	$449.00
GBT-164C24	CSC 24K	$539.00
GBT-164A32	A&T 32K	$499.00
GBT-164C32	CSC 32K	$720.00

32K STATIC RAM - CCS
4 MHZ, Bank select, 8/16 bit data

CCS-2032	A&T 32K	$599.00

16K STATIC RAM - GODBOUT
RAM 14, 10 MHZ, 24 bit addressing

GBT-143A	A&T 16K	$199.00
GBT-143C	CSC 16K	$399.00

16K STATIC RAM - CCS
4 MHZ, 8/16 bit data, bank select

CCS-2116A	A&T 16K	$299.00

8K STATIC RAM - GODBOUT
Econoram II 2MHZ, 8K, No doubt, the most popular S-100 RAM ever built.

GBT-114U	UnKit 8K	$99.95

S-100 ROM

PB1 PROM PROGRAMMER - SSM
programs 2708 or 2716's, operates as a 4K/8K EPROM board as well.

SSM-PB1K	Kit	$179.00
SSM-PB1A	A&T	$239.00

ECONOROM 2708 - GODBOUT
16K x 8 EPROM Board using 2708, Power on jump to any 256 byte

GBT 125U	UnKit	$85.00
GBT 125A	A&T	$120.00
GBT 125C	CSC	$175.00

S-100 DISK CONTROLLERS

DISK 1 - GODBOUT
DMA, Soft Sector, Controls 8" or 5¼", single or double density

GBT 171A	A&T	$450.00
GBT 171C	CSC	$555.00
GBT CPM80	CP/M 2.2 for Z80/8085 with Manuals & BIOS 8" S.D. disk	$175.00
GBT CPM86	CP/M for 8086 with manuals & BIOS 8" S/D disk	$300.00

2422A - CA. COMP. SYST.
I/O Mapped, controls 8" or 5¼", single or double density

CCS-2422	A&T with CPM 2.2 8" S.D.	$375.00

DISK JOCKEY 1 - MORROW
Single density disk controller with serial I/O, controls 8"

MDSDJ1108	A&T	$219.00

DISK JOCKEY 2D - MORROW
I/O Mapped, controls 8", single or double density, serial I/O

MDSDJ2208	A&T	$375.00

DISK DRIVES

80IR - SHUGART
Single sided double density most popular 8" drive

SHU80IR	$425.00 ea. or 2 or more	$410.00
SHUSA80IRM	Manual for 80IR drives	$10.00

DT-8 - QUME
Data track 8 double sided, double density

QME-DT8	$625.00 ea. or 2 or more	$600.00 ea.

DISK CABINETS

V-100 - VISTA
Dual 8" drive cabinet with power supply. Rack or Desk Mount

VIS-V100	$395.00

SINGLE 8" - Q.T.
Single 8" cabinet with power supply

QTC-DDC8	$195.00

5" CABINETS - VISTA

VIS-9801	Single 5" with P.S.	$75.00
VIS-9802	Dual 5" with P.S.	$95.00

S-100 DISK SUBSYSTEMS

DISCUS SINGLE SIDES MORROW
8" DBL Density drives with cabinet, power supply controller, with CP/M 2.2 with Microsoft Basic

MDSF1218	Single Drive System	$950.00
MDSF1228	Dual Drive System	$1598.00

DISCUS DOUBLE SIDED - MORROW
8" DBL Density/sided drives with cabinet Power supply controller, with CP/M 2.2 and Microsoft Basic

MDSF2218	Single Drive System	$1198.00
MDSF2228	Dual Drive System	$2190.00

26MB HARD DISK - MORROW

Special purchase, limited stock - 26MB formatted hard disk complete with cabinet, P.S., Controller, CPM 2.2 and Microsoft Basic

MDS-M26S	26 MB Subsystem List	$4995.00

SALE

★ $3950.00 ★

SAVE $1,045.00!

MICROPOLIS

Priority 1 Electronics is the worlds largest distributors of MICROPOLIS disk sub systems

S-100 I/O BOARDS

SYSTEM SUPPORT 1 - GODBOUT
Serial port (software prog baud), 4K EPROM or RAM provision, 15 levels of interrupt, real time clock, optional math processor

GBT-162U	UnKit	$295.00
GBT-162A	A&T	$360.00
GBT-162C	CSC	$460.00
GBT-9512	Math Chip	$195.00

MPX CHANNEL BOARD - GODBOUT
I/O Multiplexer, using 8085A-2 cpu on board

GBT-166A	A&T	$450.00
GBT-166C	CSC	$550.00

INTERFACER I - GODBOUT
Two Serial I/O

GBT-133A	A&T	$219.00
GBT-133C	CSC	$298.00

INTERFACER II - GODBOUT
Three parallel, one serial I/O board

GBT-150A	A&T	$219.00
GBT-150C	CSC	$298.00

MULTI I/O - MORROW DESIGNS
Three Serial, Two parallel

MDSMB3200	A&T	$309.00

SWITCHBOARD-MORROW DESIGNS
Two serial I/O, four parallel I/O, one status port, one strobe port

MDSSB2411	A&T	$239.00

I/O2 - SSM
One parallel input, one parallel output, proto work area

SSMI02K	Kit	$69.00
SSMI02A	A&T	$89.00

I/O4 - SSM
Two serial I/O, two parallel I/O

SSMI04K	Kit	$210.00
SSMI04A	A&T	$260.00

SBI-SSM
Music synthesizer board

SSMSBIK	Kit	$249.00
SSMSBIA	A&T	$310.00
SSMSBIS	Software	$ 25.00

S-100 VIDEO BOARDS

SPECTRUM - GODBOUT
Color Graphics board with Parallel I/O.

GBT-1440	UnKit	$299.00
GBT-144A	A&T	$349.00
GBT-2D	Sublogic Software	$ 35.00

VB - 3 S.S.M.
80 x 24 or 48 character video display Memory Mapped, Parallel Keyboard port

SSM-VB3K24	Kit 80x24	$359.00
SSM-VB3A24	A&T 80x24	$450.00
SSM-VB3K48	Kit 80x48	$425.00
SSM-VB3K48	A&T 80x48	$495.00
SSM-VB3UP	Upgrade Kit	$ 50.00

VB2 - SSM
I/O Mapped Video Board, with Parallel Keyboard port. 64x16

SSM-VB2K	Kit	$169.00
SSM-VB2A	A&T	$229.00

VBIC - SSM
Memory Mapped Video Board 64x16 character display or 64x16 graphics dislplay

SSM-VBICK	Kit	$169.00
SSM-VBICA	A&T	$229.00

S-100 MOTHERBOARDS

MOTHERBOARD - GODBOUT
Active termination, 6-12-20 slot

GBT-153U	Unkit 6 slot	$ 89.00
GBT-153A	A&T 6 slot	$119.00
GBT-154U	Unkit 12 slot	$129.00
GBT-154A	A&T 12 slot	$149.00
GBT-155U	Unkit 20 slot	$174.00
GBT-155A	A&T 20 slot	$189.00

WUNDERBUSS - MORROW DESIGNS
Active termination, 8-12-20 slot, peripheral power outputs (5V@1A, 12V @ 500ma, –12V @ 500ma)

MDS0800K	Kit 8 slot no connectors	$ 54.00
MDS1200K	Kit 12 slot no connectors	$ 65.00
MDS2000K	Kit 20 slot no connectors	$ 76.00
MDS0800A	A&T 8 slot	$129.00
MDS1200A	A&T	$149.00
MDS2000A	A&T 20 slot	$199.00

SILENCE + – QT COMPUTER
6, 12, and 18 slot, very high crosstalk rejection, LED power indicator, operation up to 14MHZ

QTC-MB6BB	6 slot bare board	$ 25.00
QTC-MB6K	6 slot kit	$ 40.00
QTC-MB6A	6 slot A&T	$ 50.00
QTC-MB12BB	12 slot bare board	$ 30.00
QTC-MB12K	12 slot kit	$ 70.00
QTC-MB12A	12 slot A&T	$ 90.00
QTC-MB18BB	18 slot bare board	$ 50.00
QTC-MB18K	18 slot kit	$100.00
QTC-MB18A	18 slot A&T	$140.00

S-100 MISC.

CKO17 ACTIVE TERMINATOR-GODBOUT

GBT-106U	Kit	$ 34.95

2520 - CCS
Extender/terminator, Active and/or passive

CCS2520AK	Kit	$ 59.00

EXTENDER/LOGIC PROBE-MULLEN

MUL-CK004	Kit	$ 59.00

OB1 VECTOR JUMP - SSM
with prototyping area

SSM-OB1K	Kit	$ 65.00
SSM-OB1A	A&T	$ 90.00

CLOCK CALENDAR-QT COMPUTER
seconds to leap year, on board battery back-up

QTC-CCSBB	bare board	$ 45.00
QTC-CCSK	Kit	$100.00
QTC-CCSA	A&T	$150.00
QTC-CC5D	App program (5¼" disk)	$ 10.00
QTC-CCS8D	App program (8" disk)	$ 12.00

CA, AK, HI, (213) 709-5464

PRIORITY ONE ELECTRONICS

9161-B DEERING AVE. • CHATSWORTH, CA 91311

NEED MORE INFORMATION? SEE OUR 60 PAGE CATALOG IN MAY BYTE

Terms: U.S.; VISA, MC, BAC, Check, Money Order, U.S. Funds Only. CA. residents add 6% Sales Tax. MINIMUM PREPAID ORDER $15.00. Include MINIMUM SHIPPING & HANDLING of $2.50 for the first 3 lbs., plus 25¢ for each additional pound. Orders over 50 lbs. sent freight collect. Just in case...please include your phone no. Prices subject to change without notice. We will do our best to maintain prices thru JULY, 1981. SOCKET and CONNECTOR prices based on GOLD, not exceeding $700.00 per oz.
Sales Prices are for prepaid orders only. Credit Card orders will be charged appropriate freight.

Circle 321 on Inquiry card.

ANOTHER FAMOUS
PRIORITY 1 ELECTRONICS
TRUCK LOAD PURCHASE
10 MHZ 16K A&T STATIC S-100 RAM FROM



SAVE $150.00

GBT-143A
List
$349.00

$199.00

The **RAM 14** provides 16K X 8 of reliable, totally static RAM storage. Conforming fully to the IEEE 696/S-100 bus standard, **RAM 14** not only provides 24 address lines for 16 megabyte extended addressing capability, but also includes a number of features you would only expect to find in memory boards costing considerably more. Here's a partial listing of what makes **RAM 14** your best choice!

- Operates up to 10 MHZ (90 ns RAM Chips)
- Assembled & Tested
- Meets or exceeds all IEEE 696/S-100 specifications (including timing).
- Fully static design eliminates the timing problems associated with dynamic memories.
- Switch selectable choice of 24 address lines conforming to the IEEE 696/S-100 extended addressing specifications, or 16 address lines as used in older S-100 systems.
- Ideal for multi-user installations.
- Board is addressable as one 16K x 8 block on any 4K boundary.
- Switch selectable PHANTOM disable and write protect.
- +5 Volt operation (requires no other supply voltages).
- Low power operation (900 mA typical, 1200 mA maximum).
- 1 year Factory Warranty.

CompuPro™ division of GODBOUT ELECTRONICS

Circle 321 on inquiry card.



ORDER TOLL FREE
1-800-423-5922
except CA., AK., HI., CALL
(213) 709-5464

PRIORITY ONE ELECTRONICS
9161-B DEERING AVE. • CHATSWORTH, CA 91311

Terms: U.S.; VISA, MC, BAC, Check, Money Order, U.S. Funds Only. CA. residents add 6% Sales Tax. MINIMUM PREPAID ORDER $15.00. Include MINIMUM SHIPPING & HANDLING of $2.50 for the first 3 lbs., plus 25¢ for each additional pound. Orders over 50 lbs. sent freight collect. Just in case...please include your phone no. Prices subject to change without notice. We will do our best to maintain prices thru JULY, 1981. SOCKET and CONNECTOR prices based on GOLD, not exceeding $700.00 per oz. Sales Prices are for prepaid orders only. Credit Card orders will be charged appropriate freight.

WIREMASTER

A COMPILER FOR HARDWARE

- **WIREMASTER** is a software tool to aid in the design, layout, and construction of electronic hardware. It is intended primarily for wire wrap, though it is also highly useful in the layout, error-checking, and trouble-shooting of PC boards.

- Inputs are easily derived directly from the schematic diagram and fed to **WIREMASTER** in a CP/M* text file. Outputs include a **network map** that graphically shows all pins and wires, a **wire list** sorted by lengths and levels, a **parts list**, wrap count and continuity **checklists**, plus signal and pin **cross-references**.

- The resulting information is then used for PC board layouts, error-checking, wiring, component-stuffing, and system-debugging. This forms a complete and easily updated documentation package. Although it runs on small computers, **WIREMASTER** can handle large projects.

- **WIREMASTER** runs on any Z80† CP/M system of 47K or larger, including TRS-80‡ Model II and Apple via SoftCard§.

Complete Package— $150; Manual only— $5

AFTERTHOUGHT ENGINEERING
7266 Courtney Drive
San Diego, California 92111
(714) 279-2868

Trademarks: *DigitalResearch †Zilog ‡Tandy Corp §Microsoft

Circle 11 on inquiry card.

NOW AVAILABLE...

Complete Real Estate Analysis Software

including:

- Property listing data base
- Investment profit/loss schedule
- Property management system
- Financial analysis
- Appraisal package

Round-Robin Software
P.O. Box 728
Cedar City, Utah 84720

Apple, TRS-80, Commodore Dealerships Available

Circle 341 on inquiry card.

expand your HEATH/ZENITH-89 with high resolution GRAPHICS

The XCEL™ Model 89 Graphics Unit

- 512 × 256 pixels
- Displayed on the 89
- Optional Support Software
  - -Symbol -3D
  - -Graphs -Surface
  - -Terminal Emulation

prices start at $850 plus tax and delivery

TARCO DEVELOPMENT CORPORATION

1445 Koll Circle, Suite 111, San Jose, CA 95112
(408) 947-1101
(call 800/555-1212 for our toll free number)

Circle 383 on inquiry card.

RAM

For ATARI

Get the most from your ATARI 400. Memory expansion to a full 48K is now possible with our 48K Board. Expand your ATARI 800 with our 32K Board.

48K Board $299
32K Board $199

INTEC
Suite # 111
3387 Del Rosa Ave. North
San Bernardino, CA 92404
(714) 864-5269

CA residents add 6 percent tax

ATARI is trademark of ATARI, Inc.

Circle 183 on inquiry card.

NEED DISKETTES?

Call free (800)235-4137

3M
BASF
MEMOREX
Dysan



PACIFIC EXCHANGES
100 Foothill Blvd.
San Luis Obispo, CA 93401 (In Cal. call (805) 543-1037)

Circle 298 on inquiry card.

!! REAL TIME !!

The TIME MACHINE from ALPHA OMEGA COMPUTER SYSTEMS isn't just another digital clock chip surrounded by interface circuitry. It's an intelligent microcomputer based peripheral device.

The TIME MACHINE communicates with your computer via a serial I/O port at a user selectable data rate between 300 and 2400 baud. RS-232, RS-422, or current loop communication may be used.

Battery protection against power loss is included. The TIME MACHINE automatically computes day of the week and leap year. Buffered output pulses at one second, one minute, and one hour intervals are provided.

Dimensions are 2.5 x 4.75 x 7.5 inches. Batteries, power supply, and communication cable are included.

Price is only $450 single lot and quantity discounts are available. Dealer inquiries invited. Off the shelf delivery.

ALPHA OMEGA COMPUTER SYSTEMS, INC.
P.O. Box 727 / Corvallis, Oregon 97330
Industrial Computer and Control Systems
(503) 754-1911

Circle 17 on inquiry card.

ATARI® OWNERS

SCREEN PRINT INTERFACE

Obtain hardcopy of any screen image (graphics and / or text) on either a TRENDCOM 200 or IDS 440 Paper Tiger printer. Simply attach the supplied parallel printer cable and load the software from cassette (may be transferred to Disk). Obtain a "picture" of the screen on your printer under direct (CTRL?) or program (XIO) control. Works in all graphics / text modes as well as LPRINT and LIST "P:"

Only **$139**

Parallel Printer Interface for the ATARI 400 / 800

Connects to controller jocks 3&4 works with BASIC /DOS/ ASSEMBLER Three printer connectors available:

	ATARI 400	800
TRENDCOM 100 / 200	A4P-1	A8P-1
CENTRONICS 730 / 737	A4P-2	A8P-2
CENTRONICS 36 PIN*	A4P-3	A8P-3

CA sales add 6% tax
MC / VISA accepted.

$69.95

*Fits all other parallel Centronics plus Anadex, Base 2, Epson, Comprint and Microtek. Order by part number. ATARI is a recognized trademark of ATARI, Inc.

MACROTRONICS, inc.®
1125 N. Golden State Blvd. / Suite G
Turlock, CA 95380 (A) (209) 667-2888 / 634-8888

Circle 215 on inquiry card.

A NEW WIRELESS AC REMOTE CONTROL INTERFACE for the Sears and BSR X-10 home control system. Use your present TRS-80 Level II, Apple II or S100 computer to provide complete home security through control of lights, appliances and motors with a few simple BASIC commands.

As featured in:
"COMPUTERIZE A HOME" BYTE, January 1980

Busy Box - Assembled & tested
For TRS-80 .. $109.95
For S100 .... 119.95
For Apple II ... 114.95
Realtime control
sof ware – TRS-80 19.95
To order call (516) 374-6793
or write: The MicroMint Inc.
917 Midway,
Woodmere, NY 11598



BUSY BOX™

DEALER INQUIRIES INVITED

MICRO MINT

AFFORDABLE

Here at KLOFOX, affordable is not a motto, it's a way of doing business. Prices start at $1695.00, for a single 8" drive system.

All systems feature a single board Z-80 CPU (NO BUSS HEADACHES), runs CP/M* 2.2 (BIOS INCLUDED), reliable SD recording, 64K bytes of RAM, four channel CTC, and either an 80 x 24 full-featured video interface or a two channel serial interface. PLUS a six month full warranty+.

OPTIONS:

2 Channel parallel interface- add $29.95
Both serial & video interface- add $95.95
Single to dual drive conversion kit with drive and necessary hardware- add $495.00
All options may be installed by customer.

KLOFOX
PO BOX 93
SAN LUIS OBISPO, CA 93406
(805) 541-0384

*CP/M is a trademark of Digital Research.
+Only 90 days on drives.

Circle 199 on inquiry card.



16K Static Ran Board from Memory Merchants

- Low power 16K Static RAM (2114)
- Extended address - 24 bit
- Four independent 4 K blocks
- Bank select logic
- Runs with:
  2 Mhz 8080, 4 Mhz Z80, 5 Mhz 8085

One of the 4K has "windowing" capability — any or all of the 1K sub-blocks may be removed from the memory block.

POWER:
5 v. (nominal 8V on S-100 bus)

ORGANIZATION:
Dip switch selection allows independent placement of any of the 4K blocks to any 4K boundary.

Dip switch control of windows.

BANK SELECT:
DIP switch array allows bank select port to be placed anywhere in I/O space. Jumper slide allows complete flexibility in choosing enable/disable within bank select port. DIP switch selection allows board to be enabled or disabled on power-on reset.

EXTENDED ADDRESS:
Independent DIP switch allows board to be addressed in any of the 256 64K extended address pages.

PHANTOM DISABLE/ENABLE:
Via DIP switch.

SPEED:
300 ns low power 2114 1Kx4 static memory chips. Compatible with 4 Mhz Z80, 5 Mhz 8085, and 2 Mhz 8080's.

DESIGN FEATURES:
Low power Schottky TTL circuitry. All input and outputs fully buffered. Meet specifications of IEEE 696 (S-100 standard).

CIRCUIT BOARD:
Highest quality FR4 epoxy glass material, solder mask, legend. Fully socketed.

Fully assembled and tested, with extended burn in. Serialized board.

WARRANTY
Estended warranty 6 months, no repair; instant replacement.

only $189

The Best Prices and Deliveries

CALIFORNIA COMPUTER
64K Dynamic RAM

ONLY $499

Circle 260 on inquiry card.

SYSTEM DESIGN
(Formerly Measurement Systems & Controls)
64K Dynamic RAM

DM6400 List $795 . . . . SPECIAL $599
DMB6400 w/Bank Select Special
List $995 . . . . SPECIAL $799
Cromix adapter for above $44

Mini Micro Mart, Inc. 1618 James Street, Syracuse, NY 13203
(315) 422-4467 TWX 710-541-0431

Computers, Disk Systems

ZENITH data systems

Z89-FA
List $2895
OUR PRICE
$2395

Z-89GA
List $2595, Less Disk $2149
A-87 Two Drive
Minifloppy System List $1195........ $989
Z-47DA............................ $3695
8" Two Megabyte Disk System
List $3695 .... $3059

INTERSYSTEMS

formerly ITHACA AUDIO

The new Series II CPU Board features a 4 MHz Z-80A CPU and a full-feature front panel. 20-slot actively terminated motherboard, with 25 amp power supply (50/60 Hz operation, incl. 68 cfm fan). DPS-1. CALL



COMPLETE SYSTEM with InterSystem 64K RAM, I/O Board and double density disk controller board. Full 1-year warranty, CALL



NEW! CROMEMCO SYSTEM ZERO/D

A complete 64K Computer with Double Density Disk Controller ...... List $2995

OUR PRICE $2545

Companion Disk drive for above — **Quad Density** — Total of 780 Kilobytes of storage on the two drives. ..... **List $1295**

OUR PRICE $1099

Only **$3644** for a complete 64K Disk System

SUPERBRAIN

By INTERTEC



64K Double or Quad Density units available. Uses two Z-80 CPU's. Commercial-type terminal with 12" monitor. Dual double density minifloppies. Over 350 kilobytes of storage (twice that with quad density drives). Two serial RS232 ports, I/O ports standard. Expandable with optional S-100 interface. Comes with CP/MTM 2.2 operating system. MiniMicroMart can supply a wide range of CP/M development and application software.

w/64K Double Density, List $3495 .. **$2869**
w/64K Quad Density, List $3995..... **$3395**

HEWLETT PACKARD HP-41CV

$259.

DYNABYTE

DB 8/1

DB 8/1-64 – 64K RAM SYSTEM WITH Z80 CPU and 2 serial and 1 parallel I/O. List $3395, Disc. $2850 OUR PRICE **$2795**

HEWLETT PACKARD HP-85A

Desk-Top Computer
List $3250



$2749

F.O.B. shipping point. All prices subject to change and all offers subject to withdrawal without notice. Advertised prices are for prepaid orders. Credit card and C.O.D. 2% higher. C.O.D. may require deposit.

MORROW THINKER TOYS® DISCUS M26™

26 megabytes of formatted storage
List $4,995
$4,199



THINKER TOYS® DISK SYSTEMS

Now includes CP/M® 2.2

Discus 2D, List $1199 .... $998
Discus 2D, dual-drive, List $1994 .... $1669
Discus 2 + 2, A&T, List $1549 .... $1299
Dual Discus 2 + 2, A&T, List $2748 .... $2299

All Morrow floppy disks include CP/M® 2.2 and Microsoft Basic 80

MORROW



DISCUS M-10
10 Megabyte
Wirchester

List $3695
OUR PRICE
$3095

NEW! CROMIX FROM CROMEMCO

A New UNIX Like Disk Operating System,
With true multi-user, multi-tasking capabilities
List $295 .... **OUR PRICE $249**

NEW! DOUBLE DENSITY CONTROLLER BOARD FROM CROMEMCO

With built-in diagnostics
16 FDC Controller, List $595 **OUR PRICE $505**

— WRITE FOR FREE CATALOG —

Mini Micro Mart, Inc.

1618 James Street, Syracuse, NY 13203
(315) 422-4467 TWX 710-541-0431

Circle 261 on inquiry card.

Terminals and Printers

ZENITH data systems
Z19 Video Terminal

List $995

OUR PRICE **$799**

Limited Time

Intertec
NEW INTERTUBE III

List $995 **ONLY $749**

12" display, 24 x 80 format, 18-key numeric keypad, 128 upper/lower case ASCII characters. Reverse video, blinking, complete cursor addressing and control. Special user-defined control function keys, protected and unprotected fields. Line insert/delete and character insert/delete editing, eleven special line drawing symbols.

TELEVIDEO TVI-912C

Upper and lower case, 15 baud rates: 75 to 19,000 baud, dual intensity, 24 x 80 character display, 12 x 10 resolution. Numeric pad. Programmable reversible video, auxiliary port, self-test mode, protect mode, block mode, tabbing, addressable cursor. Microprocessor controlled, programmable underline, line and character insert/delete. "C" version features typewriter-style keyboard. List $950

CALL FOR PRICE

920C (with 11 function keys, 6 edit keys and 2 transmission mode keys, List $1030

CALL FOR PRICE

950C List $1195 . . . . CALL FOR PRICE

HAZELTINE 1500

Call For Price

1410 w/numeric keypad, List $900 . . . . . . CALL
1420 w/lower case and numeric pad . . . . CALL
1510, List $1395 . . . . CALL
1520, List $1650 . . . . CALL

SOROC



IQ-120

List $995

SPECIAL $729

IQ135 $749

IQ-140 List $1495
SPECIAL $1149

CENTRONICS PRINTERS

NEW 730, parallel, friction, tractor $599
NEW 737 parallel, friction, tractor $799
779-2 w/tractor (same as TRS-80 Line Printer I), List $1350 . . . . $799
704-9 RS232 180CPS $1595
704-11 Parallel 180CPS $1695

NEC SPINWRITER™



Terminal/Keyboard as well as RO Printer Only models available.

CALL FOR PRICES!

PAPER TIGER®

IDS 445 PAPER TIGER $698
IDS 445G PAPER TIGER
Buffer w/graphics option, incl. buffer . . . $789

NEW IDS 460/560
QUALITY PRINTING AT MATRIX
SPEED — LOGIC SEEKING
PROPORTIONAL SPACING
w/auto test justification

NEW IDS PAPERTIGER 460 List $1295 . . $1099
NEW IDS PAPERTIGER 460G List $1394 . $1149
NEW IDS 560G List $1794 . . . . $1499
TRS-80 cable $45

TI-810



TI-810 Basic Unit, $1895 . **$1595**
TI-810 w/full ASCII (Lower case), vertical forms control, and compressed print . **$1795**
TI-820w/lower case List $1995 . . . . $1645
TI-820w/full ASCII, forms control, compressed print . . . . List $2150 . $1795
TI-745 Complete printing terminal with acoustic coupler, List $1695 . . . . **$1399**

ANADEX
DP9500/DP9501 PRINTERS

DP-9500, List $1650 . . . . **$1349**
DP-9501, List $1650 . . . . **$1349**

ANADEX DP-8000
80-Col. Dot Matrix. **$849**

OKIDATA
Microline 80 List $599 **ONLY** $499
Tractor Feed Option **$109**
Serial interface . . . . **$ 99**
Microline 82 List $799 . . . . $679
Microline 83 List $1260 . . . . $1069

AXIOM IMP I **$699**

Epson MX-80 List $645 . . . . $499

Above prices reflect a 2% cash discount (order prepaid prior to shipment). Add 2% to prices for credit card orders, C.O.D.'s, etc. Prices are f.o.b. shipping point. Prices are subject to change and offers subject to withdrawal without notice. **WRITE FOR FREE CATALOG.**

MiniMicroMart, Inc.

VISA · master charge

1618 James Street, Syracuse NY 13203 (315) 422-4467 TWX 710-541-0431

Circle 262 on inquiry card.

Unclassified Ads

FOR SALE: Diablo Series 30 disk drive, power supply capable of powering dual Series 30s, power cable, Diablo C.E. manual covering the Series 30, and one disk pack; $650. I'll ship. Alphanumeric printers, 2½-inch wide plain paper, 32 characters per line, 2 lines per second, using Victor print head, on-board logics, power supply, and cabinet; $50. 5 V, 1 A power supplies; some have line Sw and power on LED, all have RFI and line cord; $15. Dave Musil, 5709 W 50th St, Sioux Falls SD 57106, (605) 335-0944.

WANTED: Computer printer. Any type, but must work on the TRS-80 Model II. Mike Bryant, 4462 Old Stage Rd, Oregon WI 53575, (608) 455-4740.

WANTED: Alpha Micro AM-100 and AM-100/T processor boards. Alex Begin, 7335 Deep Run, Birmingham MI 48010, (313) 642-7512.

FOR SALE: Heath H-14 printer, serial RS-232 standard plus extra built-in parallel interface to connect to the TRS-80 expansion interface printer port. No special software needed. Used less than ten hours, excellent condition. $485. Mark Hansen, 2315 S Canterbury, Lincoln NE 68512, (402) 423-0363, ABBS 423-8086.

FOR SALE: Dynabyte DB 8/1 computer system with Z80A processor (4 MHz), two serial and one parallel I/O, and single- and double-density floppy-disk controller (will control double-sided Shugart or Remex). New, in original cartons with all documentation. Cost over $3400; first certified check for $1800 takes all. Paul Cagle, 1341 Dustin Dr, Apt 17, Yuba City CA 95991, (916) 673-5021 after 6 PM.

FOR SALE: Heath H-8 with 56 K programmable memory, H-8-4 serial board, Heath proto board, H-17 dual disk, Soroc IQ 120 terminal, IDS 125 printer, CAT Novation modem, Heath DOS, and HUG software. Complete system for $2500. Dan Woodhams, 9085 Alcosta Blvd #379, San Ramon CA 94583, (415) 829-8792.

FOR SALE: TI Silent 700 terminal with acoustical coupler. Elderly, but in fine working condition. First certified check for $750 wins this prize. I will pay shipping. Ted Van Sickle, 6541 Grand Cir, Brighton MI 48116, (313) 229-5531.

WANTED: Black-and-white or color monitor for use with Sinclair ZX80. Must be in good condition. Will pay up to $100. Mike Donahue, 125 S Kenilworth Ave, Mt Prospect IL 60056, (312) 394-4695 after 6 PM.

FOR SALE: Supertalker Speech Synthesizer and Heuristics Speech Input (32 words) cards for the Apple II. Supertalker: $195. Heuristics: $165. Both for $340. Tom Rehwoldt, 667 Marbury SE, Grand Rapids MI 49506, (616) 676-9734.

FOR SALE: Altair 8800 S-100 computer with full-function front-panel display, 16-slot motherboard, and heavy-duty power supply ($283). Contains 40 K memory ($395), Micropolis 630 K dual-disk drive 1053-2 ($410), D C Hayes modem ($164), Teletype ASR33 teletypewriter with stand ($399), and Heath H-19 video display ($399). Special system price of $1600. Shipping not included. Excellent condition. David C Mitchell, 435 Regency Ct, Aurora IL 60505, (312) 851-4631 evenings.

FOR SALE: I am selling parts and spares from my old computer to pay for my new computer. Two 8251A made by AMD; $3 each, one Intel P8085A; $10, eight COM5016 Dual Baud Rate Generator; $6 each, and one National Semiconductor SC/MPII; $7. Please add $1 for postage. Send cashier's check or money order. Thomas Papsin, 711 Black Rock Tpke, Fairfield CT 06430.

FOR SALE: Sinclair ZX80 personal computer. In perfect condition. Complete with these accessories: TV and cassette connectors, AC adapter, 4 K BASIC, and 128-page manual. $150. I pay the shipping. Richard Grier, 30 Briardale Ct, Derwood MD 20855, (301) 840-1298.

FOR SALE: Complete S-100 system including: Cromemco ZPU Z80A processor board; Info 2000 Discomen disk controller with two serial, one printer, and two parallel ports; Godbout Econoram 2 8 K static programmable-memory board; SSM I/O-4 interface board; SSM VB1-B video board plus driver software. All boards assembled, new, and working. All documentation and software for all boards included. $600 or best offer. Ricky Sacks, 4827 Court Rd, Houston TX 77053, (713) 438-7575.

UNCLASSIFIED POLICY: Readers who are soliciting or giving advice, or who have equipment to buy, sell or swap should send in a clearly typed notice to that effect. To be considered for publication, an advertisement must be clearly noncommercial, typed double spaced on plain white paper, contain 75 words or less, and include complete name and address information.

These notices are free of charge and will be printed one time only on a space available basis. Notices can be accepted from individuals or bona fide computer users clubs only. We can engage in no correspondence on these and your confirmation of placement is appearance in an issue of BYTE.

Please note that it may take three or four months for an ad to appear in the magazine.

FOR SALE: Three Cal Comp Model 110 8-inch disk drives. Brand new with case and power supply, includes installation manual. $350 each, or $1000 for all three. Bruce Aldridge, 13372 Fieldcrest Ct, Sunnymead CA 92388, (714) 653-0170.

FOR SALE: Computer system. Processors: 6800, Z80. Memory: 44 K programmable memory, 8 K programmable read-only memory. Interfaces: SwTPC MP-C, MP-L, MP-N, MP-S, JPC TC-3 4800BPS cassette-tape, Electronic Systems 111A KCS cassette-tape, Innovative AD68A A/D. Floppy-disk drive: Percom LDF 400. Printer: Base 2 800MST. Miscellaneous: Electronic Systems 109A modem with microphone, speaker, all TVT II boards, SwTPC GT-6144 graphics board, SS50 wire-wrap and extender boards, two I/O wire-wrap boards, and documentation. $2500. John S Browning, 2071B Mercury SE, Albuquerque NM 87118, (505) 266-07B3.

WANTED: Italian students interested in microcomputers would be very pleased if someone can help us with suggestions about making a microcomputer and donations of useful things to do such. Thank you in advance. Prandini Paolo, Viale Europa 72/G, 25100 Brescia, Italy.

FOR SALE: OSI Challenger, 16 K programmable memory, 8-inch dual floppy disks, documentation. Best offer. VTT terminal, 80 characters by 48 lines, uppercase and lowercase. Best offer. Altair 680, front-panel switches. Best offer. Sydney B Newell, 31 Highland St, Colorado Springs CO 80906, (303) 633-6194, (303) 634-3547.

FOR SALE: Books on electronics, computers, and programming languages. Most are of very recent vintage. Send SASE for my list. Also, I would like to purchase quality software for the TI 990 minicomputer. John Gill, Rte 5, Box 370, Blountville TN 37617.

WANTED: Your programs for a Cromemco Dazzler video display and ADS Noisemaker II sound board. Please state price and availability on KC standard cassette. Scott Griggs, 744 E 41st St, Erie PA 16504, (814) 864-8666.

FOR SALE: Used terminals: Comprint 912S 225 cps 80-column printer using dense 9 by 12 dot matrix with RS-232C serial interface at up to 4800 bps (with handshaking); $700 new, in perfect condition, will sell for $425. Also, Datapoint 25 line by 82 column video display (with Honeywell name on the plastic nonglare screen) with full keyboard and number keypad. Display has software cursor control, but no lowercase or scroll. $395 or best offer. Richard Rudell, 1530 S 6th St, Apt C1109, Minneapolis MN 55454, (612) 332-0228.

FOR SALE: Houston Instruments Hiplot plotter. Serial and parallel interfaces, several new packages of pens. Uses 8½ by 11 paper. Excellent condition. List $1100, yours for $800 or best offer. Will COD. Also, Atari 800 software: Assembler, by Quality Software (cassette and manuals). Paid $25, yours for $10 postpaid. Paul Johnson, 217 Rockingham Rd, Londonderry NH 03053, (603) 434-4116.

FOR SALE: A copy of the second issue of BYTE. In almost mint condition. Cost is $1.50 plus $0.50 for the stamps. Michael G Scott, 2204-3 Arbor Cir, Downers Grove IL 60515.

FOR SALE: Selectric mechanism printer. BCD code can be easily converted to provide excellent letter-quality print for an Apple system. Documentation for conversion and technical manual for terminal included. Sturdy, good condition. $450 delivered anywhere in New England. Bob Allison, 235 Washington St, Marblehead MA 01945, (617) 631-6222.

FOR SALE: North Star 64Q computer. New in box, never used. Cost $4300, want $3500. Also, Anabex 9500. Cost $1600, want $1200. You pay shipping. Jeff Lee, Rte 1, Box 640, American Cyn Rd, Vallejo CA 94590, (707) 642-5310.

FOR SALE: Two Intel memory boards with a total of 64 K bytes of programmable memory. Containing 250 ns 2107Cs and some interface circuitry. Each board can be used as 9 bits by 32 K or 18 bits by 16 K. Excellent for making 8- or 16-bit memory. $250 gets both boards and their documentation. Willard Korfhage, POB 5408, Richardson TX 75080.

FOR SALE: BYTE, March 1977 to February 1980, Kilobaud Microcomputing, January 1978 to February 1981, and Interface Age, November 1977 to August 1980. Excellent condition. R Kolla, 4443 Fuller St, Santa Clara CA 95050, (408) 496-6798.

FOR SALE: Tektronix Model 611 storage-display system. Brand-new tube, system completely up to factory specifications. $1500. J McCord, 330 Vereda Leyenda, Goleta CA 93117, (805) 963-6589.

FOR SALE: Facit 4070 paper-tape punch: parallel TTL interface, 75 cps, roll, and manuals. In excellent shape; $325. Digitronix 2540EP 400 cps paper-tape reader: 19-inch rack and manuals. In good shape; $225. Remex 651 paper-tape reader: 19-inch rack; $200. SB1 music board by SSM with manuals and CP/M format music floppy disk; $175. SwTPC CT1024 terminal, RS-232C, video output, 32 characters by 16 lines, with manuals; $100. Larry Snyder, S78 W17675 Canfield Dr, Muskego WI 53150, (414) 679-9706.

FOR SALE: The first year of BYTE in very good condition. Arthur Mechler, 2724 Wagner St, Cincinnati OH 45225.

WANTED: Schematics and any other technical information on a Raytheon video terminal, type DIDS-400, Model #401-2AM70. Will pay reasonable reproduction costs or will return originals after reproduction. Anthony Ploski, 40 Brookside Ter, Clark NJ 07066.

FOR SALE: Digital Group Bytemaster computer, video display, and keyboard. 64 K, 4-channel serial communications, and double-density disk controller card. Excellent condition, full documentation, in original shipping cartons. $1500 firm. Brian Goodheim, 100 S Spring St, Aspen CO 81611, (303) 925-1558.

FOR SALE: Radio-teletypewriter interface for TRS-80 Model I. Macrotronics MBO with MBOO and FSD-1 demodulator for baudot and ASCII. All factory built, one chassis with power supply, tuning meter, and audio frequency-shift-keying generator. $250. Mel Olinsky, 35 Lance Dr, Somers CT 06071, (203) 763-0581.

FOR SALE: TRS-80 Model I, Level 2, 16 K. Realistic cassette recorder CTR-80. Expansion interface with RS-232C board. Novation CAT modem, documentation, programs, manuals, etc. Will sell for $1000 or best offer. Lee Costache, 25-98 36th St, Long Island City NY 11103, (212) 545-908B.

FOR SALE: OSI Challenger IIP system with 5-inch floppy-disk drive, OS-65D operating system, 32 K programmable memory, 32 by 64 video and graphics, joysticks, sound output, printer output, books, manuals, and software. $1275. Al Casper, 3632 CTH I, Saukville WI 53080, (414) 272-0920 days, 675-6946 evenings.

FOR SALE: DG systems, both 100% functional, in dress cabinets with documentation and software. Z80, 26 K static, single 8-inch floppy, full keyboard, and monitor; $1700. Z80, 64 K static, dual 8-inch floppies, printer B, full keyboard, and monitor; $2600. Dual 8-inch floppies in dress cabinet; $800. Willing to deal. Hary Johnson, 6915 Maple Fox Ln, Houston TX 77338.

FOR SALE: MicroChess 2.0. For old-ROM PETs, incompatible with my present system. Has eight levels of play, clock, and algebraic notation on squares for move entry. Fits in 8 K of memory. Write or phone me with your offer. David Magill, 2001 Carling Ave, Apt #1709, Ottawa Ontario, K2A 3W5 Canada, (613) 722-3566.

BOMB

BYTE's Ongoing Monitor Box

Article #	Page	Article	Author(s)
1	26	The Santa Cruz Open: Othello Tournament for Computers	Frey
2	38	Build a Z8-Based Control Computer with BASIC, Part 1	Ciarcia
3	48	Harvesting the Sun's Energy	Mobus
4	60	Mountain Computer's MusicSystem	Moore
5	94	What Time Does the Sun Rise and Set?	Barkstrom
6	136	Multiprocessing with Motorola's MC6809E	Scales
7	158	Computer Simulation of a Solar-Energy System	Doan
8	174	The Atari Assembler/Editor	Pelczarski
9	178	Energy Conservation with a Microcomputer	Jackson and Callahan
10	230	Kalman Mileage Predictor-Monitor	Lobdill
11	252	The Infamous Traveling-Salesman Problem: A Practical Approach	Parry and Pfeffer
12	308	Micromodem Support in Apple Pascal	Robinson
13	326	Life After Death	Macaluso
14	334	DOSPlus: Double-Density Operating System for the TRS-80	Kolya
15	344	Percom's Doubler	Kelly
16	354	Videx Keyboard and Display Enhancer	Pelczarski
17	388	Computer-Aided Drafting with Apple Pascal	Sokol

April BOMB is Logical Choice

Once again, Steve Ciarcia won first place, this time for "Build a Low-Cost Logic Analyzer," (page 36). Steve will receive $100 for his article describing champagne troubleshooting for beer budgets. Harold Corbin took second place with his article, "An Introduction to Data Compression," (page 218) which described how to get more bang for the byte. Harold receives $50. "The MicroAce Computer," by Delmar Searls (page 46) came in third, and described the trials and tribulations of building and using this low-priced Z80-based computer kit.

Reader Service

July 1981
4171

BYTE READER SERVICE

For fastest service transfer mailer label from wrapper to coupon provided at the right. Requests cannot be honored unless zip code is given. This card valid for 90 days only. **NOTE**—If label is missing or defaced fill out coupon carefully—**PLEASE PRINT**—this is the only way to get requested material to you.

Name ______________________

(Title) ______________ (Company) ______________

Address ______________________

City ______________ State ________ Zip ________

1 21 41 61 81	101 121 141 161 181	201 221 241 261 281	301 321 341 361 381	401 421 441 461 481	501 521 541 561 581	601 621 641 661 681
2 22 42 62 82	102 122 142 162 182	202 222 242 262 282	302 322 342 362 382	402 422 442 462 482	502 522 542 562 582	602 622 642 662 682
3 23 43 63 83	103 123 143 163 183	203 223 243 263 283	303 323 343 363 383	403 423 443 463 483	503 523 543 563 583	603 623 643 663 683
4 24 44 64 84	104 124 144 164 184	204 224 244 264 284	304 324 344 364 384	404 424 444 464 484	504 524 544 564 584	604 624 644 664 684
5 25 45 65 85	105 125 145 165 185	205 225 245 265 285	305 325 345 365 385	405 425 445 465 485	505 525 545 565 585	605 625 645 665 685
6 26 46 66 86	106 126 146 166 186	206 226 246 266 286	306 326 346 366 386	406 426 446 466 486	506 526 546 566 586	606 626 646 666 686
7 27 47 67 87	107 127 147 167 187	207 227 247 267 287	307 327 347 367 387	407 427 447 467 487	507 527 547 567 587	607 627 647 667 687
8 28 48 68 88	108 128 148 168 188	208 228 248 268 288	308 328 348 368 388	408 428 448 468 488	508 528 548 568 588	608 628 648 668 688
9 29 49 69 89	109 129 149 169 189	209 229 249 269 289	309 329 349 369 389	409 429 449 469 489	509 529 549 569 589	609 629 649 669 689
10 30 50 70 90	110 130 150 170 190	210 230 250 270 290	310 330 350 370 390	410 430 450 470 490	510 530 550 570 590	610 630 650 670 690
11 31 51 71 91	111 131 151 171 191	211 231 251 271 291	311 331 351 371 391	411 431 451 471 491	511 531 551 571 591	611 631 651 671 691
12 32 52 72 92	112 132 152 172 192	212 232 252 272 292	312 332 352 372 392	412 432 452 472 492	512 532 552 572 592	612 632 652 672 692
13 33 53 73 93	113 133 153 173 193	213 233 253 273 293	313 333 353 373 393	413 433 453 473 493	513 533 553 573 593	613 633 653 673 693
14 34 54 74 94	114 134 154 174 194	214 234 254 274 294	314 334 354 374 394	414 434 454 474 494	514 534 554 574 594	614 634 654 674 694
15 35 55 75 95	115 135 155 175 195	215 235 255 275 295	315 335 355 375 395	415 435 455 475 495	515 535 555 575 595	615 635 655 675 695
16 36 56 76 96	116 136 156 176 196	216 236 256 276 296	316 336 356 376 396	416 436 456 476 496	516 536 556 576 596	616 636 656 676 696
17 37 57 77 97	117 137 157 177 197	217 237 257 277 297	317 337 357 377 397	417 437 457 477 497	517 537 557 577 597	617 637 657 677 697
18 38 58 78 98	118 138 158 178 198	218 238 258 278 298	318 338 358 378 398	418 438 458 478 498	518 538 558 578 598	618 638 658 678 698
19 39 59 79 99	119 139 159 179 199	219 239 259 279 299	319 339 359 379 399	419 439 459 479 499	519 539 559 579 599	619 639 659 679 699
20 40 60 80 100	120 140 160 180 200	220 240 260 280 300	320 340 360 380 400	420 440 460 480 500	520 540 560 580 600	620 640 660 680 700

BYTE'S BOMB is your direct line to the editor's desk. Each month, the two top-rated authors receive bonuses based on your votes. To cast your vote, first look at the list of this month's articles and corresponding article numbers (located in the unclassified ads section on the page preceding the Reader Service list), then rate each article as **Excellent, Good, Fair,** or **Poor** by circling the appropriate number in each column below. Your feedback helps to produce the best possible magazine each month.

Article No.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
Excellent	801	805	809	813	817	821	825	829	833	837	841	845	849	853	857	861	865	869	873	877	881	885	889	893	897
Good	802	806	810	814	818	822	826	830	834	838	842	846	850	854	858	862	866	870	874	878	882	886	890	894	898
Fair	803	807	811	815	819	823	827	831	835	839	843	847	851	855	859	863	867	871	875	879	883	887	891	895	899
Poor	804	808	812	816	820	824	828	832	836	840	844	848	852	856	860	864	868	872	876	880	884	888	892	896	900

Comments ______________________

July 1981
4171

BYTE READER SERVICE

For fastest service transfer mailer label from wrapper to coupon provided at the right. Requests cannot be honored unless zip code is given. This card valid for 90 days only. **NOTE**—If label is missing or defaced fill out coupon carefully—**PLEASE PRINT**—this is the only way to get requested material to you.

Name ______________________

(Title) ______________ (Company) ______________

Address ______________________

City ______________ State ________ Zip ________

1 21 41 61 81	101 121 141 161 181	201 221 241 261 281	301 321 341 361 381	401 421 441 461 481	501 521 541 561 581	601 621 641 661 681
2 22 42 62 82	102 122 142 162 182	202 222 242 262 282	302 322 342 362 382	402 422 442 462 482	502 522 542 562 582	602 622 642 662 682
3 23 43 63 83	103 123 143 163 183	203 223 243 263 283	303 323 343 363 383	403 423 443 463 483	503 523 543 563 583	603 623 643 663 683
4 24 44 64 84	104 124 144 164 184	204 224 244 264 284	304 324 344 364 384	404 424 444 464 484	504 524 544 564 584	604 624 644 664 684
5 25 45 65 85	105 125 145 165 185	205 225 245 265 285	305 325 345 365 385	405 425 445 465 485	505 525 545 565 585	605 625 645 665 685
6 26 46 66 86	106 126 146 166 186	206 226 246 266 286	306 326 346 366 386	406 426 446 466 486	506 526 546 566 586	606 626 646 666 686
7 27 47 67 87	107 127 147 167 187	207 227 247 267 287	307 327 347 367 387	407 427 447 467 487	507 527 547 567 587	607 627 647 667 687
8 28 48 68 88	108 128 148 168 188	208 228 248 268 288	308 328 348 368 388	408 428 448 468 488	508 528 548 568 588	608 628 648 668 688
9 29 49 69 89	109 129 149 169 189	209 229 249 269 289	309 329 349 369 389	409 429 449 469 489	509 529 549 569 589	609 629 649 669 689
10 30 50 70 90	110 130 150 170 190	210 230 250 270 290	310 330 350 370 390	410 430 450 470 490	510 530 550 570 590	610 630 650 670 690
11 31 51 71 91	111 131 151 171 191	211 231 251 271 291	311 331 351 371 391	411 431 451 471 491	511 531 551 571 591	611 631 651 671 691
12 32 52 72 92	112 132 152 172 192	212 232 252 272 292	312 332 352 372 392	412 432 452 472 492	512 532 552 572 592	612 632 652 672 692
13 33 53 73 93	113 133 153 173 193	213 233 253 273 293	313 333 353 373 393	413 433 453 473 493	513 533 553 573 593	613 633 653 673 693
14 34 54 74 94	114 134 154 174 194	214 234 254 274 294	314 334 354 374 394	414 434 454 474 494	514 534 554 574 594	614 634 654 674 694
15 35 55 75 95	115 135 155 175 195	215 235 255 275 295	315 335 355 375 395	415 435 455 475 495	515 535 555 575 595	615 635 655 675 695
16 36 56 76 96	116 136 156 176 196	216 236 256 276 296	316 336 356 376 396	416 436 456 476 496	516 536 556 576 596	616 636 656 676 696
17 37 57 77 97	117 137 157 177 197	217 237 257 277 297	317 337 357 377 397	417 437 457 477 497	517 537 557 577 597	617 637 657 677 697
18 38 58 78 98	118 138 158 178 198	218 238 258 278 298	318 338 358 378 398	418 438 458 478 498	518 538 558 578 598	618 638 658 678 698
19 39 59 79 99	119 139 159 179 199	219 239 259 279 299	319 339 359 379 399	419 439 459 479 499	519 539 559 579 599	619 639 659 679 699
20 40 60 80 100	120 140 160 180 200	220 240 260 280 300	320 340 360 380 400	420 440 460 480 500	520 540 560 580 600	620 640 660 680 700

To get further information on the products advertised in BYTE, fill out the reader service card with your name and address. Then circle the appropriate numbers for the advertisers you select from the list. Add an 18-cent stamp to the card, then drop it in the mail. Not only do you gain information, but our advertisers are encouraged to use the marketplace provided by BYTE. This helps us bring you a bigger BYTE. The index is provided as an additional service by the publisher, who assumes no liability for errors or omissions. *Correspond directly with company.

PLACE
FIRST
CLASS
POSTAGE
STAMP
HERE

BYTE

READER SERVICE
PO BOX 2114 GPO
NEW YORK NY 10116
USA

PLACE
FIRST
CLASS
POSTAGE
STAMP
HERE

BYTE

READER SERVICE
PO BOX 2114 GPO
NEW YORK NY 10116
USA

BYTE SUBSCRIPTIONS

For a subscription to BYTE, please complete this card.

Name ______

Address ______

City ______

State ______ Zip ______ Country ______

Card No. ______

Expiration date ______

Four digits above name—Master Charge only ______

Signature ______ Date ______

Please allow eight weeks for processing. Thank you.

	USA	Canada Mexico
☐ 1 year	☐ $19	☐ $21
☐ 2 years	☐ $34	☐ $38
☐ 3 years	☐ $49	☐ $55

☐ $43 Europe (air delivery) payment enclosed
☐ $35 Elsewhere (surface mail) payment enclosed
(Air mail rates available upon request)

Please remit in US funds drawn on a US bank. Thank you.

☐ Check enclosed (**Bonus:** [North America only] one EXTRA issue—receive 13 issues for the price of 12)

☐ Master Charge ☐ VISA

☐ Bill me (North America only)

4171

PLACE
STAMP
HERE

BYTE SUBSCRIPTIONS
PO Box 590
Martinsville NJ 08836
USA

PLACE
STAMP
HERE

BYTE SUBSCRIPTIONS
PO Box 590
Martinsville NJ 08836
USA

The Dynabyte Difference: Unequalled price/performance with total expandability.

Buying the powerful Dynabyte 5615 isn't only smart, it's cost efficient.

The 5615 is the sure way to get the system you need. With more power for the price. You can select memory to 400 KB on our S-100 bus architecture. Choose from 3 sizes of Winchesters to 45 MB and have diskette back-up to your system also. If it's tape back-up you need, then choose our 5700. If you need less storage, our 5¼″ floppy 5200, our 8″ floppy 5300 or our 5400 system using both floppies, with up to 3.6 MB capacity, can be yours.

The 5615 system is available with either single user CP/M or our enhanced MP/M for multi-user applications. Our MP/M operating system supports up to eight terminals, with a separate or shared spooler, and up to sixteen printers with no required partition space. Add to this multi-tasking, bank switching, record lockout, type-ahead and DMA and you have an MP/M operating system that supports a host of existing languages and meets minicomputer standards.

No multi-user applications library is so responsive to your needs. The 5615 features Business Manager,™ the fully integrated, menu-driven, well documented, easy to install accounting system that gives you file/record protection, HELP commands, multi-level security, keyed data access, internal disk management, available source code and more.

System expandability, power and price/performance are further enhanced by on-hand availability, quantity discounts, 180-day warranty and a national WATS line for support.

Whether you use or sell computer systems, you should ask about the microcomputer that puts minicomputer capability in your hands. That's the 5615. That's the Dynabyte Difference. Call Mike Seashols, V. P. Marketing (800) 227-8300. In California (415) 329-8021. Dynabyte, 115 Independence Drive, Menlo Park, California 94025.

DYNABYTE
Business Computers

Business Manager is a registered trademark of Dynabyte. CP/M and MP/M are registered trademarks of Digital Research Corp.

Circle 130 on inquiry card.